BEFORE THE HON'BLE CENTRAL ELECTRICITY REGULATORY COMMISSION NEW DELHI

PETITION NO	P	ΕT	T.	TI	0	N	Ν	0							
-------------	---	----	----	----	---	---	---	---	--	--	--	--	--	--	--

IN THE MATTER OF

: Petition Under Section 62 and 79 (1) (a) of the Electricity Act, 2003 read with Chapter-III of the Central Electricity Regulatory Commission (Conduct of Business) Regulations, 2023 and Chapter-3, Regulation-9 of Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations, 2024 for approval of tariff of Tanda Super Thermal Power Station Stage-I (4x110 MW) for the period from 01.04.2024 to 31.03.2029.

INDEX

SI. No.	Description	Page No.
1	Petition for Approval of Tariff of Tanda Super Thermal Power Station Stage-I (4x110 MW) for the period from 01.04.2024 to 31.03.2029	1-10
2	Affidavit	11-12
3	Appendix-I	13-83
4	Annexure-R1	84-99
5	Annexure-R2	100-107
6	Annexure-R3	108-109
7	Annexure-R4	110-112
8	Annexure-R5	113-273
9	Annexure-R6	274-275
10	Annexure-R7	276-276
11	Annexure-R8	277-278
12	Annexure-R9	279-279
13	Annexure-R10	280-280
14	Annexure-R11	281-281
15	Annexure-R12	282-302
16	Annexure-R13	303-392

17	Annexure-R14	393-398
18	Annexure-R15	399-405
19	Annexure-R16	406-411
20	Annexure-R17	412-420

BEFORE THE HON'BLE CENTRAL ELECTRICITY REGULATORY COMMISSION NEW DELHI

PETITION NO

IN THE MATTER OF

: Petition Under Section 62 and 79 (1) (a) of the Electricity Act, 2003 read with Chapter-III of the Central Electricity Regulatory Commission (Conduct of Business) Regulations, 2023 and Chapter-3, Regulation-9 of Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations, 2024 for approval of tariff of Tanda Super Thermal Power Station Stage-I (4x110 MW) for the period from 01.04.2024 to 31.03.2029.

AND IN THE MATTER OF

Petitioner: : NTPC Ltd.

NTPC Bhawan

Core-7, Scope Complex

7. Institutional Area. Lodhi Road

New Delhi-110 003.

Respondents 1. Uttar Pradesh Power Corp. Ltd. (UPPCL)

Shakti Bhawan 14, Ashok Marg, Lucknow – 226 001.

The Petitioner humbly states that:

- The Petitioner herein NTPC Ltd. (hereinafter referred to as '**Petitioner**' or '**NTPC'**), is a company incorporated under provisions of the Company Act, 1956 and a Government Company as defined under Section 2(45) of the Companies Act, 2013. Further, NTPC is a 'Generating Company' as defined under Section 2(28) of the Electricity Act, 2003.
- In terms of Section 79(1)(a) of Electricity Act, 2003, the Hon'ble Commission has been vested with the functions to regulate the tariff of NTPC, being a Generating Company owned and controlled by the Central Government. The regulation of the tariff of NTPC is as provided under Section 79(1)(a) read with

Section 61, 62 and 64 of the Electricity Act, 2003 and the Regulations notified by the Hon'ble Commission in exercise of powers under Section 178 read with Section 61 of the Electricity Act, 2003.

- The Petitioner is having power stations/ projects at different regions and places in the country. **Tanda Super Thermal Power Station Stage-I (4x110 MW)** (hereinafter referred to as Tanda St-I) is one such station located in the State of Uttar Pradesh. The power generated from Tanda St-I is being supplied to the respondents herein above.
- The Hon'ble Commission has notified the Central Electricity Regulatory Commission (Terms & Conditions of Tariff) Regulations, 2024 (hereinafter 'Tariff Regulations 2024') which came into force from 01.04.2024, specifying the terms & conditions and methodology of tariff determination for the period 01.04.2024 to 31.03.2029.
- 5) Regulation 9(2) of Tariff Regulations 2024 provides as follows:
 - "(2) In case of an existing generating station or unit thereof, or transmission system or element thereof, the application shall be made by the generating company or the transmission licensee, as the case may be, by 30.11.2024, based on admitted capital cost including additional capital expenditure already admitted and incurred up to 31.3.2024 (either based on actual or projected additional capital expenditure) and estimated additional capital expenditure for the respective years of the tariff period 2024-29 along with the true up petition for the period 2019-24 in accordance with the CERC (Terms and Conditions of Tariff) Regulations, 2019."

In terms of above, the Petitioner is filing the present petition for determination of tariff for Tanda St-I for the period from 01.04.2024 to 31.03.2029 as per the Tariff Regulations 2024.

The tariff of the Tanda St-I for the tariff period 1.4.2019 to 31.3.2024 was determined by the Hon'ble Commission vide its order dated 17.042024 in Petition No.445/GT/2020 in accordance with the CERC (Terms & Conditions of Tariff) Regulations 2019. The petitioner vide affidavit dated 21.11.2024 had filed

a separate true up petition for the period 01.04.2019 to 31.03.2024 for revision of tariff in line with the applicable provisions of Tariff Regulations 2019.

- It is submitted that Hon'ble Commission vide order dated 17.04.2024 in Petition no 445/GT/2020 has allowed a capital cost of Rs 124374.52 Lakh as on 31.03.2024 based on the admitted projected capital expenditure for the 2019-24 period. However, the actual closing capital cost as on 31.03.2024 has been worked out in the foresaid true-up petition as Rs. 124753.82 Lakh based on the actual expenditure after truing up exercise for the period 2019-24. Accordingly, the Petitioner has adjusted an amount of Rs. 379.30 Lakh from the admitted capital cost as on 31.03.2024 and accordingly the opening capital cost as on 01.04.2024 has been considered as Rs. 124753.82 Lakh in the instant petition. The Hon'ble Commission may be pleased to accordingly adopt this adjustment in the admitted capital cost as on 31.3.2024 and determine the tariff in the present petition for the period 2024-29.
- The capital cost claimed in the instant petition is based on the opening capital cost as on 01.04.2024 considered as above and projected estimated capital expenditures claimed for the period 2024-29 under Regulation 19 and Regulation 24, 25 and 26 of the Tariff Regulations, 2024.
- The Petitioner further respectfully submits that as per Regulation 36(1)(6) of the Tariff Regulations 2024, the water charges, security expenses, ash transportation expenses and capital spares consumed for thermal generating stations are to be allowed separately. The details in respect of water charges such as type of cooling water system, water consumption, rate of water charges as applicable for 2023-24 have been furnished below. In accordance with provision of the Regulations, the petitioner shall be furnishing the details of actual for the relevant year at the time of truing up and the same shall be subject to retrospective adjustment.

Description	Remarks
Type of Plant	Coal based station
Type of cooling water system	Closed Cycle

Rate of Water charges	Water Charges: Rs 12.48 (Rs/1000
	Cubic Feet)
	Royalty: Rs 6 Lakh/Cusec Per Year
Total Water Charges	Rs. 98.55 lacs

- Similarly, the Petitioner is claiming the security & ash transportation expenses based on the estimated expenses for the period 2024-29, the same shall be subject to retrospective adjustment based on actuals at the time of truing up. In respect of capital spares consumption, it is submitted that the same shall be claimed at the time of true-up in terms of the proviso to the Regulation 36(1)(6) based on actual consumption of spares during the period 2024-29.
- However, it is submitted that the expenditure towards the ash transportation charges is recurring in nature and the Petitioner has been incurring ash transportation expenditure in its stations in the current tariff period also. In case the same is permitted to be recovered after the issuance of the tariff order for the period 2024-29, there will be additional liability on the beneficiary on account of the interest payment for the period till the time the tariff petitions for the period 2024-29 is decided. To avoid the interest payment liability of the beneficiaries, it is prayed that the petitioner may be allowed to recover/ pass on the ash transportation charges on a monthly basis subject to true-up at the end of the 2024-29 period.
- The petitioner humbly submits that petition no. 227/MP/2024 has been filed by the petitioner concerning Ash Transport Expenditure for its stations which is under active consideration of this Hon'ble Commission and the outcome of the said petition will be applicable to the instant petition also.
- The petitioner has accordingly calculated the tariff for 2024-29 period based on the above and the same is enclosed as **Appendix-I** to this petition.
- 14) The Petitioner humbly submits that the pay/wage revision for the employees of the Petitioner will be due wef 01.01.2027. Further, the wage/pay revision of CISF and Kendriya Vidyalaya employees will also be due for revision during the

tariff period 2024-29. Regulation-36(1)(8) of CERC (Terms & Conditions of Tariff) Regulations-2024 provides as below:

"In the case of a generating company owned by the Central or State Government, the impact on account of implementation of wage or pay revision shall be allowed at the time of truing up of tariff."

In accordance with the above said regulation, the Petitioner shall approach the Hon'ble Commission for allowing the impact of Pay/wage revision of employees of the Petitioner i.e. NTPC Limited, CISF and Kendriya Vidyalaya (wherever applicable) as additional O&M at the time of truing-up of tariff for the control period 2024-29. Hon'ble Commission may be pleased to grant liberty to consider the impact of wage/pay revision as an additional impact on O&M from the date same is implemented and allow the same as additional O&M over and above the normative O&M.

- 15) It is submitted that in terms of Regulation 60 (5) of the Tariff Regulations 2024, the Petitioner is required to furnish details qua providing the details of Landed Price & Gross Calorific Value ("GCV") of coal in Form 15. It is further submitted that the Petitioner in terms of Regulation 40 of the Tariff Regulations 2019 was required to furnish the details for Landed Price & GCV of coal also as per Form 15 of the Tariff Regulations, 2019.
- However, in so far as the present Petition is concerned, the Petitioner has prepared & submitted the data of coal as per Form 15 of the Tariff Regulations, 2019. The same is because of the following reasons:-
 - (a) This Hon'ble Commission had notified the Tariff Regulations, 2019 on 07.03.2019 and the same was in effect till 31.03.2024.
 - (b) The Petitioner being a diligent utility has been seamlessly providing the said data of coal in terms of the prescribed format (i.e. Form 15 of Annexure-I (Part I)) of the Tariff Regulations, 2019 to this Hon'ble Commission for computation of Interest on Working Capital.
 - (c) Thereafter, this Hon'ble Commission on 15.03.2024 notified the Tariff Regulations, 2024, wherein the format of Form 15 was changed/

- amended by this Hon'ble Commission and a new format was placed in the Tariff Regulations 2024 in the month of June'2024.
- (d) By virtue of the said change, the Petitioner has been obligated to furnish the data of coal for its existing plants month wise for the preceding 12 months i.e. for FY 2023-24 for computation of Interest on Working Capital.
- It is humbly submitted that by virtue of the Tariff Regulations, 2024, this Hon'ble Commission has added a new format/ revised the format of Form-15 which has not prescribed in the past Tariff Regulations i.e. of 2019. Hence, it is only now (in the Tariff Regulations 2024) that the Petitioner has been obligated to furnish the data of coal as per the new format of Form-15.

 A True copy of the Form 15 of Tariff Regulations 2019 and Form 15 of Tariff Regulations 2024, is marked and annexed herewith as Annexure P/ [•]
- 18) It is respectfully submitted that since the format for Form 15 has been changed in Tariff Regulations, 2024 and was notified in the month of June'2024, the Petitioner could not have been aware about the said changes earlier, hence the Petitioner did not maintain the data required in new format of Form 15 of Tariff Regulations, 2024.
- Therefore, this Hon'ble Commission may kindly exempt the Petitioner from furnishing the data of coal in terms of new format of Form 15 of the Tariff Regulations, 2024 & may be allowed to furnish the details of coal for FY 2023-24 in terms of the prescribed format of Form-15 of the Tariff Regulations, 2019.
- 20) In light of the above submissions, it may kindly be noted that no prejudice shall be caused to any party if the Petitioner is allowed for providing the details of Landed Price & GCV of coal to this Hon'ble Commission in terms of Form 15 of the Tariff Regulations, 2019 as the value of Landed Price & GCV of coal will remains unaffected.

- It is submitted the Petitioner has served the copy of the Petition on to the Respondents mentioned herein above and has posted the Petition on the company website i.e. www.ntpc.co.in.
- 22) In accordance with the 'Conduct of Business Regulations 2023' of the Hon'ble Commission, the Petitioner shall, within 7 days after filing the tariff petition, publish a notice about such filing in at least two daily leading digital newspapers one in English language and another in any of the Indian languages, having wide circulation in each of the States and Union Territories where the beneficiaries are situated, as per Form 14 appended to these regulations. Subsequently, the Petitioner shall submit the proof of publications as soft copies of the publications under an affidavit through the e-filing portal of the Hon'ble Commission within one week from the date of publication. Further, the Petitioner shall also submit the detail of expenses incurred for publication of the notice along with the prayer for recovery of Publication Expenses as per Regulation-94 of CERC Tariff Regulations 2024.
- UTR No. 37c568eba62158b7b321 on 24.04.2024 for the year 2024-25 and the details of the same have been duly furnished to the Hon'ble Commission. For the subsequent years, it shall be paid as per the provisions of the CERC (Payment of Fees) Regulations, 2012 as amended. Further Regulation 94 (1) of Tariff Regulations 2024 provides that the application fee and publication expenses may be allowed to be recovered directly from the beneficiaries at the discretion of the Hon'ble Commission. Accordingly, it is prayed that Hon'ble Commission may be pleased to allow recovery of filing fee and publication fee directly from the beneficiaries.
- 24) It is submitted that the petitioner is filing this tariff petition subject to the outcome of its various appeals/ petitions pending before different courts. Besides, the petitions filed by NTPC for determination of capital base as on 31.3.2019 through true-up exercise are pending before the Hon'ble Commission and would take some time. The Petitioner, therefore, reserves its right to amend the tariff petition as per the outcome in such appeals/ petitions, if required.

Prayers

In the light of the above submissions, the Petitioner, therefore, prays that the Hon'ble Commission may be pleased to:

- i) Approve tariff of Tanda Super Thermal Power Station Stage-I (4x110 MW) for the period from 01.04.2024 to 31.03.2029.
- ii) Allow the recovery of filing fees as & when paid to the Hon'ble Commission and publication expenses from the beneficiaries.
- iii) Allow reimbursement of Ash Transportation Charges directly from the beneficiaries on monthly basis, subject to true up.
- iv) Grant liberty to approach the Hon'ble Commission to allow for the recovery of pay/wage revision due in 2024-29 period as additional O&M over and above the normative O&M.
- v) Pass any other order as it may deem fit in the circumstances mentioned above.

	Petitioner
Noida	

BEFORE THE HON'BLE CENTRAL ELECTRICITY REGULATORY COMMISSION **NEW DELHI**

PETITION NO.....

IN THE MATTER OF

Petition Under Section 62 and 79 (1) (a) of the Electricity Act, 2003 read with Chapter-III of the Central Electricity Regulatory Commission (Conduct of Business) Regulations, 2023 and Chapter-3, Regulation-9 of Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations, 2024 for determination of tariff of Tanda **Super Thermal Power Station Stage-I (4x110 MW)** for the period from 01.04.2024 to 31.03.2029.

AND IN THE MATTER OF

Petitioner:

NTPC Ltd. NTPC Bhawan Core-7, Scope Complex 7, Institutional Area, Lodhi Road New Delhi-110 003

Respondents:



Uttar Pradesh Power Corp. Ltd. (UPPCL) Shakti Bhawan 14, Ashok Marg Lucknow - 226 001

AFFIDAVIT

- I, Parimal Piyush, Son of Late Bharat Mishra, aged about 49 years, resident of IN1-2004, Inspire, Eldeco Aamantran, Sector-119, Noida (UP), do hereby solemnly affirm and state as follows:
- 1. That the deponent is the Additional General Manager (Commercial) of the Petitioner NTPC Ltd. and is well conversant with the facts and the circumstances of the case and therefore competent to swear this affidavit.
 - That the accompanying Petition under Section 62 and 79 (1) (a) of the Electricity Act, 2003, has been filed by my authorized representative under my instruction परिमल पीयूष/PARIMAL PIYUSH

अपर महाप्रबन्धक (वाणिज्यिक) Addl. General Manager (Commercial) एन टी पी सी लिमिटेड / NTPC LIMITED EOC, A-4A Sector-24, Noida-201301 (U.P.)



and the contents of the same are true and correct to the best of my knowledge and belief.

- 3. That the contents of Para No1.... to24.... as mentioned in the Petition are true and correct based on the my personal knowledge, belief and records maintained in the office.
- 4. That the annexures annexed to the Petition are correct and true copies of the respective originals.
- 5. That the Deponent has not filed any other Petition or Appeal before any other forum or court of law with respect to the subject matter of the dispute.

परिमल पीयूष/PARIMAL PI (Deponent) अपर महाप्रबन्धक (वाणिज्यिक) Addl. General Manager (Commercial) एन टी प्री सी लिमिटेड/NTPC LIMITED EOC, A-8A, Sector-24, Noida-201301 (U.P.)

Verification:

GENDRA SING

AREA VOIDA G.B.MAGAR REGN. NO. 567

Verified at Noida on this day of November 2024, that the contents of my above noted affidavit are true and correct to my knowledge and no part of it is false and nothing material has been concealed therefrom.

(Deponent)

परिमल पीयूष/PARIMAL PIYUSH अपर महाप्रबन्धक (वाणिज्यिक) Addl. General Manager (Commercial) एन टी पी सी लिमिटेड/NTPC LIMITED EOC, A-8A, Sector-24, Noida-201301 (U.P.)

YOG WORA SINGH NOTARY NOIDA GB NAGAR (U.P.) INDIA

2 5 NOV 2024

PART-I APPENDIX-I

TARIFF FILING FORMS (THERMAL)

FOR DETERMINATION OF TARIFF FOR

Tanda Super Thermal Power Station Stage-I

(From 01.04.2024 to 31.03.2029)

Checklist of Main Tariff Forms and other information for tariff filing for Thermal Stations

Form No.	Title of Tariff Filing Forms (Thermal)	Tick
FORM- 1	Summary of Tariff	✓
FORM -1 (I)	Statement showing claimed capital cost	✓
FORM -1 (II)	Statement showing Return on Equity	✓
FORM-2	Plant Characteristics	✓
FORM-3	Normative parameters considered for tariff computations	✓
FORM-3A**	Statement showing O&M Expenses	✓
FORM- 4	Details of Foreign loans	NA
FORM- 4A	Details of Foreign Equity	NA
FORM-5	Abstract of Admitted Capital Cost for the existing Projects	NA
FORM- 6	Financial Package upto COD	NA
FORM- 7	Details of Project Specific Loans	NA
FORM-8	Details of Allocation of corporate loans to various projects	✓
FORM-9A	Summary of Statement of Additional Capitalisation claimed during the period	✓
FORM-9##	Statement of Additional Capitalisation after COD	✓
FORM- 10	Financing of Additional Capitalisation	***
FORM- 11	Calculation of Depreciation on original project cost	✓
FORM- 12	Statement of Depreciation	✓
FORM- 13	Calculation of Weighted Average Rate of Interest on Actual Loans	✓
FORM- 14	Draw Down Schedule for Calculation of IDC & Financing Charges	NA
FORM- 15	Details of Fuel for Computation of Energy Charges	✓
FORM- 15A**	Details of Seconday Fuel for Computation of Energy Charges	✓
FORM- 15B**	Computation of Energy Charges	✓
FORM- 16	Details of Limestone for Computation of Energy Charge Rate	NA
FORM-17***	Details of Capital Spares	***
FORM- 18***	Non-Tariff Income	***
FORM-19***	Details of Water Charges	***
FORM-20***	Details of Statutory Charges	***

PART-I List of Supporting Forms / documents for tariff filing for Thermal Stations

Form No.	Title of Tariff Filing Forms (Thermal)	Tick
FORM-A	Abstract of Capital Cost Estimates	NA
FORM-B	Break-up of Capital Cost for Coal/Lignite based projects	NA
FORM-C	Break-up of Capital Cost for Gas/Liquid fuel based Projects	NA
FORM-D	Break-up of Construction/Supply/Service packages	NA
FORM-E	Details of variables , parameters , optional package etc. for New Project	NA
FORM-F	Details of cost over run	NA
FORM-G	Details of time over run	NA
FORM -H	Statement of Additional Capitalisation during end of the useful life	NA
FORM -I***	Details of Assets De-capitalised during the period	***
FORM -J***	Reconciliation of Capitalisation claimed vis-à-vis books of accounts	***
FORM -K***	Statement showing details of items/assets/works claimed under Exclusions	***
FORM-L	Statement of Capital cost	✓
FORM-M	Statement of Capital Woks in Progress	✓
FORM-N	Calculation of Interest on Normative Loan	✓
FORM-O	Calculation of Interest on Working Capital	✓
FORM-P	Incidental Expenditure up to SCOD and up to Actual COD	NA
FORM-Q	Expenditure under different packages up to SCOD and up to Actual COD	NA
FORM-R	Actual cash expenditure	NA
FORM-S	Statement of Liability flow	***
FORM-T	Summary of issues involved in the petition	✓

^{**} Additional Forms

^{##} Provided yearwise for the period 2024-29
*** Shall be provided at the time of true up

<u>List of supporting documents for tariff filing for Thermal Stations</u>

S. No.	Information / Document	Tick
1	Certificate of incorporation, Certificate for Commencement of Business, Memorandum of Association, & Articles of Association (For New Station setup by a company making tariff application for the first time to CERC)	NA
	A. Station wise and Corporate audited Balance Sheet and Profit & Loss Accounts with all the Schedules & annexures on COD of the Station for the new station & for the relevant years.	
2	B. Station wise and Corporate audited Balance Sheet and Profit & Loss Accounts with all the Schedules & annexures for the existing station for relevant years.	***
3	Copies of relevant loan Agreements	NA
4	Copies of the approval of Competent Authority for the Capital Cost and Financial package.	NA
5	Copies of the Equity participation agreements and necessary approval for the foreign equity.	NA
6	Copies of the BPSA/PPA with the beneficiaries, if any	NA
	Detailed note giving reasons of cost and time over run, if applicable.	
	List of supporting documents to be submitted:	
	a. Detailed Project Report	274
7	b. CPM Analysis	NA
	c. PERT Chart and Bar Chart	
	d. Justification for cost and time Overrun	
8	Generating Company shall submit copy of Cost Audit Report along with cost accounting records, cost details, statements, schedules etc. for the Generating Unit wise /stage wise/Station wise/ and subsequently consolidated at Company level as submitted to the Govt. of India for first two years i.e. 2019-20 and 2020-21 at the time of mid-term true-up in 2021-22 and for balance period of tariff period 2019-24 at the time of final true-up in 2024-25. In case of initial tariff filing the latest available Cost Audit Report should be furnished.	***
9	Any other relevant information, (Please specify)	NA
10	Reconciliation with Balance sheet of any actual additional capitalization and amongst stages of a generating station	***
11	BBMB is maintaining the records as per the relevant applicable Acts. Formats specified herein may not be suitable to the available information with BBMB. BBMB may modify the formats suitably as per available information to them for submission of required information for tariff purpose.	NA

^{***} Shall be provided at the time of true up

		Summary	of Tariff					PART- FORM- '	
Name o	of the Petitioner:	NTPC Limit	ted						
Name o	of the Generating Station:	Tanda Sup	er Thermal P	ower Station	Stage-I				
	Region/District/State):	-	egion/ Ambe			h			
	,						Amount i	n Rs. Lakh	
S. No.	Particulars	Unit	Existing 2023-24	2024-25	2025-26	2026-27	2027-28	2028-29	
1	2	3	4	5	6	7	8	9	
1.1	Depreciation	Rs Lakh	4,475.50	4,067.96	292.61	640.92	806.87	815.48	
1.2	Interest on Loan	Rs Lakh	0.00	-	100.36	255.93	278.12	216.08	
1.3	Return on Equity	Rs Lakh	7,005.89	7,059.76	7,206.70	7,396.85	7,477.79	7,481.45	
1.4	Interest on Working Capital	Rs Lakh	5,658.56	5,888.74	5,845.97	5,866.77	5,880.57	5,893.31	
1.5	O&M Expenses	Rs Lakh	22,862.28	21,896.99	22,095.75	22,308.83	22,537.38	22,782.67	
1.6	Special Allowance (If applicable)	Rs Lakh	0.00	-	-	-	-		
1.7	Unrecovered Depreciation	Rs. Lakh	0.00	16.27	0.00	0.00	0.00	0.0	
	Total	Rs Lakh	40,002.23	38,929.73	35,541.40	36,469.31	36,980.73	37,188.98	
2.1	Landed Fuel Cost of coal as per FSA approved by beneficiaries	Rs/Ton	4,757.05			4595.86			
	(%) of Fuel Quantity	(%)	66.75			67.80			
2.2	Landed Fuel Cost of Imported Coal as per FSA approved by beneficiaries	Rs/Ton		NA					
	(%) of Fuel Quantity	(%)			NA				
2.3	Landed Fuel Cost of coal other than FSA	Rs/Ton	3825.09			3956.19			
	(%) of Fuel Quantity	(%)	21.26			20.90			
2.4	Landed Fuel Cost Imported Coal other than FSA.	Rs/Ton	19,478.31						
	(%) of Fuel Quantity	(%)	11.99			11.29			
2.5	Secondary fuel oil cost	Rs/Unit	0.05	0.05	0.05	0.05	0.05	0.05	
	Energy Charge Rate ex-bus	Rs/Unit	4.78	5.12	5.12	5.12	5.12	5.12	

						PART-I FORM- 1(I)
Name o	f the Petitioner:	NTPC Limited				
Name o	f the Generating Station:	Tanda Super 1	Thermal Power	Station Stage	-l	
					Amoun	t in Rs. Lakhs
	Statement :	showing claimed ca	<u>apital cost – (A</u>	<u>+B)</u>		
S. No.	Particulars	2024-25	2025-26	2026-27	2027-28	2028-29
1	2	3	4	5	6	7
1	Opening Capital Cost	1,24,753.82	1,25,962.32	1,30,023.32	1,32,765.96	1,32,895.96
2	Add: Addition during the year	1,208.50	4,061.00	2,742.64	130.00	-
3	Less: De-capitalisation during the year	-	-	-	-	-
4	Less: Reversal during the year	-	-	-	-	-
5	Add: Discharges during the year	-	-	-	-	1
6	Closing Capital Cost	1,25,962.32	1,30,023.32	1,32,765.96	1,32,895.96	1,32,895.96
7	Average Capital Cost	1,25,358.07	1,27,992.82	1,31,394.64	1,32,830.96	1,32,895.96
	Statement showing clair	ned capital cost eli	gible for RoE (normal rate ((A)	
S. No.	Particulars	2024-25	2025-26	2026-27	2027-28	2028-29
1	2	3	4	5		7
1	Opening Capital Cost	1,24,453.01	1,25,661.51	1,29,472.51	1,32,215.15	1,32,345.15
2	Add: Addition during the year	1,208.50	3,811.00	2,742.64	130.00	1
3	Less: De-capitalisation during the year	-	-	-	-	-
4	Less: Reversal during the year	-	-	-	-	-
5	Add: Discharges during the year	-	-	-	-	_
6	Closing Capital Cost	1,25,661.51	1,29,472.51	1,32,215.15	1,32,345.15	1,32,345.15
7	Average Capital Cost	1,25,057.26	1,27,567.01	1,30,843.83	1,32,280.15	1,32,345.15

		PART-I
		FORM- 1(I)
Name of the Petitioner:	NTPC Limited	
Name of the Generating Station:	Tanda Super Thermal Power Station Stage-I	
		-

Statement showing claimed capital cost eligible for RoE@SBI MCLR+350 bp (B)

S. No.	Particulars	2024-25	2025-26	2026-27	2027-28	2028-29
1	2	3	4	5		7
1	Opening Capital Cost	300.82	300.82	550.82	550.82	550.82
2	Add: Addition during the year	-	250.00	-	-	-
3	Less: De-capitalisation during the year	-	-	-	-	-
4	Less: Reversal during the year	-	-	-	-	-
5	Add: Discharges during the year	-	-	-	-	-
6	Closing Capital Cost	300.82	550.82	550.82	550.82	550.82
7	Average Capital Cost	300.82	425.82	550.82	550.82	550.82

	Statement showing Return o	n Equity at Norm	al Rate			PART-I FORM- 1(IIA)
Name (of the Petitioner	NTPC Limited				
Name (of the Generating Station	Tanda Super T	hermal Power	Station Stage	-l	
						nt in Rs. Lakhs
S. No.	Particulars	2024-25	2025-26	2026-27	2027-28	2028-29
1	2	3	4	5	6	7
	Return on Equity eligible for RoE @ Normal Rate					
1	Gross Opening Equity (Normal)	37,335.90	37,698.45	38,841.75	39,664.54	39,703.54
2	Less: Adjustment in Opening Equity	-	-	-	-	-
3	Adjustment during the year	-				
4	Net Opening Equity (Normal)	37,335.90	37,698.45	38,841.75	39,664.54	39,703.54
5	Add: Increase in equity due to addition during the year	362.55	1143.30	822.79	39.00	0.00
7	Less: Decrease due to De-capitalisation during the year	0.00	0.00	0.00	0.00	0.00
8	Less: Decrease due to reversal during the year	0.00	0.00	0.00	0.00	0.00
9	Add: Increase due to discharges during the year	0.00	0.00	0.00	0.00	0.00
10	Net closing Equity (Normal)	37,698.45	38,841.75	39,664.54	39,703.54	39,703.54
11	Average Equity (Normal)	37,517.18	38,270.10	39,253.15	39,684.04	39,703.54
	Rate of ROE (%)-Pre Tax	15.50%	15.50%	15.50%	15.50%	15.50%
12	Rate of ROE (%)-Post Tax	18.782%	18.782%	18.782%	18.782%	18.782%
13	Total ROE	7,046.48	7,187.89	7,372.53	7,453.46	7,457.12

	Statement showing Return on Equity linked	to SBI MCLF	<u>t:</u>		FO	PART-I RM- 1(IIB)
Name o	of the Petitioner:	NTPC Limite	ed			
Name o	of the Generating Station:	Tanda Supe	r Thermal Po	ower Station	Stage-I	
					Amount in	Rs. Lakhs
S. No.	Particulars	2024-25	2025-26	2026-27	2027-28	2028-29
1	2	3	4	5	6	7
Statem	ent showing Return on Equity Eligible@SBI MCLR + 350 ba	sis points	·			
1	Gross Opening Equity (Normal)	90.25	90.25	165.25	165.25	165.25
2	Less: Adjustment in Opening Equity	0.00	0.00	0.00	0.00	0.00
3	Adjustment during the year	0.00	0.00	0.00	0.00	0.00
4	Net Opening Equity (Normal)	90.25	90.25	165.25	165.25	165.25
5	Add: Increase in equity due to addition during the year	0.00	75.00	0.00	0.00	0.00
7	Less: Decrease due to De-capitalisation during the year	0.00	0.00	0.00	0.00	0.00
8	Less: Decrease due to reversal during the year	0.00	0.00	0.00	0.00	0.00
9	Add: Increase due to discharges during the year	0.00	0.00	0.00	0.00	0.00
10	Net closing Equity (Normal)	90.25	165.25	165.25	165.25	165.25
11	Average Equity (Normal)	90.25	127.75	165.25	165.25	165.25
12	Rate of ROE (%)-Pre Tax	12.15%	12.15%	12.15%	12.15%	12.15%
12A	Rate of ROE (%)-Post Tax	14.72%	14.72%	14.72%	14.72%	14.72%
13	Total ROE	13.29	18.81	24.33	24.33	24.33

				PART-
				FORM-2
Plant Characteristics				
Name of the Petitioner	NTPC Ltd			
Name of the Generating Station	Tanda TP	S		
Unit(s)/Block(s)/Parameters	Unit-l	Unit-II	Unit-III	Unit-IV
Installed Capacity (MW)	110	110	110	110
Schedule COD as per Investment Approval	21.03.88	11.03.89	28.03.90	20.02.98
Actual COD /Date of Taken Over (as applicable)	NI BYLL		1.2000	
Pit Head or Non Pit Head	Non Pit H	ead		
Name of the Boiler Manufacture	BHEL	KOD A		
Name of Turbine Generator Manufacture	CZECH S	KUDA		
Main Steams Pressure at Turbine inlet (kg/Cm²) abs				
Main Steam Temperature at Turbine inlet (°C)				
Reheat Steam Pressure at Turbine inlet (kg/Cm ²⁾				
Reheat Steam Temperature at Turbine inlet (°C)				
Main Steam flow at Turbine inlet under MCR condition (tons/hr)				
Main Steam flow at Turbine inlet under VWO condition(tons/hr)				
Unit Gross electrical output under MCR /Rated condition (MW)				
Unit Gross electrical output under VWO condition (MW)				
Guaranteed Design Gross Turbine Cycle Heat Rate(kCal/kWh)				
Conditions on which design turbine cycle heat rate guaranteed				
% MCR				
% Makeup Water Consumption				
Design Capacity of Make up Water System				
Design Capacity of Inlet Cooling System	_			
Design Cooling Water Temperature (⁰ C)	_			
Back Pressure	_			
Steam flow at super heater outlet under BMCR condition(tons/hr)				
Steam Pressure at super heater outlet under				
BMCR condition) (kg/Cm ²⁾				
Steam Temperature at super heater outlet under				
BMCR condition (⁰ C)				
Steam Temperature at Reheater outlet at BMCR condition (°C)				
Design / Guaranteed Boiler Efficiency (%)				
Design Fuel with and without Blending of domestic/imported coal				
Type of Cooling Tower	Induced D	raft Coolin	g Tower (ID	OCT)
Type of cooling system	Closed Cy		J . J J . (IL	/
Type of Boiler Feed Pump	Motor Driv			
Fuel Details				
-Primary Fuel	Coal			
-Secondary Fuel	LDO			
-Alternate Fuels	N/A			
Special Features/Site Specific Features				
Special Technological Features				
Environmental Regulation related features	ESP,	DSI (unde	r implemen	tation)
Any other special features	<u> </u>	`	-	•

				PART-I
				FORM-2
<u>Plant</u> (Characteristics			
Name of the Petitioner	NTPC Lt	d		
Name of the Generating Station	Tanda TI	PS		
Unit(s)/Block(s)/Parameters	Unit-I	Unit-II	Unit-III	Unit-IV
	•		•	(Petioner)

Normative parameters cons	sidered for ta	riff computa	tions				PART FORM-
Name of the Petitioner:	NTPC Limite	ed					
Name of the Generating Station:	Tanda Supe	r Thermal P	ower Station	Stage-I			
-						(Year Endi	ng March
Particulars	Unit	Existing 2023-24	2024-25	2025-26	2026-27	2027-28	2028-29
1	2	3	4	5	6	7	8
Base Rate of Return on Equity at normal rate	%	15.50%	15.50%	15.50%	15.50%	15.50%	15.50%
Rate of Return on Add - cap beyond the original scope of work including additional capitalization due to Change in Law, Force Majeure	%	7.80%	12.15%	12.15%	12.15%	12.15%	12.15%
Effective Tax Rate	%	17.472%	17.472%	17.472%	17.472%	17.472%	17.4729
Target Availability	%	85.00%	85.00%	85.00%	85.00%	85.00%	85.00%
Peak Hours	%	85.00%	85.00%	85.00%	85.00%	85.00%	85.00%
Off-Peak Hours	%	85.00%	85.00%	85.00%	85.00%	85.00%	85.00%
ß- Average Monthly Frequency Response Performance	Average Monthly Frequency Response Performance 0-1 It will be provided at the time of truing up						
Auxiliary Energy Consumption	%	11.50%	12.00%	12.00%	12.00%	12.00%	12.00%
Gross Station Heat Rate	kCal/kWh	2750.00	2750.00	2750.00	2750.00	2750.00	2750.0
Specific Fuel Oil Consumption	ml/kWh	0.50	0.50	0.50	0.50	0.50	0.5
Cost of Coal/Lignite for WC	in Days	50	50	50	50	50	5
Cost of Main Secondary Fuel Oil for WC	in Months	2	2	2	2	2	
Fuel Cost for WC	in Months						
Liquid Fuel Stock for WC	in Months						
O&M Expenses	Rs lakh/MW	46.16	42.52	42.52	42.52	42.52	42.5
Maintenance Spares for WC	% of O&M	20.00%	20.00%	20.00%	20.00%	20.00%	20.009
Receivables for WC	in Days	45.00	45.00	45.00	45.00	45.00	45.0
Storage capacity of Primary fuel	MT			5 Lakh	MT		
SBI 1 Year MCLR plus 350 basis point	%	12.00%	11.90%	11.90%	11.90%	11.90%	11.90%
Blending ratio of domestic coal/imported coal	%	1129.46%	0.00%	0.00%	0.00%	0.00%	0.009
Norms for consumption of reagent		•		•	•	•	
Specific Limestone consumption for Wet Limestone FGD							
Specific Limestone consumption for Lime Spray Dryer or Semi-dry FGD							
Specific consumption of sodium bicarbonate				NA			
Specific Limestone consumption for CFBC based generating station							
specific urea consumption of the SNCR							
Specific ammonia consumption of the SCR							
Transit and Handling Losses of coal or lignite, as applicable	%	0.80%	0.80%	0.80%	0.80%	0.80%	0.809

Part-I	
FORM-3A	
ADDITIONAL FORM	

	Calculation of O&M Expenses	
Name of the Company	: NTPC Limited	

Name of the Power Station : Tanda Super Thermal Power Station Stage-I

Amount in Rs. Lakhs S.No **Particulars** 2024-25 2025-26 2026-27 2027-28 2028-29 3 4 5 6 8 O&M expenses under Reg.35(1) Normative 18,708.80 18,708.80 18,708.80 18,708.80 18,708.80 1a O&M expenses under Reg.35(6) 2a Water Charges 90.00 90.00 90.00 90.00 90.00 876.93 964.63 1061.09 1167.20 Security expenses 1283.92 To be provided at the time of Truing up 2c | Capital Spares* O&M expenses-Ash Transportation 2221.26 2332.32 2448.94 2571.39 2699.96 **Total O&M Expenses** 21896.99 22095.75 22308.83 22537.38 22782.67

^{*} Shall be provided at the time of true-up.

	FORM-8			
Details of Allocation of Corporate Bonds to various projects				
Name of the Company	NTPC LIMITED			
Name of the Power Station	Tanda Super Thermal Power Station Stage-I			
Commercial Operation Date (COD)	14-01-2000			
Bond-61				
Particulars				
Source of Loan - Bonds Series	61			
Currency	INR			
Amount of Loan sanctioned (In Lakh)	1,07,250.00			
Amount of Gross Loan drawn upto COD (In Lakh)	1,07,250.00			
Interest Type	Fixed			
Fixed Interest Rate, if applicable**	8.10%			
Base Rate, if Floating Interest	N/A			
Margin, if Floating Interest	N/A			
Are there any Caps/Floor	No			
If above is yes,specify caps/floor	N/A			
Moratorium Period (In Years)	5			
Moratorium effective from*	27-05-2016			
Repayment Period	Installments Due on 27/05/2021, 27/05/2026 & 27/05/2031			
Repayment effective from	27-05-2021			
Repayment Frequency	Installments Due on 27/05/2021, 27/05/2026 & 27/05/2031			
Repayment Instalment (In Lakh)	Installments 1st - 35,750.00 2nd - 35,750.00 3rd - 35,750.00			
Base Exchange Rate	N/A			
Door to Door Maturity (In Years)	15			
Name of the Projects	61			
Name of the Projects Tanda R& M	<u> </u>			
I anda ka ivi	400.00			

^{*}Moratorium period has been taken as the period from Deemed Date of Allotment till the date of first Redemption.

** Excluding Survillience fees of 0.03%

Details of Allocation of Corporate Bonds to Name of the Company	NTPC LIMITED	
Name of the Power Station	Tanda Super Thermal Power Station	n Stage-I
Commercial Operation Date (COD)	14-01-2000	
	(Amount in	n Rs. Lakh)
Bond-72		
Particulars		
Source of Loan - Bonds Series	72	
Currency	INR	
Amount of Loan sanctioned (In Lakh)		4,00,000
Amount of Gross Loan drawn upto COD (In L		4,00,000
Interest Type	Fixed	
Fixed Interest Rate, if applicable	5.45%	
Base Rate, if Floating Interest	N/A	
Margin, if Floating Interest	N/A	
Are there any Caps/Floor	No	
If above is yes, specify caps/floor	N/A	
Moratorium Period (In Years)	5	
Moratorium effective from*	15-10-2020	
Repayment Period	Bullet Repayment	
Repayment effective from	15-10-2025	
Repayment Frequency	Bullet Repayment	
Repayment Instalment (In Lakh)		4,00,000
Base Exchange Rate	N/A	
Door to Door Maturity (In Years)	5	
Name of the Projects	72	
TANDA R&M		1,500.00

Statement Giving De	tails of Project Financed through Form 8 TRANCHE NO	a Combination of loan
BP NO 5050000382	T00001	D0005
	Unsecured Loan From SBBJ-II	
Source of Loan :	SBBJ-II	
Currency:	INR	
Amount of Loan :	5,00,00,00,000	
Total Drawn amount :	2,00,00,00,000	
Date of Drawal:	29.06.2018	
Interest Type :	Floating	
Fixed Interest Rate :		
Base Rate, If Floating Interest	8.25%	
Margin, If Floating Interest :	0.00%	
Are there any Caps/ Floor :	Y/N	
Frequency of Intt. Payment	Monthly	
If Above is yes, specify Caps/ Floor :		
Moratorium Period :	5 Years	
Moratorium effective from :	29.06.2018	
Repayment Period (Inc Moratorium) :	15 Years	
Repayment Frequency:	10 Yearly Installments	
Repayment Type :	AVG	
First Repayment Date :	14.03.2020	
Base Exchange Rate :	RUPEE	
Date of Base Exchange Rate :	N.A.	
Project Code	Project Name	Amount
	SINGRAULI R&M	1,00,00,00,000
	Tanda R&M	1,00,00,00,000
Total Allocated	I Amount	2,00,00,00,000.00

<u> </u>	tails of Project Financed thro							
TRANCHE NO								
BP NO 5050000571	T00001	D00004						
Unsec	ured Loan From Punjab Natio	onal Bank-III						
Source of Loan :	Punjab National Bank-III							
Currency:	INR							
Amount of Loan :	20,00,00,00,000							
Total Drawn amount :	5,00,00,00,000							
Date of Drawl	21.08.2018							
Interest Type :	Floating	•						
Fixed Interest Rate :								
Base Rate, If Floating Interest	8.05%							
Margin, If Floating Interest :	0.00%							
Are there any Caps/ Floor :	Y/N							
Frequency of Intt. Payment	MONTHLY							
If Above is yes, specify Caps/ Floor :		•						
Moratorium Period :	3 Years							
Moratorium effective from :	21.08.2018							
Repayment Period (Inc Moratorium) :	12 Years							
Repayment Frequency:	9 Yearly Instalment							
Repayment Type :	AVG							
First Repayment Date :	01.02.2022							
Base Exchange Rate :	RUPEE							
Date of Base Exchange Rate :	N.A.							
Project Code	Project Name	Amount						
r loject Code	SINGRAULI R&M	1,00,00,00,000.00						
	KORBA R&M	1,00,00,00,000.00						
	RAMAGUNDAM R&M	1,00,00,00,000.00						
	VINDHYACHAL R&M	1,00,00,00,000.00						
	TANDA R&M	1,00,00,00,000.00						
T_4_1 All4	-	5,00,00,000,000.00						
Total Allocated	Amount	5,00,00,00,000.00						

PART-I
FORM- 9A
ADDITIONAL FORM

								FARI-
							ADD	FORM- 9A ITIONAL FORM
	Voar wiso St	tatement of A	dditional Capit	alication after	or COD		ADL	ITIONAL FORM
Name	of the Petitioner	tatement of A	uditional Capit	NTPC Limite				
	of the Generating Station			r Thermal Pov	wer Station S	Stage-I		
COD		14-01-2000						
For Fi	nancial Year			2024-29 (Su	mmary)			
							Am	ount in Rs Lakh
SI.			ACE C	laimed (Proje	ected)			Admitted Cos
No.	Head of Work /Equipment	2024-25	2025-26	2026-27	2027-28	2028-29	Justification	Commission, if any
1	2	3	4	5	6	7	8	9
Α.	Works eligble for RoE at Normal Rate							
1	Upgradation of SG-DCS OF U#3&4		223	246				
2	Upgradation of TG-DCS OF U#3&4		300	325				
3	Upgradation of MAXDNA-DCS OF U#3&4		350	400				
4	Upgradation of Fire detection and protection system Main Plant		100	100				
5	Upgradation of DM Plant PLC Controllers		60					
6	Upgradation of Mechanical Type Positioners		56	57			Pl. refer Form-	
7	Replacement of Main Ejector with Vacuum pump		400	400			FY	's.
8	Replacement of switchyard Isolators Stage-I			64				
9	Upgradation of HT/LT Switchgear			143.50	-			
10	Upgradation of Generator & Busbar Protection System			159.84	130.00			
11	Replacement of CRD -Retrofit of Energy chain for Trippers & Plough Feeder CHP Stage-I			196				
12	PLC Upgradation of CHP stage 1		68.20					
13	Stage 1 Ash Slurry line pipe replacement in culverts		75					
14	Stage-I Fire Hyd and Spray Pumps Replacement			33				

PART-I
PART-I FORM- 9A ADDITIONAL FORM
ADDITIONAL FORM

		ADDITIONAL FORM						
Year wise Statement of Additional Capitalisation after COD								
Name of the Petitioner	NTPC Limited							
Name of the Generating Station	Tanda Super Th	hermal Power Station Stage-I						
COD	14-01-2000							
For Financial Year	2024-29 (Summ	2024-29 (Summary)						
Amount in Rs Lakh								
	ACE Claimed (Projecte	ed) Admitted Cost						
l ei	7102 014111104 (1 10)0010	by the						

SI.			ACE CI	aimed (Proje	cted)			Admitted Cost by the
No.	Head of Work /Equipment	2024-25	2025-26	2026-27	2027-28	2028-29	Justification	Commission, if any
15	Stage-1 Clarifiers Replacement		99	99				
16	Repair/strengthening work of all RCC structures of Stage I buildings as per RLA recommendations		2,080	520			PI. refer Form- FY	-
17	Upgradation against Obsolescence of HMI of M/s BHEL with cyber security features in NTPC Tanda	881.50						
18	Supply, erection and commissioning of fire detection and fire protection system for stacker re-claimer and coal conveyor	124.00						
19	Upgradation of SG (Ovation) DCS controllers & HMI, Unit-2 Stage-I	203.00						
Total a	additional capitalization claimed with RoE at Normal Rate	1,208.50	3,811.00	2,742.64	130.00	-		
B.	Works eligble for Return on Equity linked to SBI MCLR:							
1	Augmentation of CCTV System		250.00				N	A
	additional capitalization claimed with RoE at Wtd. ge Rate of Interest (B)	-	250.000	-	-	-		
Total .	Add. Cap. Claimed (A+B)	1,208.500	4,061.000	2,742.640	130.000	-		

										PART
						Year wis	e Statemer	nt of Addition	al Capitalisation after COD	
Name	of the Petitioner					NTPC Limi				
Name	of the Generating				Tanda Sup	er Thermal	Power Station	on Stage-I		
COD						14-01-2000)		•	
For F	nancial Year					2024-25				
								Amount in F	ts Lakh	
SI.	Head of Work				ACE Claimed	(Projected)			Admitted
No.	/Equipment	Accrual basis as per Ind AS	Ind AS adjustmen t	Accrual basis as per IGAAP	Un- discharged Liability included in col. 3	Cash basis	IDC included in col. 3	Regulation s under which claimed	Justification	Cost by th Commissio if any
1	2	3	3A	3B=3+3A	4	5= (3-4)	6	7	8	9
A.	Works eligible fo	r RoE at No	rmal Rate		•			•		
1	Upgradation of HMI for cyber security features	881.50	-	881.50	-	881.50	-		CEA under the provision of Regulation (10) of the Central Electricity Authority (Technical Standards for Connectivity to the Grid) (Amendment) Regulations, 2019 issued CEA (Cyber Security in Power Sector) Guidelines, 2021 (Attached as Annexure-R/1 Colly). The CEA guidelines, 2021 require for compliance of following salient points wrt Cyber Security in Power Sector: i) Phasing out of legacy systems ii) Ensuring security hardening with additional controls in consultation with the OEM iii) Maintaining system logs at least for 6 months duration. Further, Ministry of Electronics and Information Technology (MeitY), Govt of India vide its order No- No. 20(3)/2022-CERT-In Gol dated 28.04.2022 issued Directions under subsection (6) of section 70B of the Information Technology Act, 2000 (Attached as Annexure-R/2 Colly) which inter alia provides: "All service providers, intermediaries, data centres, body corporate and Government organisations shall mandatorily enable logs of all their ICT systems and maintain them securely for a rolling period of 180 days and the same shall be maintained within the Indian jurisdiction. These should be provided to CERT-In along with reporting of any incident or when ordered / directed by CERT-In" The HMI system installed at the instant stations were based on Windows XP for which no support from OEM, M/s Microsoft is available due to declaration of obsolescence and End of Life (EOL) of Windows XP (EOL April 2014) (Attached as Annexure-R/3 Colly). Accordingly, in compliance of CEA (Cyber Security in Power Sector) Guidelines, 2021 and direction from Gol order dated 28.04.2022 the HMI system needs to be upgraded for ensuring safe and reliable operation of the Station.	NA

										PART- FORM-
Name	of the Petitioner					NTPC Lim	ited		nal Capitalisation after COD	1 OKW-
	of the Generating	Station						Power Station	on Stage-I	
COD 14-01-2000 For Financial Year 2024-25										
0	Amount in Rs Lakh									
SI.	Head of Work				ACE Claimed	(Projected)			Admitted
No.	/Equipment	Accrual basis as per Ind AS	Ind AS adjustmen t	Accrual basis as per IGAAP	Un- discharged Liability included in col. 3	Cash basis	IDC included in col. 3	Regulation s under which claimed	Justification	Cost by the Commission if any
1	2	3	3A	3B=3+3A	4	5= (3-4)	6	7	8	9
2	Fire detection and protection system for CHP area	124.00	-	124.00		124.00	-	25 (2) (c) & 26 (1) (b)	Fire Fighting System for CHP area is required to prevent any damage in case of fire, as existence of coal in CHP area makes it vulnerable to fire hazard. As per CEA (Technical Standards for Construction of Electrical Plants and Electric Lines) Regulations. 2022 (relevant pages attached as Annexure-R/4), automatic medium velocity water spray system are to be provided for area related to Coal conveyors, transfer points, crusher houses etc. Further, Hon'ble Commission vide its order dated 17.04.2024 in Petition no-445/GT/2020 allowed the work of Fire Fighting System for CHP area at a cost of Rs 224.88 Lakh. However, the work could not be completed in totality by the end of Tariff Period 2019-24. As of now only a fraction of work is yet to be done which is expected to be completed by the end of FY 2024-25. In view of the above, it is humbly submitted that Hon'ble Commission may be pleased to allow the work of Fire Detection and Protection System for CHP area at the instant station	NA
3	Upgradation of SG (Ovation) DCS controllers	203.00	-	203.00	-	203.00	-	25 (2) (c) & 26 (1) (b)	SG (Ovation) Digital Control System (DCS) is installed at the instant station for control, monitoring and protection of the boiler as a separate DCS package by OEM M/s Emerson. M/s Emerson has refused to provide support for the existing system which has got obsolete. In recent third-party network security audit report submitted by M/s Grand Thornton, it was recommended that existing DCS needs to be upgraded immediately, to mitigate critical cyber security threats. The Audit Report by M/s Grand Thornton is attached as Annexure-R/5. Also, SG (Ovation) DCS is based on Windows XP operating system, for which support from M/s Microsoft has been withdrawn the End of Life declaration by M/s Microsoft is attached as Annexure-R/3 Colly. Further, requirement of upgradation of SG DCS control system is mandated as per the provisions of CEA (Cyber Security in Power Sector) Guidelines, 2021 (Attached as Annexure-R/1 Colly) and the provisions of directions from Govt of India in respect of cyber security of important installations including power plants issued vide Order No- 20(3)/2022-CERT-In Gol dated 28.04.2022 (attached as Annexure-R2 Colly.) In view of the above, it is humbly submitted that Hon'ble Commission may be pleased to allow the replacement of the work of Upgradation of SG (Ovation) DCS controllers	NA
Sub T	<u>l</u> otal-A	1,208.50	-	1,208.50	-	1,208.50	-			
I	- · · · · · · · · · · · · · · · · · · ·	.,_55.56		.,200.00		.,200.00				

										PART-I FORM- 9				
						Year wis	e Statemer	t of Addition	al Capitalisation after COD					
Name	ame of the Petitioner					NTPC Limi	TPC Limited							
Name	ame of the Generating Station					Tanda Sup	anda Super Thermal Power Station Stage-I							
COD						14-01-2000			•					
For Fi	nancial Year					2024-25								
	Amount in Rs Lakh													
SI.	Head of Work				ACE Claimed	(Projected)				Admitted				
No.	/Equipment	Accrual basis as per Ind AS		Accrual basis as per IGAAP	Un- discharged Liability included in col. 3	Cash basis	IDC included in col. 3	Regulation s under which claimed	Justification	Cost by the Commission, if any				
1	2	3	3A	3B=3+3A	4	5= (3-4)	6	7	8	9				
В.	Works eligible fo	r Return on	Equity links	d to SBI MC	LR:									
1	NA	-		-		-		NA	NA	NA				
Sub T	otal-B					-								
Total A	Add. Cap.	1,208.50	-	1,208.50	-	1,208.50								
										(Petitioner)				

						Voorwiee	Ctatamani	t of Additions	al Capitalisation after COD	FORM-
Mamo	of the Petitioner					NTPC Lim		t of Auditiona	il Capitalisation after COD	
	of the Generating S	Station						al Power Stat	tion Stage-I	
COD	or and domeraning t					14-01-2000				
or F	inancial Year					2025-26				
									Amo	ount in Rs Lak
SI.	Head of Work			CE Claime	d (Projected)					Admitted
No.	/Equipment	Accrual basis as per Ind AS	Ind AS Adjustmen t	Accrual basis as per IGAAP	Un- discharged Liability included in col. 3	Cash basis	IDC included in col. 3	Regulation s under which claimed	Justification	Cost by the Commissio if any
1	2	3	3A	3B=3+3A	4	5= (3-4)	6	7	8	9
A.	Works eligible for	RoE at Norr	nal Rate							
1	Upgradation of SG- DCS OF U#3&4	223.00		223.00		223.00		25(2)(c) read with 102	Detailed Justification provided at SI No-A-3 of Form-9 24-25.	NA
2	Upgradation of TG- DCS OF U#3&4	300.00		300.00		300.00		25(2) (c) 26 (1) (b) read with 102	Further, the upgradation of TG DCS control system is in mandated in compliance of the requirement as per the provisions of CEA (Cyber Security in Power Sector) Guidelines, 2021 (Attached as Annexure-R/1 Colly) and as per the provisions of directions from Govt of India in respect of cyber security of important installations including power plants issued vide its order No- 20(3)/2022-CERT-In Gol dated 28.04.2022 (attached as Annexure-R2 Colly.) In view of the above, it is humbly submitted that Hon'ble Commission may be pleased to allow the replacement of the work of Upgradation of TG DCS system.	NA
3	Upgradation of MAXDNA-DCS OF U#3&4	350.00		350.00		350.00		(1) (b) read	The existing MAXDNA DCS is used for Automatic Closed Loop Control Systems such as control of Drum level, Furnace draft, Fuel firing, Airflow etc. MAXDNA DCS was supplied by M/s BHEL which has now got obsolete and no support is available from M/s BHEL. The obsolescence certificate is attached as Annexure-R/7 . Further, the upgradation of TG DCS control system is in mandated in compliance of the requirement as per the provisions of CEA (Cyber Security in Power Sector) Guidelines, 2021 (Attached as Annexure-R/1 Colly) and the provisions of directions from Govt of India in respect of cyber security of important installations including power plants issued vide its order No- 20(3)/2022-CERT-In Gol dated 28.04.2022 (attached as Annexure-R2 Colly .) In view of the above, it is humbly submitted that Hon'ble Commission may be pleased to allow the replacement of the work of Upgradation of MAXDNA DCS system.	NA

										PART FORM-
						Year wise	Statemen	t of Additiona	Il Capitalisation after COD	
Name	e of the Petitioner					NTPC Lim				
Name	e of the Generating S	Station				Tanda Sup	per Therm	al Power Sta	tion Stage-I	
COD						14-01-2000	0			
For F	inancial Year					2025-26				
									Amo	unt in Rs Lal
SI.	Head of Work							1		Admitted
No.	/Equipment	Accrual basis as per Ind AS	Ind AS Adjustmen t	Accrual basis as per IGAAP	Un- discharged Liability included in col. 3	Cash basis	IDC included in col. 3	Regulation s under which claimed	Justification	Cost by the Commissio if any
4	Upgradation of Fire detection and protection system Main Plant	100.00		100.00		100.00		25(2) (c) 26 (1) (b) read with 102	For Fire detection and protection, control panels are installed in the control room. The system works based on automatic detection of smoke and fire in the respective locations of the plant. According to feedback from smoke & fire detectors, the requisite action such as initiation of fire alarm and operation of hydrant, sprinkler etc is activated. The existing fire detection and protection system controllers and field instruments has got obsolete. Due to non availability of required spare part and support from OEM the healthiness of the fire safety system is at risk. Therefore, their upgradation is mandatory to ensure that fire fighting system is healthy and uptodate. The obsolescence certificate is attached as <code>Annexure-R/8</code> . Further CEA (Technical Standards for Construction of Electrical Plants and Electric Lines) Regulations, 2022 requires availability of comprehensive fire protection system at place to ensure safety of the plant. The relevant extract is produced as under: "(5) Fire detection, alarm and protection system.— (i) A comprehensive fire detection, alarm as well as fire protection system shall be installed for the Station in conformity with relevant Indian Standard. (ii) Automatic fire detection and alarm system shall be intelligent and addressable type and shall be provided to facilitate detection of fire at the incipient stage and give warning to the firefighting staff." In view of the above, it is humbly submitted that Hon'ble Commission may be pleased to allow the said work under Regulations 25 (2) (c) with power to relax.	NA

	PAR1 FORM-
	Year wise Statement of Additional Capitalisation after COD
Name of the Petitioner	NTPC Limited
Name of the Generating Station	Tanda Super Thermal Power Station Stage-I
COD	14-01-2000
For Financial Year	2025-26

0	inanciai Year					2025-26			Amo	ount in Rs Lakh
SI. No.	Head of Work /Equipment	Accrual basis as per Ind AS	Ind AS Adjustmen	Accrual	Un- discharged Liability included in col. 3	Cash basis	IDC included in col. 3	Regulation s under which claimed	Justification	Admitted Cost by the Commission, if any
5	Upgradation of DM Plant PLC Controllers	60.00		60.00		60.00		(1)(b) read	The existing Schneider make PLC systems were installed for monitoring, control & operation of DM plant at the instant station. These PLC systems were based on Schneider make Quantum PLC Controller. OEM M/s Schneider has declared them obsolete and discontinued support. The obsolescence letter fromOEM, M/s Schneider is attached as Annexure-R/9 Colly. Due to this, it is very difficult to maintain the control system healthy for ensuring safe and reliable operation of the DM Plant at the instant station. Further, CEA issued CEA (Cyber Security in Power Sector) Guidelines, 2021 (Attached as Annexure-R/3) in compliance of Govt of India policy for cyber security indian Computer Emergency Response Team (CERT_In). These guidelines require mandatory Compliance by all Responsible Entities. The scope under "Control Systems for System Operation and Operation Management" inter alia covers " Power Plant Control Systems". The CEA Guidelines (2021) for Cyber Security in the Power Sector mandates: (i) Phasing out legacy systems with additional security controls in consultation with the OEM, and (iii) Hardening existing systems with additional security controls in consultation with the OEM, and (iii) Maintaining system logs for a minimum of six months. Therefore, the upgradation of existing PLC systems for DM plant at the instant station is required due to its obsolescence and in compliance of CEA (Cyber Security in Power Sector) Guidelines, 2021 for ensuring safe and reliable operation of the Station. In view of the above, it is humbly submitted that Hon'ble Commission may be pleased to allow the said work under Regulations 25 (2) (c) with power to relax.	NA
6	Upgradation of Mechanical Type Positioners of Draft System	56.00		56.00		56.00		read with	The resolution/ precision in the existing actuator is +/- 2.5%, so fine control of PA header pressure & furnace pressure control loop is difficult. Sometimes these control loops get disturbed especially during frequent Ramp up & Ramp Down of unit load to meet the generation schedule provided to the station from grid controller. Fine control of PA fan blade pitch & IGV of ID Fan is required for smooth control of PA header pressure and furnace draft. The existing IGV & Blade pitch actuators for controlling the furnace draft and PA header pressure were installed at the time of commissioning of the Unit. They have become obsolete as OEM ILK has discontinued support for them. The list of actuators for whose M/s ILK has discontinued the support is attached as Annexure-R/10 The role of these actuators is very critical for maintaining requisite air flow in proportionate with fuel input into the boiler for ensuring complete combustion and avoid any residual unburnt fuel inside furnace which may cause unsafe operation of boiler. In view of criticality of role of these actuators and the fact that OEM has discontinued their support for them, they need to be upgraded to ensure efficient & reliable operation of the Plant. In view of the above, it is humbly submitted that Hon'ble Commission may be pleased to allow the said work under Regulations 25 (2) (c) read with 102.	NA

										PART- FORM-9					
						Year wise	Statemen	t of Additiona	I Capitalisation after COD						
Name	e of the Petitioner					NTPC Lim	ited								
Name	e of the Generating	Station				Tanda Sup	er Therm	al Power Stat	ion Stage-I						
COD						14-01-2000									
For F	inancial Year					2025-26									
									Amo	unt in Rs Lak					
SI.	Head of Work			CE Claimed	d (Projected)					Admitted					
No.	/Equipment	Accrual basis as per Ind AS	Ind AS Adjustmen t	Accrual basis as per IGAAP	Un- discharged Liability included in col. 3	hasis	IDC included in col. 3	Regulation s under which claimed	Justification	Cost by the Commission if any					
7	Replacement of Main Ejector with Vacuum pump	400.00		400.00		400.00		25(2)(c) read with 102	At instant station condenser vacuum is maintained by two sets of ejectors, one is starting ejectors used during unit start up and other is main ejector which is used to maintain condenser vacuum during normal operation. They work on ejector principle wherein steam is used as drive force to create vacuum inside the condensers. The steam for working of ejectors is taken from Aux PRDS system of the unit. Therefore, start up activity at TG side can only be started after charging of Aux PRDS when certain pressure is build up inside boiler. The existing ejector system is hardly in use in any of the latest plants. Support for the upkeep of the existing ejectors from OEM M/s BHEL has not there. Further, during unit start up when starting ejector is in service, the working steam is dumped to atmosphere causing enormous noise in the surroundings and loss of DM water. Tanda Stage-I being not pit head plant, frequent start up of all four Units is done to meet the beneficiary schedule. Considering the obsolescence of the ejector system and support from the OEM not being available and limitations of the ejector system during unit start up necessitates the replacement of existing steam ejectors with vacuum pump based system. Accordingly, same needs to be replaced with vacuum pump based system. In view of the above it is humbly submitted that Hon'ble Commission may be pleased to allow the work of Replacement of Ejector System with Vacuum pump.	NA					

		PART-I FORM- 9
	Year wise Statement of Additional Capitalisation after COD	
Name of the Petitioner	NTPC Limited	
Name of the Generating Station	Tanda Super Thermal Power Station Stage-I	
COD	14-01-2000	
For Financial Year	2025-26	
		Amount in Rs Lakh

SI.	Head of Work							Admitted		
No.	/Equipment	Accrual basis as per Ind AS	Ind AS Adjustmen	Accrual basis as per IGAAP	Un- discharged Liability included in col. 3	Cash basis	IDC included in col. 3	Regulation s under which claimed	Justification	Cost by the Commission, if any
8	Upgradation of CHP PLC Controllers	68.20		68.20		68.20		(1) (b) read	The existing Schneider make PLC systems were installed for monitoring, control & operation of CHP at the instant station. These PLC systems were based on Schneider make Modicon Quantum PLC Controller. OEM M/s Schneider has declared them obsolete and discontinued their support. The obsolescence letter fromOEM, M/s Schneider is attached as Annexure-R/9 Colly. Due to this, it is very difficult to maintain the control system healthy for ensuring safe and reliable operation of the CHP. Further, CEA issued CEA (Cyber Security in Power Sector) Guidelines, 2021 (Attached as Annexure-R/1 Colly) in compliance of Govt of India policy for cyber security under Indian Computer Emergency Response Team (CERT_In). These guidelines require mandatory Compliance by all Responsible Entities. The scope under "Control Systems for System Operation and Operation Management" inter alia covers "Power Plant Control Systems". The CEA Guidelines (2021) for Cyber Security in the Power Sector mandates (i) Phasing out legacy systems, with additional security controls in consultation with the OEM, and (iii) Maintaining system logs for a minimum of six months. Therefore, the upgradation of existing PLC systems for CHP at the instant station is required due to its obsolescence and in compliance of CEA (Cyber Security in Power Sector) Guidelines, 2021 for ensuring safe and reliable operation of the Station. In view of the above, it is humbly submitted that Hon'ble Commission may be pleased to allow the said work under Regulations 25 (2) (c) read with Regulation 26 (1) (b).	NA
9	Stage 1 ash slurry line pipe replacement in culverts	75.00		75.00		75.00		road with	Ash slurry pipes are used to dispose wet ash slurry from Ash slurry pit situated at Ash Handling Plant inside plant to Ash dyke. On the way from Ash Handling Plant to Ash Dyke, the ash slurry pipes pass through roads, culverts etc. The current ash slurry pipes are made of MS Pipes which are getting frequently eroded due to very corrosive nature of ash being pumped through them. The proposed work is to replace the MS make ash slurry pipes with cast basalt pipes which are highly resistant to abrasion and chemicals. This will help to reduced downtime of existing Ash slurry pipelines and also cut down maintenance cost of frequent rotation requirement and replacement of pipes. The major properties of Cast Basalt pipes is attached as Annexure-R 11 . In view of the above it is humbly submitted that Hon'ble Commission may be pleased to allow the work of replacement of MS pipe with Cast basalt pipe.	NA

		PART-I FORM- 9
	Year wise Statement of Additional Capitalisation after COD	
Name of the Petitioner	NTPC Limited	
Name of the Generating Station	Tanda Super Thermal Power Station Stage-I	
COD	14-01-2000	
For Financial Year	2025-26	
		Amount in Rs Lakh

SI.	Head of Work		Δ	CE Claime	d (Projected)				Ailio	unt in Rs Lakh Admitted		
No.	/Equipment	Accrual basis as per Ind AS	Ind AS Adjustmen	Accrual	basis as per Liability per included in col. 3		IDC included in col. 3	Regulation s under which claimed	Justification	Cost by the Commission if any		
10	Clarifiers replacement Stage- 1	98.80		98.80		98.80		26 (1) (d) read with	Clarifier-A civil structure has been critically corroded and very prone to collapse. Cla B has faced such incidence in past. As recent residual life assessment of Stage I buildings & other Civil Structures by third Party M/s NCCBM it was recommended the residual life of the structure has ended and needed strengthening. The clarifiers are for treatment raw water and hence and necessary to ensure supply of required water making of clarified water and DM water which is must to run the Units. The excerp the report by M/s NCCBM is attached as Annexure-R12 . Accordingly, to ensure sa plant and personnel same need to be replaced. In view of the above it is humbly submitted that Hon'ble Commission may be please allow the work of replacement of Stage-1 Clarifiers.			
11	Repair/strengtheni ng work of all RCC structures of Stage I buildings	2080.00		2,080.00		2,080.00		read with	As per recommendations of residual life assessment of Stage I buildings by M/s NCCBM the residual life of the structure has ended and needed strengthening. These are not only to ensure availability of the plant but also is important from the perspective of the safety of the plant & personnel. Accordingly proposed expenditure to be carried out for ensuring structural soundness of the Stage-I buildings. The excerpts of the report by M/s NCCBM is attached as Annexure-R13. In view of the above it is humbly submitted that Hon'ble Commission may be pleased to allow the work of repair/strengthening work of all RCC structures of Stage I buildings			
Sub 1	otal-A	3811.00	0.00	3811.00	0.00	3811.00	0.00					

										FORM-				
								of Additiona	I Capitalisation after COD					
	of the Petitioner					NTPC Lim								
	of the Generating S	Station				Tanda Super Thermal Power Station Stage-I								
OD						14-01-2000								
or F	inancial Year					2025-26								
								ı	Amo	unt in Rs La				
SI. No.	Head of Work /Equipment	Accrual basis as per Ind AS	Ind AS Adjustmen	Accrual	Un- discharged Liability included in col. 3	Cash basis	IDC included in col. 3	Regulation s under which claimed	Justification	Admitted Cost by th Commission if any				
В.	Works eligible for F	Return on E	quity linked	to SBI MC	LR:									
1	Augmentation of CCTV System	250.00		250.00		250.00			It is submitted that a safety advisory mandating comprehensive monitoring of overhauling work and immediate action to address pulverized fuel leakage was issued by the Central Electricity Authority (CEA) on May 23, 2022 (attached as Annexure-R/14). To comply with these directives, comprehensive plant process monitoring at various locations within the facility has become essential. Further it is submitted that given the extensive nature of overhauling work and unpredictable occurrence of potential leakages, maintaining thorough physical surveillance is not feasible. Therefore, centralized round-the-clock CCTV monitoring of overhauling activities and critical vulnerable areas within the main plant and the Coal Handling Plant (CHP) area is proposed for implementation. In light of this, the Hon'ble Commission is respectfully requested to allow this under Regulation 26(1)(b) and 26(1)(d) of the Tariff Regulations 2024.	NA				
Sub 1	otal-B	250.00	-	250.00	-	250.00	-	26 (1) (d) & 26 (1) (b)						
		4.061.00	i	4.061.00	i	4.061.00	i							

		PART-I
		FORM-9
	Year wise Statement of Additional Capitalisation after COD	
Name of the Petitioner	NTPC Limited	
Name of the Generating Station	Tanda Super Thermal Power Station Stage-I	
COD	14-01-2000	
For Financial Year	2026-27	
	Amount in	Rs Lakh

									Ar				
SI. No.	Head of Work /Equipment	Accrual basis as per Ind AS	Ind AS	ACE Claimed Accrual basis as per IGAAP	Un- discharged	Cash basis	IDC include d in col.	Regulations under which claimed	Justification				
1	2	3	3A	3B=3+3A	4	5= (3-4)	6	7	8	9			
A.	Works eligible for RoE at N	Iormal Rate											
1	Upgradation of SG-DCS OF U#3&4	246.00		246.00		246.00			Detailed Justification provided at Si No-A-3 of Form-9 24-25.	NA			
2	Upgradation of TG-DCS OF U#3&4	325.00		325.00		325.00		25(2)(c) read with 102	Detailed Justification provided at Si No-A-2 of Form-9 25-26.	NA			
3	Upgradation of MAXDNA- DCS OF U#3&4	400.00		400.00		400.00		25(2)(c) read with 102	Detailed Justification provided at SI No-A-3 of Form-9 25-26.	NA			
4	Upgradation of Fire detection and protection system Main Plant	100.00		100.00		100.00		25(2)(c) read with 102		NA			
5	Upgradation of Mechanical Type Positioners	57.00		57.00		57.00		25(2)(c) read with 102	Detailed Justification provided at SI No-A-6 of Form-9 25-26.				
6	Replacement of Ejector System with Vacuum pumps	400.00		400.00		400.00		25(2)(c) read with 102	Detailed Justification provided at SI No-A-8 of Form-9 25-26.	NA			
7	Replacement of switchyard Isolators Stage-I	64.00		64.00		64.00			Isolators of 220kV switchyard are more than 25 years old and out lived their life. The existing 220 KV switchyard not only cater to export of power from Stage-I to load centres but also acts as interchange of power during stage-I shutdown to ensure power flow. Therefore, to cater to the requirement of power flow, all the elements of switchyard including isolators need to be kept healthy. The existing isolators are old and obsolete and no support is available from the OEM. In view of the above it is humbly submitted that Hon'ble Commission may be pleased to allow the work of Replacement of switchyard Isolators Stage-I	NA			
8	Upgradation of HT/LT Switchgear	143.50		143.50		143.50		25(2)(c) read with 102	The existing circuit breakers in LT & HT switchgear is of Minimum Oil Circuit Breaker (MOCB) type which are currently not being used for such use. The breaker is key element for switchgears as main switching device. Currently, vacuum circuit breakers are used for low, medium and high voltage switchgears. The MOCB breakers have become obsolete and support from OEM is not available. Therefore, upgradation of existing HT/LT switchgear is become necessary by replacing the MOCB circuit breakers with Vacuum breakers. In view of the above it is humbly submitted that Hon'ble Commission may be pleased to allow the work of Replacement of switchyard Isolators Stage-I	NA			

				Vacan	udaa Ctata	of Additional Coultains	tion often COD	PAR FORM
	- f.d D. (()			<u>Year</u>		of Additional Capitalisa	tion after COD	
	of the Petitioner of the Generating Station				NTPC Limite		Stano I	
COD	of the Generating Station				14-01-2000	r Thermal Power Station	i Stage-i	
	inancial Year				2026-27			
9	Upgradation of Generator & Busbar Protection System	159.84	159.	84	159.84	` ' ' '	The existing Generator protection of Unit-2 & 4 and bus bar protection relays are electromechanical type supplied by M/s ABB Ltd. These electromechanical type of relays have become obsolete and no further support is available for them. Due to technological obsolescence and the need to improve reliability, the complete GRP panel replacement for Units 2 and 4 is required. It is submitted that the work of replacement obsolete electromagnetic type protection relays in northern region with state-of-art numerical relays was deliberated in 11th TCC/12th NRPC Meeting held on 21st-22nd April 2009(copy attached as Annexure-R/15). In 20th TCC/22nd NRPC meeting, held on 28-29 June 2011 it was decided that utilities would submit the details of existing and planned numerical relays for their system (copy attached as Annexure-R/16). Further, The CEA "Standard Technical Specification for Sub- critical Thermal Power Project" under sub section 5.14.4 of Section-5 (Electrical Works) provides specification for Generator Protection and relay panel. CEA guidelines provides for installation of numerical relay based Generator protection system in order to meet the variety of functionalities with adequate accuracy and reliability (copy attached as Annexure-R/17). Further, Hon'ble Commission vide its order dated 17.04.2024 in Petition no-445/GT/2020 allowed the work of replacement of obsolete electromagnetic type relay based GRP with state of art numerical relays based GRP of Unit-1 & 3 of the instant station. In view of the above, it is humbly submitted that Hon'ble Commission may be pleased to allow the work of Upgradation of Generator & Busbar Protection System.	
10	Replacement of CRD - Retrofit of Energy chain for Trippers & Plough Feeders chp stg 1	196.00	196.	00	196.00	25(2)(c) read with 102	Existing CRD system are in service for more than 15 years and have become obsolete. They are also energy intensive. No support is available from OEM. Therefore, Energy chain system to be installed for all moving trippers and plough feeders replacing the existing CRD system. In view of the above it is humbly submitted that Hon'ble Commission may be pleased to allow the work of Replacement of CRD -Retrofit of Energy chain for Trippers & Plough Feeders in CHP area.	NA
11	Fire Hyd and spray pumps replacement Stage-I	32.50	32.	50	32.50		Hydrant and spray water pumps are main source of water for fire fighting system of entire plant. These fire Hydrant and spray water pumps are very old, and spares are not available. Considering their critical role in fire fighting system, their healthiness is of paramount importance. For the healthiness and availability of the fire water pumps the exiting fire hydrant and spray water pumps need to be replaced. In view of the above it is humbly submitted that Hon'ble Commission may be pleased to allow the Fire Hyd and spray pumps replacement	NA
12	Clarifiers replacement Stage-1	98.80	98.	80	98.80	25(2) (c) & 26 (1) (d) read with 102	Detailed Justification provided at SI No-A-10 of Form-9 25-26.	NA
13	Repair/strengthening work of all RCC structures of Stage I buildings as per RLA recommendations	520.00	520.	00	520.00	25(2) (c) & 26	Detailed Justification provided at SI No-A-11 of Form-9 25-26.	NA
sub T	Total-A	2,742.64	- 2,742.	64	- 2,742.64			

											PART- FORM-9		
					Year wis	se Statement	of Additi	onal Capitalisa	tion after	COD			
Name	of the Petitioner					NTPC Limited							
Name	of the Generating Station			Tanda Supe	r Therma	I Power Station	Stage-I						
COD					14-01-2000								
For Fir	nancial Year			`		2026-27							
B.	Works eligible for Return o	n Equity linked	to SBI M	CLR:									
1	NA	-		-		-		NA		NA	NA		
Sub To	otal-B	-	-	-	-	-							
Total A	dd. Cap. Claimed (A+B)	2,742.64	-	2,742.64	-	2,742.64							
											(Petitione		

										PART FORM-
			Year v	wise Stateme	ent of Addition	nal Capitalisa	tion after	COD		
Name	of the Petitioner					NTPC Limit	ed			
Name	of the Generating Station					Tanda Supe	r Thermal	Power Station	Stage-I	
COD						14-01-2000				
or F	inancial Year					2027-28				
									Amo	ount in Rs Lak
SI.	Head of Work /Equipment		Α	CE Claimed ((Projected)			Regulations	Justification	Admitted
No.		Accrual basis as per Ind AS	l	Accrual basis as per IGAAP	Un- discharged Liability included in	Cash basis	IDC included in col. 3	under which claimed		Cost by the Commission if any
					col. 3					
1	2	3	3A	3B=3+3A	4	5= (3-4)	6	7	8	9
A.	Works eligible for RoE at Normal I	Rate								
1	Upgradation of Generator & Busbar Protection System	130		130.00		130.00			Detailed Justification provided at SI No-A9 of Form-9 26-27	NA
Sub T	otal-A	130.00		130.00		130.00				
B.	Works eligble for Return on Equity	linked to SBI	MCLR:	•		•				
1	NA	0.00		-		-		NA	NA	NA
Sub T	otal-B	-		-		-				
	Add. Cap. Claimed (A+B)	130.00		130.00		130.00				

										PART-I
										FORM-9
			<u>Yea</u>	r wise State	ment of Additi	onal Capita	lisation a	fter COD		
Name of	f the Petitioner					NTPC Lim				
	f the Generating Station					Tanda Sup	er Therm	al Power Statior	n Stage-I	
COD						14-01-2000)			
For Fina	ncial Year					2028-29				
										Amount in Rs Lakh
SI. No.	Head of Work /Equipment			CE Claimed (Regulations	Justification	Admitted Cost
		Accrual	Ind AS	Accrual	Un-	Cash	IDC	under which		by the
		basis as	Adjustment		discharged	basis	include	claimed		Commission, if
		per Ind AS		per IGAAP	Liability		d in col.			any
					included in		3			
					col. 3					
1	2	3	3A	3B=3+3A	4	5= (3-4)	6	7	8	9
	Works eligble for RoE at Nor	mal Rate								
	NA	-		-		-		NA	NA	NA
Sub Tot		-		-		-				
	Works eligble for Return on	Equity linked	to SBI MCLR:							
	NA	-		-		-		NA	NA	NA
Sub Tot	al-B	-		-		-				
Total Ad	ld. Cap. Claimed (A+B)	-	-	-	-	-				
					_				_	
										(Petitioner)

	Fina	ncina of A	Additiona	l Capitalis	ation				_	PART-	
Name of the Detitioner				NTPC Limited FORM- 10							
Name of the Petitioner	Ctation					mal Day	Ctation	Ctonol			
Name of the Generating Date of COD	Station			14-01-20		mal Powe	er Station	Stage-i			
Date of COD				14-01-20	00				\ 4 !	Do Lold	
Financial Voor (Starting	A otual						Amount in	RS Lakr			
Financial Year (Starting		1	Actual	1				Admitted			
from COD)1	2024-25	2025-26	2026-27	2027-28	2028-29	2024-25	2025-26	2026-27	2027-28	2028-29	
1		3	4	5	6	7	8	9	10	11	
Amount capitalised in Wo	rk/ Equipmer	nt	•	•				•			
Financing Details											
Loan-1											
Loan-2											
Loan-3 and so on											
Total Loan2											
			SHALI	_ BE PRO	VIDED AT	T THE TIN	IE OF TR	UE-UP.			
			SHALI	_ BE PRO	VIDED AT	THE TIM	IE OF TR	UE-UP.			
Total Loan2			SHALI	₋ BE PRO	VIDED A	THE TIM	IE OF TR	UE-UP.			
Total Loan2 Equity			SHALL	_ BE PRO	VIDED AT	THE TIM	IE OF TRI	UE-UP.			
Total Loan2 Equity Internal Resources			SHALI	₋ BE PRO	VIDED AT	THE TIM	IE OF TR	UE-UP.			

	<u>Statemen</u>	ent of Depreciation								
Name	of the Company :	NTPC Limited								
		Tanda Super Thermal Power Station Stage-I								
						(Amoı	ınt in Rs Lakh			
S. No.	Particulars	Existing 2023-24	2024-25	2025-26	2026-27	2027-28	2028-29			
1	2	3	4	5		6	8			
1	Opening Capital Cost	1,24,216.34	1,24,753.82	1,24,753.82	1,24,753.82	1,24,753.82	1,24,753.82			
2	Closing Capital Cost	1,24,753.82	1,24,753.82	1,24,753.82	1,24,753.82	1,24,753.82	1,24,753.82			
3	Average Capital Cost	1,24,485.08	1,24,753.82	1,24,753.82	1,24,753.82	1,24,753.82	1,24,753.82			
1a	Cost of IT Equipments & Software included in (1) above	188.23	186.98	186.98	186.98	186.98	186.98			
2a	Cost of IT Equipments & Software included in (2) above	186.98	186.98	186.98	186.98	186.98	186.98			
3a	Average Cost of IT Equipments & Software	187.61	186.98	186.98	186.98	186.98	186.98			
4	Freehold land	1,674.71	1,674.71	1,674.71	1,674.71	1,674.71	1,674.71			
5	Rate of depreciation	5.46%	5.46%	5.46%	5.46%	5.46%	5.46%			
6	Depreciable value	1,10,548.10	1,10,789.90	1,10,789.90	1,10,789.90	1,10,789.90	1,10,789.90			
7.	Balance useful life at the beginning of the period	1.79	0.79	-	ı	-	-			
8	Remaining depreciable value	8,011.15	4,017.56	-	-	-	-			
9	Depreciation (for the period)	4,475.50	4,017.56	-	-	-	-			
10	Depreciation (annualised)	4,475.50	4,017.56	-	-	-	-			
11	Cumulative depreciation at the end of the period	1,07,012.45	1,10,789.90	1,10,789.90	1,10,789.90	1,10,789.90	1,10,789.9			
12	Less: Cumulative depreciation adjustment on account of undischarged liabilities deducted as on 01.04.2009	-	-	-	-	-	-			
13	Add: Cumulative depreciation adjustment on account of liability Discharge	-	-	-	-	-	-			
14	Less: Cumulative depreciation adjustment on account of decapitalisation	240.11	-	-	-	-	-			
15	Net Cumulative depreciation at the end of the period after adjustments	1,06,772.34	1,10,789.90	1,10,789.90	1,10,789.90	1,10,789.90	1,10,789.9			

							PART-I			
	Statement of D	epreciation- Nev	w Asset				FORM- 12A			
Name o	of the Company :	NTPC Limited								
Name o	of the Power Station :									
						(Amou	nt in Rs Lakh)			
S. No.	Particulars	Existing 2023-24	2024-25	2025-26	2026-27	2027-28	2028-29			
1	2	3	4	5		6	8			
1	Opening Capital Cost	-	-	1,208.50	5,269.50	8,012.14	8,142.14			
2	Add Cap During the Year		1,208.50	4,061.00	2,742.64	130.00	-			
2	Closing Capital Cost	-	1,208.50	5,269.50	8,012.14	8,142.14	8,142.14			
3	Average Capital Cost	-	604.25	3,239.00	6,640.82	8,077.14	8,142.14			
1a	Cost of IT Equipments & Software included in (1) above	-	-	-	-	-	-			
2a	Cost of IT Equipments & Software included in (2) above	-	-	-	-	-	-			
3a	Average Cost of IT Equipments & Software	-	-	-	-	-	-			
4	Freehold land	-	-	-	-	-	-			
	Rate of depreciation	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%			
	Depreciable value	-	543.83	2,915.10	5,976.74	7,269.43	7,327.93			
7.	Balance useful life at the beginning of the period	1.79	0.79	-	-	-	-			
	Life of Station from COD	23.21	24.21	25.21	26.21	27.21	28.21			
7a	Effective Balance useful life at the beginning of the period for Depreciation of New Asset	NA NA	10.79	9.79	8.79	7.79	6.79			
8	Remaining depreciable value	-	543.83	2,864.70	5,633.72	6,285.49	5,537.12			
9	Depreciation (for the period)	-	50.40	292.61	640.92	806.87	815.48			
10	Depreciation (annualised)	-	50.40	292.61	640.92	806.87	815.48			
11	Cumulative depreciation at the end of the period	-	50.40	343.02	983.94	1,790.81	2,606.29			
12	Less: Cumulative depreciation adjustment on account of un- discharged liabilities deducted as on 01.04.2009	-	-	-	-	-	-			
13	Add: Cumulative depreciation adjustment on account of liability Discharge	-	-	-	-	-	-			
14	Less: Cumulative depreciation adjustment on account of decapitalisation	-	-	-	-	-	-			
יוי	Net Cumulative depreciation at the end of the period after adjustments	-	50.40	343.02	983.94	1,790.81	2,606.29			

					PART-I FORM-13				
Name of the Company	NTPC Limited								
Name of the Power Station	Tanda Super Thermal Power Station Stage-I								
	(Amount ir								
	2024-25	2025-26	2026-27	2027-28	2028-29				
Bond 61									
OP Bal	533.33	533.33	533.33	266.67	266.67				
Additions	0.00	0.00	0.00	0.00	0.00				
Repayment	0.00	0.00	266.67	0.00	0.00				
CI Bal	533.33	533.33	266.67	266.67	266.67				
Avg Loan	533.33	533.33	400.00	266.67	266.67				
Int Rate	8.1300%	8.1300%	8.1300%	8.1300%	8.1300%				
Interest	43.36	43.36	32.52	21.68	21.68				
SBBJ, D-V (Repayment from 14.03.2020 - 10 yearly)									
OP Bal	5000.00	4000.00	3000.00	2000.00	1000.00				
Additions	0.00	0.00	0.00	0.00	0.00				
Repayment	1000.00	1000.00	1000.00	1000.00	1000.00				
CI Bal	4000.00	3000.00	2000.00	1000.00	0.00				
Avg Loan	4500.00	3500.00	2500.00	1500.00	500.00				
Int Rate	8.2000%	8.2000%	8.2000%	8.2000%	8.2000%				
Interest	369.00	287.00	205.00	123.00	41.00				
Punjab National Bank-III, D-4 (Repayment from 01.04.20	22 - 9 yearly)								
OP Bal	6666.67	5555.56	4444.44	3333.33	2222.22				
Additions	0.00	0.00	0.00	0.00	0.00				
Repayment	1111.11	1111.11	1111.11	1111.11	1111.11				
Cl Bal	5555.56	4444.44	3333.33	2222.22	1111.11				
Avg Loan	6111.11	5000.00	3888.89	2777.78	1666.67				
Int Rate	7.9000%	7.9000%	7.9000%	7.9000%	7.9000%				
Interest	482.78	395.00	307.22	219.44	131.67				
Bond 72 (Bullet repaymnet 25-10-2025)									
OP Bal	781.25	781.25	0.00	0.00	0.00				

				[PART-I				
				ı	ORM-13				
Name of the Company			NTPC Limited						
Name of the Power Station	Tanda Super Thermal Power Station Stage-I								
				(Ar	mount in lacs)				
	2024-25	2025-26	2026-27	2027-28	2028-29				
Additions	0.00	0.00	0.00	0.00	0.00				
Repayment	0.00	781.25	0.00	0.00	0.00				
Cl Bal	781.25	0.00	0.00	0.00	0.00				
Avg Loan	781.25	390.63	0.00	0.00	0.00				
Int Rate	6.41%	6.41%	6.41%	6.41%	6.41%				
Interest	50.08	25.04	0.00	0.00	0.00				
Bond 72 (Bullet repaymnet 25-10-2025)									
OP Bal	718.75	718.75	0.00	0.00	0.00				
Additions	0.00	0.00	0.00	0.00	0.00				
Repayment	0.00	718.75	0.00	0.00	0.00				
Cl Bal	718.75	0.00	0.00	0.00	0.00				
Avg Loan	718.75	359.38	0.00	0.00	0.00				
Int Rate	5.48%	5.48%	5.48%	5.48%	5.48%				
Interest	39.39	19.69	0.00	0.00	0.00				
Total Loan									
OP Bal	13700.00	11588.89	7977.78	5600.00	3488.89				
Additions	0.00	0.00	0.00	0.00	0.00				
Repayment	2111.11	3611.11	2377.78	2111.11	2111.11				
Cl Bal	11588.89	7977.78	5600.00	3488.89	1377.78				
Avg Loan	12644.44	9783.33	6788.89	4544.44	2433.33				
Int Rate	7.7868%	7.8715%	8.0240%	8.0125%	7.9868%				
Interest	984.60	770.09	544.74	364.12	194.35				

		WAR				
BANK	RATE OF INTEREST	From	То	No. of Days	Weight	WAR
Punjab National Bank III	7.90%	01-Apr-23	31-Mar-24	366.00	28.91	
				366.00	28.91	7.90%
BANK	RATE OF INTEREST	From	То	No. of Days	Weight	WAR
				•		
BANK State Bank of Bikaner & Jaipur State Bank of Bikaner & Jaipur	0.08 8.1000%	From 45017 14-May-23	To 45059 45151.00	43.00	3.44	
State Bank of Bikaner & Jaipur	0.08	45017	45059	43.00 92.00	3.44 7.45	
State Bank of Bikaner & Jaipur State Bank of Bikaner & Jaipur	0.08 8.1000%	45017 14-May-23	45059 45151.00	43.00 92.00 184.00	3.44 7.45 15.00	

	Details of Refinancing											
Sr. No.	Bank	ROI on refinancing date	Date of refinancing	Refinanced with Bank	Refinanced Amount (Rs. In crore)	New Loan Amount (Rs. In crore)	ROI of relplaced Loan	savings	saving to be retained (Percent)	Remarks		
1	Power Finance Corporation - V	7.31%	15-Oct-20	Bonds Series-72	4,000.00	4,000.00	5.45%	1.86%	0.9300%	Loan outstanding as on 14.10.2020 from PFC-V have been foreclosed by way of refinancing from Bond Series-72 at a concessional rate. One-half of the savings in the interest rate is added to the weighted average rate of loan.		

Refinancing o	of PFC Loans	15.10.2020			
BP NO.	DESCRIPTION	O/s amount	Interest rate benchmark and rate on swap date	Refinanced by Loan	Interest rate benchmark and rate on swap date
5070000011	Power Finance Corporation - V	41,66,66,66,668	3Y-AAA Bond	4000Cr , HDFC-	5.45%/ Repo rate+195bps- 5.95%

	<u>rges</u> Name of the Company:		NTPC Limited				FORM-1
lam	e of the Power Station :		Tanda Super Ther	mal Power Statio	n Stage-I		
S. No.	Particulars	Unit			Apr-23		
			Domestic Coal- FSA	Domestic Coal- NTPC Mines	E-Auction Coal	Imported Coal	Bio-Mass
A)	OPENING QUANTITY						
1	Opening Quantity of Coal/ Lignite	(MT)	2,03,323	2,52,808	-	61,114	-
2	Value of Stock	(Rs.)	88,53,93,101	97,28,81,711	-	97,23,46,329	-
<u>B)</u>	QUANTITY						
3	Quantity of Coal supplied by Coal Company	(MT)	4,43,037	65,577	-	2,16,717	
4	Adjustment (+/-) in quantity supplied made by Coal Company	(MT)	-	-503	-	-	
5	Coal supplied by Coal Company (3+4)	(MT)	4,43,037	65,074	-	2,16,717	
6	Normative Transit & Handling Losses	(MT)	3,544	525	-	433	
7	Net coal / Lignite Supplied (5-6)	(MT)	4,39,493	64,549	-	2,16,284	
C)	PRICE						
8	Amount charged by the Coal Company	(Rs.)	1,12,47,10,707	15,48,89,196	-	3,15,71,83,276	
9	Adjustment (+/-) in amount charged made by Coal Company	(Rs.)	15,24,47,498	-12,14,977	-	-	
10	Handling, Sampling and such other similar charges	(Rs.)	18,31,958	2,71,273	-	8,96,475	
11 D)	Total amount Charged (8+9+10) TRANSPORATION	(Rs.)	1,27,89,90,163	15,39,45,491	-	3,15,80,79,751	
12	Transportation charges by rail ship, road transport	(Rs.)	63,20,45,436	9,56,49,677	-	-	
13	Adjustment (+/-) in amount charged made by Railways/ Transport Company	(Rs.)	-	-	-	-	
14	Demurrage Charges, if any	(Rs.)	1,27,893	-	-	-	
15	Cost of diesel in transporting coal through MGR system, if applicable	(Rs.)	-	-	-	-	
16	Total Transportation Charges (12+13+14+15)	(Rs.)	63,19,17,543	9,56,49,677	-	-	
17	Total amount Charged for coal supplied including Transportation (11+16)	(Rs.)	1,91,09,07,707	24,95,95,168	-	3,15,80,79,751	
E)	TOTAL COST						
18	Landed cost of coal (2+17)/(1+7)	Rs./MT	4,350	3,852	-	14,890	<u> </u>
	Blending Ratio	% D //AT	1	0	-	0	-
20 F)	Weighted average cost of coal QUALITY	Rs./MT					6,2
	GCV of Domestic Coal of the opening stock as						I
21	per bill of Coal Company	(kCal/Kg)	4,197	4,601			
22	GCV of Domestic Coal supplied as per bill Coal Company	(kCal/Kg)	4,306	4,472			
23	GCV of Imported Coal of the opening stock as per bill of Coal Company	(kCal/Kg)				5,201	
24	GCV of Imported Coal supplied as per bill Coal Company	(kCal/Kg)				5,178	
25	Weighted average GCV of coal/ Lignite as Billed	(kCal/Kg)			•		4,5
26	GCV of Domestic Coal of opening stock as received at Station	(kCal/Kg)	3,613	3,873			
27	GCV of Domestic Coal supplied as received at Station	(kCal/Kg)	3,583	3,601			
28	GCV of Imported Coal of opening stock as received at Station	(kCal/Kg)	-	-	-	4,900	
29	GCV of Imported Coal supplied as received at Station	(kCal/Kg)	-	-	-	4,963	
30	Weighted average GCV of coal/ Lignite as Received	(kCal/Kg)					3,90

(Petitioner)

Ona	<u>ges</u>						FORM- 1
	Name of the Company :		NTPC Limited				
	e of the Power Station :	11.24	Tanda Super Ther				
S. No.	Particulars	Unit			May-23		
			Domestic Coal- FSA	Domestic Coal- NTPC Mines	E-Auction Coal	Imported Coal	Bio-Mass
A)	OPENING QUANTITY						
1	Opening Quantity of Coal/ Lignite	(MT)	3,55,286	1,90,692	-	1,79,918	-
2	Value of Stock	(Rs.)	1,54,55,22,305	73,45,56,586	-	2,67,89,57,711	-
B)	QUANTITY						
3	Quantity of Coal supplied by Coal Company	(MT)	4,02,236	45,635	-	1,05,692	
4	Adjustment (+/-) in quantity supplied made by Coal Company	(MT)	-	-	-	-	
5	Coal supplied by Coal Company (3+4)	(MT)	4,02,236	45,635	-	1,05,692	
6	Normative Transit & Handling Losses	(MT)	3,218	365	-	211	
7	Net coal / Lignite Supplied (5-6)	(MT)	3,99,018	45,270	-	1,05,481	-
C)	PRICE						
8	Amount charged by the Coal Company	(Rs.)	1,06,96,25,872	10,66,93,156	-	1,54,32,30,620	
_	Adjustment (+/-) in amount charged made by		E 40 40 505				
9	Coal Company	(Rs.)	5,42,19,585		_		
10	Handling, Sampling and such other similar charges	(Rs.)	1,69,28,709	13,12,354	-	30,39,474	
11 D)	Total amount Charged (8+9+10) TRANSPORATION	(Rs.)	1,14,07,74,165	10,80,05,510	-	1,54,62,70,094	
12	Transportation charges by rail ship, road transport	(Rs.)	60,12,01,146	6,62,73,386	-	-	
13	Adjustment (+/-) in amount charged made by Railways/ Transport Company	(Rs.)	-	-	-	-	
14	Demurrage Charges, if any	(Rs.)	 _	11,76,202	_	_	
	Cost of diesel in transporting coal through	i i		11,70,202	_		
15	MGR system, if applicable	(Rs.)	-	-	-	-	
16	Total Transportation Charges (12+13+14+15) Total amount Charged for coal supplied	(Rs.)	60,12,01,146	6,50,97,184	-	-	
17	including Transportation (11+16)	(Rs.)	1,74,19,75,311	17,31,02,694	-	1,54,62,70,094	
<u>E)</u> 18	TOTAL COST	Rs./MT	4,358	3,847	_	14,805	
	Landed cost of coal (2+17)/(1+7) Blending Ratio	%	4,336	3,847	-	14,805	
	Weighted average cost of coal	Rs./MT	'	0	_	0	6,3
F)	QUALITY	1 (0.7)					0,0
21	GCV of Domestic Coal of the opening stock as per bill of Coal Company	(kCal/Kg)	4,273	4,575			
22	GCV of Domestic Coal supplied as per bill Coal Company	(kCal/Kg)	4,418	4,601			
23	GCV of Imported Coal of the opening stock as per bill of Coal Company	(kCal/Kg)				5,183	
24	GCV of Imported Coal supplied as per bill Coal Company	(kCal/Kg)				5,086	
25	Weighted average GCV of coal/ Lignite as Billed	(kCal/Kg)		1	1	1	4,54
26	GCV of Domestic Coal of opening stock as received at Station	(kCal/Kg)	3,592	3,818			
27	GCV of Domestic Coal supplied as received at Station	(kCal/Kg)	3,694	3,596			
28	GCV of Imported Coal of opening stock as received at Station	(kCal/Kg)	-	-	-	4,949	
29	GCV of Imported Coal supplied as received at Station	(kCal/Kg)	-	-		4,910	
	Weighted average GCV of coal/ Lignite as	(kCal/Kg)					3,92

Jame	Name of the Company :		NTPC Limited				
Jami							
	e of the Power Station :		Tanda Super Ther				
S. No.	Particulars	Unit		,	Jun-23		
			Domestic Coal- FSA	Domestic Coal- NTPC Mines	E-Auction Coal	Imported Coal	Bio-Mass
	OPENING QUANTITY						
	Opening Quantity of Coal/ Lignite	(MT)	5,17,123	1,30,362	-	2,04,358	-
2	Value of Stock	(Rs.)	2,25,37,86,683	50,14,54,518	-	3,02,54,57,008	-
	QUANTITY						
	Quantity of Coal supplied by Coal Company	(MT)	57,714	38,068	-	39,915	
4	Adjustment (+/-) in quantity supplied made by Coal Company	(MT)	-	-71	-	-	
5	Coal supplied by Coal Company (3+4)	(MT)	57,714	37,997	-	39,915	
6	Normative Transit & Handling Losses	(MT)	3,208	305	-	80	
	Net coal / Lignite Supplied (5-6)	(MT)	3,97,849	37,693	-	39,835	-
	PRICE						
	Amount charged by the Coal Company	(Rs.)	1,09,31,81,023	9,65,51,623	-	58,59,20,557	
9	Adjustment (+/-) in amount charged made by Coal Company	(Rs.)	6,98,89,488	-1,71,221	-	-3,87,64,775	
10	Handling, Sampling and such other similar charges	(Rs.)	2,98,40,853	28,32,469	-	29,69,867	
	Total amount Charged (8+9+10)	(Rs.)	1,19,29,11,364	9,92,12,871	-	55,01,25,649	
D)	TRANSPORATION						
	Transportation charges by rail ship, road transport	(Rs.)	63,45,34,477	5,44,87,734	-	-	
13	Adjustment (+/-) in amount charged made by Railways/ Transport Company	(Rs.)	-	-	-	-	
	Demurrage Charges, if any	(Rs.)	8,59,856	-	-	-	
	Cost of diesel in transporting coal through MGR system, if applicable	(Rs.)	-	-	-	-	
16	Total Transportation Charges (12+13+14+15)	(Rs.)	63,36,74,621	5,44,87,734	-	-	
	Total amount Charged for coal supplied including Transportation (11+16)	(Rs.)	1,82,65,85,985	15,37,00,605	-	55,01,25,649	
	TOTAL COST	Do MT	4.460	2 000		14 642	
	Landed cost of coal (2+17)/(1+7) Blending Ratio	Rs./MT %	4,460	3,898	0.00%	14,642	-
	Weighted average cost of coal	Rs./MT	'		0.0070		6,46
	QUALITY						-,
21	GCV of Domestic Coal of the opening stock as per bill of Coal Company	(kCal/Kg)	4,351	4,580			
	GCV of Domestic Coal supplied as per bill Coal Company	(kCal/Kg)	4,487	4,601			
	GCV of Imported Coal of the opening stock as per bill of Coal Company	(kCal/Kg)				5,147	
24	GCV of Imported Coal supplied as per bill Coal Company	(kCal/Kg)				5,081	
25	Weighted average GCV of coal/ Lignite as Billed	(kCal/Kg)					4,56
20	GCV of Domestic Coal of opening stock as received at Station	(kCal/Kg)	3,646	3,776			
21	GCV of Domestic Coal supplied as received at Station	(kCal/Kg)	3,639	3,546			
28	GCV of Imported Coal of opening stock as received at Station	(kCal/Kg)	-	-	-	4,935	
29	GCV of Imported Coal supplied as received at Station	(kCal/Kg)	-	-	-	4,971	
	Weighted average GCV of coal/ Lignite as Received	(kCal/Kg)					3,90

			.				FORM- 1
	Name of the Company :		NTPC Limited				
	e of the Power Station :		Tanda Super Ther	mal Power Statio			
S. No.	Particulars	Unit			Jul-23		
			Domestic Coal- FSA	Domestic Coal- NTPC Mines	E-Auction Coal	Imported Coal	Bio-Mass
A)	OPENING QUANTITY						
1	Opening Quantity of Coal/ Lignite	(MT)	5,86,007	74,053	-	1,51,877	-
2	Value of Stock	(Rs.)	2,61,33,33,841	28,86,95,045	-	2,22,38,51,228	-
B)	QUANTITY	(1 a=)	0.04.000	24.242		04.050	
3	Quantity of Coal supplied by Coal Company	(MT)	3,84,090	31,012	-	31,652	
4	Adjustment (+/-) in quantity supplied made by Coal Company	(MT)	-	-	-	-	
5	Coal supplied by Coal Company (3+4)	(MT)	3,84,090	31,012	-	31,652	
6	Normative Transit & Handling Losses	(MT)	3,073	248	-	63	
7	Net coal / Lignite Supplied (5-6)	(MT)	3,81,017	30,764	-	31,589	-
C)	PRICE						
8	Amount charged by the Coal Company	(Rs.)	1,12,47,01,382	10,66,60,306	-	46,18,86,933	
9	Adjustment (+/-) in amount charged made by Coal Company	(Rs.)	6,46,76,648	-	-	-2,98,830	
10	Handling, Sampling and such other similar charges	(Rs.)	44,50,714	3,59,375	-	3,66,789	
11	Total amount Charged (8+9+10)	(Rs.)	1,19,38,28,743	10,70,19,681	-	46,19,54,892	
D)	TRANSPORATION						
12	Transportation charges by rail ship, road transport	(Rs.)	50,85,42,013	1,38,63,324	-	-	
13	Adjustment (+/-) in amount charged made by Railways/ Transport Company	(Rs.)	-	-	-	-	
14	Demurrage Charges, if any	(Rs.)	5,72,421	-	-	-	
15	Cost of diesel in transporting coal through MGR system, if applicable	(Rs.)	-	-	-	-	
16	Total Transportation Charges (12+13+14+15)	(Rs.)	50,79,69,592	1,38,63,324	-	-	
17	Total amount Charged for coal supplied including Transportation (11+16)	(Rs.)	1,70,17,98,335	12,08,83,005	-	46,19,54,892	
E)	TOTAL COST	Do /MT	4 462	2 000		14 620	
18 19	Landed cost of coal (2+17)/(1+7) Blending Ratio	Rs./MT %	4,462	3,908	-	14,639	<u> </u>
	Weighted average cost of coal	Rs./MT	'				6,24
F)	QUALITY						-,-
21	GCV of Domestic Coal of the opening stock as per bill of Coal Company	(kCal/Kg)	4,411	4,585			
22	GCV of Domestic Coal supplied as per bill Coal Company	(kCal/Kg)	4,360	4,601			
23	GCV of Imported Coal of the opening stock as per bill of Coal Company	(kCal/Kg)				5,136	
24	GCV of Imported Coal supplied as per bill Coal Company	(kCal/Kg)				5,049	
25	Weighted average GCV of coal/ Lignite as Billed	(kCal/Kg)					4,54
26	GCV of Domestic Coal of opening stock as received at Station	(kCal/Kg)	3,643	3,725			
27	GCV of Domestic Coal supplied as received at Station	(kCal/Kg)	3,608	3,381			
28	GCV of Imported Coal of opening stock as received at Station	(kCal/Kg)	-	-	-	4,941	
29	GCV of Imported Coal supplied as received at Station Weighted average GCV of coal/ Lignite as	(kCal/Kg)	-	-	-	4,833	
30	Received	(kCal/Kg)					3,86

<u>na</u>	rges		NIEDO				FORM- 1
	Name of the Company :		NTPC Limited				
	e of the Power Station :	l lait	Tanda Super Ther				
S. No.	Particulars	Unit		•	Aug-23		
NO.			Domestic Coal- FSA	Domestic Coal- NTPC Mines	E-Auction Coal	Imported Coal	Bio-Mass
A)	OPENING QUANTITY				1		
1	Opening Quantity of Coal/ Lignite	(MT)	5,55,072	47,694	-	99,227	-
2	Value of Stock	(Rs.)	2,47,68,87,830	18,63,64,306	-	1,45,26,08,292	-
B)	QUANTITY						
3	Quantity of Coal supplied by Coal Company	(MT)	4,55,393	44,299	-	67,905	
4	Adjustment (+/-) in quantity supplied made by Coal Company	(MT)	-	-	-	-	
5	Coal supplied by Coal Company (3+4)	(MT)	4,55,393	44,299	-	67,905	
6	Normative Transit & Handling Losses	(MT)	3,643	354	-	136	
7	Net coal / Lignite Supplied (5-6)	(MT)	4,51,750	43,945	-	67,769	-
C)	PRICE						
8	Amount charged by the Coal Company	(Rs.)	1,31,11,23,795	15,37,21,880	-	99,45,45,576	
9	Adjustment (+/-) in amount charged made by Coal Company	(Rs.)	8,25,95,769	-	-	-	
10	Handling, Sampling and such other similar charges	(Rs.)	1,37,37,391	13,36,337	-	20,48,420	
11	Total amount Charged (8+9+10)	(Rs.)	1,40,74,56,955	15,50,58,217	-	99,65,93,996	
D)	TRANSPORATION						
12	Transportation charges by rail ship, road transport	(Rs.)	65,16,24,007	1,98,79,803	-	-	
13	Adjustment (+/-) in amount charged made by Railways/ Transport Company	(Rs.)	-	-	-	-	
14	Demurrage Charges, if any	(Rs.)	1,09,463	-	-	-	
15	Cost of diesel in transporting coal through MGR system, if applicable	(Rs.)	-	-	-	-	
16	Total Transportation Charges (12+13+14+15) Total amount Charged for coal supplied	(Rs.)	65,15,14,544	1,98,79,803	-	-	
17 E)	including Transportation (11+16)	(Rs.)	2,05,89,71,500	17,49,38,020	-	99,65,93,996	
18	Landed cost of coal (2+17)/(1+7)	Rs./MT	4,505	3,943	-	14,666	_
19	Blending Ratio	%	1	–	-	0	-
20	Weighted average cost of coal	Rs./MT					6,52
F)	QUALITY						
21	GCV of Domestic Coal of the opening stock as	(kCal/Kg)	4,375	4,632			
	per bill of Coal Company GCV of Domestic Coal supplied as per bill						
22	Coal Company GCV of Imported Coal of the opening stock as	(kCal/Kg)	4,383	4,601			
23	per bill of Coal Company GCV of Imported Coal supplied as per bill Coal	(kCal/Kg)				5,121	
24	Company Weighted average GCV of coal/ Lignite as	(kCal/Kg)				4,777	
25	Billed GCV of Domestic Coal of opening stock as	(kCal/Kg)		<u> </u>		<u> </u>	4,49
26	received at Station GCV of Domestic Coal supplied as received at	(kCal/Kg)	3,634	3,620			
27	Station GCV of Imported Coal of opening stock as	(kCal/Kg)	3,607	3,655		4.000	
28	received at Station GCV of Imported Coal supplied as received at	(kCal/Kg)	-	-	-	4,922	
29	Station Weighted average GCV of coal/ Lignite as	(kCal/Kg)	-	_	_	4,827	2 07
30	Received	(kCal/Kg)					3,87
						(Petition

	No. 20 A						FORM-
	Name of the Company :		NTPC Limited				
	e of the Power Station :	l lmit	Tanda Super Ther				
S. No.	Particulars	Unit			Sep-23		
NO.			Domestic Coal- FSA	Domestic Coal- NTPC Mines	E-Auction Coal	Imported Coal	Bio-Mass
A)	OPENING QUANTITY		. 5/1	1111 0 11111100			
1	Opening Quantity of Coal/ Lignite	(MT)	5,15,471	29,639	-	58,859	-
2	Value of Stock	(Rs.)	2,32,22,62,147	11,68,55,856	-	86,32,38,745	-
B)	QUANTITY						
3	Quantity of Coal supplied by Coal Company	(MT)	3,88,367	19,432	-	55,853	
4	Adjustment (+/-) in quantity supplied made by Coal Company	(MT)	-	-288	-	-	
5	Coal supplied by Coal Company (3+4)	(MT)	3,88,367	19,144	-	55,853	
6	Normative Transit & Handling Losses	(MT)	3,107	155	-	112	
7	Net coal / Lignite Supplied (5-6)	(MT)	3,85,260	18,989	-	55,742	-
C)	PRICE	,	· · ·	· ·		·	
8	Amount charged by the Coal Company	(Rs.)	1,29,08,74,526	5,22,55,566	-	79,08,85,739	
_	Adjustment (+/-) in amount charged made by						
9	Coal Company	(Rs.)	3,65,82,221	-7,21,103	-	-3,58,96,499	
10	Handling, Sampling and such other similar charges	(Rs.)	2,07,68,120	10,39,118	-	29,86,786	
11	Total amount Charged (8+9+10)	(Rs.)	1,34,82,24,867	5,25,73,581	-	75,79,76,027	
D)	TRANSPORATION						
12	Transportation charges by rail ship, road transport	(Rs.)	51,15,98,384	84,61,880	-	-	
13	Adjustment (+/-) in amount charged made by Railways/ Transport Company	(Rs.)	-	-	-	-	
14	Demurrage Charges, if any	(Rs.)	3,23,665	-	-	-	
15	Cost of diesel in transporting coal through MGR system, if applicable	(Rs.)	-	-	-	-	
16	Total Transportation Charges (12+13+14+15) Total amount Charged for coal supplied	(Rs.)	51,12,74,719	84,61,880	-	-	
17 E)	including Transportation (11+16) TOTAL COST	(Rs.)	1,85,94,99,586	6,10,35,461	-	75,79,76,027	
<u>-,</u> 18	Landed cost of coal (2+17)/(1+7)	Rs./MT	4,643	3,658	_	14,147	_
19	Blending Ratio	%	1	-	-	0	-
20	Weighted average cost of coal	Rs./MT		'	!	•	6,5
F)	QUALITY						
21	GCV of Domestic Coal of the opening stock as	(kCal/Kg)	4,379	4,617			
	per bill of Coal Company GCV of Domestic Coal supplied as per bill	((9)		.,017			-
22	Coal Company	(kCal/Kg)	4,692	4,601			
23	GCV of Imported Coal of the opening stock as per bill of Coal Company	(kCal/Kg)				4,980	
24	GCV of Imported Coal supplied as per bill Coal Company Weighted average GCV of coal/ Lignite as	(kCal/Kg)				4,763	
25	Billed GCV of Domestic Coal of opening stock as	(kCal/Kg)		1	Τ	I	4,5
26	received at Station GCV of Domestic Coal supplied as received at	(kCal/Kg)	3,616	3,671			
27 28	Station GCV of Imported Coal of opening stock as	(kCal/Kg)	3,617	3,544		4,879	
20 — 29	received at Station GCV of Imported Coal supplied as received at	(kCal/Kg) (kCal/Kg)	-		<u> </u>	4,838	
	Station Weighted average GCV of coal/ Lignite as					1,000	3,80
30		(kCal/Kg)					

	<u>ges</u>						FORM- 1
	Name of the Company :		NTPC Limited				
	e of the Power Station :		Tanda Super Ther	mal Power Station			
S. <u>No.</u>	Particulars	Unit			Oct-23		,
			Domestic Coal- FSA	Domestic Coal- NTPC Mines	E-Auction Coal	Imported Coal	Bio-Mass
A)	OPENING QUANTITY						
1	Opening Quantity of Coal/ Lignite	(MT)	3,76,643	28,627	-	10,023	-
2	Value of Stock QUANTITY	(Rs.)	1,74,86,11,468	10,47,25,977	-	14,17,85,967	-
<u>B)</u>		(NAT)	4 50 500	4.00.007		45 700	
3	Quantity of Coal supplied by Coal Company	(MT)	4,52,502	1,26,937	-	15,790	
4	Adjustment (+/-) in quantity supplied made by Coal Company	(MT)	-	-3,090	-	-	
5	Coal supplied by Coal Company (3+4)	(MT)	4,52,502	1,23,848	-	15,790	
6	Normative Transit & Handling Losses	(MT)	3,620	1,016	-	32	
7	Net coal / Lignite Supplied (5-6)	(MT)	4,48,882	1,22,832	-	15,759	-
C)	PRICE						
8	Amount charged by the Coal Company	(Rs.)	1,37,77,58,482	35,78,60,644	-	20,18,97,514	
9	Adjustment (+/-) in amount charged made by	(Rs.)	3,53,91,826	-77,41,074	_	-	
10	Coal Company Handling, Sampling and such other similar	(Rs.)	1,37,10,017	38,47,415	_	4,78,597	
1 1	charges	` ′	1.42.68.60.325				
11 D)	Total amount Charged (8+9+10) TRANSPORATION	(Rs.)	1,42,68,60,325	35,39,66,985	-	20,23,76,111	
12	Transportation charges by rail ship, road transport	(Rs.)	54,13,66,536	13,21,68,109	-	-	
13	Adjustment (+/-) in amount charged made by Railways/ Transport Company	(Rs.)	-	-	-	-	
14	Demurrage Charges, if any	(Rs.)	_	_	-	-	
15	Cost of diesel in transporting coal through MGR system, if applicable	(Rs.)	-	-	-	-	
16	Total Transportation Charges (12+13+14+15)	(Rs.)	54,13,66,536	13,21,68,109	-	-	
17	Total amount Charged for coal supplied including Transportation (11+16)	(Rs.)	1,96,82,26,861	48,61,35,094	-	20,23,76,111	
E)	TOTAL COST						
18	Landed cost of coal (2+17)/(1+7)	Rs./MT	4,502	3,901	-	13,349	-
<u> 19</u>	Blending Ratio	% D- /MT	1	0	-	0	
50	Weighted average cost of coal	Rs./MT					5,07
F)	GCV of Domestic Coal of the opening stock as			ī		1	<u> </u>
21	per bill of Coal Company	(kCal/Kg)	4,519	4,611			
22	GCV of Domestic Coal supplied as per bill Coal Company	(kCal/Kg)	4,354	4,601			
23	GCV of Imported Coal of the opening stock as per bill of Coal Company	(kCal/Kg)				4,873	
24	GCV of Imported Coal supplied as per bill Coal Company	(kCal/Kg)				4,749	
25	Weighted average GCV of coal/ Lignite as Billed	(kCal/Kg)		T		T	4,46
26	GCV of Domestic Coal of opening stock as received at Station GCV of Domestic Coal supplied as received at	(kCal/Kg)	3,634	3,684			
27	Station GCV of Imported Coal of opening stock as	(kCal/Kg)	3,757	4,084			
28	received at Station GCV of Imported Coal supplied as received at	(kCal/Kg)	-	-	-	4,859	
29	Station Weighted average GCV of coal/ Lignite as	(kCal/Kg)	-	-	-	4,927	
30	Received	(kCal/Kg)					3,80

	ges Name of the Company :		NTPC Limited				FORM-
lam	e of the Power Station :		Tanda Super Thei	mal Power Statio	n Stane-I		
S.		Unit	Tanda Guper Thei		Nov-23		
No.	Particulars				20		
			Domestic Coal- FSA	Domestic Coal- NTPC Mines	E-Auction Coal	Imported Coal	Bio-Mass
A)	OPENING QUANTITY						
1	Opening Quantity of Coal/ Lignite	(MT)	2,49,091	1,41,459	-	5,781	-
2	Value of Stock	(Rs.)	1,12,15,04,769	55,18,49,881	-	7,71,76,241	-
B)	QUANTITY						
3	Quantity of Coal supplied by Coal Company	(MT)	3,86,490	1,22,191	-	73,029	
4	Adjustment (+/-) in quantity supplied made by Coal Company	(MT)	-	-	-	-	
5	Coal supplied by Coal Company (3+4)	(MT)	3,86,490	1,22,191	-	73,029	
6	Normative Transit & Handling Losses	(MT)	3,092	978	-	146	
7	Net coal / Lignite Supplied (5-6)	(MT)	3,83,398	1,21,213	-	72,883	-
C)	PRICE						<u> </u>
8	Amount charged by the Coal Company	(Rs.)	1,24,25,65,718	33,03,42,967	-	97,46,36,535	
9	Adjustment (+/-) in amount charged made by Coal Company	(Rs.)	4,01,77,265	-	-	-4,81,84,289	
10	Handling, Sampling and such other similar charges	(Rs.)	20,69,217	5,45,725	-	3,22,777	
11	Total amount Charged (8+9+10)	(Rs.)	1,28,48,12,200	33,08,88,692	-	92,67,75,023	
D)	TRANSPORATION						<u> </u>
12	Transportation charges by rail ship, road transport	(Rs.)	51,44,04,242	14,91,76,125	-	-	
13	Adjustment (+/-) in amount charged made by Railways/ Transport Company	(Rs.)	-	-	-	-	
14	Demurrage Charges, if any	(Rs.)	67,725	-	-	-	
15	Cost of diesel in transporting coal through MGR system, if applicable	(Rs.)	-	-	-	-	
16	Total Transportation Charges (12+13+14+15) Total amount Charged for coal supplied	(Rs.)	51,43,36,517	14,91,76,125	-	-	
17 E)	including Transportation (11+16) TOTAL COST	(Rs.)	1,79,91,48,718	48,00,64,817	-	92,67,75,023	
<u>-,</u> 18	Landed cost of coal (2+17)/(1+7)	Rs./MT	4,618	3,929	_	12,762	_
19	Blending Ratio	%	1	0	-	0	-
20	Weighted average cost of coal	Rs./MT		'		•	5,7
F)	QUALITY						
21	GCV of Domestic Coal of the opening stock as	(kCal/Kg)	4,430	4,603			
22	per bill of Coal Company GCV of Domestic Coal supplied as per bill	(kCal/Kg)	4,206	3,763			
	Coal Company	- 37	,	.,			
23	GCV of Imported Coal of the opening stock as per bill of Coal Company	(kCal/Kg)				4,793	
24	GCV of Imported Coal supplied as per bill Coal Company	(kCal/Kg)				4,614	
25	Weighted average GCV of coal/ Lignite as Billed	(kCal/Kg)		ı	1	T	4,3
26	GCV of Domestic Coal of opening stock as received at Station GCV of Domestic Coal supplied as received at	(kCal/Kg)	3,779	4,083			
27	Station GCV of Imported Coal of opening stock as	(kCal/Kg)	3,599	3,567			
28	received at Station GCV of Imported Coal supplied as received at	(kCal/Kg)	-	-	-	4,903	
29	Station Weighted average GCV of coal/ Lignite as	(kCal/Kg)	-	-	-	4,764	
30	Received	(kCal/Kg)					3,8

	ils of Source wise Fuel for Computation of Er	nergy					PART-I
Char	Name of the Company :		NTPC Limited				FORM- 15
Nam	e of the Power Station :			mal Power Station	Stage-I		
S. No.	Particulars	Unit	·		ec-23		
NO.			Domestic Coal- FSA	Domestic Coal- NTPC Mines	E-Auction Coal	Imported Coal	Bio-Mass
A)	OPENING QUANTITY						
1	Opening Quantity of Coal/ Lignite	(MT)	2,64,558	1,34,530	-	4,794	
2	Value of Stock	(Rs.)	1,18,64,70,242	61,78,29,364	-	6,11,76,888	-
B)	QUANTITY						
3	Quantity of Coal supplied by Coal Company	(MT)	3,25,961	3,89,891	-	81,240	-
4	Adjustment (+/-) in quantity supplied made by Coal Company	(MT)	-	-8,799	-	-	-
5	Coal supplied by Coal Company (3+4)	(MT)	3,25,961	3,81,092	-	81,240	-
6	Normative Transit & Handling Losses	(MT)	2,608	3,119	-	162	-
7	Net coal / Lignite Supplied (5-6)	(MT)	3,23,354	3,77,973	-	81,078	-
C)	PRICE						
8	Amount charged by the Coal Company	(Rs.)	91,16,80,500	1,03,79,37,938	-	1,10,52,47,846	-
9	Adjustment (+/-) in amount charged made by Coal Company	(Rs.)	6,09,82,798	-2,20,95,157	-	-1,67,95,374	-
10	Handling, Sampling and such other similar charges	(Rs.)	1,14,47,450	1,21,33,363	-	25,28,192	-
11	Total amount Charged (8+9+10)	(Rs.)	98,41,10,748	1,02,79,76,143	-	1,09,09,80,664	-
D)	TRANSPORATION						
12	Transportation charges by rail ship, road transport	(Rs.)	36,97,15,702	47,35,18,930	-	-	-
13	Adjustment (+/-) in amount charged made by Railways/ Transport Company	(Rs.)	-	-	-	-	-
14	Demurrage Charges, if any	(Rs.)	92,454	-	-	-	-
15	Cost of diesel in transporting coal through MGR system, if applicable	(Rs.)	-	-	-	-	-
16	Total Transportation Charges (12+13+14+15)	(Rs.)	36,96,23,248	47,35,18,930	-	-	-
17	Total amount Charged for coal supplied including Transportation (11+16)	(Rs.)	1,35,37,33,997	1,50,14,95,074	-	1,09,09,80,664	-
E)	TOTAL COST						
18	Landed cost of coal (2+17)/(1+7)	Rs./MT	4,321	4,135	-	13,417	-
19	Blending Ratio Weighted average cost of coal	% Do /MT	1	0	-	0	6,107
20 E \		Rs./MT	<u> </u>				6,107
F) 21	GCV of Domestic Coal of the opening stock as per bill of Coal Company	(kCal/Kg)	4,294	4,223			
22	GCV of Domestic Coal supplied as per bill Coal Company	(kCal/Kg)	3,959	4,051			
23	GCV of Imported Coal of the opening stock as per bill of Coal Company	(kCal/Kg)				4,625	
24	GCV of Imported Coal supplied as per bill Coal Company	(kCal/Kg)				4,632	
25	Weighted average GCV of coal/ Lignite as Billed	(kCal/Kg)		I	1	I	4,212
26	GCV of Domestic Coal of opening stock as received at Station	(kCal/Kg)	3,761	4,001			
27	GCV of Domestic Coal supplied as received at Station	(kCal/Kg)	3,487	3,728			
28	GCV of Imported Coal of opening stock as received at Station	(kCal/Kg)	-	-	-	4,772	-
29	GCV of Imported Coal supplied as received at Station	(kCal/Kg)	-	-	-	4,849	-
30	Weighted average GCV of coal/ Lignite as Received	(kCal/Kg)		1		1	3,874
			61			(1	Petitioner)

61

Jiidi	rges		NTDOLLER				FORM- 1
	Name of the Company :	ı	NTPC Limited		<u> </u>		
	e of the Power Station :	Unit	Tanda Super Ther	mal Power Station			
S. No.	Particulars	Unit		•	Jan-24		
NO.			Domestic Coal- FSA	Domestic Coal- NTPC Mines	E-Auction Coal	Imported Coal	Bio-Mass
A)	OPENING QUANTITY						
1	Opening Quantity of Coal/ Lignite	(MT)	1,69,761	4,01,530	-	11,733	-
2	Value of Stock	(Rs.)	73,34,90,014	1,66,04,27,585	-	15,74,30,224	-
B)	QUANTITY						
3	Quantity of Coal supplied by Coal Company	(MT)	4,38,552	1,95,038	-	1,05,835	
4	Adjustment (+/-) in quantity supplied made by Coal Company	(MT)	-	-7,924	-	-	
5	Coal supplied by Coal Company (3+4)	(MT)	4,38,552	1,87,113	-	1,05,835	
6	Normative Transit & Handling Losses	(MT)	3,508	1,497	-	212	
7	Net coal / Lignite Supplied (5-6)	(MT)	4,35,044	1,85,616	-	1,05,623	-
C)	PRICE						
8	Amount charged by the Coal Company	(Rs.)	1,34,13,38,526	53,63,93,236	-	1,50,21,49,957	
_	Adjustment (+/-) in amount charged made by	(D)	0.00.05.005	4.00.74.400			
9	Coal Company	(Rs.)	2,98,35,335	-1,98,74,423	-	-	
10	Handling, Sampling and such other similar charges	(Rs.)	1,50,96,858	67,24,121	-	36,48,756	
11	Total amount Charged (8+9+10)	(Rs.)	1,38,62,70,720	52,32,42,933	-	1,50,57,98,713	
D)	TRANSPORATION						
12	Transportation charges by rail ship, road transport	(Rs.)	60,62,79,320	22,25,98,609	-	-	
13	Adjustment (+/-) in amount charged made by Railways/ Transport Company	(Rs.)	-	-	-	-	
14	Demurrage Charges, if any	(Rs.)	2,08,846	-	-	-	
15	Cost of diesel in transporting coal through MGR system, if applicable	(Rs.)	-	-	-	-	
16	Total Transportation Charges (12+13+14+15)	(Rs.)	60,60,70,474	22,25,98,609	-	-	
17	Total amount Charged for coal supplied including Transportation (11+16)	(Rs.)	1,99,23,41,194	74,58,41,542	-	1,50,57,98,713	
<u>E)</u> 18	TOTAL COST Landed cost of coal (2+17)/(1+7)	Rs./MT	4,507	4,098		14,172	
19	Blending Ratio	%	4,507	4,036	-	14,172	_
	Weighted average cost of coal	Rs./MT	<u>'</u>				6,31
F)	QUALITY	1.00,,,,,,					
21	GCV of Domestic Coal of the opening stock as per bill of Coal Company	(kCal/Kg)	4,105	4,102			
22	GCV of Domestic Coal supplied as per bill Coal Company	(kCal/Kg)	4,251	4,269			
23	GCV of Imported Coal of the opening stock as per bill of Coal Company	(kCal/Kg)				4,632	
24	GCV of Imported Coal supplied as per bill Coal Company	(kCal/Kg)				4,635	
25	Weighted average GCV of coal/ Lignite as Billed	(kCal/Kg)			1	T	4,27
26	GCV of Domestic Coal of opening stock as received at Station	(kCal/Kg)	3,620	3,843			
27	GCV of Domestic Coal supplied as received at Station GCV of Imported Coal of opening stock as	(kCal/Kg)	3,516	3,715			
28	received at Station GCV of Imported Coal supplied as received at	(kCal/Kg)	-	-	-	4,887	
29	Station Weighted average GCV of coal/ Lignite as	(kCal/Kg)	-	-	-	4,831	0.0=
30	Received	(kCal/Kg)					3,87
							Petitione

Detai Char	ils of Source wise Fuel for Computation of Er	nergy					PART-I FORM- 15
Onai	Name of the Company :		NTPC Limited				I OKWI- 13
Nam	e of the Power Station :			mal Power Station	Stage-I		
S. No.	Particulars	Unit		Fe	eb-24		
110.			Domestic Coal- FSA	Domestic Coal- NTPC Mines	E-Auction Coal	Imported Coal	Bio-Mass
A)	OPENING QUANTITY						
1	Opening Quantity of Coal/ Lignite	(MT)	3,31,989	4,27,149	-	46,946	-
2 B)	Value of Stock QUANTITY	(Rs.)	1,49,62,59,863	1,75,05,58,604	-	66,53,34,039	-
3	Quantity of Coal supplied by Coal Company	(MT)	4,27,290	1,74,661	_	16,333	_
	Adjustment (+/-) in quantity supplied made by		4,21,230		_	10,333	_
4	Coal Company	(MT)	-	-3,201	-	-	-
5	Coal supplied by Coal Company (3+4)	(MT)	4,27,290	1,71,460	-	16,333	-
	Normative Transit & Handling Losses	(MT)	3,418	1,372	-	33	-
7 C)	Net coal / Lignite Supplied (5-6) PRICE	(MT)	4,23,872	1,70,088	-	16,300	-
8	Amount charged by the Coal Company	(Rs.)	1,36,04,52,008	45,18,56,373	-	23,21,10,457	-
9	Adjustment (+/-) in amount charged made by Coal Company	(Rs.)	19,12,508	-78,49,445	-	-3,68,07,697	-
10	Handling, Sampling and such other similar	(Rs.)	1,65,65,951	60,24,059	-	5,63,311	-
11	charges Total amount Charged (8+9+10)	(Rs.)	1,37,89,30,467	45,00,30,987	_	19,58,66,071	_
D)	TRANSPORATION	(113.)	1,57,09,50,407	+5,00,50,867	_	19,00,00,071	_
12	Transportation charges by rail ship, road transport	(Rs.)	61,75,51,154	23,25,49,203	-	-	-
13	Adjustment (+/-) in amount charged made by Railways/ Transport Company	(Rs.)	-	-	-	-	-
14	Demurrage Charges, if any	(Rs.)	2,27,432	_	_	_	_
	Cost of diesel in transporting coal through	,	2,21,432	_	_	_	_
15	MGR system, if applicable	(Rs.)	-	-	-	-	-
16	Total Transportation Charges (12+13+14+15)	(Rs.)	61,73,23,722	23,25,49,203	-	-	-
17	Total amount Charged for coal supplied including Transportation (11+16)	(Rs.)	1,99,62,54,189	68,25,80,190	-	19,58,66,071	-
E)	TOTAL COST						
	Landed cost of coal (2+17)/(1+7)	Rs./MT	4,621	4,074	-	13,617	-
19	Blending Ratio	%	1	0	-	0	-
20	Weighted average cost of coal	Rs./MT					6,079
F)	GCV of Domestic Coal of the opening stock as			1	1	<u> </u>	I
21	per bill of Coal Company	(kCal/Kg)	4,214	4,152			
22	GCV of Domestic Coal supplied as per bill Coal Company	(kCal/Kg)	3,902	4,151			
23	GCV of Imported Coal of the opening stock as per bill of Coal Company	(kCal/Kg)				4,635	
24	GCV of Imported Coal supplied as per bill Coal Company	(kCal/Kg)				4,901	
25	Weighted average GCV of coal/ Lignite as Billed	(kCal/Kg)					4,192
26	GCV of Domestic Coal of opening stock as received at Station	(kCal/Kg)	3,639	3,843			
27	GCV of Domestic Coal supplied as received at Station	(kCal/Kg)	3,131	3,555			
28	GCV of Imported Coal of opening stock as received at Station	(kCal/Kg)	-	-	-	4,924	-
29	GCV of Imported Coal supplied as received at Station	(kCal/Kg)	-	-	-	4,964	-
30	Weighted average GCV of coal/ Lignite as Received	(kCal/Kg)		I	l	I	3,759
			63			(I	Petitioner)

supplied by Coal Company (3+4) native Transit & Handling Losses coal / Lignite Supplied (5-6) E unt charged by the Coal Company stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(MT) (Rs.) (MT) (MT) (MT) (MT) (Rs.) (Rs.) (Rs.) (Rs.)	Domestic Coal- FSA 4,38,732 2,02,71,94,454 5,51,675 - 5,51,675 4,413 5,47,262 2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	Domestic Coal- NTPC Mines 4,01,270 1,63,47,71,000 1,40,572 -2,543 1,38,029 1,104 1,36,925 33,28,08,265 -64,02,571 81,90,125 33,45,95,819	E-Auction Coal	S,235	Bio-Mass
NING QUANTITY ning Quantity of Coal/ Lignite e of Stock NTITY nitity of Coal supplied by Coal Company stment (+/-) in quantity supplied made by Company supplied by Coal Company (3+4) native Transit & Handling Losses coal / Lignite Supplied (5-6) E unt charged by the Coal Company stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges l amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(MT) (Rs.) (MT) (MT) (MT) (MT) (MT) (Rs.) (Rs.) (Rs.)	Domestic Coal- FSA 4,38,732 2,02,71,94,454 5,51,675 - 5,51,675 4,413 5,47,262 2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	Domestic Coal- NTPC Mines 4,01,270 1,63,47,71,000 1,40,572 -2,543 1,38,029 1,104 1,36,925 33,28,08,265 -64,02,571 81,90,125	E-Auction Coal	5,235 7,12,78,187	350 350 40,68,569
NING QUANTITY ning Quantity of Coal/ Lignite e of Stock INTITY nitity of Coal supplied by Coal Company stment (+/-) in quantity supplied made by Company supplied by Coal Company (3+4) native Transit & Handling Losses coal / Lignite Supplied (5-6) EE unt charged by the Coal Company stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(MT) (Rs.) (MT) (MT) (MT) (MT) (MT) (Rs.) (Rs.) (Rs.)	4,38,732 2,02,71,94,454 5,51,675 - 5,51,675 4,413 5,47,262 2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	Domestic Coal- NTPC Mines 4,01,270 1,63,47,71,000 1,40,572 -2,543 1,38,029 1,104 1,36,925 33,28,08,265 -64,02,571 81,90,125	E-Auction Coal	5,235 7,12,78,187	350 350 40,68,569
ning Quantity of Coal/ Lignite e of Stock INTITY Intity of Coal supplied by Coal Company stment (+/-) in quantity supplied made by Company supplied by Coal Company (3+4) native Transit & Handling Losses coal / Lignite Supplied (5-6) E unt charged by the Coal Company stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(Rs.) (MT) (MT) (MT) (MT) (MT) (Rs.) (Rs.) (Rs.)	4,38,732 2,02,71,94,454 5,51,675 - 5,51,675 4,413 5,47,262 2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	1,40,572 -2,543 1,38,029 1,104 1,36,925 33,28,08,265 -64,02,571 81,90,125		5,235 7,12,78,187	35 35 35 40,68,56
ning Quantity of Coal/ Lignite e of Stock INTITY Intity of Coal supplied by Coal Company stment (+/-) in quantity supplied made by Company supplied by Coal Company (3+4) native Transit & Handling Losses coal / Lignite Supplied (5-6) E unt charged by the Coal Company stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(Rs.) (MT) (MT) (MT) (MT) (MT) (Rs.) (Rs.) (Rs.)	2,02,71,94,454 5,51,675 - 5,51,675 4,413 5,47,262 2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	1,63,47,71,000 1,40,572 -2,543 1,38,029 1,104 1,36,925 33,28,08,265 -64,02,571 81,90,125	-	7,12,78,187	356 356 40,68,569
e of Stock INTITY Intity of Coal supplied by Coal Company Intity of Coal supplied by Coal Company Intity of Coal supplied by Coal Company Intity of Coal Supplied made by Intity of Coal Company (3+4) Intity of Coal Company (3+6) Intity of Coal Company Intity of Coal Coal Coal Coal Coal Coal Coal Coal	(Rs.) (MT) (MT) (MT) (MT) (MT) (Rs.) (Rs.) (Rs.)	2,02,71,94,454 5,51,675 - 5,51,675 4,413 5,47,262 2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	1,63,47,71,000 1,40,572 -2,543 1,38,029 1,104 1,36,925 33,28,08,265 -64,02,571 81,90,125	-	7,12,78,187	35 35 35 40,68,56
Intity of Coal supplied by Coal Company Intity of Coal supplied by Coal Company Intity of Coal supplied by Coal Company Intity of Coal supplied made by Intity of Coal Company (3+4) Intity of Coal Company (3+6) Intity of Coal Company Intity of Coal Coal Company Intity of Coal Coal Coal Coal Coal Coal Coal Coal	(MT) (MT) (MT) (MT) (MT) (Rs.) (Rs.) (Rs.)	5,51,675 5,51,675 4,413 5,47,262 2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	1,40,572 -2,543 1,38,029 1,104 1,36,925 33,28,08,265 -64,02,571 81,90,125	-	-	35 35 35 40,68,56
ntity of Coal supplied by Coal Company stment (+/-) in quantity supplied made by Company supplied by Coal Company (3+4) native Transit & Handling Losses coal / Lignite Supplied (5-6) E unt charged by the Coal Company stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(MT) (MT) (MT) (MT) (Rs.) (Rs.) (Rs.)	5,51,675 4,413 5,47,262 2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	-2,543 1,38,029 1,104 1,36,925 33,28,08,265 -64,02,571 81,90,125	-	- - - - -12,52,724	35 35 40,68,56
stment (+/-) in quantity supplied made by Company supplied by Coal Company (3+4) native Transit & Handling Losses coal / Lignite Supplied (5-6) E unt charged by the Coal Company stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(MT) (MT) (MT) (MT) (Rs.) (Rs.) (Rs.)	5,51,675 4,413 5,47,262 2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	-2,543 1,38,029 1,104 1,36,925 33,28,08,265 -64,02,571 81,90,125	-	- - - - -12,52,724	35 35 40,68,56
Company supplied by Coal Company (3+4) mative Transit & Handling Losses coal / Lignite Supplied (5-6) E unt charged by the Coal Company stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(MT) (MT) (MT) (Rs.) (Rs.) (Rs.) (Rs.)	4,413 5,47,262 2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	1,38,029 1,104 1,36,925 33,28,08,265 -64,02,571 81,90,125	-	- - - -12,52,724	35 40,68,56
native Transit & Handling Losses coal / Lignite Supplied (5-6) E unt charged by the Coal Company stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(MT) (MT) (Rs.) (Rs.) (Rs.)	4,413 5,47,262 2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	1,104 1,36,925 33,28,08,265 -64,02,571 81,90,125	-	-12,52,724	35 40,68,56
coal / Lignite Supplied (5-6) EE unt charged by the Coal Company stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(MT) (Rs.) (Rs.) (Rs.) (Rs.)	5,47,262 2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	1,36,925 33,28,08,265 -64,02,571 81,90,125	-	-12,52,724	40,68,56
unt charged by the Coal Company stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(Rs.) (Rs.) (Rs.) (Rs.)	2,08,61,25,292 39,81,855 3,21,42,112 2,12,22,49,259	33,28,08,265 -64,02,571 81,90,125	-	-12,52,724	40,68,56
unt charged by the Coal Company stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(Rs.) (Rs.) (Rs.)	39,81,855 3,21,42,112 2,12,22,49,259	-64,02,571 81,90,125	-	-12,52,724	
stment (+/-) in amount charged made by Company dling, Sampling and such other similar ges I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(Rs.) (Rs.) (Rs.)	39,81,855 3,21,42,112 2,12,22,49,259	-64,02,571 81,90,125	-	-12,52,724	
Company dling, Sampling and such other similar ges l amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	(Rs.) (Rs.)	3,21,42,112 2,12,22,49,259	81,90,125	-	-12,52,724	20 41
ges I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by ways/ Transport Company	(Rs.)	2,12,22,49,259		-	-	20 41
I amount Charged (8+9+10) NSPORATION sportation charges by rail ship, road sport stment (+/-) in amount charged made by vays/ Transport Company	,		33,45,95,819			20,41
sportation charges by rail ship, road sport street (+/-) in amount charged made by ways/ Transport Company	(Rs.)	77.44.44.040		-	-12,52,724	40,88,98
sport stment (+/-) in amount charged made by vays/ Transport Company	(Rs.)	77 44 44 040				
vays/ Transport Company		77,14,41,942	22,46,33,383	-	-	
Ol if	(Rs.)	-	-	-	-	
urrage Charges, if any	(Rs.)	3,47,292	-	-	-	
of diesel in transporting coal through	(Rs.)	-	-	-	-	
Transportation Charges (12+13+14+15)	(Rs.)	77,10,94,650	22,46,33,383	-	-	
l amount Charged for coal supplied ding Transportation (11+16)	(Rs.)	2,89,33,43,909	55,92,29,202	-	-12,52,724	40,88,98
AL COST						
			 	-		11,66
		1	-	-	0	5,78
	KS./WH	+				5,70
of Domestic Coal of the opening stock as	(kCal/Kg)	4,036	4,152			
of Domestic Coal supplied as per bill	(kCal/Kg)	4,601	3,783			3,41
of Imported Coal of the opening stock as	(kCal/Kg)				4,706	
of Imported Coal supplied as per bill Coal	(kCal/Kg)					
party ghted average GCV of coal/ Lignite as	(kCal/Kg)		1	I	1	4,37
of Domestic Coal of opening stock as ved at Station	(kCal/Kg)	3,406	3,776			
of Domestic Coal supplied as received at on	(kCal/Kg)	3,731	3,624			3,41
of Imported Coal of opening stock as ved at Station	(kCal/Kg)	-	-	-	4,935	
on	(kCal/Kg)	-	-	-		
ghted average GCV of coal/ Lignite as eived	(kCal/Kg)					3,70
	ed cost of coal (2+17)/(1+7) ing Ratio Inted average cost of coal LITY of Domestic Coal of the opening stock as II of Coal Company of Domestic Coal supplied as per bill Company of Imported Coal of the opening stock as II of Coal Company of Imported Coal supplied as per bill Coal supplied as received at Station of Domestic Coal of opening stock as red at Station of Imported Coal of opening stock as red at Station of Imported Coal of opening stock as red at Station of Imported Coal supplied as received at In Imported Coal supplied as received at In Intel average GCV of coal/ Lignite as	red cost of coal (2+17)/(1+7) ring Ratio Rs./MT ring Ratio Rs./MT Rs./MT ITY of Domestic Coal of the opening stock as II of Coal Company of Domestic Coal supplied as per bill Company of Imported Coal of the opening stock as II of Coal Company of Imported Coal supplied as per bill Coal ring red average GCV of coal/ Lignite as red at Station of Domestic Coal supplied as received at In of Imported Coal of opening stock as red at Station of Imported Coal of opening stock as red at Station of Imported Coal of opening stock as red at Station of Imported Coal of opening stock as red at Station of Imported Coal of opening stock as red at Station of Imported Coal of opening stock as red at Station of Imported Coal supplied as received at In Of Imported Coal Supplied Imported Coa	ed cost of coal (2+17)/(1+7) Ing Ratio Inted average cost of coal Interval of Domestic Coal of the opening stock as II of Coal Company II of Imported Coal supplied as per bill Coal II of Coal Company II of Imported Coal of opening stock as II of Coal Coal II opening stock as II of Coal Coal II opening stock as II of Coal Coal II opening stock as II of Imported Coal of opening stock as II of Imported Coal of opening stock as II of Imported Coal Supplied as received at In In II of Imported Coal Supplied as received at In II of Imported Coal Supplied as received at In II of Imported Coal Supplied as received at In II of Imported Coal Supplied as received at In II of Imported Coal Supplied as received at In II of Imported Coal Supplied as received at In II of Imported Coal Supplied as received at In II of Imported Coal Supplied as received at In II of Imported Coal Supplied as received at In II of II	ed cost of coal (2+17)/(1+7) Ing Ratio Inted average cost of coal ITY of Domestic Coal of the opening stock as II of Coal Company of Domestic Coal supplied as per bill Company of Imported Coal of the opening stock as II of Coal Company of Imported Coal supplied as per bill Company of Imported Coal supplied as per bill Coal It of Coal Company of Imported Coal supplied as per bill Coal It of Coal Company of Imported Coal supplied as per bill Coal It of Coal Company of Imported Coal supplied as per bill Coal It of Coal Company of Imported Coal supplied as per bill Coal It of Coal/Kg) It coal/Kg	ed cost of coal (2+17)/(1+7) ing Ratio % 1	ed cost of coal (2+17)/(1+7)

				FORM- 15/	
	of Secondary Fuel for Computation of Energy Charges	<u> </u>			
Name o	f the Company		NTPC Limited		
Name o	f the Power Station		I .	per Thermal Power	
141110 0	This i ower station		Station S	tage-l	
				Amount in R	
SI.No.	Month	Unit		Apr-23	
			HFO	LDO	
1	Opening Quantity of Oil	KL	0	4,980.1	
2	Value of Opening	(Rs)	_	43,49,02,434.4	
3	Quantity of Oil supplied by Oil Company	KL	-	3,034.91	
4	Adjustment (+/-) in quantity supplied made by Oil Company	KL		· · · · · · · · · · · · · · · · · · ·	
5	Oil supplied by oil company (3+4)	KL	-	3,034.91	
6	Normative Transit & Handling Losses	KL	_	,	
7	Net Oil Supplied (5-6)	KL	_	3,034.91	
8	Amount charged by the Oil Company	(Rs)	_	23,06,12,622.00	
	Adjustment(+/-) in amount charged made by Oil Company	(111)			
9		(Rs)	_		
10	Handling, Sampling and such other Similar Charges	(Rs)	-		
11	Total amount charged (8+9+10)	(Rs)	-	23,06,12,622.00	
12	Transportation charges by rail / ship / road transport				
	By Rail	(Rs)	-		
	By Road	(Rs)	-		
	By Ship	(Rs)	_		
	Adjustment (+/-) in amount charged made by	, ,			
13	Railways/Transport Company	(Rs)	-		
14	Demurrage Charges, if any	(Rs)	-		
	Cost of diesel in transporting Oil through MGR system, if				
15	applicable	(Rs)	-		
16	Total Transportation Charges (12+/-13-14+15)	(Rs)	-	-	
	Total amount Charged for fuel supplied including			22.06.42.622.00	
17	Transportation (11+16)	(Rs)	-	23,06,12,622.00	
18	Landed Cost of Oil (LDO/HFO) (2+17)/(1+7)	(Rs)		83,033.31	
19	Blending Ratio		-	100%	
20	Weighted average cost of Secondary Fuel/ For Month	(kCal/Ltr)		83033.31	
	GCV of Oil of the Opening stock as per bill of Oil company				
21		(kCal/Ltr)			
22	GCV of oil supplied as per bill of oil company	(kCal/Ltr)			
	GCV if Imported coal of the opening stock as per bill of Oil				
23	company	(kCal/Ltr)			
24	GCV of Imported Oil supplied as per bill of coal company	(kCal/Ltr)			
25	Weighted average GCV if Oil as billed	(kCal/Ltr)			
26	GCV of Oil of the Opening stock as received at station	(kCal/Ltr)			
27	GCV of Oil supplied	(kCal/Ltr)			
	GCV of Imported coal of the Opening stock as received at	1			
28	station	(kCal/Ltr)			
29	GCV of Imported coal supplied as received at station	(kCal/Ltr)		0000.00	
30	Weighted Average GCV of Secondary Fuel/ as recevied	(kCal/Ltr)		9380.00	

			PART FORM- 15		
etails (of Secondary Fuel for Computation of Energy Charges	<u> </u>	1		
	f the Company		NTPC Lin	nited	
			Tanda Super Thermal Pow Station Stage-I		
iame of	f the Power Station				
				Amount in F	
SI.No.	Month	Unit		May-23	
			HFO	LDO	
1	Opening Quantity of Oil	KL	 •	7,470.03	
2	Value of Opening	(Rs)		62,02,61,901.95	
3	Quantity of Oil supplied by Oil Company	KL (N3)		02,02,01,001.00	
4	Adjustment (+/-) in quantity supplied made by Oil Company	KL		_	
5	Oil supplied by oil company (3+4)	KL		_	
6	Normative Transit & Handling Losses	KL			
7	Net Oil Supplied (5-6)	KL			
8	Amount charged by the Oil Company	(Rs)			
0	Adjustment(+/-) in amount charged made by Oil Company	(1\5)	1	-	
9	Adjustitient(17-) in amount charged made by Oil Company	(Rs)			
10	Handling, Sampling and such other Similar Charges	(Rs)			
11	Total amount charged (8+9+10)	(Rs)		_	
12	Transportation charges by rail / ship / road transport	(113)		-	
12	By Rail	(Rs)			
	By Road	(Rs)			
	By Ship	(Rs)			
	Adjustment (+/-) in amount charged made by	(1/5)			
13	Railways/Transport Company	(Rs)			
14	Demurrage Charges, if any	(Rs)			
17	Cost of diesel in transporting Oil through MGR system, if	(113)			
15	applicable	(Rs)			
16	Total Transportation Charges (12+/-13-14+15)	(Rs)	_	_	
	Total amount Charged for fuel supplied including	(1.1.)			
17	Transportation (11+16)	(Rs)	-	-	
18	Landed Cost of Oil (LDO/HFO) (2+17)/(1+7)	(Rs)		83,033.3	
19	Blending Ratio	()	-	100	
20	Weighted average cost of Secondary Fuel/ For Month	(kCal/Ltr)		83033.31	
	GCV of Oil of the Opening stock as per bill of Oil company	(1100111211)		1	
21		(kCal/Ltr)			
22	GCV of oil supplied as per bill of oil company	(kCal/Ltr)			
	GCV if Imported coal of the opening stock as per bill of Oil				
23	company	(kCal/Ltr)			
24	GCV of Imported Oil supplied as per bill of coal company	(kCal/Ltr)			
25	Weighted average GCV if Oil as billed	(kCal/Ltr)			
26	GCV of Oil of the Opening stock as received at station	(kCal/Ltr)			
27	GCV of Oil supplied	(kCal/Ltr)			
	GCV of Imported coal of the Opening stock as received at				
28	station	(kCal/Ltr)			
29	GCV of Imported coal supplied as received at station	(kCal/Ltr)			
30	Weighted Average GCV of Secondary Fuel/ as recevied	(kCal/Ltr)		9380.00	
			I		

Name of the Company Name of the Power Station SI.No.		NTPC Lin		
SI.No. Month 1 Opening Quantity of Oil 2 Value of Opening 3 Quantity of Oil supplied by Oil Company 4 Adjustment (+/-) in quantity supplied made by Oil Company 5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 GCV if Imported Coal of the opening stock as per bill of Oil company 22 GCV of Imported Oil supplied as per bill of coal company 23 Weighted average GCV if Oil as billed				
SI.No. Month 1 Opening Quantity of Oil 2 Value of Opening 3 Quantity of Oil supplied by Oil Company 4 Adjustment (+/-) in quantity supplied made by Oil Company 5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 GCV if Imported coal of the opening stock as per bill of Oil company 22 GCV of Imported Oil supplied as per bill of coal company 23 Weighted average GCV if Oil as billed		Tanda Sı	mited	
SI.No. Month 1 Opening Quantity of Oil 2 Value of Opening 3 Quantity of Oil supplied by Oil Company 4 Adjustment (+/-) in quantity supplied made by Oil Company 5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 GCV if Imported coal of the opening stock as per bill of Oil company 22 GCV of Imported Oil supplied as per bill of coal company 23 Weighted average GCV if Oil as billed		Tanda Super Thermal Power Station Stage-I		
1 Opening Quantity of Oil 2 Value of Opening 3 Quantity of Oil supplied by Oil Company 4 Adjustment (+/-) in quantity supplied made by Oil Company 5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported Coal of the opening stock as per bill of Oil company GCV if Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed				
1 Opening Quantity of Oil 2 Value of Opening 3 Quantity of Oil supplied by Oil Company 4 Adjustment (+/-) in quantity supplied made by Oil Company 5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported Coal of the opening stock as per bill of Oil company GCV if Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed	1		Amount in F	
2 Value of Opening 3 Quantity of Oil supplied by Oil Company 4 Adjustment (+/-) in quantity supplied made by Oil Company 5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV if Imported Oil supplied as per bill of coal company 9 Veighted average GCV if Oil as billed	Unit		Jun-23	
2 Value of Opening 3 Quantity of Oil supplied by Oil Company 4 Adjustment (+/-) in quantity supplied made by Oil Company 5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company 22 GCV of Imported Oil supplied as per bill of coal company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed		HFO	LDO	
2 Value of Opening 3 Quantity of Oil supplied by Oil Company 4 Adjustment (+/-) in quantity supplied made by Oil Company 5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company 22 GCV of Imported Oil supplied as per bill of coal company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	KL		6,404.0	
3 Quantity of Oil supplied by Oil Company 4 Adjustment (+/-) in quantity supplied made by Oil Company 5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV if Imported Coil supplied as per bill of coal company Weighted average GCV if Oil as billed	(Rs)		53,17,48,392.4	
4 Adjustment (+/-) in quantity supplied made by Oil Company 5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	KL	_	-	
5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 GCV of Imported Coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	KL			
6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 GCV of Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed	KL	_	 	
7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company 23 COV of Imported Oil supplied as per bill of coal company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	KL	<u> </u>		
Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company 23 COV of Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed	KL	<u> </u>	_	
Adjustment(+/-) in amount charged made by Oil Company Handling, Sampling and such other Similar Charges Total amount charged (8+9+10) Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV of Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed	(Rs)	<u> </u>	 -	
9 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company 23 GCV of Imported Oil supplied as per bill of coal company 24 GCV of Imported Oil supplied as per bill of coal company	(113)		+	
Total amount charged (8+9+10) Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV of Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed	(Rs)			
Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed	(Rs)			
12 Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if 15 applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	(Rs)	_	_	
By Rail By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if 15 applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	(.15)			
By Road By Ship Adjustment (+/-) in amount charged made by 13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if 15 applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	(Rs)			
By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV if Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed	(Rs)			
Adjustment (+/-) in amount charged made by Railways/Transport Company Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV of Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed	(Rs)			
13 Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if 15 applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	(110)			
Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV if Imported Coal of the opening stock as per bill of Oil company Weighted average GCV if Oil as per bill of coal company Weighted average GCV if Oil as billed	(Rs)			
Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company COV of Oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV of Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed	(Rs)			
15 applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	(.15)			
Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed	(Rs)			
Total amount Charged for fuel supplied including Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed	(Rs)	-	_	
17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed				
18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	(Rs)	-	-	
19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	(Rs)		83,033.3	
20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company 23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed		-	100	
GCV of Oil of the Opening stock as per bill of Oil company 21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed	(kCal/Ltr)		83033.31	
21 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed		Ì	T	
GCV if Imported coal of the opening stock as per bill of Oil company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	(kCal/Ltr)			
23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed	(kCal/Ltr)			
 GCV of Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed 				
25 Weighted average GCV if Oil as billed	(kCal/Ltr)			
	(kCal/Ltr)			
26 GCV of Oil of the Opening stock as received at station	(kCal/Ltr)			
20 00 00 00 00 00 00 00 00 00 00 00 00 0	(kCal/Ltr)			
27 GCV of Oil supplied	(kCal/Ltr)			
GCV of Imported coal of the Opening stock as received at				
28 station	(kCal/Ltr)	<u> </u>		
29 GCV of Imported coal supplied as received at station	(kCal/Ltr)			
30 Weighted Average GCV of Secondary Fuel/ as recevied	(kCal/Ltr)		9380.00	

SI.No. Month Unit	PART- RM- 15					
SI.No. Month Unit Jul-23					of Secondary Fuel for Computation of Energy Charges	Details o
SI.No. Month Unit Jul-23		ited	NTPC Lim	-		
Station Stage	I Powe	per Therma	Tanda Sup			
SI.No. Month		age-l	Station St		i the Fower Station	vallie Oi
Net	unt in F	Amo				
1		Jul-23		Unit	Month	SI.No.
2)	LDC	HFO			
2	5,933.0	5		KL	Opening Quantity of Oil	1
3 Quantity of Oil supplied by Oil Company						2
Adjustment (+/-) in quantity supplied made by Oil Company 5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 (Rs) 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport 13 By Rail 14 By Road 15 By Road 16 By Ship 17 Adjustment (+/-) in amount charged made by 18 Railways/Transport Company 19 (Rs) 10 Handling, Sampling and such other Similar Charges 10 (Rs) 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport 13 By Road 14 By Road 15 By Road 16 Rs) 17 Cost of diesel in transporting Oil through MGR system, if applicable 18 Total Transportation Charges (12+/-13-14+15) 19 Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month 21 GCV of Oil supplied as per bill of oil company 22 GCV of oil supplied as per bill of oil company 23 GCV of Imported coal of the opening stock as per bill of Oil 24 company 25 Weighted average GCV if Oil as billed 26 GCV of Oil supplied 37 GCV of Oil supplied 38 Secondary Fuel/ For Month 39 GCV of Oil of the Opening stock as per bill of Oil 30 company 31 GCV of Oil supplied as per bill of coal company 32 (kCal/Ltr) 33 GCV of Oil of the Opening stock as received at station 34 GCV of Imported Coal of the Opening stock as received at station 35 GCV of Oil supplied 36 GCV of Oil supplied 37 GCV of Imported Coal of the Opening stock as received at station 36 GCV of Imported Coal of the Opening stock as received at station 37 GCV of Imported Coal of the Opening stock as received at station 38 GCV of Imported Coal of the Opening stock as received at station 38 GCV of Imported Coal of the Opening stock as received at station 38 GCV of Imported Coal of the Opening stock as received at station 38 GCV of I	_	, , , , , ,	-			
5 Oil supplied by oil company (3+4) KL - 6 Normative Transit & Handling Losses KL - 7 Net Oil Supplied (5-6) KL - 8 Amount charged by the Oil Company (Rs) - 9 Adjustment(+/-) in amount charged made by Oil Company (Rs) - 10 Handling, Sampling and such other Similar Charges (Rs) - 11 Total amount charged (8+9+10) (Rs) - 12 Transportation charges by rail / ship / road transport (Rs) - By Rail (Rs) (Rs) - By Road (Rs) (Rs) (Rs) By Ship (Rs) (Rs) (Rs) 13 Railways/Transport Company (Rs) (Rs) 14 Demurrage Charges, if any (Rs) (Rs) Cost of diesel in transporting Oil through MGR system, if applicable (Rs) (Rs) 15 applicable (Rs) - 16 Total Transportation Charges (12+/-13-14+15) (Rs) -						
Normative Transit & Handling Losses	_		-			
Net Oil Supplied (5-6)			_			
Adjustment(+/-) in amount charged made by Oil Company Adjustment(+/-) in amount charged made by Oil Company By Rail Rss By Road Rss By Ship Rail Rss Adjustment (+/-) in amount charged made by Rss By Road Rss By Ship Rail Rss By Ship Rss Adjustment (+/-) in amount charged made by Rss Adjustment (+/-) in amount charged made by Rss By Ship Rss Adjustment (+/-) in amount charged made by Rss By Ship Rss Adjustment (+/-) in amount charged made by Rss By Ship Rss Adjustment (+/-) in amount charged made by Rss By Ship Rss Adjustment (+/-) in amount charged made by Rss By Ship Rss Cost of diesel in transporting Oil through MGR system, if Ass By Ship Rss Cost of diesel in transporting Oil through MGR system, if Ass By Ship Rss Cost of diesel in transporting Oil through MGR system, if Ass By Ship Rss Cost of diesel in transporting Oil through MGR system, if Ass By Ship Rss Cost of diesel in transporting Oil through MGR system, if Ass By Ship Rss Cost of diesel in transporting Oil through MGR system, if Ass By Ship Rss Cost of diesel in transporting Oil through MGR system, if Ass By Ship Rss Cost of diesel in transporting Oil through MGR system, if Ass By Ship Rss Cost of Gil amportation Charges (12+/-13-14+15) Rss By Ship Rss Cost of Oil of the Opening stock as per bill of Oil company By Ship Rss Cost of Oil supplied as per bill of Oil company Cost of Oil supplied as per bill of Oil company Cost of Oil of the Opening stock as received at station Ry Ship Rss By Ship Rss Cost of Oil supplied Ry Ship Rss By Ship Rss			_			
Adjustment(+/-) in amount charged made by Oil Company			_	_		
10				(110)		
10 Handling, Sampling and such other Similar Charges (Rs) 11 Total amount charged (8+9+10) (Rs) - 12 Transportation charges by rail / ship / road transport By Rail (Rs) By Road (Rs) By Road (Rs) By Ship (Rs) Adjustment (+/-) in amount charged made by Railways/Transport Company (Rs) 10 Demurrage Charges, if any (Rs) Cost of diesel in transporting Oil through MGR system, if applicable (Rs) 15 applicable (Rs) 16 Total Transportation Charges (12+/-13-14+15) (Rs) - Total amount Charged for fuel supplied including (Rs) 17 Transportation (11+16) (Rs) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) (Rs) (Rs) 19 Blending Ratio - 20 Weighted average cost of Secondary Fuel/ For Month (kCal/Ltr) (SCV of Oil of the Opening stock as per bill of Oil company (kCal/Ltr) 21 GCV of Imported coal of the opening stock as per bill of Oil company (kCal/Ltr) 22 GCV of Oil supplied as per bill of coal company (kCal/Ltr) 23 company (kCal/Ltr) 24 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil supplied (kCal/Ltr) 27 GCV of Oil supplied 28 station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)				(Rs)		9
11 Total amount charged (8+9+10) (Rs) - 12 Transportation charges by rail / ship / road transport By Rail (Rs) By Road (Rs) By Ship (Rs) Adjustment (+/-) in amount charged made by Rail (Rs) Railways/Transport Company (Rs) 13 Railways/Transport Company (Rs) Cost of diesel in transporting Oil through MGR system, if applicable (Rs) 15 applicable (Rs) 16 Total Transportation Charges (12+/-13-14+15) (Rs) Total amount Charged for fuel supplied including 17 Transportation (11+16) (Rs) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) (Rs) 83,1 19 Blending Ratio - 20 Weighted average cost of Secondary Fuel/ For Month (kCal/Ltr) GCV of Oil of the Opening stock as per bill of Oil company 21 (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company (kCal/Ltr) 23 company (kCal/Ltr) 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil supplied (kCal/Ltr) 27 GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 Station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)				· · ·	Handling, Sampling and such other Similar Charges	
Transportation charges by rail / ship / road transport By Rail By Road Rs) By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company (Rs) Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Rs) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV of Oil mported coal of the opening stock as per bill of Oil company CCV of Oil of the Opening stock as received at station RS) RS) (Rs)	_		-	_ `	· · · ·	
By Rail By Road By Ship Road Rs) By Ship Railways/Transport Company Railways/Transport Company Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Rs) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV of Oil supplied as per bill of oil company GCV of Oil of the Opening stock as per bill of Oil Company GCV of Oil of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station GCV of Imported coal supplied as received at station CCV of Imported coal of the CCV of Imported coal supplied as received at station CCV						
By Road By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Rish Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Ooll company GCV of Oil of the Opening stock as per bill of Oil company GCV of Oil of the Opening stock as per bill of Oil company GCV of Oil of the Opening stock as per bill of Oil company GCV of Oil of the Opening stock as per bill of Oil company GCV of Imported Coal of the opening stock as per bill of Oil company GCV of Oil of the Opening stock as per bill of Oil company GCV of Oil of the Opening stock as per bill of Oil company GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) GCV of Oil of the Opening stock as received at station (kCal/Ltr) GCV of Oil of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr)				(Rs)		
By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company (Rs) Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable (Rs) Total Transportation Charges (12+/-13-14+15) (Rs) Total amount Charged for fuel supplied including Transportation (11+16) (Rs) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV if Imported Oil supplied as per bill of coal company GCV of Oil of the Opening stock as per bill of Oil company GCV of Oil of the Opening stock as per bill of Oil company GCV of Imported Oil supplied as per bill of coal company (KCal/Ltr) GCV of Oil of the Opening stock as per bill of Oil company GCV of Imported Oil supplied as per bill of coal company (KCal/Ltr) GCV of Oil of the Opening stock as received at station GCV of Oil supplied GCV of Imported coal of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station GCV of Imported coal supplied as received at station (KCal/Ltr)				· · ·	•	
Adjustment (+/-) in amount charged made by Railways/Transport Company (Rs) Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable (Rs) Total Transportation Charges (12+/-13-14+15) (Rs) Total amount Charged for fuel supplied including Transportation (11+16) (Rs) Blanded Cost of Oil (LDO/HFO) (2+17)/(1+7) (Rs) Blending Ratio Weighted average cost of Secondary Fuel/ For Month (kCal/Ltr) GCV of Oil of the Opening stock as per bill of Oil company CV GCV of Oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil COMPANY COMPANY COMPANY CKCal/Ltr) CGCV of Oil of the Opening stock as per bill of Oil COMPANY CKCal/Ltr) CGCV of Oil of the Opening stock as per bill of Oil COMPANY CKCal/Ltr) CGCV of Oil of the Opening stock as received at station CKCal/Ltr) CGCV of Oil of the Opening stock as received at station CKCal/Ltr) CGCV of Imported coal of the Opening stock as received at station CKCal/Ltr) CGCV of Imported coal of the Opening stock as received at station CKCal/Ltr) CGCV of Imported coal of the Opening stock as received at station CKCal/Ltr) CGCV of Imported coal of the Opening stock as received at station CKCal/Ltr) CGCV of Imported coal supplied as received at station CKCal/Ltr)				· · ·	•	
Railways/Transport Company Railways/Transport Company Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Res Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV if Imported Oil supplied as per bill of coal company Weighted average GCV if Oil as billed GCV of Oil of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Oil supplied GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr)				(. 15)		
Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Rs) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV if Imported Coal of the opening stock as per bill of Oil Company GCV of Oil of the Opening stock as per bill of Oil Company GCV of Imported Coal of the opening stock as per bill of Oil Company GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) GCV of Oil of the Opening stock as received at station (kCal/Ltr) GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr)				(Rs)		13
Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company 4 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 station (kCal/Ltr) CCV of Imported coal supplied as received at station (kCal/Ltr) (kCal/Ltr)				· · ·		14
15 applicable 16 Total Transportation Charges (12+/-13-14+15) 17 Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed GCV of Oil of the Opening stock as received at station (kCal/Ltr) 26 GCV of Oil supplied GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal supplied as received at station (kCal/Ltr)						
Total amount Charged for fuel supplied including Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company 23 company CW GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed CCV of Oil of the Opening stock as received at station (kCal/Ltr) 26 GCV of Oil supplied (kCal/Ltr) CCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal supplied as received at station (kCal/Ltr) CCV of Imported coal supplied as received at station (kCal/Ltr) CCV of Imported coal supplied as received at station (kCal/Ltr)				(Rs)		15
17 Transportation (11+16) (Rs) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) (Rs) 83,4 19 Blending Ratio - 20 Weighted average cost of Secondary Fuel/ For Month (kCal/Ltr) 83033.31 GCV of Oil of the Opening stock as per bill of Oil company (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company (kCal/Ltr) GCV if Imported coal of the opening stock as per bill of Oil company (kCal/Ltr) 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 station (kCal/Ltr)	-		-	(Rs)	Total Transportation Charges (12+/-13-14+15)	16
Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV of Imported Coal of the opening stock as per bill of Oil Weighted average GCV if Oil as billed GCV of Oil of the Opening stock as received at station GCV of Imported Coal of the Opening stock as received at station GCV of Oil supplied GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal supplied as received at station (kCal/Ltr)					Total amount Charged for fuel supplied including	
19 Blending Ratio - 20 Weighted average cost of Secondary Fuel/ For Month (kCal/Ltr) 83033.31 GCV of Oil of the Opening stock as per bill of Oil company (kCal/Ltr) 21 GCV of oil supplied as per bill of oil company (kCal/Ltr) GCV if Imported coal of the opening stock as per bill of Oil company (kCal/Ltr) 23 company (kCal/Ltr) 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal supplied as received at station (kCal/Ltr) 28 station (kCal/Ltr)	-		-	(Rs)	Transportation (11+16)	17
Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company (kCal/Ltr) CCV of oil supplied as per bill of oil company (kCal/Ltr) CCV if Imported coal of the opening stock as per bill of Oil company (kCal/Ltr) CCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) Weighted average GCV if Oil as billed (kCal/Ltr) CCV of Oil of the Opening stock as received at station (kCal/Ltr) CCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CCV of Imported coal supplied as received at station (kCal/Ltr) CCV of Imported coal supplied as received at station (kCal/Ltr)	,033.3	83		(Rs)	Landed Cost of Oil (LDO/HFO) (2+17)/(1+7)	18
GCV of Oil of the Opening stock as per bill of Oil company 21 (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company (kCal/Ltr) GCV if Imported coal of the opening stock as per bill of Oil 23 company (kCal/Ltr) 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 Station (kCal/Ltr)	100°		-	, ,	Blending Ratio	19
GCV of Oil of the Opening stock as per bill of Oil company 21 (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company (kCal/Ltr) GCV if Imported coal of the opening stock as per bill of Oil 23 company (kCal/Ltr) 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station GCV of Imported coal supplied as received at station (kCal/Ltr) 28 station (kCal/Ltr)		83033.31		(kCal/Ltr)	Weighted average cost of Secondary Fuel/ For Month	20
GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company (kCal/Ltr) GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) Weighted average GCV if Oil as billed (kCal/Ltr) GCV of Oil of the Opening stock as received at station (kCal/Ltr) GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal supplied as received at station (kCal/Ltr)					GCV of Oil of the Opening stock as per bill of Oil company	
GCV if Imported coal of the opening stock as per bill of Oil company (kCal/Ltr) GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) Weighted average GCV if Oil as billed (kCal/Ltr) GCV of Oil of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal supplied as received at station (kCal/Ltr) (kCal/Ltr)				(kCal/Ltr)		21
23 company (kCal/Ltr) 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) 28 GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)				(kCal/Ltr)		22
24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)					GCV if Imported coal of the opening stock as per bill of Oil	
25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)				(kCal/Ltr)		23
26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at 28 station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)				(kCal/Ltr)		24
27 GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 GCV of Imported coal supplied as received at station (kCal/Ltr)				(kCal/Ltr)		25
GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 GCV of Imported coal supplied as received at station (kCal/Ltr)				(kCal/Ltr)		26
28 station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)				(kCal/Ltr)		27
29 GCV of Imported coal supplied as received at station (kCal/Ltr)						
						
30 Weighted Average GCV of Secondary Fuel/ as recevied (kCal/Ltr) 9380.00		<u> </u>		<u> </u>	·	
		9380.00		(kCal/Ltr)	Weighted Average GCV of Secondary Fuel/ as recevied	30

				PART- FORM- 15	
Details o	of Secondary Fuel for Computation of Energy Charges	1			
Name of the Company				nited	
	I the Damer Otetier		Tanda Su	per Thermal Powe	
Name of the Power Station			Station Stage-I		
				Amount in R	
SI.No.	Month	Unit	Aug-23		
			HFO	LDO	
1	Opening Quantity of Oil	KL	 •	5,442.0	
2	Value of Opening	(Rs)		45,18,70,348.2	
3	Quantity of Oil supplied by Oil Company	KL (N3)		+0,10,70,040.2	
4	Adjustment (+/-) in quantity supplied made by Oil Company	KL			
5	Oil supplied by oil company (3+4)	KL		T _	
6	Normative Transit & Handling Losses	KL		<u> </u>	
7	Net Oil Supplied (5-6)	KL			
8	Amount charged by the Oil Company	(Rs)		<u>-</u>	
0	Adjustment(+/-) in amount charged made by Oil Company	(1/2)		-	
9	Adjustition (17-) in amount charged made by Oil Company	(Rs)			
10	Handling, Sampling and such other Similar Charges	(Rs)			
11	Total amount charged (8+9+10)	(Rs)		_	
12	Transportation charges by rail / ship / road transport	(113)		 	
12	By Rail	(Rs)		1	
	By Road	(Rs)			
	By Ship	(Rs)			
	Adjustment (+/-) in amount charged made by	(1/5)			
13	Railways/Transport Company	(Rs)			
14	Demurrage Charges, if any	(Rs)			
17	Cost of diesel in transporting Oil through MGR system, if	(113)			
15	applicable	(Rs)			
16	Total Transportation Charges (12+/-13-14+15)	(Rs)	_	_	
	Total amount Charged for fuel supplied including	(1.10)			
17	Transportation (11+16)	(Rs)	-	-	
18	Landed Cost of Oil (LDO/HFO) (2+17)/(1+7)	(Rs)		83,033.3	
19	Blending Ratio	(110)		1009	
20	Weighted average cost of Secondary Fuel/ For Month	(kCal/Ltr)		83033.31	
	GCV of Oil of the Opening stock as per bill of Oil company	(ROGI/Ett)			
21	get of the company	(kCal/Ltr)			
22	GCV of oil supplied as per bill of oil company	(kCal/Ltr)			
	GCV if Imported coal of the opening stock as per bill of Oil	(1121111211)			
23	company	(kCal/Ltr)			
24	GCV of Imported Oil supplied as per bill of coal company	(kCal/Ltr)			
25	Weighted average GCV if Oil as billed	(kCal/Ltr)			
26	GCV of Oil of the Opening stock as received at station	(kCal/Ltr)			
27	GCV of Oil supplied	(kCal/Ltr)			
	GCV of Imported coal of the Opening stock as received at	1 ` ′			
28	station	(kCal/Ltr)			
29	GCV of Imported coal supplied as received at station	(kCal/Ltr)			
30	Weighted Average GCV of Secondary Fuel/ as recevied	(kCal/Ltr)		9380.00	
				PETITIONE	

				PART- FORM- 15	
Details of Secondary Fuel for Computation of Energy Charges					
Name of the Company				imited	
Name of the Power Station			Tanda Super Thermal Power Station Stage-I		
			SI.No.	Month	Unit
HFO	LDO				
1	Opening Quantity of Oil	KL	 	5,115.0	
	Value of Opening	(Rs)		42,47,18,455.5	
3	Quantity of Oil supplied by Oil Company	KL		42,47,10,400.0	
4	Adjustment (+/-) in quantity supplied made by Oil Company	KL			
5	Oil supplied by oil company (3+4)	KL		1 _	
6	Normative Transit & Handling Losses	KL			
7	Net Oil Supplied (5-6)	KL		_	
8	Amount charged by the Oil Company	(Rs)			
U	Adjustment(+/-) in amount charged made by Oil Company	(1/2)			
9	Adjustment (17-) in amount charged made by on company	(Rs)		6,66,282.00	
10	Handling, Sampling and such other Similar Charges	(Rs)		0,00,202.00	
11	Total amount charged (8+9+10)	(Rs)		6,66,282.00	
12	Transportation charges by rail / ship / road transport	(110)		0,00,202.00	
12	By Rail	(Rs)			
	By Road	(Rs)			
	By Ship	(Rs)			
	Adjustment (+/-) in amount charged made by	(1/5)			
13	Railways/Transport Company	(Rs)			
14	Demurrage Charges, if any	(Rs)			
- ' '	Cost of diesel in transporting Oil through MGR system, if	(110)			
15	applicable	(Rs)			
16	Total Transportation Charges (12+/-13-14+15)	(Rs)		_	
	Total amount Charged for fuel supplied including	(1.10)			
17	Transportation (11+16)	(Rs)	-	6,66,282.00	
18	Landed Cost of Oil (LDO/HFO) (2+17)/(1+7)	(Rs)		83,163.57	
19	Blending Ratio	()	-	1009	
20	Weighted average cost of Secondary Fuel/ For Month	(kCal/Ltr)		83163.57	
	GCV of Oil of the Opening stock as per bill of Oil company	(1135.1121.)			
21	g and a sum of a magnetic first and a sum of a sum of the sum of t	(kCal/Ltr)			
22	GCV of oil supplied as per bill of oil company	(kCal/Ltr)			
	GCV if Imported coal of the opening stock as per bill of Oil				
23	company	(kCal/Ltr)			
24	GCV of Imported Oil supplied as per bill of coal company	(kCal/Ltr)			
25	Weighted average GCV if Oil as billed	(kCal/Ltr)			
26	GCV of Oil of the Opening stock as received at station	(kCal/Ltr)			
27	GCV of Oil supplied	(kCal/Ltr)			
	GCV of Imported coal of the Opening stock as received at				
28	station	(kCal/Ltr)			
29	GCV of Imported coal supplied as received at station	(kCal/Ltr)			
30	Weighted Average GCV of Secondary Fuel/ as recevied	(kCal/Ltr)		9380.00	
				PETITIONE	

					PART-I M- 15 <i>I</i>
Details of Secondary Fuel for Computation of Energy Charges Name of the Company					
				mited	
Name of the Dawer Otation			Tanda Super Thermal		
Name o	Name of the Power Station			tation Stage	-I
				Amou	unt in R
SI.No.	Month	Unit	Oct-23		
			HFO	LDO)
1	Opening Quantity of Oil	KL		4	,762.0
2	Value of Opening	(Rs)		39,60,27	
3	Quantity of Oil supplied by Oil Company	KL	_	00,00,00	-
4	Adjustment (+/-) in quantity supplied made by Oil Company	KL			
5	Oil supplied by oil company (3+4)	KL	-		-
6	Normative Transit & Handling Losses	KL	_		
7	Net Oil Supplied (5-6)	KL	_		_
8	Amount charged by the Oil Company	(Rs)	_		_
	Adjustment(+/-) in amount charged made by Oil Company	(.15)			
9		(Rs)			
10	Handling, Sampling and such other Similar Charges	(Rs)			
11	Total amount charged (8+9+10)	(Rs)	-		-
12	Transportation charges by rail / ship / road transport				
	By Rail	(Rs)			
	By Road	(Rs)			
	By Ship	(Rs)			
	Adjustment (+/-) in amount charged made by	(111)			
13	Railways/Transport Company	(Rs)			
14	Demurrage Charges, if any	(Rs)			
	Cost of diesel in transporting Oil through MGR system, if				
15	applicable	(Rs)			
16	Total Transportation Charges (12+/-13-14+15)	(Rs)	-		-
	Total amount Charged for fuel supplied including				
17	Transportation (11+16)	(Rs)	-		-
18	Landed Cost of Oil (LDO/HFO) (2+17)/(1+7)	(Rs)		83,	163.5
19	Blending Ratio		-		100°
20	Weighted average cost of Secondary Fuel/ For Month	(kCal/Ltr)		83163.57	
	GCV of Oil of the Opening stock as per bill of Oil company				
21		(kCal/Ltr)			
22	GCV of oil supplied as per bill of oil company	(kCal/Ltr)			
	GCV if Imported coal of the opening stock as per bill of Oil				
23	company	(kCal/Ltr)			
24	GCV of Imported Oil supplied as per bill of coal company	(kCal/Ltr)			
25	Weighted average GCV if Oil as billed	(kCal/Ltr)			
26	GCV of Oil of the Opening stock as received at station	(kCal/Ltr)			
27	GCV of Oil supplied	(kCal/Ltr)			
	GCV of Imported coal of the Opening stock as received at				
28	station	(kCal/Ltr)	1		
29	GCV of Imported coal supplied as received at station	(kCal/Ltr)	1		
30	Weighted Average GCV of Secondary Fuel/ as recevied	(kCal/Ltr)	ļ	9380.00	
				PETI1	TIONE

				PART-I FORM- 15 <i>A</i>		
Details of Secondary Fuel for Computation of Energy Charges Name of the Company						
				mited		
Name of the Power Station			Tanda Super Thermal Powe Station Stage-I			
			Amount in R			
SI.No.	Month	Unit	Nov-23			
			HFO	LD(0	
1	Opening Quantity of Oil	KL			3,400.0	
2	Value of Opening	(Rs)		28,27,5		
3	Quantity of Oil supplied by Oil Company	KL	_		-	
4	Adjustment (+/-) in quantity supplied made by Oil Company	KL				
5	Oil supplied by oil company (3+4)	KL	_		-	
6	Normative Transit & Handling Losses	KL	_			
7	Net Oil Supplied (5-6)	KL	_		_	
8	Amount charged by the Oil Company	(Rs)	_		_	
	Adjustment(+/-) in amount charged made by Oil Company	(1.10)				
9		(Rs)				
10	Handling, Sampling and such other Similar Charges	(Rs)				
11	Total amount charged (8+9+10)	(Rs)	-		-	
12	Transportation charges by rail / ship / road transport	, ,				
	By Rail	(Rs)				
	By Road	(Rs)				
	By Ship	(Rs)				
	Adjustment (+/-) in amount charged made by	(111)				
13	Railways/Transport Company	(Rs)				
14	Demurrage Charges, if any	(Rs)				
	Cost of diesel in transporting Oil through MGR system, if					
15	applicable	(Rs)				
16	Total Transportation Charges (12+/-13-14+15)	(Rs)	-		-	
	Total amount Charged for fuel supplied including					
17	Transportation (11+16)	(Rs)	-		-	
18	Landed Cost of Oil (LDO/HFO) (2+17)/(1+7)	(Rs)		83	3,163.57	
19	Blending Ratio		-		100%	
20	Weighted average cost of Secondary Fuel/ For Month	(kCal/Ltr)		83163.57		
	GCV of Oil of the Opening stock as per bill of Oil company					
21		(kCal/Ltr)				
22	GCV of oil supplied as per bill of oil company	(kCal/Ltr)				
	GCV if Imported coal of the opening stock as per bill of Oil					
23	company	(kCal/Ltr)				
24	GCV of Imported Oil supplied as per bill of coal company	(kCal/Ltr)				
25	Weighted average GCV if Oil as billed	(kCal/Ltr)				
26	GCV of Oil of the Opening stock as received at station	(kCal/Ltr)				
27	GCV of Oil supplied	(kCal/Ltr)				
	GCV of Imported coal of the Opening stock as received at					
28	station	(kCal/Ltr)				
29	GCV of Imported coal supplied as received at station	(kCal/Ltr)		0000 00		
30	Weighted Average GCV of Secondary Fuel/ as recevied	(kCal/Ltr)		9380.00		

				PART- FORM- 15
Details o	of Secondary Fuel for Computation of Energy Charge	<u>s</u>		
Name of	the Company		NTPC Li	imited
Namo of	the Power Station		Tanda S	Super Thermal
Name of	the Fower Station		Power S	Station Stage-I
				Amount in R
SI.No.	Month	Unit		Dec-23
			HFO	LDO
1	Opening Quantity of Oil	KL		2,827.0
2	Value of Opening	(Rs)		23,51,06,489.3
3	Quantity of Oil supplied by Oil Company	KL		3,097.62
4	Adjustment (+/-) in quantity supplied made by Oil Company	KL		-,
5	Oil supplied by oil company (3+4)	KL		3,097.62
6	Normative Transit & Handling Losses	KL		<u> </u>
7	Net Oil Supplied (5-6)	KL		3,097.62
8	Amount charged by the Oil Company	(Rs)		27,51,49,937.55
	Adjustment(+/-) in amount charged made by Oil Company	, ,		, , ,
9		(Rs)		
10	Handling, Sampling and such other Similar Charges	(Rs)		
11	Total amount charged (8+9+10)	(Rs)		27,51,49,937.5
12	Transportation charges by rail / ship / road transport	•		
	By Rail	(Rs)		
	By Road	(Rs)		
	By Ship	(Rs)		
	Adjustment (+/-) in amount charged made by	, ,		
13	Railways/Transport Company	(Rs)		
14	Demurrage Charges, if any	(Rs)		
	Cost of diesel in transporting Oil through MGR system, if			
15	applicable	(Rs)		
16	Total Transportation Charges (12+/-13-14+15)	(Rs)	-	-
	Total amount Charged for fuel supplied including		l _	27,51,49,937.5
17	Transportation (11+16)	(Rs)		
18	Landed Cost of Oil (LDO/HFO) (2+17)/(1+7)	(Rs)		86,124.21
19	Blending Ratio		-	1000
20	Weighted average cost of Secondary Fuel/ For Month	(kCal/Ltr)		86124.21
a ·	GCV of Oil of the Opening stock as per bill of Oil company			
21		(kCal/Ltr)		
22	GCV of oil supplied as per bill of oil company	(kCal/Ltr)		
00	GCV if Imported coal of the opening stock as per bill of Oil	(1-0 -1/1 +-)		
23	company	(kCal/Ltr)	<u> </u>	
24	GCV of Imported Oil supplied as per bill of coal company	(kCal/Ltr)	<u> </u>	
25	Weighted average GCV if Oil as billed	(kCal/Ltr)	<u> </u>	
26	GCV of Oil outpolied	(kCal/Ltr)	<u> </u>	
27	GCV of Oil supplied GCV of Imported coal of the Opening stock as received at	(kCal/Ltr)	 	
28	station	(kCal/Ltr)		
28 29	GCV of Imported coal supplied as received at station	(kCal/Ltr)	 	
30	Weighted Average GCV of Secondary Fuel/ as recevied	(kCal/Ltr)	 	9380.00
30	Trialities Average OOV or Decording I deli as recevied	[(NOal/LII)	 	9300.00
				PETITIONE
				PETITIONE

Details of Secondary Fuel for Computation of Energy Charges Name of the Company Name of the Power Station Tanda Super Thermal Power Station Stage-I Amount in SI.No. Month Unit Jan-24 HFO LDO					PART- FORM- 15
SI.No. Month Unit Jan-24 Power Station Stage-I Amount is Jan-24 HFO LDO	Details (of Secondary Fuel for Computation of Energy Charges	<u> </u>		
Si.No. Month Unit Jan-24	Name of	f the Company		NTPC Li	mited
Si.No. Month Unit Jan-24	\lama a	I the Dower Station		Tanda S	uper Thermal
SI.No.	vame of	r the Power Station			
Net Section					Amount in R
1	SI.No.	Month		Jan-24	
Value of Opening				HFO	LDO
Value of Opening	1	Opening Quantity of Oil	KL		5,540.6
Adjustment (+/-) in quantity supplied made by Oil Company KL Oil supplied by Oil company (3+4) Normative Transit & Handling Losses KL Net Oil Supplied (5-6) Adjustment (+/-) in amount charged made by Oil Company Adjustment (+/-) in amount charged made by Oil Company Adjustment (+/-) in amount charged made by Oil Company Handling, Sampling and such other Similar Charges (Rs) Total amount charged (8+9+10) Transportation charges by rail / ship / road transport By Rail By Road By Ship Adjustment (+/-) in amount charged made by Rish Ship Adjustment (+/-) in amount charged made by Rish Ship Adjustment (+/-) in amount charged made by Rish Ship Adjustment (+/-) in amount charged made by Rish Ship Adjustment (+/-) in amount charged made by Rish Ship Cost of diesel in transporting Oil through MGR system, if applicable Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company (KCal/Ltr) GCV of Imported coal of the Opening stock as received at station Rish Adjustry Rish Call Transportation (Rcal/Ltr) Rish Call Transportation (11+16) Rish C					47,71,84,728.7
4 Adjustment (+/-) in quantity supplied made by Oil Company 5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 (Rs) 10 Handling, Sampling and such other Similar Charges 11 Total amount charged (8+9+10) 12 Transportation charges by rail / ship / road transport 13 Railways/Transport Company 14 Demurrage Charges, if any 15 Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) 17 Total amount Charged for fuel supplied including 17 Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 24 GCV of Oil supplied as per bill of oil company 25 GCV of Oil supplied 26 GCV of Oil supplied 27 GCV of Oil supplied 38 Selve Adjustment 40 GCV of Imported coal of the Opening stock as received at station 40 KCal/Ltr) 41 GCV of Imported coal of the Opening stock as received at station 41 GCV of Imported coal supplied as received at station 42 GCV of Imported coal supplied as received at station 43 ECV of Imported coal supplied as received at station 44 CCV of Imported coal supplied as received at station 45 CCV of Imported coal supplied as received at station 46 CCV of Imported coal supplied as received at station 47 CCV of Imported coal supplied as received at station 48 CCV of Imported coal supplied as received at station 48 CCV of Imported coal supplied as received at station 49 GCV of Imported coal supplied as received at station 50 CCV of Imported coal supplied as received at station 50 CCV of Imported coal supplied as received at station 50 CCV of Imported coal supplied as received at station 50 CCV of Imported coal supplied as received at station 50 CCV of Imported coal supplied as received at station 50 CCV of Imported coal supplied as received at station 50 CCV of Imported coal suppl					-
5 Oil supplied by oil company (3+4) 6 Normative Transit & Handling Losses KL 7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 Handling, Sampling and such other Similar Charges (Rs) 10 Handling, Sampling and such other Similar Charges (Rs) 11 Total amount charged (8+9+10) (Rs) 12 Transportation charges by rail / ship / road transport 13 By Rail 14 By Road (Rs) 15 By Road (Rs) 16 By Ship (Rs) 17 Adjustment (+/-) in amount charged made by (Rs) 18 Adjustment (+/-) in amount charged made by (Rs) 19 Adjustment (+/-) in amount charged made by (Rs) 10 Adjustment (+/-) in amount charged made by (Rs) 11 Total amount Charges (12+/-13-14+15) (Rs) 12 Cost of diesel in transporting Oil through MGR system, if applicable (Rs) 13 Pajlicable (Rs) 14 Demurrage Charges, if any 15 Cost of diesel in transporting Oil through MGR system, if applicable (Rs) 16 Total Transportation Charges (12+/-13-14+15) (Rs) 17 Total amount Charged for fuel supplied including Transportation (11+16) (Rs) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) (Rs) 19 Blending Ratio (Rs) 20 Weighted average cost of Secondary Fuel/ For Month (Rcal/Ltr) 21 GCV of Oil of the Opening stock as per bill of Oil company 22 GCV of Oil supplied as per bill of oil company (RCal/Ltr) 23 GCV of Oil of the Opening stock as received at station (RCal/Ltr) 24 GCV of Imported Coal of the Opening stock as received at station (RCal/Ltr) 25 GCV of Oil supplied 26 GCV of Oil supplied 27 GCV of Imported coal of the Opening stock as received at station (RCal/Ltr) 28 GCV of Imported coal of the Opening stock as received at station (RCal/Ltr) 29 GCV of Imported coal of the Opening stock as received at station (RCal/Ltr)					_
Normative Transit & Handling Losses					_
7 Net Oil Supplied (5-6) 8 Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9 Handling, Sampling and such other Similar Charges (Rs) 10 Handling, Sampling and such other Similar Charges (Rs) 11 Total amount charged (8+9+10) (Rs) 2 Transportation charges by rail / ship / road transport By Rail By Road (Rs) By Road (Rs) By Ship Adjustment (+/-) in amount charged made by (Rs) Adjustment (+/-) in amount charged made by (Rs) Adjustment (+/-) in amount charged made by (Rs) Adjustment (1-/-) in amount charged made by (Rs) (Rs) Adjustment (1-/-) in amount charged made by (Rs) (Rs) Adjustment (1-/-) in amount charged made by (Rs) (Rs) Adjustment (1-/-) in amount charged made by (Rs) (Rs) Adjustment (1-/-) in amount charged made by (Rs) (Rs) Adjustment (1-/-) in amount charged for full amount of the sample made by (Rs) (Rs) Adjustment (1-/-) in amount charged for full amount of the full					
Amount charged by the Oil Company Adjustment(+/-) in amount charged made by Oil Company 9		•			_
Adjustment(+/-) in amount charged made by Oil Company (Rs) 10 Handling, Sampling and such other Similar Charges (Rs) 11 Total amount charged (8+9+10) (Rs) 12 Transportation charges by rail / ship / road transport By Rail By Road (Rs) By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company (Rs) 13 Railways/Transport Company (Rs) Cost of diesel in transporting Oil through MGR system, if applicable (Rs) 15 applicable (Rs) 16 Total Transportation Charges (12+/-13-14+15) (Rs) Total amount Charged for fuel supplied including Transportation (11+16) (Rs) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio CoV of Oil of the Opening stock as per bill of Oil company (kCal/Ltr) CGCV of Oil supplied as per bill of oil company (kCal/Ltr) CGCV of Imported Coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CGCV of Imported coal of the Opening stock as received at station (kCal/Ltr)		,			_
10			'		
10 Handling, Sampling and such other Similar Charges (Rs) 11 Total amount charged (8+9+10) (Rs) 12 Transportation charges by rail / ship / road transport By Rail (Rs) By Road (Rs) By Ship (Rs) Adjustment (+/-) in amount charged made by Railways/Transport Company (Rs) Cost of diesel in transporting Oil through MGR system, if applicable (Rs) 15 applicable (Rs) 16 Total Transportation Charges (12+/-13-14+15) (Rs) Total amount Charged for fuel supplied including Transportation (11+16) (Rs) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) (Rs) 80,914 19 Blending Ratio - 10 20 Weighted average cost of Secondary Fuel/ For Month (Kcal/Ltr) 80914.96 COV of Oil of the Opening stock as per bill of Oil company (KCal/Ltr) GCV of Imported coal of the opening stock as per bill of Oil company (KCal/Ltr) GCV of Oil supplied as per bill of coal company (KCal/Ltr) GCV of Oil of the Opening stock as received at station (KCal/Ltr) GCV of Imported coal of the Opening stock as received at station (KCal/Ltr) GCV of Imported coal of the Opening stock as received at station (KCal/Ltr) GCV of Imported coal of the Opening stock as received at station (KCal/Ltr) GCV of Imported coal of the Opening stock as received at station (KCal/Ltr) GCV of Imported coal of the Opening stock as received at station (KCal/Ltr)	9		(Rs)		-2,88,62,688.5
Transportation charges by rail / ship / road transport By Rail By Road (Rs) By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company (Rs) Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Rs) Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company COV of Oil of the Opening stock as per bill of Oil company COV of Oil of the Opening stock as per bill of Oil COV of Oil of the Opening stock as per bill of Oil COV of Oil of the Opening stock as per bill of Oil COV of Oil of the Opening stock as per bill of Oil COV of Oil of the Opening stock as per bill of Oil COV of Oil of the Opening stock as per bill of Oil COV of Oil of the Opening stock as per bill of Oil COV of Oil of the Opening stock as per bill of Oil COV of Oil of the Opening stock as per bill of Oil COV of Oil of the Opening stock as received at station (kCal/Ltr) COV of Imported Coal of the Opening stock as received at station (kCal/Ltr) COV of Imported Coal of the Opening stock as received at station COV of Imported Coal of the Opening stock as received at station COV of Imported Coal supplied as received at station (kCal/Ltr)	10	Handling, Sampling and such other Similar Charges	(Rs)		
Transportation charges by rail / ship / road transport By Rail By Road (Rs) By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company (Rs) Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Rs) Total Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV of Oil of the Opening stock as received at station Rs) (Rs) - 2,88,62,688 Rs) 2,88,62,688 Rs) - 2,88,62,688 Rs) - 2,88,62,688 Rs) - 4,88,62,688 Rs) - 4,88,62,688 Rs) - 6,89,14 - 7,88,62,688 Rs) - 10 - 80,914 - 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90 - 90	11	Total amount charged (8+9+10)	(Rs)		-2,88,62,688.5
By Rail By Road By Ship Road By Ship Railways/Transport Company Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Res Blending Ratio Cover of Oil of the Opening stock as per bill of Oil company Cover of Oil of the Opening stock as received at station Cover of diesel in transportation Charges (12+/-13-14+15) Res Cover of diesel in transportation Charges (12+/-13-14+15) Res Cover of diesel in transportation Charges (12+/-13-14+15) Res Cover of Union Charges (12+/-13-14+15) Res Cover of Union Charges (12+/-13-14+15) Res Cover of Oil (LDO/HFO) (2+17)/(1+7) Res Cover of Oil (LDO/HFO) (2+17)/(1+7) Res Cover of Oil of the Opening stock as per bill of Oil company Res Cover of Oil of the Opening stock as per bill of Oil company Res Cover of Oil of the Opening stock as per bill of Oil company Res Cover of Oil of the Opening stock as per bill of Oil company Res Cover of Oil of the Opening stock as received at station Res Cover of Oil of the Opening stock as received at station Res Cover of Imported Coal of the Opening stock as received at station Res Res Cover of Imported Coal of the Opening stock as received at station Res Res Cover of Imported Coal of the Opening stock as received at station Res Res Cover of Imported Coal of the Opening stock as received at station Res Res Cover of Imported Coal of the Opening stock as received at station Res Res Cover of Imported Coal of the Opening stock as received at station Res Res Cover of Imported Coal of the Opening stock as received at station Res Res Cover of Imported Coal of the Opening stock as received at station Res Res Cover of Oil of Imported Coal of the Opening stock as received at station Res Res Cover of Imported Coal of the Opening stock as received at station Res Res Cover of Oil of Imported Coal of the Opening stock as received at station Res Res Cover of Imported Coal of Imported Coal Supplied as received at station	12	Transportation charges by rail / ship / road transport	, ,		
By Road By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company (Rs) Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable (Rs) Total Transportation Charges (12+/-13-14+15) (Rs) Total amount Charged for fuel supplied including Transportation (11+16) (Rs) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV of Oil supplied as per bill of coal company Weighted average GCV if Oil as billed GCV of Oil of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Oil supplied (kCal/Ltr) GCV of Imported Coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported Coal of the Opening stock as received at station GCV of Imported Coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported Coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported Coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported Coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported Coal of the Opening stock as received at station (kCal/Ltr)			(Rs)		
By Ship Adjustment (+/-) in amount charged made by Railways/Transport Company (Rs) 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable (Rs) 15 applicable (Rs) 16 Total Transportation Charges (12+/-13-14+15) (Rs) 17 Total amount Charged for fuel supplied including Transportation (11+16) (Rs) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) (Rs) (Rs) 19 Blending Ratio COV of Oil of the Opening stock as per bill of Oil company (CV of Oil of the Opening stock as per bill of Oil company COV if Imported coal of the opening stock as per bill of Oil company (CV of Oil of Imported Coil supplied as per bill of coal company (CV of Oil of the Opening stock as per bill of Oil company (CV of Oil of Imported Coil supplied as per bill of coal company (CV of Oil of the Opening stock as per bill of Oil company (CV of Oil of the Opening stock as per bill of Oil company (CV of Oil of the Opening stock as per bill of Oil company (CV of Oil of the Opening stock as per bill of Oil (KCal/Ltr) (CV of Oil of the Opening stock as received at station (CV of Oil of the Opening stock as received at station (CV of Oil supplied (CV of Oil of the Opening stock as received at station (CV of Imported Coal of the Opening stock as received at station (CV of Imported Coal supplied as received at station (CV of Imported Coal supplied as received at station (CV of Imported Coal supplied as received at station (CV of Imported Coal supplied as received at station (CV of Imported Coal supplied as received at station (CV of Imported Coal supplied as received at station (CV of Imported Coal supplied as received at station (CV of Imported Coal supplied as received at station (CV of Imported Coal supplied as received at station		·	- ` '		
Adjustment (+/-) in amount charged made by Railways/Transport Company 14 Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable 15 applicable 16 Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company CSV of Oil of the Opening stock as per bill of Coal company CSV of Oil of the Opening stock as per bill of Oil CSV of Oil of the Opening stock as per bill of Oil CSV of Oil of the Opening stock as per bill of Oil CSV of Imported Oil supplied as per bill of coal company CSV of Imported Oil supplied as per bill of Coal company (kCal/Ltr) CSV of Oil of the Opening stock as received at station (kCal/Ltr) CSCV of Oil supplied CSCV of Oil supplied CSCV of Oil supplied CSCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CSCV of Imported coal of the Opening stock as received at station (kCal/Ltr) CSCV of Imported coal of the Opening stock as received at station (kCal/Ltr)			· , ,		
Railways/Transport Company Demurrage Charges, if any Cost of diesel in transporting Oil through MGR system, if applicable Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company Company GCV if Imported coal of the opening stock as per bill of Oil Company Comp					
Cost of diesel in transporting Oil through MGR system, if applicable 16 Total Transportation Charges (12+/-13-14+15) (Rs) Total amount Charged for fuel supplied including Transportation (11+16) (Rs) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) (Rs) 80,914 19 Blending Ratio - 10 Weighted average cost of Secondary Fuel/ For Month (kCal/Ltr) 80914.96 GCV of Oil of the Opening stock as per bill of Oil company (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company (kCal/Ltr) 23 company (kCal/Ltr) 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)	13		(Rs)		
15 applicable 16 Total Transportation Charges (12+/-13-14+15) 17 Total amount Charged for fuel supplied including 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company 24 GCV of Imported Oil supplied as per bill of coal company 25 Weighted average GCV if Oil as billed CCV of Oil of the Opening stock as received at station CCV of Oil supplied CCV of Oil supplied CCV of Oil of the Opening stock as received at station CCV of Oil supplied CCV of Imported coal of the Opening stock as received at station CCV of Imported coal of the Opening stock as received at station CCV of Imported coal supplied as received at station CCV of Imported coal supplied as received at station CCV of Imported coal supplied as received at station CCV of Imported coal supplied as received at station CCV of Imported coal supplied as received at station CCV of Imported coal supplied as received at station CCV of Imported coal supplied as received at station CCV of Imported coal supplied as received at station CCV of Imported coal supplied as received at station CCV of Imported coal supplied as received at station	14	Demurrage Charges, if any	(Rs)		
Total Transportation Charges (12+/-13-14+15) Total amount Charged for fuel supplied including Transportation (11+16) Res Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company Company GCV if Imported coal of the opening stock as per bill of Oil company		Cost of diesel in transporting Oil through MGR system, if			
Total amount Charged for fuel supplied including Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil 23 company (kCal/Ltr) 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed CCV of Oil of the Opening stock as received at station CCV of Imported Coal of the Opening stock as received at station CCV of Imported Coal of the Opening stock as received at station CCV of Imported Coal of the Opening stock as received at station CCV of Imported Coal of the Opening stock as received at station CCV of Imported Coal of the Opening stock as received at station CCV of Imported Coal of the Opening stock as received at station CCV of Imported Coal supplied as received at station CCV of Imported Coal supplied as received at station CCV of Imported Coal supplied as received at station CCV of Imported Coal supplied as received at station CCV of Imported Coal supplied as received at station CCV of Imported Coal supplied as received at station CCV of Imported Coal supplied as received at station CCV of Imported Coal supplied as received at station CCV of Imported Coal supplied as received at station CCV of Imported Coal supplied as received at station	15		(Rs)		
Transportation (11+16) 18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) 19 Blending Ratio 20 Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company 21 (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company 23 company CV of Imported Oil supplied as per bill of coal company CV of Imported Oil supplied as per bill of coal company EV OCV of Oil of the Opening stock as received at station CV of Oil of the Opening stock as received at station CV of Oil of the Opening stock as received at station CV of Oil supplied CV of Imported Coal of the Opening stock as received at station CV of Imported coal of the Opening stock as received at station CV of Imported coal of the Opening stock as received at station CV of Imported coal of the Opening stock as received at station CV of Imported coal supplied as received at station CV of Imported coal supplied as received at station CV of Imported coal supplied as received at station CV of Imported coal supplied as received at station CV of Imported coal supplied as received at station CV of Imported coal supplied as received at station CV of Imported coal supplied as received at station	16		(Rs)	-	-
18 Landed Cost of Oil (LDO/HFO) (2+17)/(1+7) (Rs) 80,914 19 Blending Ratio - 10 20 Weighted average cost of Secondary Fuel/ For Month (kCal/Ltr) 80914.96 GCV of Oil of the Opening stock as per bill of Oil company (kCal/Ltr) 22 GCV of oil supplied as per bill of oil company (kCal/Ltr) GCV if Imported coal of the opening stock as per bill of Oil company (kCal/Ltr) 23 company (kCal/Ltr) 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 station (kCal/Ltr)		Total amount Charged for fuel supplied including			2 99 62 699 51
Blending Ratio Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company GCV of Imported Oil supplied as per bill of coal company KCal/Ltr) Weighted average GCV if Oil as billed GCV of Oil of the Opening stock as received at station GCV of Imported Coal of the Opening stock as received at station GCV of Imported Coal of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal supplied as received at station (kCal/Ltr) GCV of Imported coal supplied as received at station (kCal/Ltr)	17	Transportation (11+16)	(Rs)	_	-2,00,02,000.3
Weighted average cost of Secondary Fuel/ For Month GCV of Oil of the Opening stock as per bill of Oil company (kCal/Ltr) GCV of oil supplied as per bill of oil company (kCal/Ltr) GCV if Imported coal of the opening stock as per bill of Oil company (kCal/Ltr) GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) Weighted average GCV if Oil as billed GCV of Oil of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal supplied as received at station (kCal/Ltr)	18	Landed Cost of Oil (LDO/HFO) (2+17)/(1+7)	(Rs)		80,914.96
GCV of Oil of the Opening stock as per bill of Oil company 21	19	Blending Ratio		-	100°
21	20	,	(kCal/Ltr)		80914.96
22 GCV of oil supplied as per bill of oil company GCV if Imported coal of the opening stock as per bill of Oil company (kCal/Ltr) 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 Station (kCal/Ltr)		GCV of Oil of the Opening stock as per bill of Oil company			
GCV if Imported coal of the opening stock as per bill of Oil company (kCal/Ltr) GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) Weighted average GCV if Oil as billed (kCal/Ltr) GCV of Oil of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) GCV of Imported coal supplied as received at station (kCal/Ltr)					
23 company (kCal/Ltr) 24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) 28 GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)	22		(kCal/Ltr)	ļ	
24 GCV of Imported Oil supplied as per bill of coal company (kCal/Ltr) 25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) 28 GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)	0.5				
25 Weighted average GCV if Oil as billed (kCal/Ltr) 26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)				<u> </u>	
26 GCV of Oil of the Opening stock as received at station (kCal/Ltr) 27 GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)		· · · · · · · · · · · · · · · · · · ·		<u> </u>	
27 GCV of Oil supplied (kCal/Ltr) GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)				ļ	
GCV of Imported coal of the Opening stock as received at station (kCal/Ltr) 28 GCV of Imported coal supplied as received at station (kCal/Ltr)		· •		ļ	
28 station (kCal/Ltr) 29 GCV of Imported coal supplied as received at station (kCal/Ltr)	27		(kCal/Ltr)	ļ	
29 GCV of Imported coal supplied as received at station (kCal/Ltr)	00	, , , , , , , , , , , , , , , , , , , ,	(1:0 -1/1-1-)		
				1	
30				1	0390.00
	30	Ivveignied Average GCV or Secondary Fuel/ as recevied	(KCal/Ltr)	 	9380.00
I					

					PART- M- 15/			
etails (of Secondary Fuel for Computation of Energy Charges	S	1					
	f the Company	_	NTPC Li	imited				
			Tanda S	uper Therma	al			
lame of	f the Power Station			Station Stage				
					ınt in R			
SI.No.	Month	Unit	Feb-24					
			HFO					
1	Opening Quantity of Oil	KL			,906.6			
2	Value of Opening	(Rs)		39,70,21				
3	Quantity of Oil supplied by Oil Company	KL	_	00,10,21	,000.c			
4	Adjustment (+/-) in quantity supplied made by Oil Company	KL						
5	Oil supplied by oil company (3+4)	KL	_					
6	Normative Transit & Handling Losses	KL						
7	Net Oil Supplied (5-6)	KL	_		_			
8	Amount charged by the Oil Company	(Rs)	_		_			
	Adjustment(+/-) in amount charged made by Oil Company	(.15)						
9		(Rs)						
10	Handling, Sampling and such other Similar Charges	(Rs)						
11	Total amount charged (8+9+10)	(Rs)	-		-			
12	Transportation charges by rail / ship / road transport							
	By Rail	(Rs)						
	By Road	(Rs)						
	By Ship	(Rs)						
	Adjustment (+/-) in amount charged made by	(* ***)						
13	Railways/Transport Company	(Rs)						
14	Demurrage Charges, if any	(Rs)						
	Cost of diesel in transporting Oil through MGR system, if							
15	applicable	(Rs)						
16	Total Transportation Charges (12+/-13-14+15)	(Rs)			-			
	Total amount Charged for fuel supplied including							
17	Transportation (11+16)	(Rs)	_		-			
18	Landed Cost of Oil (LDO/HFO) (2+17)/(1+7)	(Rs)		80,	914.9			
19	Blending Ratio		-		100			
20	Weighted average cost of Secondary Fuel/ For Month	(kCal/Ltr)		80914.96				
	GCV of Oil of the Opening stock as per bill of Oil company							
21		(kCal/Ltr)						
22	GCV of oil supplied as per bill of oil company	(kCal/Ltr)						
	GCV if Imported coal of the opening stock as per bill of Oil							
23	company	(kCal/Ltr)						
24	GCV of Imported Oil supplied as per bill of coal company	(kCal/Ltr)						
25	Weighted average GCV if Oil as billed	(kCal/Ltr)						
26	GCV of Oil of the Opening stock as received at station	(kCal/Ltr)						
27	GCV of Oil supplied	(kCal/Ltr)						
00	GCV of Imported coal of the Opening stock as received at	(1.0.17.1)						
28	station	(kCal/Ltr)	1					
29	GCV of Imported coal supplied as received at station	(kCal/Ltr)		0200 00				
30	Weighted Average GCV of Secondary Fuel/ as recevied	(kCal/Ltr)		9380.00				
				PETIT				

					PART-I M- 15/		
etails	of Secondary Fuel for Computation of Energy Charges	<u> </u>	1				
	f the Company	<u></u>	NTPC L	imited			
	•		Tanda S	Super Therm	al		
lame of	f the Power Station		Power Station Stage-I				
					ınt in R		
SI.No.	Month	Unit		Mar-24			
			HFO	LDO			
1	Opening Quantity of Oil	KL	1 0		,025.6		
2	Value of Opening	(Rs)		32,57,35			
3	Quantity of Oil supplied by Oil Company	KL		02,07,00	-		
4	Adjustment (+/-) in quantity supplied made by Oil Company	KL					
5	Oil supplied by oil company (3+4)	KL		1			
6	Normative Transit & Handling Losses	KL					
7	Net Oil Supplied (5-6)	KL			_		
8	Amount charged by the Oil Company	(Rs)					
0	Adjustment(+/-) in amount charged made by Oil Company	(113)					
9	Adjustificity (1/-) in amount charged made by on company	(Rs)					
10	Handling, Sampling and such other Similar Charges	(Rs)					
11	Total amount charged (8+9+10)	(Rs)					
12	Transportation charges by rail / ship / road transport	(110)					
12	By Rail	(Rs)					
	By Road	(Rs)					
	By Ship	(Rs)	1				
	Adjustment (+/-) in amount charged made by	(110)					
13	Railways/Transport Company	(Rs)					
14	Demurrage Charges, if any	(Rs)					
	Cost of diesel in transporting Oil through MGR system, if	' '					
15	applicable	(Rs)					
16	Total Transportation Charges (12+/-13-14+15)	(Rs)	-		-		
	Total amount Charged for fuel supplied including						
17	Transportation (11+16)	(Rs)	-		-		
18	Landed Cost of Oil (LDO/HFO) (2+17)/(1+7)	(Rs)		80,9	914.96		
19	Blending Ratio		-		1009		
20	Weighted average cost of Secondary Fuel/ For Month	(kCal/Ltr)		80914.96			
	GCV of Oil of the Opening stock as per bill of Oil company						
21		(kCal/Ltr)					
22	GCV of oil supplied as per bill of oil company	(kCal/Ltr)					
	GCV if Imported coal of the opening stock as per bill of Oil						
23	company	(kCal/Ltr)					
24	GCV of Imported Oil supplied as per bill of coal company	(kCal/Ltr)					
25	Weighted average GCV if Oil as billed	(kCal/Ltr)					
26	GCV of Oil of the Opening stock as received at station	(kCal/Ltr)	<u> </u>				
27	GCV of Oil supplied	(kCal/Ltr)					
	GCV of Imported coal of the Opening stock as received at	1, 2					
28	station	(kCal/Ltr)	<u> </u>				
29	GCV of Imported coal supplied as received at station	(kCal/Ltr)	<u> </u>	0000.00			
30	Weighted Average GCV of Secondary Fuel/ as recevied	(kCal/Ltr)	 	9380.00			

Part-I Form-15B ADDITIONAL FORM

Name of the Company	NTPC Limited
Name of the Power Station	Tanda Super Thermal Power Station Stage-I

Computation of Energy Charges

				2024-25	2025-26	2026-27	2027-28	2028-29
1	Rate of Energy Charge from Sec. Fue Oil/ Alternate Fuel (p/kwh)	l (REC)s	$= (Q_s)_n \times P_s$	4.140	4.140	4.140	4.140	4.140
2	Heat Contribution from SFO / Alternate Fuel	e (H _s)	= $(Qs)_n \times (GCV)_s$	4.690	4.690	4.690	4.690	4.690
3	Heat Contribution from coal	$(H_p)_s$	= GHR- H _s	2745.31	2745.31	2745.31	2745.31	2745.31
4	Specific Primary Fuel Consumption	(Qp) _n	$= H_p / (GCV)_p$	0.729	0.729	0.729	0.729	0.729
5	Rate of Energy charge from Primary Fuel (p/kwh)	(REC) _p		446.692	446.692	446.692	446.692	446.692
6	Rate of Energy charge ex-bus (p/kWh)	(REC)	= ((REC) _s + (REC) _p / (1-(AUX))	451.373	451.373	451.373	451.373	451.373

	Part-l
Foi	m-15B
ΔΠΟΙΤΙΟΝΔΙ	FORM

Computation of Energy Charges						
NTPC Limited						
Tanda Super Thermal Power Station Stage-I						·
		2024-25	2025-26	2026-27	2027-28	2028-29
No of Days in the period	Days	365	365	365	366	3
No of Days in the year	Days	365	365	365	366	3
Sp. Oil consumption	ml/kwh	0.5	0.5	0.5	0.5	
Auxiliary consumption	%	12.00%	12.00%	12.00%	12.00%	12.0
Heat Rate	Kcal/Kwh	2,750.00	2,750.00	2,750.00	2,750.00	2,750.
Computation of Variable Charges						
Variable Charge (Coal)	p/kwh	507.604	507.604	507.604	507.604	507.6
Variable Charge (Oil)	p/kwh	4.704	4.704	4.704	4.704	4.7
Total	p/kwh	512.308	512.308	512.308	512.308	512.3
Price of fuel from Form-15/15A						
1 1100 01 1401 110111 1 01111 10/10/1						
Coal Cost	(Rs./MT)	6123.76	6123.76	6123.76	6123.76	6123
Oil Cost	(Rs./MT) (Rs./KL)	6123.76 82793.86	6123.76 82793.86	6123.76 82793.86	6123.76 82793.86	6123 82793
Oil Cost Computation of Fuel Expenses for Calculat ESO in a year	(Rs./KL)	82793.86 2883.09	82793.86 2883.09	82793.86 2883.09	82793.86 2890.99	82793 2883
Oil Cost Computation of Fuel Expenses for Calculat ESO in a year ESO for 50 days	(Rs./KL)	2883.09 394.944	2883.09 394.944	2883.09 394.944	2890.99 394.944	82793 2883 394.
Oil Cost Computation of Fuel Expenses for Calculat ESO in a year ESO for 50 days Cost of coal for 50 Days	(Rs./KL) ion of IWC: (MUs) (MUs) (Rs. Lakh)	2883.09 394.944 20047.52	2883.09 394.944 20047.52	2883.09 394.944 20047.52	2890.99 394.944 20047.52	2883 394. 2004 7
Computation of Fuel Expenses for Calculat ESO in a year ESO for 50 days Cost of coal for 50 Days Cost of oil for 2 months	(Rs./KL) ion of IWC: (MUs) (MUs) (Rs. Lakh) (Rs. Lakh)	2883.09 394.944 20047.52 226.04	2883.09 394.944 20047.52 226.04	2883.09 394.944 20047.52 226.04	2890.99 394.944 20047.52 226.66	288: 394. 2004
Coal Cost Oil Cost Computation of Fuel Expenses for Calculat ESO in a year ESO for 50 days Cost of coal for 50 Days Cost of oil for 2 months Energy Expenses for 45 days	(Rs./KL) ion of IWC: (MUs) (MUs) (Rs. Lakh)	2883.09 394.944 20047.52	2883.09 394.944 20047.52	2883.09 394.944 20047.52	2890.99 394.944 20047.52	2883 394. 2004 7
Computation of Fuel Expenses for Calculat ESO in a year ESO for 50 days Cost of coal for 50 Days Cost of oil for 2 months Energy Expenses for 45 days Coal	(Rs./KL) ion of IWC: (MUs) (MUs) (Rs. Lakh) (Rs. Lakh)	2883.09 394.944 20047.52 226.04	2883.09 394.944 20047.52 226.04	2883.09 394.944 20047.52 226.04	2890.99 394.944 20047.52 226.66	82793 2883
Computation of Fuel Expenses for Calculat ESO in a year ESO for 50 days Cost of coal for 50 Days Cost of oil for 2 months Energy Expenses for 45 days Coal	(Rs./KL) ion of IWC: (MUs) (MUs) (Rs. Lakh) (Rs. Lakh)	2883.09 394.944 20047.52 226.04 18209.98	2883.09 394.944 20047.52 226.04 18209.98	2883.09 394.944 20047.52 226.04 18209.98	2890.99 394.944 20047.52 226.66 18209.98	2883 394. 2004 220 18209
Computation of Fuel Expenses for Calculat ESO in a year ESO for 50 days Cost of coal for 50 Days Cost of oil for 2 months Energy Expenses for 45 days Coal Wtd. Avg. Price of Coal	(Rs./KL) ion of IWC: (MUs) (MUs) (Rs. Lakh) (Rs. Lakh)	2883.09 394.944 20047.52 226.04 18209.98	2883.09 394.944 20047.52 226.04 18209.98	2883.09 394.944 20047.52 226.04 18209.98	2890.99 394.944 20047.52 226.66 18209.98	2883 394 2004 220 18209
Computation of Fuel Expenses for Calculat ESO in a year ESO for 50 days Cost of coal for 50 Days Cost of oil for 2 months Energy Expenses for 45 days Coal Wtd. Avg. Price of Coal Wtd. Avg. GCV of Coal as received	(Rs./KL) ion of IWC: (MUs) (MUs) (Rs. Lakh) (Rs. Lakh) (Rs. Lakh)	2883.09 394.944 20047.52 226.04 18209.98 2024-25 6123.76	2883.09 394.944 20047.52 226.04 18209.98	2883.09 394.944 20047.52 226.04 18209.98 2026-27 6123.76	2890.99 394.944 20047.52 226.66 18209.98 2027-28 6123.76	2883 394. 20047 220 18209
Computation of Fuel Expenses for Calculat ESO in a year ESO for 50 days Cost of coal for 50 Days Cost of oil for 2 months Energy Expenses for 45 days Coal Wtd. Avg. Price of Coal Wtd. Avg. GCV of Coal as received Wtd. Avg. GCV of Coal as received after adjustement of 85 kcal/kg	(Rs./KL) ion of IWC: (MUs) (MUs) (Rs. Lakh) (Rs. Lakh) (Rs. Lakh) (Rs. Lakh)	2883.09 394.944 20047.52 226.04 18209.98 2024-25 6123.76 3848.58	2883.09 394.944 20047.52 226.04 18209.98 2025-26 6123.76 3848.58	2883.09 394.944 20047.52 226.04 18209.98 2026-27 6123.76 3848.58	2890.99 394.944 20047.52 226.66 18209.98 2027-28 6123.76 3848.58	2883 3944 2004 220 18209 2028-2 6123 3848
Computation of Fuel Expenses for Calculat ESO in a year ESO for 50 days Cost of coal for 50 Days Cost of oil for 2 months Energy Expenses for 45 days Coal Wtd. Avg. Price of Coal Wtd. Avg. GCV of Coal as received	(Rs./KL) ion of IWC: (MUs) (MUs) (Rs. Lakh) (Rs. Lakh) (Rs. Lakh) (Rs. Lakh)	2883.09 394.944 20047.52 226.04 18209.98 2024-25 6123.76 3848.58	2883.09 394.944 20047.52 226.04 18209.98 2025-26 6123.76 3848.58	2883.09 394.944 20047.52 226.04 18209.98 2026-27 6123.76 3848.58	2890.99 394.944 20047.52 226.66 18209.98 2027-28 6123.76 3848.58	2883 3944 2004 220 18209 2028-2 6123 3848

78

																PART- FORM-
					Sta	tement of Ca	pital cost									FUKIVI-
	of the Petitioner	NTPC Limited	-													
	of the Generating Station		Thermal Po	wer Station Sta	age-l											
COD		14-01-2000														
or Fi	nancial Year	2024-29														
<u> </u>	D # 1		2224.25				1									Rs Lal
SI. No.	Particulars	Accrual	2024-25 Un-	Cash Basis	Accrual	2025-26 Un-	Cash	Accrual	2026-27 Un-	Cash	Accrual	2027-28 Un-	Cash	Accrual	2028-29 Un-	Ca
NO.		Basis	discharged	Cash basis	Basis	-	Basis	Basis	discharged	Basis	Basis		Basis	Basis		Ba
		Dasis	Liabilities		Dasis	Liabilities	Dasis	Dasis	Liabilities	Dasis	Dasis	Liabilities	Dasis	Dasis	Liabilities	Ба
	a) Opening Gross Block Amount as per	1,47,804.53	546.48	1,47,258.05			-			!						
	books	.,,		.,,												
	b) Amount of IDC in A(a) above	4,058.92		4,058.92												
	c) Amount of FC in A(a) above	0.00		-	SHALL BE PROVIDED AT THE TIME OF TRUE-UP.											
	d) Amount of FERV in A(a) above	4,120.65		4,120.65												
	e) Amount of Hedging Cost in A(a) above	0.00		-												
	f) Amount of IEDC in A(a) above	0.00		-												
	a) Addition in Gross Block Amount during															
	the period (Direct purchases)															
-	b) Amount of IDC in B(a) above															
d	c) Amount of FC in B(a) above															
	d) Amount of FERV in B(a) above															
-	e) Amount of Hedging Cost in B(a) above															
	f) Amount of IEDC in B(a) above															
-	a) Addition in Gross Block Amount during															
	the period (Transferred from CWIP)															
	b) Amount of IDC in C(a) above															
С	c) Amount of FC in C(a) above	-														
	d) Amount of FERV in C(a) above	4														
	e) Amount of Hedging Cost in C(a) above															
	f) Amount of IEDC in C(a) above					SHA	LL BE PR	OVIDED A	T THE TIME	OF TRUE	E-UP.					
	a) Deletion in Gross Block Amount during															
-	the period															
	b) Amount of IDC in D(a) above	-														
	c) Amount of FC in D(a) above d) Amount of FERV in D(a) above	-														
	e) Amount of FERV III D(a) above	1														
	f) Amount of IEDC in D(a) above	-														
	a) Closing Gross Block Amount as per	-														
-	books															
-	b) Amount of IDC in E(a) above	1														
	c) Amount of FC in E(a) above	1														
	d) Amount of FERV in E(a) above	1														
	e) Amount of Hedging Cost in E(a) above	1														
1	, , , , , , , , , , , , , , , , , , , ,	1														
	f) Amount of IEDC in E(a) above	1														

Petitioner

																PAI FORM
				Si	atement	of Capital Wo	rks in P	rogress								
am	e of the Petitioner	NTPC Limit	ed					- 3								
	e of the Generating Station		r Thermal Po	ower Statio	n Stage-l											
COD	or the Contrating Station	14-01-2000		onor otatio	n otago i											
	inancial Year	2024-29														
•••	manolal real	2024-23													(Amount in	De L
SI.	Particulars	2024-25 2025-26							2026-27			2027-28			2028-29	NS LC
No.	Particulars	ccrual Basis		Cash	Accrual	2025-26 Un-	Cash	Accrual	Un-	Cash	Accrual	Un-	Cash	Accrual	Un-	Ca
NO.		CCI uai Dasis	discharged	Basis	Basis	discharged	Basis	Basis	discharged	Basis	Basis	discharged	Basis	Basis	discharged	1
			Liabilities	Dasis	Dasis	Liabilities	Dasis	Dasis	Liabilities	Dusis	Dasis	Liabilities	Dasis	Dusis	Liabilities	Das
_	a) Opening CWIP as per books	2,514.70		2,265.15												
	b) Amount of IDC in A(a) above	2,514.70	249.00	2,203.13	1											
	c) Amount of FC in A(a) above	_		_	†											
Α	d) Amount of FERV in A(a) above			_	SHALL BE PROVIDED AT THE TIME OF TRUE-UP.											
	e) Amount of Hedging Cost in A(a) above	_		_	†											
	f) Amount of IEDC in A(a) above	-			†											
	a) Addition in CWIP during the period	-	1													
	b) Amount of IDC in B(a) above															
В	c) Amount of FC in B(a) above															
D	d) Amount of FERV in B(a) above	1														
	e) Amount of Hedging Cost in B(a) above	1														
	f) Amount of IEDC in B(a) above															
	a) Transferred to Gross Block Amount during the	4														
	b) Amount of IDC in C(a) above	_														
С	c) Amount of FC in C(a) above d) Amount of FERV in C(a) above	-														
	e) Amount of Hedging Cost in C(a) above	1														
	f) Amount of IEDC in C(a) above															
	a) Deletion in CWIP during the period					SI	HALL BE	PROVIDED	AT THE TIME	E OF TRU	E-UP.					
	b) Amount of IDC in D(a) above															
D	c) Amount of FC in D(a) above															
	d) Amount of FERV in D(a) above															
	e) Amount of Hedging Cost in D(a) above															
	f) Amount of IEDC in D(a) above	4														
	a) Closing CWIP as per books b) Amount of IDC in E(a) above	1														
	c) Amount of IDC in E(a) above	1														
Е	d) Amount of FERV in E(a) above	1														
	e) Amount of Hedging Cost in E(a) above	1														

Petitioner

								PART-I FORM- N
		Calculation of	of Interest on No	rmative Loan				
lame	of the Company :		NTPC Limited					
lame	of the Power Station :		Tanda Super T	hermal Power	Station Stage-	1		
							(Amoun	t in Rs Lak
S. No.	Particulars		Existing 2023-24	2024-25	2025-26	2026-27	2027-28	2028-29
1	2		3	4	5		6	8
1	Gross Normative Ioan – Opening	Α	86,951.44	87,327.68	88,173.63	91,016.33	92,936.17	93,027.1
2	Cumulative repayment of Normative loan up to previous year	В	86,951.44	87,327.68	88,173.63	88,466.24	89,107.16	89,914.0
3	Net Normative Ioan – Opening	C=A-B	-	-	-	2,550.09	3,829.01	3,113.1
4	Add: Increase due to addition during the year / period	D	561.32	845.95	2,842.70	1,919.85	91.00	
5	Less: Decrease due to de-capitalisation during the year / period	E	191.25	-	-	-	-	
6	Less: Decrease due to reversal during the year / period	F		-	-	-	-	
7	Add: Increase due to discharges during the year / period	G	6.17	-	-	-	-	-
8	Normative Loan Closing	H=C+D-E-F+G	376.23	845.95	2842.70	4469.93	3920.01	3113.
9	Repayment of Loan during the year]	376.23	845.95	292.61	640.92	806.87	815.
10	Repayment adjustment on account of decapitalization	J	0.00	0.00	0.00	0.00	0.00	0.
11	Net Repayment of loan during the year	K=I-J	376.23	845.95	292.61	640.92	806.87	815.4
12	Net Normative loan - Closing	L=H-K	-	-	2,550.09	3,829.01	3,113.14	2,297.6
13	Average Normative Ioan	M=Average(C,L)	-	-	1,275.04	3,189.55	3,471.08	2,705.4
14	Weighted average rate of interest	N	7.7980%	7.7868%	7.8715%	8.0240%	8.0125%	7.9868
15	Interest on Loan	O=MxN	0.00	0.00	100.36	255.93	278.12	216.
15	Cumulative repayment of Normative loan at the end of the period	P=B+K	87,327.68	88,173.63	88,466.24	89,107.16	89,914.03	90,729.

(Petitioner)

							PART 1
							FORM- C
		Calculation	on of Interest on V	Vorking Capital			
Name	of the Company :	NTPC Limited					
	of the Power Station :	Tanda Super Thermal Power Station Stage-I					
						(Amo	unt in Rs Lakh
S. No	. Particulars	Existing 2023-24	2024-25	2025-26	2026-27	2027-28	2028-29
1	2	3	4	5	6	7	8
1	Cost of Coal/Lignite	18,798.11	20047.52	20047.52	20047.52	20047.52	20047.52
2	Cost of Main Secondary Fuel Oil	226.37	226.04	226.04	226.04	226.66	226.04
3	Fuel Cost						
4	Liquid Fuel Stock						
5	O & M Expenses	1,833.18	1824.75	1841.31	1859.07	1878.12	1898.56
6	Maintenance Spares	4,399.63	4379.40	4419.15	4461.77	4507.48	4556.53
7	Receivables	21,897.35	23007.53	22591.80	22706.20	22756.79	22794.92
8	Total Working Capital	47154.64	49485.24	49125.83	49300.60	49416.57	49523.58
9	Rate of Interest	12.00%	11.90%	11.90%	11.90%	11.90%	11.90%
10	Interest on Working Capital	5658.56	5888.74	5845.97	5866.77	5880.57	5893.31

	Summa	ry of issue involved i	n the petition			PART FORM-	
Name of	f the Company :	NTPC Limited					
	f the Power Station :	Tanda Super Therma	al Power Station	n Stage-I			
1	Petitioner:	TPC Limited					
2 Subject Determination of Tariff for 2024-29 period							
3	Prayer: i)Approve tariff of Tanda Super Thermal Power Station Stage-I (4x110 MW) for the period from 01.04.2024 to 31.03.2029. ii)Allow the recovery of filing fees as & when paid to the Hon'ble Commission and publication expenses from the beneficiaries. iii)Allow reimbursement of Ash Transportation Charges directly from the beneficiaries on monthly basis, subject to true up. iv)Grant liberty to approach the Hon'ble Commission to allow for the recovery of pay/wage revision due in 2024-29 period as additional O&M over and above the normative O&M. v)Pass any other order as it may deem fit in the circumstances mentioned above						
4	Respondents						
	Name of Respondents						
	Uttar Pradesh Power Corp. Ltd	L (UPPCL)					
	Rajasthan Urja Vikas Nigam Limited (RUVNL) Tata Rayar Palki Distribution Limited						
	3. Tata Power Delhi Distribution Limited						
	BSES Rajdhani Power Limited. BSES Yamuna Power Limited,						
	6. Haryana Power Purchase Cen	tro					
	,						
	7. Punjab State Power Corporation Limited, 8. Himachal Pradesh State Electricity Board Limited,						
	B. Himachai Pradesh State Electricity Board Limited, Power Development Department (J&K)						
	10. Electricity Department, Union Territory of Chandigarh						
	11. Uttarakhand Power Corporation Limited.						
	11. Ottaraknand Power Corporation Limited.						
5	Project Scope						
	Capital Cost as on 01.04.2024	404======					
	(Rs. Lakh)	124753.82					
	Date of Station COD			14-01-2000			
	Claim (Rs Lakh)	2024-25	2025-26	2026-27	2027-28	2028-29	
	AFC	38,929.73	35,541.40	36,469.31	36,980.73	37,188.98	
	Closing Capital Cost	1,25,962.32	1,30,023.32	1,32,765.96	1,32,895.96	1,32,895.96	
	Initial spare			N/A			
	NAPAF (Gen) 85%						
	Any Specific						
	Any Specific					Pe	

ANNEXURE-R1



भारत सरकार
Government of India
विद्युत मंत्रालय
Ministry of Power
केन्द्रीय विद्युत प्राधिकरण
Central Electricity Authority
सूचना प्रौद्योगिकी एवं साइबर सुरक्षा प्रभाग
Information Technology & Cyber Security Division

विषय: CEA (Cyber Security in Power Sector) Guidelines, 2021.

CEA is mandated to prepare 'Guidelines on Cyber Security' in Power Sector under the provision of regulation (10) of the Central Electricity Authority (Technical Standards for Connectivity to the Grid) (Amendment) Regulations, 2019. Guidelines on Cyber Security in Power Sector incorporating the cardinal principles has been prepared by CEA. In compliance to the provision of the above regulation, CEA (Cyber Security in Power Sector) Guidelines, 2021 are issued for compliance by all entities listed in the clause 2.3 (Applicability of the Guidelines) of the guidelines.

Encl: Guidelines on Cyber Security

(V.K Mishra) Secretary CEA

CEA (Cyber Security in Power Sector) Guidelines, 2021

1.0 Background

- 1.1 Cyber intrusion attempts and Cyber-attacks in any critical sector are carried out with a malicious intent. In Power Sector it's either to compromise the Power Supply System or to render the grid operation in-secure. Any such compromise, may result in maloperations of equipments, equipment damages or even in a cascading grid brownout/blackout. The much hyped air gap myth between IT and OT Systems now stands shattered. The artificial air gap created by deploying firewalls between any IT and OT System can be jumped by any insider or an outsider through social engineering. Cyber-attacks are staged through tactics & techniques of Initial Access, Execution, Persistence, Privilege Escalation, Defence Evasion, Command and Control, Exfiltration. After gaining the entry inside the system through privilege escalation, the control of IT network and operations of OT systems can be taken over even remotely by any cyber adversary. The gain of sensitive operational data through such intrusions may help the Nation/State sponsored or non-sponsored adversaries and cyber attackers to design more sinister and advanced cyber-attacks.
- Government of India has set up the Indian Computer Emergency Response Team (CERT-In) for Early Warning and Response to cyber security incidents and to have collaboration at National and International level for information sharing on mitigation of cyber threats. CERT-In regularly issues advisories on safeguarding computer systems and publishes Security Guidelines which are widely circulated for compliances. All Central Government Ministries/ Departments and State/Union Territory Governments have been advised to conduct cyber security audit of their entire Cyber Infrastructure including websites at regular interval through CERT-In empanelled Auditors so as to identify gaps and appropriate corrective actions to be taken in cyber security practices. CERT-In extends supports to enable Responsible Entity in conducting cyber security mock drills and in assessment of their preparation to withstand cyber-attacks. The Responsible Entity must submit Reports of Cyber Audit of cyber security controls, architecture, vulnerability management, network security and periodic cyber security drills to sectoral CERT as well as CERT-In. Team of experts shall review these reports and shortcomings if any in the compliances shall be flagged by them. CERT-In on regular basis also conducts workshops and training programs to enhance Cyber awareness of all Stakeholders.
- 1.3 Ministry of Power has created 6(six) sectoral CERTs namely Thermal, Hydro, Transmission, Grid Operation, RE and Distribution for ensuring cyber security in Indian Power Sector. Each Sectoral CERT has prepared their sub-sector specific model Cyber Crisis Management Plan(C-CMP) for countering cyber-attacks and cyber terrorism. Each Sectoral CERT has circulated their model C-CMPs for preparation and implementation of organization specific C-CMP by each of their Constituent Utility.
- 1.4 All Responsible Entities, Service Providers, Equipment Suppliers/Vendors and Consultants engaged in Power Sector are equally responsible for ensuring cyber security of the Indian Power Supply System. They are to act timely upon each threat intelligence,

advisories and other inputs received from authenticated sources, for continuous improvement in their cyber security posture.

- 1.5 In the current Indian scenario though many cyber security directives and guidelines exists, but none of them are power sector specific. Ministry of Power has directed CEA to prepare Regulation on Cyber Security in Power Sector. And as an interim measures CEA has been directed to issue Guideline on Cyber Security in Power Sector, under the provision of Regulation 10 on Cyber Security in the "Central Electricity Authority (Technical Standards for Connectivity to the Grid) (Amendment) Regulations, 2019".
- 1.6 The Guidelines on Cyber Security, in the form of Articles written below, requires mandatory Compliance by all Responsible Entities. The Guidelines shall come into effect from the date of issue by Central Electricity Authority, New Delhi.
- 2.0 Hereby the Guidelines on Cyber Security are drawn in the form of Articles for compliance by the Requester as well as User under the following provision of Regulation 10 on Cyber Security, in the "Central Electricity Authority (Technical Standards for Connectivity to the Grid) (Amendment) Regulations, 2019".

"The requester and the user shall comply with cyber security guidelines issued by the Central Government, from time to time, and the technical standards for communication system in Power Sector laid down by the Authority."

2.1 **Objective of issuing Guideline**:

- a) Creating cyber security awareness
- b) Creating a secure cyber ecosystem,
- c) Creating a cyber-assurance framework,
- d) Strengthening the regulatory framework,
- e) Creating mechanisms for security threat early warning, vulnerability management and response to security threats,
- f) Securing remote operations and services,
- g) Protection and resilience of critical information infrastructure,
- h) Reducing cyber supply chain risks,
- i) Encouraging use of open standards,
- j) Promotion of research and development in cyber security,
- k) Human resource development in the domain of Cyber Security,
- 1) Developing effective public private partnerships,
- m)Information sharing and cooperation
- n) Operationalization of the National Cyber Security Policy

2.2 Within the text of these Articles, 'Responsible Entity' shall mean all:

- a) Transmission Utilities as well as Transmission Licensees.
- b) Load despatch centres (State, Regional and National),
- c) Generation utilities (Hydro, Thermal, Nuclear, RE),
- d) Distribution Utilities
- e) Generation Aggregators,
- f) Trading Exchanges,
- g) Regional Power Committees, and
- h) Regulatory Commissions.

2.3 Applicability:

All Responsible Entities as well as System Integrators, Equipment Manufacturers, Suppliers/Vendors, Service Providers, IT Hardware and Software OEMs engaged in the Indian Power Supply System.

2.4 Scope:

2.4.1 Control Systems for System Operation and Operation Management.

- a) Grid Control and Management Systems,
- b) Power Plant Control Systems,
- c) Central Systems used to monitor and control of distributed generation and loads e.g. virtual power plants, storage management, central control rooms for hydroelectric plants, photovoltaic/wind power installations,
- d) Systems for fault management and work force management,
- e) Metering and measurement management systems,
- f) Data archiving systems,
- g) Parameterisation, configuration and programming systems,
- h) Supporting systems required for operation of the above mentioned systems,

2.4.2 Communication System.

- a) Routers switches and firewalls,
- b) Communication technology-related network components,
- c) Wireless digital systems.
- d) Control Centre to Control Centre Communications for data exchange on ICCP. (IEC 61850/60850-5/TASE.2/)

2.4.3 Secondary, Automation and Tele control technologies

- a) Control and Automation components,
- b) Control and field devices,
- c) Tele control devices,
- d) Programmable logic controllers / Remote Terminal Units, including digital sensor and actuators elements.
- e) Protection devices,
- f) Safety components,
- g) Digital measurement and metering installations,
- h) Synchronisation devices,
- i) Excitation Systems,

3.0 Definition of Terms:

- 1. **Access Management**: shall mean set of policies and procedures of the Responsible Entity for allowing Personnel, devices and IoT to securely perform a broad range of operational, maintenance, and asset management tasks either on site or remotely as laid down in Clause 5.2.5 of IS 16335.
- 2. **Accreditation:** shall mean the process of verifying that an organisation is capable of conducting the tests and assessments against a product/process that are required to be certified.

- 3. **Accreditation Body:** shall mean an organisation that has been accredited to verify the credentials and capabilities of the organisations that wish to become a certification body.
- 4. **Act:** shall mean the Information Technology Act, 2000 (21 of 2000)
- 5. **Asset**: shall mean anything that has value to the organization.
- 6. **Certification:** shall mean the process of verifying that a product has been manufactured in conformance with a set of predefined standards and/or regulations by an organisation, that is accredited to conduct the certification process
- 7. **Certification Body:** shall mean an organisation that has been accredited by an accreditation body to certify products / process against a certification scheme.
- 8. **Certification Scheme:** shall mean the processes, paperwork, tools, and documentation that define how a product or manufacturer is certified
- 9. **Chief Information Security Officer:** shall means the designated employee of Senior management level directly reporting to Managing Director/Chief Executive Officer/Secretary of the Responsible Entity, having knowledge of Information Security and related issues, responsible for cyber security efforts and initiatives including planning, developing, maintaining, reviewing and implementation of Information Security Policies
- 10. **Critical Assets:** shall mean the facilities, systems and equipment which, if destroyed, degraded or otherwise declared unavailable, would affect the reliability or operability of the Power Supply System.
- 11. **Critical System:** shall mean cyber assets essential to the reliable operation of critical asset. Critical System consists of those cyber assets that have at least one of the following characteristics:
 - a) The cyber asset uses a routable protocol to communicate outside the electronic security perimeter.
 - b) The cyber asset uses a routable protocol within a control centre.
 - c) The cyber asset is dial-up accessible.
- 12. **Critical Information Infrastructure:** shall mean Critical Information Infrastructure as defined in explanation of sub-section (1) of Section 70 of the Act.
- 13. **Cyber Assets**: shall mean the programmable electronic devices, including the hardware, software and data in those devices that are connected over a network, such as LAN, WAN and HAN.
- 14. **Cyber Crisis Management Plan:** shall mean a framework for dealing with cyber related incidents for a coordinated, multi-disciplinary and broad-based approach for rapid identification, information exchange, swift response and remedial actions to mitigate and recover from malicious cyber related incidents impacting critical processes.
- 15. **Cyber Security Breach**: shall mean any cyber incident or cyber security violation that results in unauthorized or illegitimate access or use by a person as well as an entity, of data, applications, services, networks and/or devices through bypass of the underlying cyber security protocols, policies and mechanisms resulting in the compromise of the confidentiality, integrity or availability of data/information maintained in a computer resource or cyber asset.
- 16. **Cyber Security Incident:** shall mean any real or suspected adverse cyber security event that violates, explicitly or implicitly, cyber security policy of Responsible Entity resulting in unauthorized access, denial of service or disruption, unauthorized use of computer resource for processing or storage of information or changes to data or information

- without authorization, leading to harm to the power grid or its critical sub-sectoral elements Generation, Transmission and Distribution.
- 17. **Cyber Security Policy:** shall mean documented set of business rules and processes for protecting information, computer resources, networks, devices, Industrial Control Systems and other OT resources.
- 18. **Electronic Security Perimeter:** shall mean the logical border surrounding a network to which the Cyber Systems of Power Supply System are connected using a routable protocol.
- 19. **Information Security Division:** shall mean a division accountable for cyber security and protection of the Critical System of the Responsible Entity.
- 20. **Protected System:** shall mean any computer, computer system or computer network of the Responsible Entity notified under section 70 of the Act, in the official gazette by appropriate Government.
- 21. **Security Architecture:** shall mean a framework and guidance to implement and operate a system using the appropriate security controls with the goal to maintain the system's quality attributes like confidentiality, integrity, availability, accountability and assurance.
- 22. **Vulnerability:** shall mean intrinsic properties of something resulting in susceptibility to a risk source that can lead to an event with a consequence
- 23. **Vulnerability Assessment:** shall mean a process of identifying and quantifying vulnerabilities

4.0 Standards

Reference	Description			
ISO/IEC 15408	Common Criteria Certification Standard			
ISO/IEC 17011	General requirements for accreditation bodies accrediting conformity assessment bodies			
ISO/IEC 17025	General requirements for the competence of testing and calibration laboratories			
ISO/IEC 21827	Systems Security Engineering - Capability Maturity Model (SSE-CMM)			
ISO/IEC 24748-1	Systems and software engineering — Life cycle management — Part 1: Guidelines for life cycle management.			
ISO 27001/2	Information Security Management			
ISO/ IEC 27019	Information technology — Security techniques — Information Security controls for the energy utility industry			
ISO/IEC 61508	Functional Safety of Electrical / Electronic / Programmable Electronic Safety-related Systems			
IEC 61850	Communication networks and systems for power utility automation			
IEC 62351	Standards for Securing Power System Communications			
IEC 62443	Cyber Security for Industrial Control Systems			
IS 16335	Power Control Systems – Security Requirements.			

5.0 Abbreviations

Abbreviations		Description		
a)	BES	Bulk Electric System		

b)	CDAC	Centre for Development of Advanced Computing
c)	CEA	Central Electricity Authority
d)	CERC	Central Electricity Regulatory Commission
e)	CERT	Computer Emergency Response Team
f)	CERT-In	Indian Computer Emergency Response Team
g)	CII	Critical Information Infrastructure
h)	CISO	Chief Information Security Officer
i)	CSK	Cyber Swachhta Kendra
j)	COTS	Commercial off-the Shelf
k)	ESP	Electronic Security perimeter
1)	ICS	Industrial Control Systems
m)	ICT	Information and Communications Technology
n)	IEC	International Electro Technical Commission
o)	ISAC	Information Sharing and Analysis Centre
p)	ISD	Information Security Division
q)	ISO	International Organization for Standardization
r)	ISMS	Information Security Management System
s)	IT	Information Technology
t)	FAT	Factory Acceptance Test
u)	NABL	National Accreditation Board for Testing and Calibration Laboratories
v)	NCIIPC	National Critical Information Infrastructure Protection Centre
w)	NLDC	National Load Dispatch Centre
x)	NPTI	National Power Training Institute
y)	NSCS	National Security Council Secretariat
z)	OEM	Original Equipment Manufacturer
aa)	OT	Operational Technology
bb)	RLDC	Regional Load Dispatch Centres
cc)	SAT	Site Acceptance Test
dd)	SERC	State Electricity Regulatory Commission
ee)	SCADA	Supervisory Control and Data Acquisition Systems
ff)	SIEM	Security Information and Event Management
gg)	SLA	Service Level Agreement
hh)	SLDC	State Load Dispatch Centre
::>	OCI	O1:4 O:1 - C.I 1:-

QCI

ii)

Quality Council of India

CEA (Cyber Security in Power Sector) Guidelines, 2021

Article 1. Cyber Security Policy.

a. Cardinal Principles: The Responsible entity will strictly adhere to following cardinal principles while framing cyber security policy:

- i. There is hard isolation of their OT Systems from any internet facing IT system.
- ii. May keep only one of their IT systems with internet facing at any of their site/location if required which is isolated from all OT zones and kept in a separate room under the security and control of CISO.
- iii. Downloading/Uploading of any data/information from their internet facing IT system is done only through an identifiable whitelisted device followed by scanning of both for any vulnerability/malware as per the SOP laid down and for all such activities digital logs are maintained and retained under the custody of CISO for at least 6 months. The log shall be readily to carry out the forensic analysis if asked by investigation agency.
- iv. List of whitelisted IP addresses for each firewall is maintained by CISO and each firewall is configured for allowing communication with the whitelisted IP addresses only.
- v. Communication between OT equipment/systems is done through the secure channel preferably of POWERTEL through the fibre optic cable. Security configuration of the communication channel is also to be ensured.
- vi. All ICT based equipment/system deployed in infrastructure/system mandatorily CII are sourced from the list of the "Trusted Sources" as and when drawn by MoP/CEA.
- b. The Responsible Entity shall be ISO/IEC 27001 certified (including sector specific controls as per ISO/IEC 27019).
- c. The Responsible Entity shall have a Cyber Security Policy drawn upon the guidelines issued by NCIIPC.
- d. The Responsible Entity shall ensure annual review of their Cyber Security Policy by subject matter expert and changes shall be made therein only after obtaining the due approval from Board of Directors.
- e. The process of Access Management for all Cyber Assets owned or under control of the Responsible Entity shall be detailed in the Cyber Security Policy.
- f. The Cyber Security Policy shall leverage state-of-art cyber security technologies and relevant processes at multiple layers to mitigate the cyber security risks.
- g. The Responsible Entity shall be solely responsible to get Cyber Security Policy implemented through its Information Security Division (ISD).
- h. The CISO shall record the reason(s) for exemption required, if any, in case, unable to comply with any of the provision(s) of the Cyber Security Policy. Any exception shall be allowed only after an approval of provisions of compensatory control(s) to mitigate residual cyber security risks.

- i. The CISO shall record the exemptions sought in statement of applicability controls, while getting the ISO 27001 certified. All exemptions and its justification need to be in conformance with Cyber Security Policy of the Responsible Entity.
- j. The Responsible Entity shall allocate sufficient Annual budget for enhancing cyber security posture, enhanced year over year.
- k. The Responsible Entity shall work in collaboration with other Industry Stakeholders as well as Academia to promote R&D activity in the domain of cyber security.
- 1. The Responsible Entity shall ensure that cyber security issues are taken up as agenda items in their Board meetings once in every three months.

Article 2 Appointment of CISO.

- a) The Responsible Entity shall mandatorily appoint a CISO and shall confirm to qualification, if any, **laid** by Quality Council of India (QCI). In absence, the work of CISO shall be looked upon by Alternate CISO. In case qualification for appointment of Alternate CISO has been relaxed for reasons recorded thereof, Alternate CISO has to mandatorily acquire the minimum required cyber security skill sets within six months from the date of his appointment.
- b) The Responsible Entity shall regularly update details of CISO and Alternate CISO, with the Sectoral CERT, as well as on ISAC-Power Portal.
- c) Roles and Responsibility of CISOs shall be as laid by CERT-In and ring-fenced to ensure cyber security of the Cyber Assets of the Responsible Entity.

Article 3: Identification of Critical Information Infrastructure (CII).

- a) The Responsible Entity shall submit to NCIIPC through Sectoral CERT, details of Cyber Assets which uses a routable protocol to communicate outside the Electronic Security Perimeter drawn by the Responsible Entity or a routable protocol within a control centre and dial-up accessible Cyber Assets, within 30 days from the date of their commissioning in the System.
- b) The Responsible Entity shall submit details of Critical Business Processes and underlying information infrastructure along with mapped impact and Risk Profile to NCIIPC and shall get their CIIs identified in consultation with NCIIPC. The process of the notification/declaration by Appropriate Government shall follow thereafter.
- c) The Responsible Entity shall review their declared/notified CIIs at least once a year to examine changes if any in the functional dependencies, protocols and technologies or upon any change in security architecture. The Responsible Entity shall review their declared/notified CIIs once in every 6 months, in case if NCIIPC has directed them to constitute an Information Security Steering Committee.
- d) The Responsible Entity shall ensure that all cyber assets of their identified/notified CIIs are recorded in the asset register and considered for risk assessment as well as for finalization of controls in statement of applicability.

Article 4. Electronic Security Perimeter

a) The Responsible Entity shall identify and document the Electronic Security Perimeter(s) and all Access Points to the perimeter(s).

- b) The Responsible Entity shall follow procedure of identifying "Electronic Security Perimeter" in case of distributed and/or hybrid information infrastructure, as per IEC 62443 / IS16335 (as amended from time to time).
- c) The Responsible Entity shall ensure that every Critical System resides within an Electronic Security Perimeter.
- d) The Responsible Entity shall perform a cyber-Vulnerability Assessment of each electronic Access Points to the Electronic Security Perimeter(s) at least once in every 6 (six) months and/or after any change in Security Architecture.
- e) The Responsible Entity shall ensure that all critical, high and medium vulnerabilities identified as a result of cyber Vulnerability Assessment shall be closed and verified for the effective closure.

Article 5. Cyber Security Requirements

- a) The Responsible Entity shall have an Information Security Division (ISD), headed by CISO.
- b) The Responsible Entity shall ensure that the ISD must be functional on 24x7x365 basis and is manned by sufficient numbers of Engineers having valid certificate of successful completion of course on cyber security of Power Sector from the Training Institutes designated by CEA.
- c) The Responsible Entity shall ensure that ISD
 - 1) has on-boarded Cyber Swachhta Kendra(CSK) of CERT-In, if they have public IPs
 - 2) has timely acted upon the advisories, guidelines and directive of NCIIPC, CSK, CERT-In and Sectoral CERTs,
 - 3) has deployed an Intrusion Detection System and Intrusion Prevention System capable of identifying behavioural anomaly in both IT as well as OT Systems.
 - 4) shares reports on incident response and targeted malware samples with CERT-In,
 - 5) updates the firmware/software with the digitally signed OEM validated patches only.
 - 6) enables only those ports and services that are required for normal operations. In case of any emergency the procedure as laid in Access management be followed.
 - 7) maintains firewall logs for the last 6 months duration. Firewall logs shall be analysed and all critical and high severity comments shall be addressed for effective closure.
 - 8) retains document of FAT, SAT test results and report/ certificate of cyber tests carried out for compliance of Government Orders and Cyber Security Audit.*
 - 9) maintains all cyber logs and cyber forensic records of any incident for at least** 90 days.
 - * FAT, SAT must include comprehensive cyber security tests of the component/equipment/system to be delivered/delivered at site.
 - ** 90 days from date of the commissioning of the system/recovery from any incident, whichever is later.
- d) The Responsible Entity shall routinely audit and test security properties of the Critical System and must act upon, in case if any new vulnerabilities is identified through testing or by the equipment manufacturer.

- e) The Responsible Entity shall design a secure architecture for control system appropriate for their process control environment*.
- f) All State Load Dispatch Centres(SLDCs) shall comply with the directions issued by the National Load Dispatch Centre(NLDC) as well as Regional Load Dispatch Centres(RLDCs) U/s 29 (1) of the Electricity Act, 2003 to ensure stability and cyber security of grid operation and achieve efficiency in the grid operation. In case of any non-compliance, the Head of SLDC shall be responsible and shall be liable for Penalty as per the provision of CERC/SERC.

*There are so many different types of systems in existence and so many possible solutions, it is important that the selection process ensures that the level of protection is commensurate with the business risk and the Responsible Entity shall not rely on one single security measure for its defence. (Reference IEC/TR62351-10 Edition1.0 2012-10 Power systems management and associated information exchange –Data and communications security – Part 10: Security architecture guidelines).

Article 6 Cyber Risk Assessment and Mitigation Plan

- a) The Responsible Entity shall document in their Cyber Security Policy a Cyber Risk Assessment and Mitigation Plans drawn upon the best practises being followed in the Power Sector, and the same shall be approved by Board of Directors.
- b) The Cyber Risk Assessment and Mitigation Plans shall clearly define the matrix for assessing the cyber risk of both IT and OT environment and risk acceptance criteria.
- c) The Cyber Risk Assessment Plan shall be capable to demonstrate that repeated cyber security risk assessment delivers consistent, valid and comparable results.
- d) The review of cyber risk assessment shall be carried out at least once in a Quarter. The actionable of risk treatment and mitigation shall be tracked in this review for their effectiveness.
- e) The CISO shall be responsible for implementation and regular review, on the basis of internal and external feedbacks, of the Cyber Risk Assessment and Mitigation Plans.

Article 7 Phasing out of Legacy System

- a) As the life cycle of the Power System Equipment/System is longer than that of IT Systems deployed therein, the Responsible Entity shall ensure that all IT technologies in the Power System Equipment/System should have the ability to be upgraded.
- b) The Responsible Entity shall ensure that the Information Security Division shall draw the list of all communicable equipments/systems nearing end life or are left without support from OEM. Thereafter CISO shall identify equipment/systems to be phased out from the list drawn, firm up their replacement plan and put up the replacement plan for approval before the Board of Directors.
- c) The CISO shall ensure that till equipments/systems nearing end life or left without support from OEM are not replaced, their cyber security is hardened and ensured through additional controls provisioned in consultation with the OEM or alternate Supplier(s)*.
 - *e.g. Use of CDAC developed AppSamvid and whitelisting of applications installed may be explored across all legacy systems.
- d) The Responsible Entity shall document in their Cyber Security Policy a Standard Operating Procedure for safe and secure disposal of outlived or legacy devices.

Article 8. Cyber Security Training.

- a) The Responsible Entity shall establish, document, implement, and maintain an annual cyber security training program for personnel having authorized cyber or authorized physical access (unescorted or escorted) to their Critical Systems.
- b) The Responsible Entity shall review annually their cyber security training program and shall update it whenever necessary. Annual Review shall record evaluation of the effectiveness of the trainings held.
- c) The Responsible Entity shall ensure that Cyber Security training program designed for their IT as well as OT O&M Personnel must include following topics and as per their functional requirements and security concerns additional topics shall be added:
 - 1) User authentication and authorization.
 - 2) Cyber Security and Protection mechanisms of IT/OT/ICS Systems.
 - 3) Introduction to various standards i.e. ISO/IEC:15408, ISO/IEC:24748-1, ISO: 27001, ISO: 27002, ISO 27019, IS 16335, IEC/ISO:62443.
 - 4) Training on implementation of ISO/IEC 27001 and awareness on IEC 62443.
 - 5) Vulnerability Assessment in the Critical System.
 - 6) Monitoring and preserving of electronic logs of access of Critical Assets.
 - 7) Detecting cyber-attacks on SCADA and ICS systems
 - 8) The handling of Critical System during cyber crisis.
 - 9) Action plans and procedures to recover or re-establish normal functioning of Critical Assets and access thereto following a Cyber Security Incident.
 - 10) Hands on SCADA operation at any of the Regional Load Dispatch Centre.
 - 11) Handling of risks involved in the procurement of COTS Products.
- d) All Personnel engaged in O&M of IT & OT Systems shall mandatorily undergo courses on cyber security of Power Sector from any of the training institute designated by CEA, immediately within 90 days from the notification of CEA Guidelines on Cyber Security in Power Sector.
- e) The Responsible Entity shall ensure that none of their newly hired or the current Personnel have access to the Critical System, prior to the satisfactory completion of cyber security training programme from the Training Institutes designated in India, except in specified circumstances such as cyber crisis or an emergency.
- f) NPTI in consultation with CEA shall identify and design domain specific courses on Cyber Security for different target groups. The "Governing Board for PSO Training and Certification" shall approve the content, duration etc of these courses and shall review it Annually. NPTI shall conduct these courses at all of their branches on regular basis and shall maintain the list of the Participants successfully completing the course.

Article 9 Cyber Supply Chain Risk Management

- a) The Responsible Entity shall ensure that, as and when Ministry of Power, Government of India notifies the Model Contractual Clauses on cyber security, these clauses are included in their every Bid invited for procurement of any ICT based components/equipments/System to be used for Power System.
- b) The Responsible Entity shall ensure that all the Communicable Intelligent Equipments and the Service Level Agreements (SLAs) for their Critical Systems shall be sourced from the list of the "Trusted Sources" as and when drawn by MoP/CEA.

- c) The Responsible Entity shall ensure that, in case, for the any Communicable Intelligent Devices, if no Trusted Source has been identified, then the successful bidder in compliance with the provisions made in MoP order dated 2.7.2020 and any other relevant MoP order has got the product cyber tested for any kind of embedded malware/Trojan/cyber threat and for adherence to Indian Standards at the designated lab.
- d) The Responsible Entity shall ensure that the essential cyber security tests are carried out successfully during FAT, SAT as detailed in **Annexure A.** The equipment/System besides for functionality shall also be tested in the factory for vulnerabilities, design flaws, parts being counterfeit or tainted, so as to minimize problems during on-site-testing and installation. Cyber Security Conformance Testing are to be carried out in the designated Lab as listed in **Annexure-I of MoP Order No. 12/13/2020-T&R dt. 8th June, 2021(Order at Annexure-B).**
- e) The Responsible Entity shall ensure that the Equipment/System supplied by the successful bidder shall accompany with a certificate^{\$, #} obtained by OEM from a certification body accredited to assess devices and process for conformances to IEC 62443-4 standards during design and manufacture. The Responsible Entity shall accept the certificate submitted along with the supplied Equipment/System only if it's in line with the Testing Protocol as notified by Ministry of Power, Government of India, from time to time.
- f) The Responsible Entity in compliance to the requirement of Article 9(e) shall also accept, till the setting up of an adequate certification facility in the India, a digitally signed self-declaration of conformance to the IEC 62443-4 standards during design and manufacture of the equipment/system, if submitted by the OEM.
- g) The Responsible Entity shall dispose all unserviceable or obsolete Communicable Intelligent Devices as per the procedure laid in their Cyber Risk Assessment and Mitigation Plans which shall be in line with the prevailing best practices.
- \$ The National & International certification may be specified in the tender for critical systems/sub-systems being procured by the Responsible Entity.

Certification Schemes:

Embedded Device Security Assurance Certification is for an individual product, System Security Assurance Certification is for a set of products in a system (possibly from different vendors)

Security Development Lifecycle Assurance Certification is for the development processes that a manufacturer uses for developing products.

Article 10 Cyber Security Incident Report and Response Plan

- a) The CISO of the Responsible Entity shall report in the formats prescribed by CERT-In, all Cyber Security Incidents, classified as reportable events.
- b) Root cause analysis for all reportable events shall be carried out and corrective action taken, so as to ensure that any re-occurrence of such event can be managed with ease.
- c) The Responsible Entity shall mandatorily define in their Cyber Security Policy, criteria(s) identified on the basis of impact analysis, for declaring the occurrence of

- Cyber Security Incident(s) as a Cyber Crisis in the System owned or controlled by them.
- d) The Responsible Entity shall mandatorily designate an Officer along with his/her standby by name and designation and empower them to declare an occurrence of the incident(s) as "Cyber Crisis". The contact details of these Officers shall be updated in the C-CMP within 15 days of changes if any due to transfer or superannuation etc.
- e) The CISO shall ensure that during any Cyber Security Incident, ISD monitors and minutely records every details of cyber security events and incidents in both IT as well as the OT System owned or controlled by the Responsible Entity.
- f) The CISO shall ensure that each cyber incident is handled strictly as per Cyber Security Incident Response Plan detailed in the latest C-CMP approved by the Board of Directors.
- g) The Responsible Entity shall ensure that the efficacy of the Cyber Security Incident Response Plan is tested annually through mock drill(s) carried out, if feasible, as simulation exercise(s) or as table top exercise(s) with wider participation of their employees, in consultation with CERT-In and sectoral CERT. In case if any shortcoming is observed in the Cyber Security Incident Response Plan suitable changes shall be made in it.
- h) The Responsible Entity shall ensure that the CISO compiles details of incident detection, incident handling, learnings from each incident and damage claims made if any and shall report to CERT-In as well as upload information on ISAC-Power Portal.

Article 11 Cyber Crisis Management Plan(C-CMP)

- a) The Responsible Entity shall prepare a Cyber Crisis Management Plan and submit to their sectoral-CERT for review with intimation to Ministry of Power/CISO-MoP. Responsible Entity shall update their C-CMP on the basis of comments made by sectoral-CERT and then submit for vetting to CERT-In. The C-CMP shall be updated once again to include the observations made by CERT-In before seeking approval of Board of Directors for implementation of C-CMP.
- b) The Responsible Entity shall ensure that the C-CMP is reviewed at least annually. The CISO shall ensure that all changes are made in C-CMP only with the due approval of Board of Directors and the changes made in C-CMP have been communicated through a verifiable means to all the concerned Personnel of the Responsible Entity.
- c) The CISOs shall be the custodian of all the cyber security related documents including Cyber Crisis Management Plan, Risk Treatment Plan, Statement of Applicability of controls, and compliance to regulator's requirement.
- d) The CISO shall be accountable for ensuring enforcement of C-CMP by Information Security Division of the Responsible Entity, during a cyber-crisis, as and when declared by the designated Officer. (refer Article 10(d))

Article 12: Sabotage Reporting%

- a) The Responsible Entity shall incorporate procedure for identifying and reporting of sabotage in their Cyber Security Policy within 30 days from issue of the Guidelines, or grant of licence under the appropriate legal provisions to the Responsible Entity.
- b) The CISO shall be held liable for non-reporting of identified sabotage(s) as per procedure laid for identifying and reporting of sabotage in the Cyber Security Policy of the Responsible Entity.

- c) The CISO shall prepare a detailed report on disturbances or unusual occurrences, identified, suspected or determined to be caused by sabotage in the Critical System of the Responsible Entity, and shall submit the report to the Sectoral CERT as well as to CERT-In within 24 hours of its occurrence.
- d) The CISO shall submit to NCIIPC within 24 hours of occurrence the report on every sabotage classified as cyber incidents(s) on "Protected System".
- e) The CISO upon occurrence on every sabotage shall take custody of all log records as well as digital forensic records of affected Cyber Assets, Intrusion Detection System, Intrusion Protection System, SIEM and shall preserve them for at least 90 days and shall make them available as and when called upon for investigation by the concerned Agencies.

[%]Disturbances or unusual occurrences, suspected or determined to be caused by sabotage.

Sabotage e.g. can be a forced intrusion in un-manned/manned facility and taking control of operation of Critical System through a communicating device.

Article 13 Security and Testing of Cyber Assets

- a) The Responsible Entity shall ensure security of all in-service phase as well as standby Cyber Assets through regular firmware/Software updates and patching, Vulnerability management, Penetration testing (of combined installations), securing configuration, supplementing security controls. CISO shall maintain details of update version of each firmware and software and their certification if received from OEMs.
- b) The Responsible Entity shall carry out regularly Vulnerability Assessment of all Cyber Assets owned or under their control. If a Cyber Asset is found vulnerable to any exploits or upon any patch updates or major configuration changes, then further Penetration Testing may be carried out offline or in a suitably configured laboratory test-bed to determine other vulnerabilities that may have not been identified so far.
- c) The Responsible Entity shall specify security requirement and evaluation criteria during each phase of their procurement Process.
- d) The Responsible Entity shall ensure that all Cyber Assets being procured shall conform to the type tests as mentioned in the specification for type testing listed in the bid document. Type test reports of tests conducted in NABL accredited Labs or internationally accredited labs (with in last 5 years from the date of bid opening) shall be mandated to be submitted along with bid. In case, the submitted Type Test reports are not as per specification, the re-tests shall be conducted without any cost implication to the Responsible Entity.
- e) The Responsible Entity shall ensure that all Communicable devices are tested for communication protocol as per the ISO/IEC/IS standards listed in MoP Order No. 12/13/2020-T&R dated 8th June, 2021(Annexure-B).
- f) The Responsible Entity shall ensure that all Critical Systems designed with Open Source Software are adequately cyber secured.
- g) The Responsible Entity as a best practise upon any incidence of Cyber Security Breach shall carry out cyber security tests at any lab designated for cyber testing by Ministry of Power. These tests shall be similar to Pre Commissioning Security Test and those essential for carrying out Post Incident Forensics Analysis.

Article 14 Cyber Security Audit

- a) The Responsible Entity shall implement Information Security Management System (ISMS) covering all its Critical Systems.
- b) The Responsible Entity shall through a CERT-In Empanelled Cyber Security OT Auditor shall get their IT as well as OT System audited at least once in every 6 (six) months and shall close all critical and high vulnerabilities within a period of one month and medium as well as low non-conformity before the next audit. Effective closure of all non-conformities shall be verified during the next audit.
- c) The Cyber Security Audit shall be as per ISO/IEC 27001 along with sector specific standard ISO/IEC 27019, IS 16335 and other guidelines issued by appropriate Authority if any. These mentioned standards shall be current with all amendments if any and in case if any standard is superseded, the new standard shall be applicable. CISO shall ensure immediate closure of non-conformance, based on the criticality and by means all non-conformances are to be closed before the next audit.
- d) The Responsible Entity shall ensure that CISO has all the required systems and documents in place, as mandated by NSCS for base line cyber security audit.

ANNEXURE-R2

No. 20(3)/2022-CERT-In Government of India Ministry of Electronics and Information Technology (MeitY) Indian Computer Emergency Response Team (CERT-In)

Electronics Niketan, 6 CGO Complex, New Delhi-110003

Dated: 28 April, 2022

Subject: Directions under sub-section (6) of section 70B of the Information Technology Act, 2000 relating to information security practices, procedure, prevention, response and reporting of cyber incidents for Safe & Trusted Internet.

Whereas, the Central Government in terms of the provisions of sub-section (1) of section 70B of Information Technology (IT) Act, 2000 (IT Act, 2000) has appointed "Indian Computer Emergency Response Team (CERT-In)" vide notification dated 27th October 2009 published in the official Gazette and as per provisions of sub-section (4) of section 70B of IT Act, 2000 The Indian Computer Emergency Response Team shall serve as the national agency for performing the following functions in the area of cyber security:-

- a) collection, analysis and dissemination of information on cyber incidents;
- b) forecast and alerts of cyber security incidents;
- c) emergency measures for handling cyber security incidents;
- d) coordination of cyber incidents response activities;
- e) issue guidelines, advisories, vulnerability notes and whitepapers relating to information security practices, procedures, prevention, response and reporting of cyber incidents;
- f) such other functions relating to cyber security as may be prescribed.

And whereas, "The Information Technology (The Indian Computer Emergency Response Team and Manner of performing functions and duties) Rules, 2013" were notified and published vide notification dated 16.01.2014 by the Central Government in exercise of the powers conferred by clause (zf) of sub-section (2) of section 87 read with sub-section (5) of section 70B of the IT Act, 2000.

And whereas, as per provisions of sub-section (6) of section 70B of the IT Act, 2000, CERT-In is empowered and competent to call for information and give directions to the service providers, intermediaries, data centres, body corporate and any other person for carrying out the activities enshrined in sub-section (4) of section 70B of the IT Act, 2000.

And whereas, various instances of cyber incidents and cyber security incidents have been and continue to be reported from time to time and in order to coordinate response activities as well as emergency measures with respect to cyber security incidents, the requisite information is either sometime not found available or readily not available with service providers/data centres/body corporate and the said primary information is essential to carry out the analysis, investigation and coordination as per the process of law.

And whereas, it is considered expedient in the interest of the sovereignty or integrity of India, defence of India, security of the state, friendly relations with foreign states or public order or for preventing incitement to the commission of any cognizable offence using computer resource or for handling of any cyber incident, that following directions are issued to augment and strengthen the cyber security in the country:

- (i) All service providers, intermediaries, data centres, body corporate and Government organisations shall connect to the Network Time Protocol (NTP) Server of National Informatics Centre (NIC) or National Physical Laboratory (NPL) or with NTP servers traceable to these NTP servers, for synchronisation of all their ICT systems clocks. Entities having ICT infrastructure spanning multiple geographies may also use accurate and standard time source other than NPL and NIC, however it is to be ensured that their time source shall not deviate from NPL and NIC.
- (ii) Any service provider, intermediary, data centre, body corporate and Government organisation shall mandatorily report cyber incidents as mentioned in Annexure I to CERT-In within 6 hours of noticing such incidents or being brought to notice about such incidents. The incidents can be reported to CERT-In via email (incident@cert-in.org.in), Phone (1800-11-4949) and Fax (1800-11-6969). The details regarding methods and formats of reporting cyber security incidents is also published on the website of CERT-In www.cert-in.org.in and will be updated from time to time.

- (iii) When required by order/direction of CERT-In, for the purposes of cyber incident response, protective and preventive actions related to cyber incidents, the service provider/intermediary/data centre/body corporate is mandated to take action or provide information or any such assistance to CERT-In, which may contribute towards cyber security mitigation actions and enhanced cyber security situational awareness. The order / direction may include the format of the information that is required (up to and including near real-time), and a specified timeframe in which it is required, which should be adhered to and compliance provided to CERT-In, else it would be treated as non-compliance of this direction. The service providers, intermediaries, data centres, body corporate and Government organisations shall designate a Point of Contact to interface with CERT-In. The Information relating to a Point of Contact shall be sent to CERT-In in the format specified at Annexure II and shall be updated from time to time. All communications from CERT-In seeking information and providing directions for compliance shall be sent to the said Point of Contact.
- (iv) All service providers, intermediaries, data centres, body corporate and Government organisations shall mandatorily enable logs of all their ICT systems and maintain them securely for a rolling period of 180 days and the same shall be maintained within the Indian jurisdiction. These should be provided to CERT-In along with reporting of any incident or when ordered / directed by CERT-In.
- (v) Data Centres, Virtual Private Server (VPS) providers, Cloud Service providers and Virtual Private Network Service (VPN Service) providers, shall be required to register the following accurate information which must be maintained by them for a period of 5 years or longer duration as mandated by the law after any cancellation or withdrawal of the registration as the case may be:
 - a. Validated names of subscribers/customers hiring the services
 - b. Period of hire including dates
 - c. IPs allotted to / being used by the members
 - d. Email address and IP address and time stamp used at the time of registration / on-boarding
 - e. Purpose for hiring services
 - f. Validated address and contact numbers
 - g. Ownership pattern of the subscribers / customers hiring services

(vi) The virtual asset service providers, virtual asset exchange providers and custodian wallet providers (as defined by Ministry of Finance from time to time) shall mandatorily maintain all information obtained as part of Know Your Customer (KYC) and records of financial transactions for a period of five years so as to ensure cyber security in the area of payments and financial markets for citizens while protecting their data, fundamental rights and economic freedom in view of the growth of virtual assets.

For the purpose of KYC, the Reserve Bank of India (RBI) Directions 2016 / Securities and Exchange Board of India (SEBI) circular dated April 24, 2020 / Department of Telecom (DoT) notice September 21, 2021 mandated procedures as amended from time to time may be referred to as per Annexure III.

With respect to transaction records, accurate information shall be maintained in such a way that individual transaction can be reconstructed along with the relevant elements comprising of, but not limited to, information relating to the identification of the relevant parties including IP addresses along with timestamps and time zones, transaction ID, the public keys (or equivalent identifiers), addresses or accounts involved (or equivalent identifiers), the nature and date of the transaction, and the amount transferred.

And whereas, the meaning to the terms 'cyber incident' or 'cyber security incident' or 'computer resource' or other terms may be ascribed as defined in the IT Act, 2000 or "The Information Technology (The Indian Computer Emergency Response Team and Manner of performing functions and duties) Rules, 2013" as the case may be.

And whereas, in case of any incident, the above-referred entities must furnish the details as called for by CERT-In. The failure to furnish the information or non-compliance with the ibid. directions, may invite punitive action under subsection (7) of the section 70B of the IT Act, 2000 and other laws as applicable.

This direction will become effective after 60 days from the date on which it is issued.

Types of cyber security incidents mandatorily to be reported by service providers, intermediaries, data centres, body corporate and Government organisations to CERT-In:

[Refer Rule 12(1)(a) of The Information Technology (The Indian Computer Emergency Response Team and Manner of Performing Functions and Duties) Rules, 2013]

- i. Targeted scanning/probing of critical networks/systems
- ii. Compromise of critical systems/information
- iii. Unauthorised access of IT systems/data
- iv. Defacement of website or intrusion into a website and unauthorised changes such as inserting malicious code, links to external websites etc.
- v. Malicious code attacks such as spreading of virus/worm/Trojan/Bots/ Spyware/Ransomware/Cryptominers
- vi. Attack on servers such as Database, Mail and DNS and network devices such as Routers
- vii. Identity Theft, spoofing and phishing attacks
- viii. Denial of Service (DoS) and Distributed Denial of Service (DDoS) attacks
 - ix. Attacks on Critical infrastructure, SCADA and operational technology systems and Wireless networks
 - x. Attacks on Application such as E-Governance, E-Commerce etc.
 - xi. Data Breach
- xii. Data Leak
- xiii. Attacks on Internet of Things (IoT) devices and associated systems, networks, software, servers
- xiv. Attacks or incident affecting Digital Payment systems
- xv. Attacks through Malicious mobile Apps
- xvi. Fake mobile Apps
- xvii. Unauthorised access to social media accounts
- xviii. Attacks or malicious/ suspicious activities affecting Cloud computing systems/servers/software/applications
 - xix. Attacks or malicious/suspicious activities affecting systems/ servers/ networks/ software/ applications related to Big Data, Block chain, virtual assets, virtual asset exchanges, custodian wallets, Robotics, 3D and 4D Printing, additive manufacturing, Drones

xx. Attacks or malicious/ suspicious activities affecting systems/ servers/software/ applications related to Artificial Intelligence and Machine Learning

The incidents can be reported to CERT-In via email (incident@cert-in.org.in), Phone (1800-11-4949) and Fax (1800-11-6969). The details regarding methods and formats of reporting cyber security incidents is also published on the website of CERT-In www.cert-in.org.in and will be updated from time to time.

Annexure II

Format for providing Point of Contact (PoC) information by Service providers, intermediaries, data centres, body corporate and Government organisations to CERT-In

The Information relating to the Point of Contact shall be sent to CERT-In via email (info@cert-in.org.in) in the format specified below and shall be updated from time to time:

Name	
Designation	
Organisation Name	
Office Address	
Email ID	
Mobile No.	
Office Phone	
Office Fax	

KYC Requirements

For the purpose of KYC, any of following Officially Valid Document (OVD) as a measure of identification procedure prescribed by the Reserve Bank of India (Know Your Customer (KYC)) Directions, 2016 / Securities and Exchange Board of India Clarification on Know Your Client (KYC) **Process** and Use of Technology for **KYC** vide Circular SEBI/HO/MIRSD/DOP/CIR/P/2020/73 dated April 24, 2020 / The Department of Telecom File No: 800-12/2021- AS.II dated September 21, 2021 on Self-KYC (S-KYC) as an alternate process for issuing of new mobile connections to Local and Outstation category customers, shall be used and maintained:

- a. The passport,
- b. The driving license,
- c. Proof of possession of Aadhaar number,
- d. The Voter's Identity Card issued by the Election Commission of India,
- e. Job card issued by NREGA duly signed by an officer of the State Government and
- f. Letter issued by the National Population Register containing details of name and address.
- g. Validated phone number
- h. Trading account number and details, Bank account number and bank details

For the purpose of KYC for business entities (B2B), documents mentioned in the Customer Due Diligence (CDD) process prescribed in Reserve Bank of India Master Direction - Know Your Customer (KYC) Direction, 2016 as updated from time to time shall be used and maintained.

Windows XP

ANNEXURE-R3

Windows XP follows the Fixed Lifecycle Policy.

This applies to the following editions: Home, Professional, Professional for Embedded Systems, Professional x64, Starter

(i) Important

Support for this product has ended. See migration guidance below.

Support dates are shown in the Pacific Time Zone (PT) - Redmond, WA, USA.

Support Dates

Listing	Start Date	Mainstream End Date	Extended End Date
Windows XP	Dec 31, 2001	Apr 14, 2009	Apr 8, 2014

Releases

Version	Start Date	End Date
Service Pack 3	Apr 21, 2008	Apr 8, 2014
Service Pack 2	Sep 17, 2004	Jul 13, 2010
Service Pack 1a	Feb 3, 2003	Oct 10, 2006
Service Pack 1	Aug 30, 2002	Oct 10, 2006
Original Release	Dec 31, 2001	Aug 30, 2005

Links

- Migration guidance
- Service pack policy

① Note

The start date for Microsoft Windows XP Professional x64 Edition was April 24, 2005.

Editions

- Home
- Professional
- Professional for Embedded Systems
- Professional x64
- Starter

REGD. No. D. L.-33004/99



सी.जी.-डी.एल.-अ.-02012023-241581 CG-DL-E-02012023-241581

असाधारण EXTRAORDINARY

भाग III—खण्ड 4 PART III—Section 4

प्राधिकार से प्रकाशित PUBLISHED BY AUTHORITY

सं. 699] No. 699] नई दिल्ली, मंगलवार, दिसम्बर 27, 2022/पौष 6, 1944 NEW DELHI, TUESDAY, DECEMBER 27, 2022/PAUSHA 6, 1944

केंद्रीय विद्युत प्राधिकरण

अधिसूचना

नई दिल्ली, 23 दिसम्बर, 2022

केविप्रा-टीएच-17/1/2021-टीईटीडी प्रभाग.—विद्युत अधिनियम, 2003 (2003 का 36) की धारा 177 के उप धारा (3) के साथ पठित विद्युत (पिछले प्रकाशन की प्रक्रिया) नियम, 2005 के नियम (3) के उप नियम (2) द्वारा यथाअपेक्षित केंद्रीय विद्युत प्राधिकरण (विद्युत संयंत्रों और विद्युत लाइनों के निर्माण के लिए तकनीकी मानक) विनियम, 2022 का प्रारूप छ: दैनिक समाचार पत्रों में प्रकाशित किया गया था, उन सभी व्यक्तियों से, जिनके उनसे प्रभावित होने की संभावना थी, उस तारीख से जिसको उक्त प्रारूप विनियमों से युक्त समाचार पत्र की प्रतियां जनता को उपलब्ध करा दी गई थीं, सैंतालीस दिन की अविध के समाप्ति से पूर्व आक्षेप और सुझाव आमंत्रित किये गये थे;

और उक्त समाचार पत्रों की प्रतियां, जिनमें सार्वजनिक सूचनाएं और उक्त प्रारूप विनियम सम्मिलित हैं, केंद्रीय विद्युत प्राधिकरण की वेबसाइट पर 30 दिसंबर, 2021 को जनता को उपलब्ध करा दिए गए थे;

और उक्त प्रारूप विनियमों पर जनता से प्राप्त आपत्तियों और सुझावों पर केंद्रीय विद्युत प्राधिकरण द्वारा विचार कर लिया गया था;

अत:, विद्युत अधिनियम, 2003 (2003 का 36) की धारा 177 की उप-धारा (1) के साथ पठित उक्त अधिनियम की धारा 73 के खण्ड (ख) द्वारा प्रदत्त शक्तियों का प्रयोग करते हुए, केंद्रीय विद्युत प्राधिकरण निम्नलिखित विनियम बनाता है, अर्थात्: -

अध्याय 1

 संक्षिप्त नाम, प्रारंभ और लागू होना - (1) इन विनियमों का संक्षिप्त नाम केंद्रीय विद्युत प्राधिकरण (विद्युत संयंत्रों और विद्युत लाइनों के निर्माण के लिए तकनीकी मानक) विनियम, 2022 है।

8672 GI/2022 (1)

mineralised water of the Station in twenty hours of operation of the de-mineralised plant.

- (c) Adequate redundancy shall be provided in the number of de-mineralising streams.
- (ii) The demineralized water shall be stored in minimum two nos. de-mineralised water storage tanks of total storage capacity equal to twenty four hour Station requirement.
- (e) Waste Water Treatment System.—

The waste water generated at various locations shall be segregated at the source of generation according to its type:

Provided that similar type of waste water shall be collected at one point and suitably treated for reuse in the plant:

Provided further that the treatment of plant waste water shall be in accordance with the statutory requirements.

(5) Fire detection, alarm and protection system.—

- (i) A comprehensive fire detection, alarm as well as fire protection system shall be installed for the Station in conformity with relevant Indian Standard.
- (ii) Automatic fire detection and alarm system shall be intelligent and addressable type and shall be provided to facilitate detection of fire at the incipient stage and give warning to the firefighting staff.
- (iii) Major equipment to be used for fire detection and protection system shall be in accordance with relevant Indian Standard or Underwriters Laboratories, USA or Factory Mutuals, USA or Loss Prevention Certification Board, United Kingdom or VDS (Germany).
- (iv) Dedicated fire water storage and pumping facilities of adequate capacities shall be provided for the fire fighting system as per Tariff Advisory Committee guidelines:

Provided that the main fire water pumps shall be electrically driven and standby pumps shall be diesel engine driven.

- (v) Necessary hydrant system, complying with Tariff Advisory Committee guidelines, shall be provided at various locations to cover the entire Station.
- (vi) All major and minor fire risks in the Station shall be protected against fire by suitable automatic fire protection systems:

Provided that the following systems shall be generally adopted for various fire risks:

- (a) Each transformer and reactor shall be provided as per Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations, 2010 or any successor or subsequent Regulations in this regard.
- (b) Automatic high velocity water spray system as per IS 15325, shall be provided for the following areas namely: -
 - (ba) Lubricating oil systems including storage tanks, purifier units, coolers, turbine oil canal pipelines;
 - (bb) Generator seal oil system tanks, coolers;
 - (bc) Steam generator burner fronts.
- (c) Steam turbine bearing housing and air pre-heater shall be provided with manually actuated high velocity water spray system.
- (d) Automatic medium velocity water spray system, complying with Tariff Advisory Committee guidelines, shall be provided for the areas relating to:
 - (da) Cable galleries, cable vaults, cable spreader rooms, cable risers, cable shafts etc.;
 - (db) Coal conveyors, transfer points, crusher houses etc.;
 - (dc) Fuel oil pumping stations;
 - (dd) Light Diesel Oil and day oil tanks;
 - (de) Reliable standby power supply system building.
- (e) Automatic foam system shall be provided for fuel oil storage tanks as per National Fire Protection Association guidelines.
- (f) Automatic inert gas flooding system, comprising of 2x100% inert gas cylinder batteries conforming to National Fire Protection Association, shall be provided for Unit control rooms, control equipment rooms and area above false ceiling of these rooms.

- (vii) Portable fire extinguisher as per Tariff Advisory Committee guidelines shall be provided for each room/area of power station in addition to fixed fire protection system to extinguish fire in its early phase to prevent its spread.
- (viii) Fire station and fire tenders along with trained staff shall be provided for the Station.
- (ix) Passive fire protection measures such as fire barriers for cable galleries and shafts etc., fire retardant coatings, fire resistant penetration sealing for all openings in floors, ceilings, walls etc., fire proof doors etc. shall be provided to prevent spreading and for containment of fire.

(6) Compressed air system.—

(a) Compressed air system comprising of instrument air and service air shall be provided to cater to the requirement for operation of various pneumatically operated drives and general purpose cleaning and maintenance services:

Provided that air dryers shall be provided for instrument air to achieve desired dryness.

(b) At least one number air compressor shall be provided as standby.

(7) Ventilation and air-conditioning system.—

- (a) Suitable ventilation and air-conditioning system shall be provided to achieve proper working environment in the Station.
- (b) (i) Central control room, local control rooms and service building for Operation and Maintenance personnel shall be air conditioned:

Provided that the air- conditioned areas shall be maintained at about 25°C and 50 % relative humidity for comfort conditions.

(ii) Water chilling unit shall be of 2x100% or 3x50% capacity and condensing units shall be of 2x100% capacity:

Provided that the package type air-conditioners shall have 2x100% capacity or 3x50% capacity equipment:

Provided further that for window air conditioners and split air conditioners, if used for small control rooms, at least one unit shall be kept as standby.

- (c) The type of ventilation systems to be provided, excluding for air conditioned areas shall be as under:—
 - (i) All floors of TG building, switchgear: Evaporating cooling system rooms and cable gallery
 - (ii) Other buildings: Mechanical ventilation system
- (8) **Mill rejects system.**—The mill rejects system shall be provided to collect reject from coal mills in case of vertical mills:

Provided that the system shall be of mechanized type i.e. drag chain conveyor or pneumatically pressurized conveying system:

Provided further that the system shall consist of collection of rejects from each coal mill and transport to silos for final disposal.

(9) Electric overhead travelling crane .—

(a) The Electric Overhead Travelling cranes shall be provided for maintenance of Turbine Generator cycle equipment and Circulating Water pumps:

Provided that these shall comply with the requirements of latest versions of relevant Indian Standard:

Provided further that the crane capacity shall be taken as five percent more than the single heaviest equipment to be lifted by the crane.

- (b) Two Electric Overhead Travelling cranes may be provided for maintenance of Turbine Generator cycle equipment in case more than two steam turbine generators are housed in the Turbine Generator hall.
- (10) **Laboratories.—** The Station shall be provided with following laboratories namely:-
 - (a) Electrical laboratory with necessary equipment and instruments for testing and maintenance of electrical equipment;
 - (b) Control and Instrumentation laboratory with necessary equipment and instruments for testing, calibration and maintenance of control and instrumentation systems;
 - (c) Chemical laboratories with necessary equipment, instruments and reagents for chemical analysis in



NTPC TANDA

OT Assessment Report

Cycle-2 & Revalidation _C1





Version Control							
Version	Date	Created by	Reviewed / Modified by	Approved by	Report Stage		
1.0	16-12-2022	Akhil Kumar Agile	Rahul Sharma	Harish Sah	Stage-1		
1.1	06-10-2023	Ujjwal Ranjan	Amit Kumar / Sonal Malhotra	Harish Sah	C2_Stage1 & Revalidation_C1		

Report Distribution		
Name	Organization	Purpose
Suresh Kumar/ Manish Kumar	NTPC	For intimation of
Mishra/ Vivek Bhardwaj/		vulnerabilities and their
Abhishek Kumar Singh		closure
Suneel Kumar Palavalasa/	NTPC	For information please
Some Nath Kundu		



Contents

Contents	3
Report Guide	5
Introduction	6
Project Background	6
Project Timeline and Team	7
Executive Summary	7
C&I Department	9
Observations:	9
Network Architecture Review	10
Existing Network Architecture	10
Proposed Network Architecture	11
Firewall Vulnerability Summary	12
Revalidation	16
Unit 1	16
Asset Classification	16
DCS 2(Emerson Make)	17
Risk	19
Devices Vulnerability Summary	23
Asset Inventory detail	33
Mapping of Vulnerabilities with Assets (DCS1)	33
Mapping of Vulnerabilities with Assets (DCS2)	33
Unit 2	34
Asset Classification	34
Risk	36
Devices Vulnerability Summary	41
Asset Inventory detail	54
Mapping of Vulnerabilities with Assets (DCS1)	55
Mapping of Vulnerabilities with Assets (DCS2)	55
Unit 3	55
Asset Classification	55
Risk	58
Devices Vulnerability Summary	63
Asset Inventory detail	80
Mapping of Vulnerabilities with Assets (DCS1)	81
Mapping of Vulnerabilities with Assets (DCS2)	81



Unit 4	81
Asset Classification	81
Risk	83
Devices Vulnerability Summary	88
Asset Inventory	107
Mapping of Vulnerabilities with Assets (DCS1)	107
Mapping of Vulnerabilities with Assets (DCS2)	108
Unit -6	108
Asset classification	108
Risk	110
Devices Vulnerability Summary	115
Asset Inventory	132
Mapping of Vulnerabilities with Assets (DCS1)	132
Mapping of Vulnerabilities with Assets (DCS2)	133
Recommendations:	133
Station LAN Vulnerability Summary	134
Electrical Department	138
SAS Network	138
Asset classification	138
Risk	139
Revalidation	140
Devices Vulnerability Summary	140
Asset Inventory	160
Final Mapping of Electrical Dept Assets:	160



Report Guide

The following table depicts the flow of this report.

Section	Description				
Introduction	This section basically sets the tone of the vulnerability assessment and OT assessment report and draws the boundaries of the report in terms of its objective, scope, project timeline, project team from both sides.				
Executive Summary	This section is prepared for quick management reference. It contains summary of observations from our review of network security test.				
Detailed Report	This section presents the detail of the observations/ gaps found in OT Assessment along with the following:				
	Risk rating				
	Description of observation				
	 Recommendation to address the risk 				
	Proof of Concept				
	Revalidation Status				




Introduction

Project Background

Grant Thornton Bharat LLP (GT) was engaged to conduct Network vulnerability assessment for **NTPC TANDA** OT assets. This network vulnerability assessment was conducted using the tools and techniques that a malicious attacker would use to try and compromise Security of OT Infrastructure with respect to **IEC62443 framework**.

IEC 62443 takes a risk-based approach to cyber security, which is based on the concept that it is neither efficient nor sustainable to try to protect all assets in equal measure. Instead, users must identify what is most valuable and requires the greatest protection and identify vulnerabilities.

Security Benchmarking using IEC 62443 Security Levels



The purpose of this assessment is to identify technical as well as logical vulnerabilities in the publicly exposed assets and provide recommendations for risk mitigation that may arise on successful exploitation of these vulnerabilities. The idea behind this testing is to discover whether an attacker may leverage flaws in the applications and supporting infrastructure to compromise the security at **NTPC TANDA**.



Project Timeline and Team

Cycle 1 - OT assessment timeline as follows:

Assessment Start Date	Assessment End Date
08-12-2022	14-12-2-22

Cycle 1 - Following team member was involved in this assessment:

GT Security Team	Contact Information
Akhil Kumar Agile	M: +91 8309008428
	E: akhilkumar.agile@in.gt.com

Cycle -1 - Revalidation & Cycle-2 - OT assessment timeline as follows:

Unit Assessed	Start Date	End Date
Unit 1 – Unit 6	14-07-2023	21-07-2023


Cycle -1 - Revalidation & Cycle- 2 Following team member was involved in this assessment:

GT Security Team	Contact Information
Ujjwal Ranjan	M: +91 7739756835
	<u>E:</u> Ujjwal.ranjan@in.gt.com

Executive Summary

In this report, we provide an overview of current visibility and insight into your OT environment from a risk point of view. We are providing the observation and recommendation based on the theories of defence in depth architecture which is explained in IEC 62443 for applying multiple countermeasures in a layered or stepwise manner.





This report provides detailed vulnerability and risk assessment conducted for **NTPC TANDA**. The Cycle 1 assessment was carried during Dec 2022 for which Revalidation of Cycle-1 & Assessment of Cycle-2 was carried during July'2023.

Cycle - 2: C&I

- 1. Active assessment / Passive Assessment has not been carried out as all are in running condition
- 2. Physical assessment activity has been carried out.
- 3. Firewall rules and policies were reviewed.

Network Architecture

Existing network architecture reviewed and based on that proposed a new architecture.

Station LAN

1. Active assessment was carried out for stage 2 station LAN.

Electrical

1. Passive assessment was performed on SAS network.



2. Physical assessment was performed.

Note: Based on the assessment, risk mitigation and remediation are needed to reduce the risk of nation-level threat vector and improve the cyber posture.

C&I Department

Observations:

- 1. It has been observed that as of now there is no biometric lock in any programmer room of all units. Hence, it is recommended to have biometric lock to ensure physical Security.
- It has been observed that site is managing the Asset list through excel based approach, but IPs of all
 devices is missing in that sheet. Hence, it is recommended to have up to date asset list with IP
 addresses or adopt some tool-based asset management technique which will increase the visibility of
 assets in your infrastructure.
- 3. It has also been observed that the no workstation & Servers have unique and strong password, also the password policy is not enforced in any system. Hence, it is recommended to have unique and strong password for all devices which must be updated in 90 to 180 days.
- 4. It has also been observed that Anti-Virus installed in all workstation & servers are outdated and there is no mechanism of its updating is available with site. So, it is recommended to adopt mechanism for AV patch update. Also make sure that the mechanism must be documented and in accordance with respective OEM.
- 5. As per the discussion with site Spoc regarding the scrap policy, it has been observed that all the workstation, server and field devices which are defected is declared as e-scrap and is directly sent to central store for scrapping. Hence, it is recommended to remove the hard disk for every device before scrapping it and that hard disk must be retained by the C&I Department.
- 6. It has been observed that almost all operator workstation is running on engineer account including UCR of all units and offsites. Hence, it is recommended to run all OWS on operator account with having very less or no privilege.
- 7. It has been observed all the group policies like account lockout, audit, advance audit, software restriction policies are not configured in any of the system installed. Hence, it is recommended to configure those policies.
- 8. It has been observed that many of the devices are running on obsolete OS i.e., Windows XP or Windows Server 2012 R2 which is going to obsolete in oct 2023. Hence, it is recommended to Upgrade the OS for all the outdated devices.
- 9. It has been observed that there is no role-based account has been created. There are the common users found with different privilege such as operator, engineer and administrator. When common user account used by different individual cannot create audit log for individual activity. Hence, it is recommended to configure role-based account.
- 10. It has also been observed that as of now the site have no patching mechanism and none of the devices is patched with latest OS updated. Hence, it is recommended to adopt some documented patching mechanism and perform this activity after a fixed interval of time. The time interval for patching will be decided by local cyber security response team and that also must be documented in same.



An instinct for growth


- 11. It has been observed that USB storage devices is enabled in few devices. It is recommended to disable the USB status in all workstations and servers and privilege to access the registry is only given to administrator.
- 12. It has been observed that OS firewall is disabled in all servers and workstation. It is recommended to enable the firewall in all devices.
- 13. It has been observed that several OS ports like port 80,135-139, 443, 445 etc. are found open and several services such as DHCP Client, DCOM+, etc. are running in all servers and workstation. These ports and services possess many vulnerabilities and provide the gateway for any kind of intrusion on the HMI. Hence, it is recommended to get a list of ports & services used by the application installed by OEM and close all the remaining unused ports and stop the services which are not required.

Note: All these observations belong to all stages and their offsites as well.

Network Architecture Review

Existing Network Architecture


Below is the existing architecture of OT environment of NTPC Tanda.





Proposed Network Architecture

Below is proposed architecture which include security control implementation as ISA99/IEC62443 and CEA guidelines.



Recommendations:

Recommendations:

- 1. Integration of cyber stack with DCS which include below mentioned components:
 - Centralized Patch Manager: This Server ensure consistent and timely patching, reducing the risk of security breaches and improving overall system stability. This component follows server-client architecture where Patch Manager will act as a server and DCS workstations & Servers act as a client and validated OS patches are imported in Patch Manager via CD and Patch Manager automatically deploy patches in agents.



- Centralized Antivirus Manager: This component follows server-client architecture where
 Antivirus Manager will act as a server and DCS workstations act as a client and validated
 AV definitions are imported in AV Manager via CD and AV Manager automatically deploy
 definitions in agents.
- Backup/Recovery server: The role of this component is to take schedule backup of DCS
 critical assets and to recover the workstations if workstation got corrupted. This
 component also follows server-client based mechanism.
- SEIM: The role of this Server is to collect, analyse, and correlate security event logs from
 various sources within an OT network. It provides a centralized view of security events,
 enables threat detection, incident response, and compliance monitoring. This Server has
 features like log management, real-time monitoring, incident management, and reporting.
- 2. **Firewall:** It is recommended to place one firewall between 4 Interface Switches and Hydrogen Plant to eliminate any kind of unforeseen event to FWPH and Hydrogen Plant which is critical in nature for plant safety.

Jump Box: This device is used to provide controlled remote access. In existing scenario, there is no remote mechanism available with the site. By providing a jump box, only one remote session takes place at a time. All activity log gets generated, and this event gets recorded.

Firewall

Recommendations:

- 1. It is recommended to update the firewall to the latest firmware version.
- 2. Disable ping (ICMP) response on WAN port.
- 3. Disable UPnP (Universal plug-and-play).
- 4. Disable IDENT (i.e., port 113).
- 5. Disable remote management of the firewall.
- 6. The setting for a firewall policy should be as specific as possible. Do not allow 'Any' source or destination port and protocol also in any defined rule.
- 7. Periodic check for incoming/outgoing traffic security policy.
- 8. Allow only HTTPS access to the GUI and SSH access to the CLI.
- 9. Set up two-factor authentication for administrator.
- 10. Modify administrator account lockout duration and threshold values.
- 11. It is recommended that all management access from the internet is turned off.
- 12. Ensure that your SNMP setting are using SNMPv3 with encryption.
- 13. Default user account should be disabled and default password must be changed.


Vulnerability Summary

Domain	Critical	High	Medium	Low	Total
Vulnerability Assessment	0	2	3	4	9

Observation Summary

The chart given below represents the vulnerabilities found during network Vulnerability Assessment.





Vulnerability Assessment Test Observations

The below table illustrates the distribution of observations of Vulnerability Assessment based on the risk categorization i.e. Critical, High, Medium and Low

Vulnerabilities &	Affected IP	Risk	Observations	Recommendations	Status
Impact SSL Certificate Signed Using Weak Hashing Algorithm Impact: An attacker can exploit this to generate another certificate with the same digital signature, allowing an attacker to masquerade as the affected service.	172.18.160.50	High	It has been observed that SSL certificate is signed using SHA-1 With RSA Encryption.	It is recommended to sign SSL certificate using strong encryption algorithm such as SHA-512. References: https://tools.ietf.org/html/rfc3279	OPEN
SSL Medium Strength Cipher Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength encryption if the	172.18.160.50	High	It has been observed that SSL is using medium strength encryption such as DES-CBC3-SHA which can be easily compromised if the attacker is on the same physical network.	It is recommended to reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: https://www.openssl.org/blog/blog/2016/08/24/sweet32/	OPEN



attacker is on the same physical network.					
SSL RC4 Cipher Suites Supported (Bar Mitzvah) Impact: If plaintext is repeatedly encrypted (e.g., HTTP cookies), and an attacker is able to obtain many (i.e., tens of millions) ciphertexts, the attacker may be able to derive the plaintext.	172.18.160.50	Medium	It has been observed that remote host is using weak cipher suite such as MD5 and SHA-1.	It is recommended to reconfigure the affected application, if possible, to avoid use of RC4 ciphers. Consider using TLS 1.2 with AES-GCM suites subject to browser and web server support. References: https://www.rc4nomore.com/ http://cr.yp.to/talks/2013.0 3.12/slides.pdf http://www.isg.rhul.ac.uk/tls/ s/ https://www.imperva.com/ docs/HII Attacking SSL when_using_RC4.pdf	OPEN
TLS Version 1.1 Protocol Deprecated Impact: Ciphers that support encryption before MAC computation, and authenticated encryption modes such as GCM cannot be used with TLS 1.1. Hence an attacker can perform man-in-the-middle attack against the remote host.	172.18.160.50	Mediu m	It has been observed that remote host supports TLS version 1.1.	It is recommended to enable support for TLS 1.2 and/or 1.3 and disable support for TLS 1.1. References: https://datatracker.ietf.org/doc/html/rfc8996	OPEN
Unencrypted Telnet Server Impact: An attacker may eavesdrop on a Telnet session and obtain credentials or other sensitive information. Use of SSH is preferred	172.18.160.50	Mediu m	It is observed SSH is preferred over Telnet since it protects credentials from eavesdropping and can tunnel additional data streams such as an X11 session.	It is recommended to Disable the Telnet service and use SSH instead. References: How to Disable Telnet and Enable SSH on Cisco IOS Devices (networkstraining.com)	OPEN



An instinct for growth[™]

	T	1	T		1
nowadays as it protects credentials from eavesdropping and can tunnel additional data streams such as the X11 session.					
SSH Server CBC Mode Ciphers Enabled. Impact: The SSH server is configured to support Cipher Block Chaining (CBC) encryption. This may allow an attacker to recover the plaintext message from the ciphertext.	172.18.160.50	Low	It was observed that the SSH server is configured to use Cipher Block Chaining.	It is recommended to contact the vendor or consult product documentation to disable CBC mode cipher encryption and enable CTR or GCM cipher mode encryption.	OPEN
SSH Weak Key Exchange Algorithms Enabled Impact: An attacker can easily exploit the remote SSH server that is configured to allow weak key exchange algorithms.	172.18.160.50	Low	It has been observed that remote host allow weak key exchange algorithms.	It is recommended to disable the weak key exchange algorithms. References: SSH Weak Key Exchange Algorithms Enabled - Virtue Security	OPEN
SSH Weak MAC Algorithms Enabled Impact: An attacker may try to exploit the host as the remote SSH server is configured to allow key exchange algorithms which are considered weak.	172.18.160.50	Low	It has been observed that the remote SSH server is configured to allow key exchange algorithms which are considered weak.	It is recommended to contact the vendor or consult product documentation to disable the weak algorithms. References: Disable SSH Weak MAC Algorithms in Linux - DbAppWeb.com	OPEN
SSL Certificate Chain Contains RSA Keys Less Than 2048 bits. Impact: According to industry standards set by the Certification Authority/Browser (CA/B) Forum, certificates issued after January 1, 2014, must be at least 2048 bits. Some browser SSL	172.18.160.50	Low	It was observed that at least one of the X.509 certificates sent by the remote host has a key that is shorter than 2048 bits	It is recommended to replace the certificate in the chain with the RSA key less than 2048 bits in length with a longer key, and reissue any certificates signed by the old certificate.	OPEN



implementations may reject keys less than 2048 bits after January 1, 2014. Additionally, some SSL certificate vendors may revoke certificates less than 2048 bits before January 1, 2014.		

Revalidation

C&I

- 1. Revalidation of Active assessment / Passive Assessment has not been carried out as all are in running condition
- 2. Revalidation of Physical assessment activity has been carried out.

Station LAN

1. Revalidation of Active assessment was carried out for stage 2 station LAN.

Electrical

1. Revalidation of active assessment was not carried out as it is same.

Unit 1


Asset Classification

DCS 1 (BHEL Make)

The assessment was able to identify 66 all devices and discovered 52 vulnerabilities.

Based on the assessment, risk mitigation and remediation are needed to reduce the risk of nation-level threat vector and improve the cyber posture.






DCS 2(Emerson Make)

The assessment was able to identify 73 all devices and discovered 48 vulnerabilities.

Based on the assessment, risk mitigation and remediation are needed to reduce the risk of nation-level threat vector and improve the cyber posture.



Vendors

DCS₁

undefined	Broadcom	Cisco	HP
35	1	1	1
LCFC(HeFei) Electr	PEGATRON	TRANSMITTON LTD.	
1	1	26	



undefined Cisco Dell Inc. Emerson Process 45 11 6 8 LCFC(HeFei) Electr... VMware, Inc. 2 1

Asset Types

DCS₁


- 52 computer is	13 switch	1
------------------	-----------	---

DCS₂


-	62	WAP	1	computer	7	router	2
switch	1						

Operating systems

DCS₁







Risk

Vulnerability Score

DCS₁

GT Risk Assessment Report provides a comprehensive risk analysis related to network behaviour and assets. Based on overall assessment for NTPC TANDA, all network risk score is 6.8 (Medium risk)






GT Risk Assessment Report provides a comprehensive risk analysis related to network behaviour and assets. Based on overall assessment for NTPC TANDA, all network risk score is 6.7 (Medium risk)




Vulnerabilities per type

DCS₁



DCS₂



Top 30 Vulnerabilities on Network Devices



DCS₁

CVE	LABEL	CVE SCORE	CWE NAME	CVE CREATION TIME	TIME
CVE-2006- 4950	00:16:9d:fd:da: cf	10.0	Improper Input Validation	2006-09-23 10:07:00	2022-12-13 14:28:28
CVE-2017- 12240	00:16:9d:fd:da: cf	9.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-09-29 01:34:00	2022-12-13 14:28:28
CVE-2007- 2586	00:16:9d:fd:da: cf	9.3	Incorrect Authorization	2007-05-10 00:19:00	2022-12-13 14:28:28
CVE-2007- 5552	00:16:9d:fd:da: cf	93	Numeric Errors	2007-10-18 20:17:00	2022-12-13 14:28:28
CVE-2007-5381	00:16:9d:fd:da: cf	93	Improper Restriction of Operations within the Bounds of a Mernory Buffer	2007-10-12 01:17:00	2022-12-13 14:28:28
CVE-2019- 16009	00:16:9d:fd:da: cf	8.8	Cross-Site Request Forgery (CSRF)	2020-09-23 01:15:00	2022-12-13 14:28:28
CVE-2017-6743	00:16:9d:fd:da: cf	8.8	Improper Restriction of Operations within the Bounds of a Mernory Buffer	2017-07-17 21:29:00	2022-12-13 14:28:28
CVE-2017- 3864	00:16:9d:fd:da: cf	8.6	Improper Input Validation	2017-03-22 19:59:00	2022-12-13 14:28:28
CVE-2016- 6380	00:16:9d:fd:da: cf	8.1	Improper Input Validation	2016-10-05 20:59:00	2022-12-13 14:28:28
CVE-2011-0946	00:16:9d:fd:da: cf	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-13 14:28:28
CVE-2011-3279	00:16:9d:fd:da: cf	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-13 14:28:28
CVE-2013-1142	00:16:9d:fd:da: cf	7.8	Concurrent Execution using Shared Resource with Improper Synchronization (Race Condition)	2013-03-28 23:55:00	2022-12-13 14:28:28
CVE-2009- 2051	00:16:9d:fd:da: cf	7.8	Improper Input Validation	2009-08-27 17:00:00	2022-12-13 14:28:28
CVE-2021- 34699	00:16:9d:fd:da: cf	7.7	Interpretation Conflict	2021-09-23 03:15:00	2022-12-13 14:28:28
CVE-2017-3857	00:16:9d:fd:da: cf	7.5	Uncontrolled Resource Consumption	2017-03-22 19:59:00	2022-12-13 14:28:28
CVE-2003- 0647	00:16:9d:fd:da: cf	7.5	Improper Restriction of Operations within the Bounds of a Memory Buffer	2003-08-27 04:00:00	2022-12-13 14:28:28
CVE-2022- 20726	00:16:9d:fd:da: cf	7.5	Improper Neutralization of Input During Web Page Generation (*Cross-site Scripting*)	2022-04-1515:15:00	2022-12-13 14:28:28
CVE-2022- 20724	00:16:9d:fd:da: cf	7.5	Concurrent Execution using Shared Resource with Improper Synchronization (Race Condition)	2022-04-1515:15:00	2022-12-13 14:28:28
CVE-1999-0293	00:16:9d:fd:da: cf	7.5	Improper Input Validation	1998-01-01 05:00:00	2022-12-13 14:28:28
CVE-2019- 12655	00:16:9d:fd:da: cf	7.5	Buffer Copy without Checking Size of Input ('Classic Buffer Overflow')	2019-09-25 21:15:00	2022-12-13 14:28:28
CVE-2016-1409	00:16:9d:fd:da: cf	7.5	Improper Input Validation	2016-05-29 22:59:00	2022-12-13 14:28:28
CVE-2016- 6384	00:16:9d:fd:da: cf	7.5	Improper Input Validation	2016-10-05 17:59:00	2022-12-13 14:28:28
CVE-2016-6393	00:16:9d:fd:da: cf	7.5	Resource Management Errors	2016-10-05 20:59:00	2022-12-13 14:28:28
CVE-2016-6415	00:16:9d:fd:da: cf	7.5	Exposure of Sensitive Information to an Unauthorized Actor	2016-09-19 01:59:00	2022-12-13 14:28:28
CVE-2019-1748	00:16:9d:fd:da: cf	7.4	Improper Certificate Validation	2019-03-28 00:29:00	2022-12-13 14:28:28
CVE-2008-1150	00:16:9d:fd:da: cf	7.1	Resource Management Errors	2008-03-27 17:44:00	2022-12-13 14:28:28
CVE-2007-5551	00:16:9d:fd:da: cf	7.1	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-18 20:17:00	2022-12-13 14:28:28
CVE-2008-1151	00:16:9d:fd:da: cf	7.1	Resource Management Errors	2008-03-27 17:44:00	2022-12-13 14:28:28
CVE-2008- 4963	00:16:9d:fd:da: cf	7.1	Improper Input Validation	2008-11-06 15:55:00	2022-12-13 14:28:28
CVE-2008- 4609	00:16:9d:fd:da: cf	7.1	Configuration	2008-10-20 17:59:00	2022-12-13 14:28:28



CVE	LABEL	CVE SCORE	CWE NAME	CVE CREATION TIME	TIME
CVE-2006- 4950	00:1d:e5:ac:28: 54	10.0	Improper Input Validation	2006-09-23 10:07:00	2022-12-15 21:59:08
CVE-2017- 12240	00:1d:e5:ac:28: 54	9.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-09-29 01:34:00	2022-12-15 21:59:08
CVE-2007- 2586	00:1d:e5:ac:28: 54	9.3	Incorrect Authorization	2007-05-10 00:19:00	2022-12-15 21:59:08
CVE-2007- 5552	00:1d:e5:ac:28: 54	9.3	Numeric Errors	2007-10-18 20:17:00	2022-12-15 21:59:08
CVE-2017- 6743	00:1d:e5:ac:28: 54	8.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-07-17 21:29:00	2022-12-15 21:59:08
CVE	LABEL	CVE SCORE	CWE NAME	CVE CREATION TIME	TIME
CVE-2019- 16009	00:1d:e5:ac:28: 54	8.8	Cross-Site Request Forgery (CSRF)	2020-09-23 01:15:00	2022-12-15 21:59:08
CVE-2017- 3864	00:1d:e5:ac:28: 54	8.6	Improper Input Validation	2017-03-22 19:59:00	2022-12-15 21:59:08
CVE-2016- 6380	00:1d:e5:ac:28: 54	8.1	Improper Input Validation	2016-10-05 20:59:00	2022-12-15 21:59:08
CVE-2011-3279	00:1d:e5:ac:28: 54	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 21:59:08
CVE-2009- 2051	00:1d:e5:ac:28: 54	7.8	Improper Input Validation	2009-08-27 17:00:00	2022-12-15 21:59:08
CVE-2011-0946	00:1d:e5:ac:28: 54	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 21:59:08
CVE-2013-1142	00:1d:e5:ac:28: 54	7.8	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2013-03-28 23:55:00	2022-12-15 21:59:08
CVE-2021- 34699	00:1d:e5:ac:28: 54	7.7	Interpretation Conflict	2021-09-23 03:15:00	2022-12-15 21:59:08
CVE-1999- 0293	00:1d:e5:ac:28: 54	7.5	Improper Input Validation	1998-01-01 05:00:00	2022-12-15 21:59:08
CVE-2017-3857	00:1d:e5:ac:28: 54	7.5	Uncontrolled Resource Consumption	2017-03-22 19:59:00	2022-12-15 21:59:08
CVE-2016-1409	00:1d:e5:ac:28: 54	7.5	Improper Input Validation	2016-05-29 22:59:00	2022-12-15 21:59:08
CVE-2022- 20724	00:1d:e5:ac:28: 54	7.5	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2022-04-15 15:15:00	2022-12-15 21:59:08
CVE-2016-6415	00:1d:e5:ac:28: 54	7.5	Exposure of Sensitive Information to an Unauthorized Actor	2016-09-19 01:59:00	2022-12-15 21:59:08
CVE-2016-6393	00:1d:e5:ac:28: 54	7.5	Resource Management Errors	2016-10-05 20:59:00	2022-12-15 21:59:08
CVE-2016- 6384	00:1d:e5:ac:28: 54	7.5	Improper Input Validation	2016-10-05 17:59:00	2022-12-15 21:59:08
CVE-2019- 12655	00:1d:e5:ac:28: 54	7.5	Buffer Copy without Checking Size of Input (Classic Buffer Overflow)	2019-09-25 21:15:00	2022-12-15 21:59:08
CVE-2003- 0647	00:1d:e5:ac:28: 54	7.5	Improper Restriction of Operations within the Bounds of a Memory Buffer	2003-08-27 04:00:00	2022-12-15 21:59:08
CVE-2022- 20726	00:1d:e5:ac:28: 54	7.5	Improper Neutralization of Input During Web Page Generation ('Cross-site Scripting')	2022-04-15 15:15:00	2022-12-15 21:59:08
CVE-2008- 4609	00:1d:e5:ac:28: 54	7.1	Configuration	2008-10-20 17:59:00	2022-12-15 21:59:08
CVE-2008- 4963	00:1d:e5:ac:28: 54	7.1	Improper Input Validation	2008-11-06 15:55:00	2022-12-15 21:59:08
CVE-2008-1151	00:1d:e5:ac:28: 54	7.1	Resource Management Errors	2008-03-27 17:44:00	2022-12-15 21:59:08
CVE-2008-1150	00:1d:e5:ac:28: 54	7.1	Resource Management Errors	2008-03-27 17:44:00	2022-12-15 21:59:08
CVE-2007-5551	00:1d:e5:ac:28: 54	7.1	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-18 20:17:00	2022-12-15 21:59:08
CVE-2007- 5548	00:1d:e5:ac:28: 54	6.9	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-18 20:17:00	2022-12-15 21:59:08
CVE-2008- 5230	00:1d:e5:ac:28: 54	6.8	Cryptographic Issues	2008-11-25 23:30:00	2022-12-15 21:59:08

Vulnerability summary



DCS₁

Malware detected	0
Different Operating Systems	5
Different Types of Technologies	8
Attempted Links to Public Internet	0
Multi-homed Assets	0
Different Firmware Versions	2
Clients Accessing SMB Shares	0
Insecure Protocol Links in the Environment	1

DCS₂

Malware detected	0
Different Operating Systems	7
Different Types of Technologies	7
Attempted Links to Public Internet	0
Multi-homed Assets	23
Different Firmware Versions	2
Clients Accessing SMB Shares	7
Insecure Protocol Links in the Environment	106

Devices Vulnerability Summary

Domain	Critical	High	Medium	Low	Total
Vulnerability Assessment	8	4	6	1	19
Re-validation(closed)	0	0	0	0	0
Re-validation(open)	8	4	6	1	19



Observation Summary

The chart given below represents the vulnerabilities found during network vulnerability testing:

Fig:1




Fig:2



Figure 1: Vulnerability Assessment Test Observations

Illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Figure 2: Vulnerability Assessment Test Observations- Revalidation

Illustrates the closure of Vulnerabilities based on the categorization i.e., Closed, Open.

Note:

Closed: Count considered having vulnerability in all the IP addresses as closed.

Open: Count considered having vulnerability in minimum one IP address as open/unreachable, it may have more different IP addresses which may have the same vulnerability as closed.

Vulnerability Assessment Test Observations

The below table illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Vulnerabilities &	Affected IP	Risk	Observations	Recommendations	Sta	Revalidati
Impact					tus	on status
Microsoft RDP RCE (CVE-2019-0708) (BlueKeep) (uncredentialed check)	172.16.160.16 172.17.160.16	Criti cal	It was observed that the remote host is affected by a remote code execution vulnerability.	It is recommended to implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by Microsoft.	Op en	Open



An unauthenticated, remote attacker can exploit this, via a series of specially crafted requests, to execute arbitrary code. Microsoft Windows Server 2003	172.16.160.14	Criti	It is observed that	It is recommended to upgrade to a version	Op	Open
Unsupported Installation Detection. Impact: Lack of support implies that no new security patches for the product will be released by the vendor. As a result, it is likely to contain security vulnerabilities. Furthermore, Microsoft is unlikely to investigate or acknowledge reports of vulnerabilities. Microsoft Windows	172.16.160.10	Criti	the remote operating system is no longer supported.	of Windows that is currently supported.	Op	Open
Impact: Lack of support implies that no new security patches for the product will be released by the vendor. As a result, it is likely to contain security vulnerabilities. Furthermore, Microsoft is unlikely to investigate or acknowledge reports of vulnerabilities.	172.16.160.12 172.16.160.18 172.16.160.20 172.16.160.22 172.16.160.6 172.16.160.6 172.16.160.8 172.17.160.12 172.17.160.12 172.17.160.20 172.17.160.20 172.17.160.4 172.17.160.6 172.17.160.6 172.17.160.8	cal	the remote operating system is no longer supported.	upgrade to a version of Windows that is currently supported.	en	
MS05-027: Vulnerability in SMB Could Allow Remote Code Execution (896422) (uncredentialed check) Impact:	172.16.160.20 172.16.160.22 172.16.160.4 172.16.160.6 172.17.160.20 172.17.160.22 172.17.160.4 172.17.160.6	Criti cal	It is observed that an arbitrary code can be executed on the remote host due to a flaw in the SMB implementation.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003. Reference:	Op en	Open



	T	1	T	10 10	1	T 1
The remote version of Windows contains a flaw in the Server Message Block (SMB) implementation that may allow an attacker to execute arbitrary code on the remote host. An attacker does not need to be authenticated to exploit this flaw.				https://learn.microsof t.com/en-us/security- updates/SecurityBull etins/2005/ms05-027		
MS06-040: Vulnerability in Server Service Could Allow Remote Code Execution (921883) (uncredentialed check) Impact: The remote host is vulnerable to a buffer overrun in the 'Server' service that may allow an attacker to execute arbitrary code on the remote host with 'SYSTEM' privileges.	172.16.160.20 172.16.160.22 172.16.160.4 172.16.160.6 172.17.160.20 172.17.160.22 172.17.160.4 172.17.160.6	Criti	It is observed that an arbitrary code can be executed on the remote host due to a flaw in the 'Server' service.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003. References: https://learn.microsoft.com/en-us/security-updates/SecurityBulletins/2006/ms06-040	Op en	Open
MS08-067: Microsoft Windows Server Service Crafted RPC Request Handling Remote Code Execution (958644) (ECLIPSEDWING) (uncredentialed check) Impact: An unauthenticated, remote attacker can exploit this, via a specially crafted RPC request, to execute arbitrary code with 'System' privileges.	172.16.160.10 172.16.160.12 172.16.160.14 172.16.160.20 172.16.160.22 172.16.160.6 172.16.160.6 172.16.160.8 172.17.160.12 172.17.160.20 172.17.160.20 172.17.160.4 172.17.160.6 172.17.160.6 172.17.160.6 172.17.160.8	Criti	It is observed that the remote Windows host is affected by a remote code execution vulnerability.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003.	Op en	Open



MS09-001: Microsoft Windows SMB Vulnerabilities Remote Code Execution (958687) (uncredentialed check) Impact: The remote host is affected by a memory corruption vulnerability in SMB that may allow an attacker to execute arbitrary code or perform a denial of service against the remote host.	172.16.160.12 172.16.160.14 172.16.160.18 172.16.160.20 172.16.160.22 172.16.160.4 172.16.160.6 172.16.160.8 172.17.160.12 172.17.160.18 172.17.160.20 172.17.160.22 172.17.160.4	Criti	It is observed that it is possible to crash the remote host due to a flaw in SMB.	It is recommended to update set of patches for Windows 2000, XP, 2003, Vista and 2008 provided by Microsoft	Op en	Open
Unsupported Windows OS (remote) Impact: The remote version of Microsoft Windows is either missing a service pack or is no longer supported. As a result, it is likely to contain security vulnerabilities.	172.16.160.10 172.16.160.12 172.16.160.14 172.16.160.18 172.16.160.20 172.16.160.22 172.16.160.6 172.16.160.6 172.16.160.8 172.17.160.12 172.17.160.12 172.17.160.22 172.17.160.22 172.17.160.4 172.17.160.6 172.17.160.6 172.17.160.6 172.17.160.6 172.17.160.60 172.17.160.8	Criti	It was observed that the remote version of Microsoft Windows is either missing a service pack or is no longer supported	It is recommended to upgrade to a supported service pack or operating system	Op en	Open
MS06-035: Vulnerability in Server Service Could Allow Remote Code Execution (917159) (uncredentialed check) Impact: The remote host is vulnerable to heap overflow in the 'Server' service that may allow an attacker to execute arbitrary code on the remote host with 'SYSTEM' privileges.	172.16.160.20 172.16.160.22 172.16.160.4 172.16.160.6 172.17.160.20 172.17.160.22 172.17.160.4 172.17.160.6	High	It was observed that an arbitrary code can be executed on the remote host due to a flaw in the 'Server' service.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003.	Op en	Open

In addition to this, the remote host is also						
affected by an information disclosure vulnerability in SMB						
that may allow an attacker to obtain portions of the memory of the remote host.						
						_
MS12-020: Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check)	172.16.160.16 172.17.160.16	High	It was observed that the remote Windows host could allow arbitrary code execution.	It is recommended to implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by Microsoft.	Op en	Open
Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop Protocol (RDP) on the remote Windows host. The vulnerability is due to the way that RDP accesses an object in memory that has been improperly initialized or has been deleted.						
If RDP has been enabled on the affected system, an unauthenticated, remote attacker could leverage this vulnerability to cause the system to execute arbitrary code by sending a sequence of specially crafted RDP packets to it.						
MS17-010: Security Update for Microsoft Windows SMB Server (4013389) (ETERNALBLUE) (ETERNALCHAMPIO N) (ETERNALROMANCE	172.16.160.10 172.16.160.12 172.16.160.14 172.16.160.18 172.16.160.20 172.16.160.22 172.16.160.4 172.16.160.6 172.16.160.60	High	It has been observed that device is not updated to the MS SMB security patch (MS17-010)	It is recommended to follow the below mentioned. Microsoft has released a set of patches for Windows Vista, 2008, 7, 2008	Op en	Open
(ETERNALSYNERGY	172.16.160.8			R2, 2012, 8.1, RT		



An instinct for growth[™]

) (WannaCry)	172.17.160.12			8.1, 2012 R2, 10, and		
(EternalRocks)	172.17.160.18			2016. Microsoft has		
(Petya)	172.17.160.20			also released		
(uncredentialed	172.17.160.22			emergency patches		
check)	172.17.160.4					
	172.17.160.6			for Windows		
Impact:	172.17.160.60			operating systems		
An unauthenticated,	172.17.160.8			that are no longer		
remote attacker can				supported, including		
exploit these				Windows XP, 2003,		
vulnerabilities, via a				and 8.		
specially crafted						
packet, to execute				References:		
arbitrary code. (CVE-						
2017-0143, CVE-2017-				https://learn.microsof		
0144, CVE-2017-0145,				t.com/en-us/security-		
CVE-2017-0146, CVE-				updates/securitybulle		
2017-0148)				tins/2017/ms17-010		
- An information						
disclosure vulnerability						
exists in Microsoft						
Server Message Block						
1.0 (SMBv1) due to						
improper handling of						
certain requests. An						
unauthenticated,						
remote attacker can						
exploit this, via a						
specially crafted						
packet, to disclose						
sensitive information.						
(CVE-2017-0147)	470 40 400 40		10.2			
SMB NULL Session		High	It is observed that	It is recommended to	Op	Open
Authentication.	172.16.160.12		it is possible to log	contact the product	en	
Impact:	172.16.160.14		into the remote	vendor for		
The remote host is			host with a NULL	recommended		
running and SMB			session.	solutions.		
protocol. It is possible	172.16.160.22					
to log into the browser	172.16.160.4 172.16.160.6					
or spoolss pipes using a NULL session (i.e.,	172.16.160.60					
with no login or						
password).	172.16.160.8					
password).	172.17.160.12					
Depending on the	172.17.160.18					
configuration, it may be	172.17.160.20					
1 -	172.17.160.22					
possible for an	172.17.160.4					
unauthenticated,	172.17.160.60					
remote attacker to	172.17.160.8					
leverage this issue to						
get information about						
the remote host.						
and remote most.						



Microsoft Windows EFSRPC NTLM Reflection Elevation of Privilege (PetitPotam) (Remote). Impact: An unauthenticated, remote attacker can exploit this, by sending a specially-crafted EFSRPC request, to cause the affected host to connect to a malicious server. An attacker can then utilize an NTLM relay to impersonate the target host and authenticate against remote services.	172.16.160.14	Medi um	It is observed that the remote host is affected by an NTLM reflection elevation of privilege vulnerability.	It is recommended to apply the updates supplied by the vendor. Optionally, refer to Microsoft's KB5005413 for mitigation guidance. RPC filters may also be implemented to block remote access to the interface UUIDs necessary for this exploit.	Op en	Open
MS16-047: Security Update for SAM and LSAD Remote Protocols (3148527) (Badlock) (uncredentialed check) Impact: Ciphers that support encryption before MAC computation, and authenticated encryption modes such as GCM cannot be used with TLS 1.0. Hence an attacker can perform man-in-the- middle attack against the remote host.	172.16.160.14	Medium	It has been observed that the remote Windows host is affected by an elevation of privilege vulnerability.	It is recommended to implement the Microsoft released set of patches for Windows Vista, 2008, 7, 2008 R2, 2012, 8.1, RT 8.1, 2012 R2, and 10. References: http://badlock.org/	Op en	Open
Remote Desktop Protocol Server Manin-the-Middle Weakness Impact: The MiTM attack of this nature would allow the attacker to obtain any sensitive information transmitted, including authentication credentials.	172.16.160.16 172.17.160.16	Medi um	It is observed the remote version of the Remote Desktop Protocol Server (Terminal Service) is vulnerable to a man-in-the-middle (MiTM) attack. The RDP client makes no effort to validate the identity of the server when	It is recommended to force the use of SSL as a transport layer for this service if supported, or/and. Select the 'Allow connections only from computers running Remote Desktop with Network Level Authentication' setting if it is available.	Op en	Open



			setting up			
			encryption.	References: http://technet.micros oft.com/en- us/library/cc782610.a spx https://www.tenable.c om/plugins/nessus/1 8405		
SMB Signing not required. Impact: An unauthenticated, remote attacker can exploit this to conduct man-in-the-middle attacks against the SMB server.	172.16.160.10 172.16.160.12 172.16.160.14 172.16.160.18 172.16.160.20 172.16.160.22 172.16.160.4 172.16.160.6 172.16.160.8 172.17.160.12 172.17.160.18 172.17.160.20 172.17.160.20 172.17.160.6 172.17.160.6 172.17.160.6 172.17.160.6 172.17.160.6	Medi um	It was observed that signing is not required on the remote SMB server.	Enforce message signing in the host's configuration. On Windows, this is found in the policy setting 'Microsoft network server: Digitally sign communications (always)'. On Samba, the setting is called 'server signing'.	Op en	Open
Terminal Services Encryption Level is Medium or Low Impact: An attacker can eavesdrop on the communications more easily and obtain screenshots and/or keystrokes.	172.16.160.16 172.17.160.16	Medi um	It has been observed that the remote Terminal Services is t configured to use Medium cryptography.	It is recommended to Change RDP encryption level to High & FIPS Compliant References: https://techgenix.com/Windows Terminal/Services/#:~:text=Medium%3A%20encrypts%20both%20the%20data%20sent%20from%20client,40%20bit%20key%2C%20depending%20on%20the%20client%20version.	Op en	Open



Unencrypted Telnet Server Impact: Using Telnet over an unencrypted channel is not recommended as logins, passwords, and commands are transferred in cleartext. This allows a remote, man-in-the-middle attacker to eavesdrop on a Telnet session to obtain credentials or other sensitive information and to modify traffic exchanged between a client and server. SSH is preferred over Telnet since it protects credentials from eavesdropping and can tunnel additional data streams such as an X11 session.	172.16.200.201 172.16.200.202 172.16.200.203 172.16.200.204 172.16.200.205 172.17.200.201	Medium	It is observed that the remote Telnet server transmits traffic in cleartext.	It is recommended to disable the Telnet service and use SSH instead.	Op en	Open
Terminal Services Encryption Level is not FIPS-140 Compliant Impact: The attacker observed the encryption setting used by the remote Terminal Services after the attacker easy to expose the all sensitive data	172.16.160.16 172.17.160.16	Low	It is observed the Client Compatible setting encrypts data sent between the client and the server at the maximum key strength supported by the client.	It is recommended to change RDP encryption level to: 4. FIPS Compliant References: https://www.tenable.com/plugins/nessus/30218	Op en	Open



Asset Inventory detail

Inventory Overview

This section focuses on asset tracking, asset discovery and asset classification. These are the first steps for ensuring operational continuity, reliability and safety. They provide the user with a full context for security events and support routine procedures aimed at improving overall cyber hygiene. Creating an inventory of devices in the network, as well as understanding the relationships and connections between them, is a crucial component in network security.

Asset List DCS-1



Asset List DCS-2



Mapping of Vulnerabilities with Assets (DCS1)

Final Mapping of Assets:

Refer below excel file contains mapping of vulnerabilities & open ports with the assets, it provides the details of vulnerabilities observed in each asset.



Mapping of Vulnerabilities with Assets (DCS2)

Final Mapping of Assets:

Refer below excel file contains mapping of vulnerabilities & open ports with the assets, it provides the details of vulnerabilities observed in each asset.






Unit 2

Asset Classification


DCS 1 (BHEL Make)

The assessment was able to identify 64 all devices and discovered 52 vulnerabilities. Based on the assessment, risk mitigation and remediation are needed to reduce the risk of nation-level threat vector and improve the cyber posture.



C&I - Unit -2 DCS 2 (Emerson Make)

The assessment was able to identify 71 all devices and discovered 47 vulnerabilities. Based on the assessment, risk mitigation and remediation are needed to reduce the risk of nation-level threat vector and improve the cyber posture.



Vendors

undefined	Broadcom	Cisco	LCFC(HeFei) Electr
23	9	5	2
PEGATRON	TRANSMITTON LTD.	VMware, Inc.	
2	22	1	



C&I - Unit -2 DCS 2

undefined	Cisco	Dell Inc.	LCFC(HeFei) Electr
40	7	6	2
MICRO INDUSTRIES	VMware, Inc.		
15	1		

Asset Types


C&I - Unit -2 DCS 1

_	50	\\/ \ D	1	computer	12	switch	1
_	50	VVAP	I	computer	12	SVVILCIT	<u>'</u>

C&I - Unit -2 DCS 2


switch 1 - 76 computer 12 router 23	-	60	WA	P.	1	computer	7	router	2
- 76 computer 12 router 23	switch	1							
	-		76	comp	outer	12		router	23

Operating systems





C&I - Unit -2 DCS 2



Risk

Vulnerability Score

DCS₁

GT Risk Assessment Report provides a comprehensive risk analysis related to network behaviour and assets. Based on overall assessment for **NTPC TANDA**, all network risk score is 6.8 (Medium risk)



NAME	TYPE	OS/FIRMWARE	COUN T	SCORE DISTRIBUTION	SCORE High)	GROUPS (Lo	ow, Medium,
ws-c2950c-24	switch	Firmware: 12.1(22)ea6	52	ومالوه والمناوي	2	40	9
2OPSTN_1	comput er	Windows XP	686		29	463	194
2OPSTN_2	comput er	Windows XP	686		29	463	194
2OPSTN_3	comput er	Windows XP	686		2 9	463	194
2OPSTN_4	comput er	Windows XP	686		2 9	463	194
2OPSTN_5	comput er	Windows XP	686		29	463	194
2ENGG	comput er	Windows XP	686		2 9	463	194
2LVS_1	comput er	Windows XP	686		29	463	194
2LVS_2	comput er	Windows XP	686		29	463	194
2LVS_3	comput er	Windows XP	686		2 9	463	194
WCCBLRLAP6 60	WAP	Windows XP SP2/SP3 / 10 / 11 / Server / Server 2016 / Server 2019 / Server 2022	320		1 75	2	44
Assets w	ith co	nfirmed CPEs					7
Assets w	ith Fir	mware Discovered					110
Number	of Hos	sts with Vulnerabilities					1
Number	of Vul	nerabilities					52
/ulnerab	ility A	verage Score					6.8

DCS₂


GT Risk Assessment Report provides a comprehensive risk analysis related to network behaviour and assets. Based on overall assessment for **NTPC TANDA**, all network risk score is 6.7(Medium Risk)






Vulnerabilities per type

DCS₁




DCS₂



Top 30 Vulnerabilities on Network Devices

DCS₁

CVE	LABEL	CVE SCORE	CWE NAME	CVE CREATION TIME	TIME
CVE-2006- 4950	00:16:9dæd:41: d1	10.0	Improper Input Validation	2006-09-23 10:07:00	2022-12-13 15:36:38
CVE-2017- 12240	00:16:9d:ed:41: d1	9.8	Improper Restriction of Operations within the Bounds of a Mernory Buffer	2017-09-29 01:34:00	2022-12-13 15:36:38
CVE-2007- 2586	00:16:9d:ed:41: d1	9.3	Incorrect Authorization	2007-05-10 00:19:00	2022-12-13 15:36:38
CVE-2007-5381	00:16:9dæd:41: d1	9.3	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-12 01:17:00	2022-12-13 15:36:38
CVE-2007- 5552	00:16:9dæd:41: d1	9.3	Numeric Errors	2007-10-18 20:17:00	2022-12-13 15:36:38
CVE-2017-6743	00:16:9dæd:41: d1	8.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-07-17 21:29:00	2022-12-13 15:36:38
CVE-2019- 16009	00:16:9d:ed:41: d1	8.8	Cross-Site Request Forgery (CSRF)	2020-09-23 01:15:00	2022-12-13 15:36:38
CVE-2017- 3864	00:16:9d:ed:41: d1	8.6	Improper Input Validation	2017-03-22 19:59:00	2022-12-13 15:36:38
CVE-2016- 6380	00:16:9d:ed:41: d1	8.1	Improper Input Validation	2016-10-05 20:59:00	2022-12-13 15:36:38
CVE-2013-1142	00:16:9d:ed:41: d1	7.8	Concurrent Execution using Shared Resource with Improper Synchronization (Race Condition)	2013-03-28 23:55:00	2022-12-13 15:36:38
CVE-2009- 2051	00:16:9d:ed:41: d1	7.8	Improper Input Validation	2009-08-27 17:00:00	2022-12-13 15:36:38
CVE-2011-0946	00:16:9d:ed:41: d1	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-13 15:36:38
CVE-2011-3279	00:16:9d:ed:41: d1	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-13 15:36:38
CVE-2021- 34699	00:16:9d:ed:41: d1	7.7	Interpretation Conflict	2021-09-23 03:15:00	2022-12-13 15:36:38
CVE-2017-3857	00:16:9d:ed:41: d1	7.5	Uncontrolled Resource Consumption	2017-03-22 19:59:00	2022-12-13 15:36:38
CVE-2022- 20726	00:16:9d:ed:41: d1	7.5	Improper Neutralization of Input During Web Page Generation (Cross-site Scripting)	2022-04-15 15:15:00	2022-12-13 15:36:38
CVE-2019- 12655	00:16:9d:ed:41: d1	7.5	Buffer Copy without Checking Size of Input ('Classic Buffer Overflow')	2019-09-25 21:15:00	2022-12-13 15:36:38
CVE-1999-0293	00:16:9d:ed:41: d1	7.5	Improper Input Validation	1998-01-01 05:00:00	2022-12-13 15:36:38
CVE-2016-6415	00:16:9d:ed:41: d1	7.5	Exposure of Sensitive Information to an Unauthorized Actor	2016-09-19 01:59:00	2022-12-13 15:36:38
CVE-2016-6393	00:16:9d:ed:41: d1	7.5	Resource Management Errors	2016-10-05 20:59:00	2022-12-13 15:36:38
CVE-2016- 6384	00:16:9d:ed:41: d1	7.5	Improper Input Validation	2016-10-05 17:59:00	2022-12-13 15:36:38
CVE-2022- 20724	00:16:9d:ed:41: d1	7.5	Concurrent Execution using Shared Resource with Improper Synchronization (Race Condition)	2022-04-15 15:15:00	2022-12-13 15:36:38
CVE-2016-1409	00:16:9d:ed:41: d1	7.5	Improper Input Validation	2016-05-29 22:59:00	2022-12-13 15:36:38
CVE-2003- 0647	00:16:9d:ed:41: d1	7.5	Improper Restriction of Operations within the Bounds of a Memory Buffer	2003-08-27 04:00:00	2022-12-13 15:36:38
CVE-2019-1748	00:16:9dæd:41: d1	7.4	Improper Certificate Validation	2019-03-28 00:29:00	2022-12-13 15:36:38
CVE-2008-1151	00:16:9d:ed:41: d1	7.1	Resource Management Errors	2008-03-27 17:44:00	2022-12-13 15:36:38
CVE-2007-5551	00:16:9dæd:41: d1	7.1	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-18 20:17:00	2022-12-13 15:36:38
CVE-2008- 4963	00:16:9d:ed:41: d1	7.1	Improper Input Validation	2008-11-06 15:55:00	2022-12-13 15:36:38
CVE-2008- 4609	00:16:9dæd:41: d1	7.1	Configuration	2008-10-20 17:59:00	2022-12-13 15:36:38
CVE-2008-1150	00:16:9d:ed:41: d1	7.1	Resource Management Errors	2008-03-27 17:44:00	2022-12-13 15:36:38



CVE	LABEL	CVE SCORE	CWE NAME	CVE CREATION TIME	TIME
CVE-2006- 4950	u4-root- sw.cisco.com	10.0	Improper Input Validation	2006-09-23 10:07:00	2022-12-15 22:20:27
CVE-2017- 12240	u4-root- sw.cisco.com	9.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-09-29 01:34:00	2022-12-15 22:20:27
CVE-2007- 2586	u4-root- sw.cisco.com	9.3	Incorrect Authorization	2007-05-10 00:19:00	2022-12-15 22:20:27
CVE-2007- 5552	u4-root- sw.cisco.com	9.3	Numeric Errors	2007-10-18 20:17:00	2022-12-15 22:20:27
CVE-2017- 6743	u4-root- sw.cisco.com	8.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-07-17 21:29:00	2022-12-15 22:20:27
CVE-2019- 16009	u4-root- sw.cisco.com	8.8	Cross-Site Request Forgery (CSRF)	2020-09-23 01:15:00	2022-12-15 22:20:27
CVE-2017- 3864	u4-root- sw.cisco.com	8.6	Improper Input Validation	2017-03-22 19:59:00	2022-12-15 22:20:27
CVE-2016- 6380	u4-root- sw.cisco.com	8.1	Improper Input Validation	2016-10-05 20:59:00	2022-12-15 22:20:27
CVE-2009- 2051	u4-root- sw.cisco.com	7.8	Improper Input Validation	2009-08-27 17:00:00	2022-12-15 22:20:27
CVE-2011- 0946	u4-root- sw.cisco.com	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 22:20:27
CVE-2011-3279	u4-root- sw.cisco.com	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 22:20:27
CVE-2013-1142	u4-root- sw.cisco.com	7.8	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2013-03-28 23:55:00	2022-12-15 22:20:27
CVE-2021- 34699	u4-root- sw.cisco.com	7.7	Interpretation Conflict	2021-09-23 03:15:00	2022-12-15 22:20:27
CVE-1999- 0293	u4-root- sw.cisco.com	7.5	Improper Input Validation	1998-01-01 05:00:00	2022-12-15 22:20:27
CVE-2022- 20726	u4-root- sw.cisco.com	7.5	Improper Neutralization of Input During Web Page Generation ('Cross-site Scripting')	2022-04-15 15:15:00	2022-12-15 22:20:27
CVE-2022- 20724	u4-root- sw.cisco.com	7.5	Concurrent Execution using Shared Resource with Improper Synchronization (Race Condition)	2022-04-15 15:15:00	2022-12-15 22:20:27
CVE-2019- 12655	u4-root- sw.cisco.com	7.5	Buffer Copy without Checking Size of Input ('Classic Buffer Overflow')	2019-09-25 21:15:00	2022-12-15 22:20:27
CVE-2017- 3857	u4-root- sw.cisco.com	7.5	Uncontrolled Resource Consumption	2017-03-22 19:59:00	2022-12-15 22:20:27
CVE-2016- 6415	u4-root- sw.cisco.com	7.5	Exposure of Sensitive Information to an Unauthorized Actor	2016-09-19 01:59:00	2022-12-15 22:20:27
CVE-2016- 6393	u4-root- sw.cisco.com	7.5	Resource Management Errors	2016-10-05 20:59:00	2022-12-15 22:20:27
CVE-2016- 6385	u4-root- sw.cisco.com	7.5	Resource Management Errors	2016-10-05 20:59:00	2022-12-15 22:20:27
CVE-2016- 6384	u4-root- sw.cisco.com	7.5	Improper Input Validation	2016-10-05 17:59:00	2022-12-15 22:20:27
CVE-2016- 1409	u4-root- sw.cisco.com	7.5	Improper Input Validation	2016-05-29 22:59:00	2022-12-15 22:20:27
CVE-2008- 4609	u4-root- sw.cisco.com	7.1	Configuration	2008-10-20 17:59:00	2022-12-15 22:20:27
CVE-2008- 4963	u4-root- sw.cisco.com	7.1	Improper Input Validation	2008-11-06 15:55:00	2022-12-15 22:20:27
CVE-2007- 5551	u4-root- sw.cisco.com	7.1	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-18 20:17:00	2022-12-15 22:20:27
CVE-2007- 5548	u4-root- sw.cisco.com	6.9	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-18 20:17:00	2022-12-15 22:20:27
CVE-2008- 5230	u4-root- sw.cisco.com	6.8	Cryptographic Issues	2008-11-25 23:30:00	2022-12-15 22:20:27
CVE-2013- 6686	u4-root- sw.cisco.com	6.8	Improper Input Validation	2013-11-18 03:55:00	2022-12-15 22:20:27
CVE-2020- 3204	u4-root- sw.cisco.com	6.7	Improper Input Validation	2020-06-03 18:15:00	2022-12-15 22:20:27



Vulnerability summary

DCS₁

5
6
_
0
0
2
0
12

DCS₂

Malware detected	0
Different Operating Systems	5
Different Types of Technologies	5
Attempted Links to Public Internet	0
Multi-homed Assets	38
Different Firmware Versions	2
Clients Accessing SMB Shares	6
Insecure Protocol Links in the Environment	136

Clients accessing SMB Shares

FROM	то	PROTOCOL	TX PACKETS	TX BYTES
192.168.9.149	192.168.8.201	smb		
192.168.9.149	192.168.8.160	smb		
192.168.9.149	192.168.8.211	smb		
192.168.9.149	192.168.8.200	smb		
192.168.9.149	192.168.8.161	smb		
192.168.9.149	192.168.8.210	smb		



Devices Vulnerability Summary

Domain	Critical	High	Medium	Low	Total
Vulnerability Assessment	10	5	12	3	30
Re-validation(closed)	0	0	0	0	0
Re-validation(open)	10	5	12	3	30

Observation Summary

The chart given below represents the vulnerabilities found during network vulnerability testing:

Fig:1




Fig:2




Figure 1: Vulnerability Assessment Test Observations

Illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Figure 2: Vulnerability Assessment Test Observations- Revalidation

Illustrates the closure of Vulnerabilities based on the categorization i.e., Closed, Open.

Note:

Closed: Count considered having vulnerability in all the IP addresses as closed.

Open: Count considered having vulnerability in minimum one IP address as open/unreachable, it may have more different IP addresses which may have the same vulnerability as closed.



Vulnerability Assessment Test Observations

The below table illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Vulnerabilities &	Affected IP	Risk	Observations	Recommendations	Sta	Revalidati
Impact					tus	on status
Microsoft IIS 6.0	192.168.8.160	Criti	It was observed	It is recommended to	Op	Open
Unsupported Version	192.168.8.161	cal	that an	upgrade to a version	en	
Detection			unsupported	of Microsoft IIS that is		
			version of	currently supported.		
Impact:			Microsoft IIS is	currently supported.		
			running on the			
Lack of support implies			remote Windows host.			
that no new security patches for the product			11051.			
will be released by the						
vendor. As a result, it is						
likely to contain						
security vulnerabilities.						
Microsoft Windows	172.16.160.36	Criti	It is observed that	It is recommended to	Op	Open
Server 2003	172.16.160.38	cal	the remote	upgrade to a version	en	
Unsupported	172.17.160.36 192.168.8.160		operating system	of Windows that is		
Installation Detection.	192.168.8.161		is no longer supported.	currently supported.		
Detection.	192.168.8.200		Supported.			
Impact:	102.100.0.200					
Lack of support implies						
that no new security						
patches for the product						
will be released by the						
vendor. As a result, it is						
likely to contain						
security vulnerabilities. Furthermore, Microsoft						
is unlikely to						
investigate or						
acknowledge reports of						
vulnerabilities.						
Microsoft Windows	172.16.160.24	Criti	It is observed that	It is recommended to	Op	Open
XP Unsupported	172.16.160.26	cal	the remote	upgrade to a version	en	
Installation	172.16.160.28		operating system	of Windows that is		
Detection.	172.16.160.30		is no longer	currently supported.		
Impact:	172.16.160.32 172.16.160.34		supported.			
Lack of support implies	172.16.160.34					
that no new security	172.16.160.42					
patches for the product						
will be released by the	172.17.160.24					
vendor. As a result, it is	172.17.160.26					
likely to contain	172.17.160.28					
security vulnerabilities.	172.17.160.30					
Furthermore, Microsoft	172.17.160.32					
is unlikely to investigate or	172.17.160.40 172.17.160.42					
investigate or	172.17.100.42	İ				



acknowledge reports of vulnerabilities.	172.17.160.44 192.168.8.201 192.168.8.210 192.168.8.211					
MS05-027: Vulnerability in SMB Could Allow Remote Code Execution (896422) (uncredentialed check) Impact: The remote version of Windows contains a flaw in the Server Message Block (SMB) implementation that may allow an attacker to execute arbitrary code on the remote host. An attacker does not need to be authenticated to exploit this flaw.	172.16.160.24 172.16.160.26 172.16.160.30 172.16.160.40 172.16.160.44 172.17.160.24 172.17.160.30 172.17.160.40 172.17.160.44 192.168.8.201	Criti	It is observed that an arbitrary code can be executed on the remote host due to a flaw in the SMB implementation.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003. Reference: https://learn.microsoft.com/en-us/security-updates/SecurityBulletins/2005/ms05-027	Op en	Open
MS06-040: Vulnerability in Server Service Could Allow Remote Code Execution (921883) (uncredentialed check) Impact: The remote host is vulnerable to a buffer overrun in the 'Server' service that may allow an attacker to execute arbitrary code on the remote host with 'SYSTEM' privileges.	172.16.160.24 172.16.160.26 172.16.160.30 172.16.160.40 172.16.160.44 172.17.160.24 172.17.160.26 172.17.160.30 172.17.160.40 172.17.160.44 192.168.8.201	Criti	It is observed that an arbitrary code can be executed on the remote host due to a flaw in the 'Server' service.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003. References: https://learn.microsoft.com/en-us/security-updates/SecurityBulletins/2006/ms06-040	Op en	Open
MS08-067: Microsoft Windows Server Service Crafted RPC Request Handling Remote Code Execution (958644) (ECLIPSEDWING)	172.16.160.24 172.16.160.26 172.16.160.30 172.16.160.34 172.16.160.36 172.16.160.40 172.16.160.40	Criti cal	It is observed that the remote Windows host is affected by a remote code execution vulnerability.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003.	Op en	Open



(uncredentialed check) Impact: An unauthenticated, remote attacker can exploit this, via a specially crafted RPC request, to execute arbitrary code with 'System' privileges.	172.16.160.44 172.17.160.24 172.17.160.26 172.17.160.30 172.17.160.40 172.17.160.42 172.17.160.44 192.168.8.161 192.168.8.200 192.168.8.201					
MS09-001: Microsoft Windows SMB Vulnerabilities Remote Code Execution (958687) (uncredentialed check) Impact: The remote host is affected by a memory corruption vulnerability in SMB that may allow an attacker to execute arbitrary code or perform a denial of service against the remote host.	172.16.160.26 172.16.160.28 172.16.160.30 172.16.160.34 172.16.160.36 172.16.160.40 172.16.160.42 172.16.160.44 172.17.160.24 172.17.160.26 172.17.160.28 172.17.160.30 172.17.160.36	Criti	It is observed that it is possible to crash the remote host due to a flaw in SMB.	It is recommended to update set of patches for Windows 2000, XP, 2003, Vista and 2008 provided by Microsoft	Op en	Open
SSL Version 2 and 3 Protocol Detection. Impact: The remote service accepts connections encrypted using SSL 2.0 and/or SSL 3.0. These versions of SSL are affected by several cryptographic flaws, including: - An insecure padding scheme with CBC ciphers. - Insecure session renegotiation and resumption schemes.	192.168.8.160 192.168.8.200	Criti	It is observed that the remote service encrypts traffic using a protocol with known weaknesses.	It is recommended to consult the application's documentation to disable SSL 2.0 and 3.0. Use TLS 1.2 (with approved cipher suites) or higher instead.	Op en	Open



						Т
An attacker can exploit these flaws to conduct man-in-the-middle attacks or to decrypt communications between the affected service and clients. Unsupported Web Server Detection Impact: According to its version, the remote web server is obsolete and no longer maintained by its vendor or provider. Lack of support implies that no new security patches for the product will be released by the vendor. As a result, it may contain security	192.168.8.160 192.168.8.161	Criti	It was observed that the remote web server is obsolete / unsupported.	It is recommended to remove the web server if it is no longer needed. Otherwise, upgrade to a supported version if possible or switch to another server.	Op en	Open
vulnerabilities.						
Unsupported Windows (remote) Impact: The remote version of Microsoft Windows is either missing a service pack or is no longer supported. As a result, it is likely to contain security vulnerabilities.	172.16.160.24 172.16.160.26 172.16.160.28 172.16.160.30 172.16.160.32 172.16.160.34 172.16.160.38 172.16.160.40 172.16.160.42 172.16.160.42 172.16.160.44 172.17.160.24 172.17.160.28 172.17.160.30 172.17.160.30 172.17.160.30 172.17.160.40 172.168.8.160 192.168.8.200 192.168.8.201 192.168.8.210 192.168.8.211	Criti	It was observed that the remote version of Microsoft Windows is either missing a service pack or is no longer supported	It is recommended to upgrade to a supported service pack or operating system	Op en	Open



MS06.035:	172 16 160 24	High	It was shoomed	It is recommended to	On	Open
MS06-035: Vulnerability in Server Service Could Allow Remote Code Execution (917159) (uncredentialed check) Impact: The remote host is vulnerable to heap overflow in the 'Server' service that may allow an attacker to execute arbitrary code on the remote host with 'SYSTEM' privileges. In addition to this, the remote host is also affected by an information disclosure vulnerability in SMB that may allow an attacker to obtain portions of the memory of the remote host.	172.16.160.24 172.16.160.30 172.16.160.32 172.16.160.40 172.16.160.44 172.17.160.26 172.17.160.30 172.17.160.32 172.17.160.40 172.17.160.44 192.168.8.201	High	It was observed that an arbitrary code can be executed on the remote host due to a flaw in the 'Server' service.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003.	Op en	Open
MS17-010: Security Update for Microsoft Windows SMB Server (4013389) (ETERNALBLUE) (ETERNALCHAMPIO N) (ETERNALROMANCE) (ETERNALSYNERGY) (WannaCry) (EternalRocks) (Petya) (uncredentialed check) Impact: An unauthenticated, remote attacker can exploit these vulnerabilities, via a specially crafted packet, to execute arbitrary code. (CVE-2017-0143, CVE-2017-0144, CVE-2017-0145, CVE-2017-0146, CVE-2017-0148)	172.16.160.24 172.16.160.26 172.16.160.28 172.16.160.30 172.16.160.32 172.16.160.34 172.16.160.38 172.16.160.40 172.16.160.42 172.17.160.24 172.17.160.26 172.17.160.28 172.17.160.30 172.17.160.30 172.17.160.30 172.17.160.40 172.17.160.40 172.17.160.40 172.17.160.40 172.17.160.40 192.168.8.160 192.168.8.200 192.168.8.201 192.168.8.210 192.168.8.211	High	It has been observed that device is not updated to the MS SMB security patch (MS17-010)	It is recommended to follow the below mentioned. Microsoft has released a set of patches for Windows Vista, 2008, 7, 2008 R2, 2012, 8.1, RT 8.1, 2012 R2, 10, and 2016. Microsoft has also released emergency patches for Windows operating systems that are no longer supported, including Windows XP, 2003, and 8. References: https://learn.microsoft.com/en-us/security-updates/securitybulletins/2017/ms17-010	Op en	Open

	T	T			1	1
- An information disclosure vulnerability exists in Microsoft Server Message Block 1.0 (SMBv1) due to improper handling of certain requests. An unauthenticated, remote attacker can exploit this, via a specially crafted packet, to disclose sensitive information. (CVE-2017-0147)						
SMB NULL Session Authentication. Impact: The remote host is running and SMB protocol. It is possible to log into the browser or spoolss pipes using a NULL session (i.e., with no login or password). Depending on the configuration, it may be possible for an unauthenticated, remote attacker to leverage this issue to get information about the remote host.	172.16.160.24 172.16.160.26 172.16.160.28 172.16.160.30 172.16.160.34 172.16.160.36 172.16.160.40 172.16.160.42 172.16.160.42 172.16.160.44 172.17.160.26 172.17.160.28 172.17.160.30 172.17.160.30 172.17.160.40 172.17.160.40 172.17.160.42 172.17.160.42 172.17.160.44 192.168.8.160 192.168.8.200 192.168.8.201 192.168.8.210 192.168.8.210	High	It is observed that it is possible to log into the remote host with a NULL session.	It is recommended to contact the product vendor for recommended solutions.	Op en	Open
SSL Certificate Signed Using Weak Hashing Algorithm Impact: These signature algorithms are known to be vulnerable to collision attacks. An attacker can exploit this to generate another certificate with the same digital signature, allowing an attacker to masquerade as the affected service.	192.168.8.211 192.168.8.160 192.168.8.200	High	It was observed that the remote service uses an SSL certificate chain that has been signed using a cryptographically weak hashing algorithm (e.g. MD2, MD4, MD5, or SHA1).	It is recommended to have the SSL certificate reissued.	Op en	Open



An instinct for growth $\!\!\!\!^{^{\!\scriptscriptstyle{\mathsf{M}}}}$

SSL Medium	192.168.8.160	High	It has been	It is recommended to	Op	Open
Strength Cipher	192.168.8.200	riigii	observed that SSL	reconfigure the	en	Open
Suites Supported	102.100.0.200		is using medium	_	en	
(SWEET32)			strength	affected application if		
(011==10=)			encryption which	possible to avoid use		
Impact:			can be easily	of medium strength		
The remote host			compromised if	ciphers.		
			the attacker is on			
supports the use of			the same physical	References:		
SSL ciphers that offer			network.	[SOLVED] how to		
medium				disable ssl medium		
strength encryption				strength cipher suites		
that it is considerably				supported (sweet32)		
easier to circumvent						
medium strength				in GPO - Microsoft		
encryption if the				Remote Desktop		
attacker is on the same				<u>Services</u>		
physical network.				(spiceworks.com)		
1 7						
Microsoft Windows	172.16.160.36	Medi	It is observed that	It is recommended to	Op	Open
EFSRPC NTLM	172.16.160.38	um	the remote host is	apply the updates	en	•
Reflection Elevation	172.17.160.36	C	affected by an	supplied by the		
of Privilege	192.168.8.160		NTLM reflection			
(PetitPotam)	192.168.8.161		elevation of	vendor. Optionally,		
(Remote).	192.168.8.200		privilege	refer to Microsoft's		
Impact:			vulnerability.	KB5005413 for		
An unauthenticated,				mitigation guidance.		
remote attacker can				RPC filters may also		
exploit this, by sending				be implemented to		
a specially-crafted				block remote access		
EFSRPC request, to				to the interface		
cause the affected host				UUIDs necessary for		
to connect to a				this exploit.		
malicious server. An				tilis exploit.		
attacker can then						
utilize an NTLM relay to						
impersonate the target						
host and authenticate						
against remote services.						
Microsoft Windows	192.168.8.200	Medi	It is observed that	It is recommended to	Op	Open
SMB	102.100.0.200		it is possible to		-	Open
LsaQueryInformation		um	obtain the host	prevent anonymous	en	
Policy Function SID			SID for the remote	lookups of the host		
Enumeration Without		1	host, without	SID by setting the		
Credentials			credentials.	'RestrictAnonymous'		
				registry setting to an		
Impact:				appropriate value.		
By emulating the call to				References:		
LsaQueryInformationP						
olicy(), it was possible		1		https://learn.microsof		
to obtain the host SID						
(Security Identifier),				t.com/en-		
without credentials.				us/previous-		
	ĺ	1	I	versions/tn-		



The host SID can then be used to get the list of local users.				archive/bb418944(v= technet.10)?redirecte dfrom=MSDN		
MS16-047: Security Update for SAM and LSAD Remote Protocols (3148527) (Badlock) (uncredentialed check) Impact: Ciphers that support encryption before MAC computation, and authenticated encryption modes such as GCM cannot be used with TLS 1.0. Hence an attacker can perform man-in-the- middle attack against the remote host.	172.16.160.36 172.16.160.38 172.17.160.36 192.168.8.160 192.168.8.161 192.168.8.200	Medi um	It has been observed that the remote Windows host is affected by an elevation of privilege vulnerability.	It is recommended to implement the Microsoft released set of patches for Windows Vista, 2008, 7, 2008 R2, 2012, 8.1, RT 8.1, 2012 R2, and 10. References: http://badlock.org/	Op en	Open
SMB Signing not required. Impact: An unauthenticated, remote attacker can exploit this to conduct man-in-the-middle attacks against the SMB server.	172.16.160.36 172.16.160.38 172.16.160.40	Medi	It was observed that signing is not required on the remote SMB server.	It is recommended to enforce message signing in the host's configuration. On Windows, this is found in the policy setting 'Microsoft network server: Digitally sign communications (always)'. On Samba, the setting is called 'server signing'.	Op en	Open



SSL / TLS Renegotiation Handshakes MiTM Plaintext Data Injection Impact:	192.168.8.160 192.168.8.200	Medi um	It is observed that the remote service allows insecure renegotiation of TLS / SSL connections.	It is recommended to contact the vendor for specific patch information	Op en	Open
An unauthenticated, remote attacker may be able to leverage this issue to inject an arbitrary amount of plaintext into the beginning of the application protocol stream, which could facilitate man-in-the-middle attacks if the service assumes that the sessions before and after renegotiation are from the same 'client' and merges them at the application layer.						
SSL Certificate Expiry Impact: Websites with expired certificates are prone to attacks by hackers or attackers.	192.168.8.160 192.168.8.200	Medi um	It is observed to when using an expired SSL certificate, there is a continuous risk to the encryption and mutual authentication of website.	It is recommended to Purchase or generate a new SSL certificate to replace the existing one. References: https://www.tenable.com/plugins/nessus/15901 https://nvd.nist.gov/vuln/detail/CVE-2015-3886	Op en	Open
SSL RC4 Cipher Suites Supported (Bar Mitzvah) Impact: If plaintext is repeatedly encrypted (e.g., HTTP cookies), and an attacker is able to obtain many (i.e., tens of millions) ciphertexts, the	192.168.8.160 192.168.8.200	Medi um	It has been observed that remote host is using weak cipher suite.	It is recommended to reconfigure the affected application, if possible, to avoid use of RC4 ciphers. Consider using TLS 1.2 with AES-GCM suites subject to browser and web server support. References:	Op en	Open




						T
attacker may be able to derive the plaintext.				SSL RC4 Cipher Suites Supported (Bar Mitzvah) (microsoft.com)		
SSL Weak Cipher Suites Supported Impact: The attackers can spoof the identity of the victim. Unlike CAissued certificates, self-signed certificates cannot be revoked. The inability to quickly find and revoke private key associated with a self-signed certificate creates serious risk.	192.168.8.160 192.168.8.200	Medi um	It is observed this is considerably easier to exploit if the attacker is on the same physical network.	It is recommended to Reconfigure the affected application, if possible to avoid the use of weak ciphers. References: How to Disable Weak SSL Protocols and Ciphers in IIS Wayne Zimmerman's Blog	Op en	Open
SSL/TLS EXPORT_RSA <= 512-bit Cipher Suites Supported (FREAK) Impact: The remote host supports EXPORT_RSA cipher suites with keys less than or equal to 512 bits. An attacker can factor a 512-bit RSA modulus in a short amount of time. A man-in-the middle attacker may be able to downgrade the session to use EXPORT_RSA cipher suites (e.g. CVE-2015-0204). Thus, it is recommended to remove support for weak cipher suites.	192.168.8.160 192.168.8.200	Medi um	It is observed that the remote host supports a set of weak ciphers.	It is recommended to reconfigure the service to remove support for EXPORT_RSA cipher suites.	Op en	Open
SSLv3 Padding Oracle on Downgraded Legacy Encryption	192.168.8.160 192.168.8.200	Medi um	It has been observed that the remote host is vulnerable to	It is recommended to disable SSLv3. Services that must support SSLv3 should enable the	Op en	Open



			T		1	1
Vulnerability (POODLE) Impact: An attacker can perform a man-in-the-middle (MitM) information disclosure known as POODLE. MitM attackers can decrypt a selected byte of a cipher text in as few as 256 tries if they are able to force a victim application to repeatedly send the same data over newly created SSL 3.0 connections.			padding oracle attack.	TLS Fallback SCSV mechanism until SSLv3 can be disabled. References: How to fix POODLE vulnerability (SSL v3) in Windows - Windows VPS Hosting Blog - AccuWeb Hosting		
TLS Version 1.0 Protocol Detection Impact: An attacker can cause connection failures and they can trigger the use of TLS 1.0 to exploit vulnerabilities like BEAST (Browser Exploit Against SSL/TLS). Websites using TLS 1.0 will be considered noncompliant by PCI after 30 June 2018.	192.168.8.160 192.168.8.200	Medi um	It is observed to TLS 1.2 is more secure, an attacker can cause connection failures and they can trigger the use of TLS 1.0 to exploit vulnerabilities.	It is recommended to Enable support for TLS 1.2 and 1.3, and disable support for TLS 1.0. References: https://datatracker.ietf.org/doc/html/rfc8996	Op en	Open
Unencrypted Telnet Server Impact: An attacker may eavesdrop on a Telnet session and obtain credentials or other sensitive information. Use of SSH is preferred nowadays as it protects credentials from eavesdropping and can tunnel additional data streams such as the X11 session.	172.16.200.213 172.16.200.214 172.16.200.216 172.17.200.212 172.17.200.213 172.17.200.214	Medi um	It is observed SSH is preferred over Telnet since it protects credentials from eavesdropping and can tunnel additional data streams such as an X11 session.	It is recommended to Disable the Telnet service and use SSH instead. References: How to Disable Telnet and Enable SSH on Cisco IOS Devices (networkstraining.com)	Op en	Open



CCI Contificate Obside	400 400 0 400	Law	lk was shaary			0000
SSL Certificate Chain Contains RSA Keys Less Than 2048 bits. Impact: According to industry standards set by the Certification Authority/Browser (CA/B) Forum, certificates issued after January 1, 2014 must be at least 2048 bits. Some browser SSL implementations may reject keys less than 2048 bits after January 1, 2014. Additionally, some SSL certificate vendors may revoke certificates less than 2048 bits before January 1, 2014.	192.168.8.160 192.168.8.200	Low	It was observed that at least one of the X.509 certificates sent by the remote host has a key that is shorter than 2048 bits	It is recommended to replace the certificate in the chain with the RSA key less than 2048 bits in length with a longer key, and reissue any certificates signed by the old certificate.	Op en	Open
SSL/TLS Diffie-Hellman Modulus <= 1024 Bits (Logjam) Impact: Through cryptanalysis, a third party may be able to find the shared secret in a short amount of time (depending on modulus size and attacker resources). This may allow an attacker to recover the plaintext or potentially violate the integrity of connections.	192.168.8.160 192.168.8.200	Low	It was observed that the remote host allows SSL/TLS connections with one or more Diffie-Hellman moduli less than or equal to 1024 bits.	It is recommended to reconfigure the service to use a unique Diffie-Hellman moduli of 2048 bits or greater.	Op en	Open



An instinct for growth

SSL/TLS	192.168.8.160	Low	It is observed that	It is recommended to	Op	Open
EXPORT_DHE <=	192.168.8.200		the remote host	reconfigure the	en	
512-bit Export Cipher			supports a set of	service to remove		
Suites Supported			weak ciphers.	support for		
(Logjam)				EXPORT_DHE		
				cipher suites.		
Impact:				cipilei suites.		
The remote host						
supports EXPORT_DHE cipher						
suites with keys less						
than or equal to 512						
bits. Through						
cryptanalysis, a third						
party can find the						
shared secret in a short						
amount of time.						
A man-in-the middle						
attacker may be able to						
downgrade the session						
to use EXPORT_DHE						
cipher suites. Thus, it is						
recommended to						
remove support for						
weak cipher suites.						

Asset Inventory detail

Inventory Overview

This section focuses on asset tracking, asset discovery and asset classification. These are the first steps for ensuring operational continuity, reliability and safety. They provide the user with a full context for security events and support routine procedures aimed at improving overall cyber hygiene. Creating an inventory of devices in the network, as well as understanding the relationships and connections between them, is a crucial component in network security.

Asset List DCS-1



Asset List DCS-2





Mapping of Vulnerabilities with Assets (DCS1)

Final Mapping of C&I Unit-2 Dept Assets:

Refer below excel file contains mapping of vulnerabilities & open ports with the assets, it provides the details of vulnerabilities observed in each asset.



Mapping of Vulnerabilities with Assets (DCS2)

Final Mapping of C&I Unit-2 Dept Assets:

Refer below excel file contains mapping of vulnerabilities & open ports with the assets, it provides the details of vulnerabilities observed in each asset.




Unit 3

Asset Classification

DCS 1(BHEL Make)

The assessment was able to identify 103 all devices and discovered 48 vulnerabilities.

Based on the assessment, risk mitigation and remediation are needed to reduce the risk of nation-level threat vector and improve the cyber posture.






DCS 2 (Emerson Make)

The assessment was able to identify 71 all devices and discovered 48 vulnerabilities.

Based on the assessment, risk mitigation and remediation are needed to reduce the risk of nation-level threat vector and improve the cyber posture.



Vendors

DCS₁

undefined	Broadcom	Cisco	HP
59	5	3	3
LCFC(HeFei) Electr	PEGATRON	-	TRANSMITTON LTD.
2	1	5	24
VMware, Inc.			

DCS₂

undefined	Cisco	Dell Inc.	LCFC(HeFei) Electr
40	6	6	2
MICRO INDUSTRIES			
17			
undefined	Broadcom	Cisco	Hirschmann
101	6	3	3
Intel Corporate	LCFC(HeFei) Electr	TRANSMITTON LTD.	VMware, Inc.
26	2	1	1



Asset Types

DCS₁


- 90 computer	12	switch	1
---------------	----	--------	---

DCS₂


_	60	computer	Q	router	2	switch	1
_	60	computer	0	Touter		30011011	1

Operating systems


DCS₁



DCS₂







Risk

Vulnerability Score

DCS₁

GT Risk Assessment Report provides a comprehensive risk analysis related to network behaviour and assets. Based on overall assessment for **NTPC TANDA**, all network risk score is 6.7(Medium Risk)

NAME	ТҮРЕ	OS/FIRMWARE	COUNT	SCORE DISTRIBUTION	SCO	RE GROUPS (L	ow, Medium, H	igh)
ws-c2950c-24	switch	Firmware: 12.1(22)ea9	48	حباست	2	37	8	
OWS1	computer	Windows XP	686		29	463	194	
4OPSTN_2	computer	Windows XP	686		29	463	194	
4OPSTN_3	computer	Windows XP	686		29	463	194	
4ENGG	computer	Windows XP	686		29	463	194	
4LVS_1	computer	Windows XP	686	والمساورة والمساورة	29	463	194	
3EWS	computer	Windows XP	686	and the second	29	463	194	
OWS2	computer	Windows XP	686	and the second	29	463	194	
3STORIAN	computer	Windows XP	686	and the second	29	463	194	
WCCBLRLAP660	computer	Windows XP SP2	1027	والمتعادية	21	498	508	
4STORIAN_2	computer	Windows Server 2003 R2 SP2	341	والمراجع المراجع	2	240	99	
4STORIAN_1	computer	Windows Server 2003 SP1	52	سلست	1	35	16	
Assets witl	h confirm	ned CPEs						1
Assets witl	h Firmwa	are Discovered						141
Number of	f Hosts w	ith Vulnerabilities	5					1
Number of	f Vulnera	bilities						48
Vulnerabili	ity Avera	ge Score						6.7




DCS₂


GT Risk Assessment Report provides a comprehensive risk analysis related to network behaviour and assets. Based on overall assessment for **NTPC TANDA**, all network risk score is 6.7(Medium risk)

NAME	TYPE	OS/FIRMWARE	COUNT	SCORE DISTRIBUTION	sco	RE GROUPS (L	ow, Medium, High)	
ws-c2950-24	switch	Firmware: 12.1(22)ea5	48		2	37	8	
DROP201	computer	Windows XP	686		29	463	194	
DROP210	computer	Windows XP	686		29	463	194	
DROP211	computer	Windows XP	686		29	463	194	
WCCBLRLAP660	computer	Windows XP SP2	1027	والمستوال	21	498	508	
DROP160	computer	Windows Server 2003 R2 SP1	43		2	26	15	
DROP161	computer	Windows Server 2003 R2 SP1	43	والمراجعين	2	26	15	
DROP200	computer	Windows Server 2003 R2 SP2	341	عباست	2	240	99	
Assets with	confirm	ned CPEs						1
Assets with	Firmwa	re Discovered					10	09
Number of Hosts with Vulnerabilities								1
Number of	Number of Vulnerabilities							
Vulnerabili	ty Avera	ge Score					(6.7

Vulnerabilities per type

C&I - Unit -3 DCS 1







Top 30 Vulnerabilities on Network Devices

CVE	LABEL	CVE SCORE	CWE NAME	CVE CREATION TIME	TIME
CVE-2006- 4950	00:1c:0f:75:c8: 4d	10.0	Improper Input Validation	2006-09-23 10:07:00	2022-12-15 10:22:00
CVE-2017- 12240	00:1c:0f:75:c8: 4d	9.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-09-29 01:34:00	2022-12-15 10:22:00
CVE-2007- 2586	00:1c:0f:75:c8: 4d	9.3	Incorrect Authorization	2007-05-10 00:19:00	2022-12-15 10:22:00
CVE-2007- 5552	00:1c:0f:75:c8: 4d	9.3	Numeric Errors	2007-10-18 20:17:00	2022-12-15 10:22:00
CVE-2017- 6743	00:1c:0f:75:c8: 4d	8.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-07-17 21:29:00	2022-12-15 10:22:00
CVE-2019- 16009	00:1c:0f:75:c8: 4d	8.8	Cross-Site Request Forgery (CSRF)	2020-09-23 01:15:00	2022-12-15 10:22:00
CVE-2017- 3864	00:1c:0f:75:c8: 4d	8.6	Improper Input Validation	2017-03-22 19:59:00	2022-12-15 10:22:00
CVE-2016- 6380	00:1c:0f:75:c8: 4d	8.1	Improper Input Validation	2016-10-05 20:59:00	2022-12-15 10:22:00
CVE-2011-3279	00:1c:0f:75:c8: 4d	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 10:22:00
CVE-2009- 2051	00:1c:0f:75:c8: 4d	7.8	Improper Input Validation	2009-08-27 17:00:00	2022-12-15 10:22:00
CVE-2011-0946	00:1c:0f:75:c8: 4d	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 10:22:00
CVE-2013-1142	00:1c:0f:75:c8: 4d	7.8	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2013-03-28 23:55:00	2022-12-15 10:22:00
CVE-2021- 34699	00:1c:0f:75:c8: 4d	7.7	Interpretation Conflict	2021-09-23 03:15:00	2022-12-15 10:22:00
CVE-1999-0293	00:1c:0f:75:c8: 4d	75	Improper Input Validation	1998-01-01 05:00:00	2022-12-15 10:22:00
CVE-2017-3857	00:1c:0f:75:c8: 4d	75	Uncontrolled Resource Consumption	2017-03-22 19:59:00	2022-12-15 10:22:00
CVE-2016-1409	00:1c:0f:75:c8: 4d	75	Improper Input Validation	2016-05-29 22:59:00	2022-12-15 10:22:00
CVE-2022- 20724	00:1c:0f:75:c8: 4d	75	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2022-04-15 15:15:00	2022-12-15 10:22:00
CVE-2016-6415	00:1c:0f:75:c8: 4d	75	Exposure of Sensitive Information to an Unauthorized Actor	2016-09-19 01:59:00	2022-12-15 10:22:00
CVE-2016-6393	00:1c:0f:75:c8: 4d	7.5	Resource Management Errors	2016-10-05 20:59:00	2022-12-15 10:22:00
CVE-2016- 6384	00:1c:0f:75:c8: 4d	75	Improper Input Validation	2016-10-05 17:59:00	2022-12-15 10:22:00
CVE-2019- 12655	00:1c:0f:75:c8: 4d	75	Buffer Copy without Checking Size of Input ('Classic Buffer Overflow')	2019-09-25 21:15:00	2022-12-15 10:22:00
CVE-2003- 0647	00:1c:0f:75:c8: 4d	75	Improper Restriction of Operations within the Bounds of a Memory Buffer	2003-08-27 04:00:00	2022-12-15 10:22:00
CVE-2022- 20726	00:1c:0f:75:c8: 4d	75	Improper Neutralization of Input During Web Page Generation ('Cross-site Scripting')	2022-04-15 15:15:00	2022-12-15 10:22:00
CVE-2008- 4609	00:1c:0f:75:c8: 4d	7.1	Configuration	2008-10-20 17:59:00	2022-12-15 10:22:00
CVE-2008- 4963	00:1c:0f:75:c8: 4d	7.1	Improper Input Validation	2008-11-06 15:55:00	2022-12-15 10:22:00
CVE-2008-1151	00:1c:0f:75:c8: 4d	7.1	Resource Management Errors	2008-03-27 17:44:00	2022-12-15 10:22:00
CVE-2008-1150	00:1c:0f:75:c8: 4d	7.1	Resource Management Errors	2008-03-27 17:44:00	2022-12-15 10:22:00
CVE-2007-5551	00:1c:0f:75:c8: 4d	7.1	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-18 20:17:00	2022-12-15 10:22:00
CVE-2007- 5548	00:1c:0f:75:c8: 4d	6.9	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-18 20:17:00	2022-12-15 10:22:00
CVE-2008- 5230	00:1c:0f:75:c8: 4d	6.8	Cryptographic Issues	2008-11-25 23:30:00	2022-12-15 10:22:00



CVE	LABEL	CVE SCORE	CWE NAME	CVE CREATION TIME	TIME
CVE-2006- 4950	00:1c:b1:b2:53: 94	10.0	Improper Input Validation	2006-09-23 10:07:00	2022-12-15 22:34:31
CVE-2017- 12240	001cb1b253: 94	9.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-09-29 01:34:00	2022-12-15 22:34:31
CVE-2007- 2586	00:1cb1:b253: 94	9.3	Incorrect Authorization	2007-05-10 00:19:00	2022-12-15 22:34:31
CVE-2007- 5552	00:1cb1:b253: 94	93	Numeric Errors	2007-10-18 20:17:00	2022-12-15 22:34:31
CVE-2017-6743	00:1cb1:b253: 94	8.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-07-17 21:29:00	2022-12-15 22:34:31
CVE-2019- 16009	00:1cb1:b253: 94	8.8	Cross-Site Request Forgery (CSRF)	2020-09-23 01:15:00	2022-12-15 22:34:31
CVE-2017- 3864	00:1cb1:b253: 94	8.6	Improper Input Validation	2017-03-22 19:59:00	2022-12-15 22:34:31
CVE-2016- 6380	00:1cb1:b253: 94	8.1	Improper Input Validation	2016-10-05 20:59:00	2022-12-15 22:34:31
CVE-2011-3279	00:1cb1:b253: 94	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 22:34:31
CVE-2009- 2051	00:1cb1:b253: 94	7.8	Improper Input Validation	2009-08-27 17:00:00	2022-12-15 22:34:31
CVE-2011-0946	00:1cb1:b253: 94	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 22:34:31
CVE-2013-1142	00:1cb1:b253: 94	7.8	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2013-03-28 23:55:00	2022-12-15 22:34:31
CVE-2021- 34699	00:1cb1:b253: 94	7.7	Interpretation Conflict	2021-09-23 03:15:00	2022-12-15 22:34:31
CVE-1999-0293	00:1cb1:b253: 94	7.5	Improper Input Validation	1998-01-01 05:00:00	2022-12-15 22:34:31
CVE-2017-3857	00:1cb1:b253: 94	7.5	Uncontrolled Resource Consumption	2017-03-22 19:59:00	2022-12-15 22:34:31
CVE-2016-1409	00:1cb1:b253: 94	7.5	Improper Input Validation	2016-05-29 22:59:00	2022-12-15 22:34:31
CVE-2022- 20724	00:1cb1:b253: 94	7.5	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2022-04-15 15:15:00	2022-12-15 22:34:31
CVE-2016-6415	00:1cb1:b253: 94	7.5	Exposure of Sensitive Information to an Unauthorized Actor	2016-09-19 01:59:00	2022-12-15 22:34:31
CVE-2016-6393	00:1cb1:b253: 94	7.5	Resource Management Errors	2016-10-05 20:59:00	2022-12-15 22:34:31
CVE-2016- 6384	00:1cb1:b253: 94	7.5	Improper Input Validation	2016-10-05 17:59:00	2022-12-15 22:34:31
CVE-2019- 12655	00:1cb1:b253: 94	7.5	Buffer Copy without Checking Size of Input ('Classic Buffer Overflow')	2019-09-25 21:15:00	2022-12-15 22:34:31
CVE-2003- 0647	00:1cb1:b253: 94	7.5	Improper Restriction of Operations within the Bounds of a Memory Buffer	2003-08-27 04:00:00	2022-12-15 22:34:31
CVE-2022- 20726	00:1cb1:b253: 94	7.5	Improper Neutralization of Input During Web Page Generation ('Cross-site Scripting')	2022-04-15 15:15:00	2022-12-15 22:34:31
CVE-2008- 4609	00:1cb1:b253: 94	7.1	Configuration	2008-10-20 17:59:00	2022-12-15 22:34:31
CVE-2008- 4963	00:1cb1:b253: 94	7.1	Improper Input Validation	2008-11-0615:55:00	2022-12-15 22:34:31
CVE-2008-1151	00:1cb1:b253: 94	7.1	Resource Management Errors	2008-03-27 17:44:00	2022-12-15 22:34:31
CVE-2008-1150	00:1cb1:b253: 94	7.1	Resource Management Errors	2008-03-27 17:44:00	2022-12-15 22:34:31
CVE-2007-5551	00:1cb1:b253: 94	7.1	Improper Restriction of Operations within the Bounds of a Mernory Buffer	2007-10-18 20:17:00	2022-12-15 22:34:31
CVE-2007- 5548	00:1cb1:b253: 94	6.9	Improper Restriction of Operations within the Bounds of a Mernory Buffer	2007-10-18 20:17:00	2022-12-15 22:34:31
CVE-2008- 5230	001cb1b253: 94	6.8	Cryptographic Issues	2008-11-25 23:30:00	2022-12-15 22:34:31



Vulnerability summary

C&I - Unit -3 DCS 1

Malware detected	0
Different Operating Systems	6
Different Types of Technologies	8
Attempted Links to Public Internet	0
Multi-homed Assets	O
Different Firmware Versions	2
Clients Accessing SMB Shares	19
Insecure Protocol Links in the Environment	103

Clients accessing SMB Shares

FROM	то	PROTOCOL	TX PACKETS	TX BYTES
172.16.160.56	172.16.160.8	smb		
172.16.200.149	172.16.160.86	smb		
172.16.200.149	172.16.160.8	smb		
172.16.200.149	172.16.160.54	smb		
172.16.200.149	172.16.160.84	smb		
172.16.200.149	172.16.160.80	smb		
172.16.200.149	172.16.160.78	smb		
172.16.200.149	172.16.3.37	smb		
172.16.200.149	172.16.160.4	smb		
172.16.200.149	172.16.160.56	smb		
172.16.200.149	172.16.3.35	smb		
172.16.200.149	172.16.160.58	smb		
172.16.200.149	172.16.3.36	smb		
172.16.200.149	172.16.3.34	smb		
172.16.200.149	172.16.160.50	smb		
172.16.200.149	172.16.160.46	smb		
172.16.200.149	172.16.3.32	smb		
172.16.200.149	172.16.160.52	smb		
172.16.200.149	172.16.160.48	smb		

Malware detected	0
Different Operating Systems	6
Different Types of Technologies	5
Attempted Links to Public Internet	0
Multi-homed Assets	38
Different Firmware Versions	2
Clients Accessing SMB Shares	6
Insecure Protocol Links in the Environment	140



Clients accessing SMB Shares						
FROM	то	PROTOCOL	TX PACKETS	TX BYTES		
192.168.3.149	192.168.2.211	smb				
192.168.3.149	192.168.2.210	smb				
192.168.3.149	192.168.2.160	smb				
192.168.3.149	192.168.2.161	smb				
192.168.3.149	192.168.2.201	smb				
192.168.3.149	192.168.2.200	smb				

Devices Vulnerability Summary

Unit 3

Domain	Critical	High	Medium	Low	Total
Vulnerability Assessment	12	7	18	4	41
Re-validation(closed)	0	0	0	0	0
Re-validation(open)	12	7	18	4	41

Observation Summary

The chart given below represents the vulnerabilities found during network vulnerability testing:

Fig:1




Fig:2




Figure 1: Vulnerability Assessment Test Observations

Illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Figure 2: Vulnerability Assessment Test Observations- Revalidation

Illustrates the closure of Vulnerabilities based on the categorization i.e., Closed, Open.



Note:

Closed: Count considered having vulnerability in all the IP addresses as closed.

Open: Count considered having vulnerability in minimum one IP address as open/unreachable, it may have more different IP addresses which may have the same vulnerability as closed.

Vulnerability Assessment Test Observations

The below table illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Vulnerabilities &	Affected IP	Risk	Observations	Recommendations	Sta	Revalidati
Impact Conficker Worm Detection (uncredentialed check) Impact: This worm has several capabilities which allow an attacker to execute arbitrary code on the remote operating system. The remote host might also be attempting to propagate the worm to third party hosts.	172.17.160.78 172.17.160.8 172.17.160.86	Criti cal	It was observed that the remote host seems to be infected by a variant of the Conficker worm.	It is recommended to update your Antivirus and perform a full scan of the remote operating system.	Op en	Open
Microsoft IIS 6.0 Unsupported Version Detection Impact: Lack of support implies that no new security patches for the product will be released by the vendor. As a result, it is likely to contain security vulnerabilities.	192.168.2.160 192.168.2.161	Criti	It was observed that an unsupported version of Microsoft IIS is running on the remote Windows host.	It is recommended to upgrade to a version of Microsoft IIS that is currently supported.	Op en	Open
Microsoft RDP RCE (CVE-2019-0708) (BlueKeep) (uncredentialed check) Impact: An unauthenticated, remote attacker can exploit this, via a series of specially crafted	192.168.2.160 192.168.2.161 192.168.2.200	Criti cal	It was observed that the remote host is affected by a remote code execution vulnerability.	It is recommended to implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by Microsoft.	Op en	Open



An instinct for growth $^{^{\mathsf{T}}}$

requests, to execute arbitrary code.						
Microsoft Windows Server 2003 Unsupported Installation Detection.	192.168.2.160 192.168.2.161 192.168.2.200	Criti cal	It is observed that the remote operating system is no longer supported.	It is recommended to upgrade to a version of Windows that is currently supported.	Op en	Open
Lack of support implies that no new security patches for the product will be released by the vendor. As a result, it is likely to contain security vulnerabilities. Furthermore, Microsoft is unlikely to investigate or acknowledge reports of vulnerabilities.	470.40.400.4					
Microsoft Windows XP Unsupported Installation Detection. Impact: Lack of support implies that no new security patches for the product will be released by the vendor. As a result, it is likely to contain security vulnerabilities. Furthermore, Microsoft is unlikely to investigate or acknowledge reports of vulnerabilities.	172.16.160.4 172.17.160.4 172.17.160.78 172.17.160.8 172.17.160.86 192.168.2.201 192.168.2.210 192.168.2.211	Criti	It is observed that the remote operating system is no longer supported.	It is recommended to upgrade to a version of Windows that is currently supported.	Op en	Open
MS05-027: Vulnerability in SMB Could Allow Remote Code Execution (896422) (uncredentialed check) Impact:	172.16.160.4 172.17.160.4 192.168.2.201	Criti cal	It is observed that an arbitrary code can be executed on the remote host due to a flaw in the SMB implementation.	upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003. Reference:	Op en	Open
The remote version of Windows contains a flaw in the Server Message Block (SMB) implementation that may allow an attacker to execute arbitrary code on the remote				https://learn.microsoft.co m/en-us/security- updates/SecurityBulletin s/2005/ms05-027		



192.168.2.201	Criti cal	It is observed that a flaw in the client service for NetWare may allow an attacker to execute arbitrary code on the remote host.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003.	Op en	Open
172.16.160.4 172.17.160.4 192.168.2.160 192.168.2.161 192.168.2.200 192.168.2.201 192.168.2.210 192.168.2.211	Criti cal	It is observed that the remote Windows host is affected by a remote code execution vulnerability.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003.	Op en	Open
172.16.160.4 172.17.160.4 172.17.160.78 172.17.160.8 172.17.160.86 192.168.2.160 192.168.2.161 192.168.2.200 192.168.2.201	Criti cal	It is observed that it is possible to crash the remote host due to a flaw in SMB.	It is recommended to update set of patches for Windows 2000, XP, 2003, Vista and 2008 provided by Microsoft	Op en	Open
	172.16.160.4 172.17.160.4 192.168.2.160 192.168.2.200 192.168.2.201 192.168.2.211 192.168.2.211 192.168.2.211 172.17.160.4 172.17.160.8 172.17.160.8 172.17.160.86 192.168.2.161 192.168.2.200	172.16.160.4 172.17.160.4 192.168.2.160 192.168.2.200 192.168.2.201 192.168.2.211 192.168.2.211 192.168.2.211 172.17.160.4 172.17.160.8 172.17.160.8 172.17.160.8 172.17.160.8 192.168.2.160 192.168.2.161 192.168.2.200 192.168.2.201	172.16.160.4 172.17.160.4 172.17.160.8 172.	172.16.160.4 172.17.160.4 192.168.2.200 192.168.2.160 192.168.2.160 192.168.2.161 172.17.160.4 172.17.160.8 172.17.160.8 172.17.160.8 192.168.2.160 192.168.2.200 19	172.16.160.4 172.17.160.4 192.168.2.211 172.17.160.8 192.168.2.161 192.168.2.161 192.168.2.161 192.168.2.161 192.168.2.200 192.168.2.200 192.168.2.200 192.168.2.200 192.168.2.200 192.168.2.200 192.168.2.200 192.168.2.201 192.168.2.201 192.168.2.201 192.168.2.201 192.168.2.201 192.168.2.201 192.168.2.201 192.168.2.201 192.168.2.201 192.168.2.201 192.168.2.201 192.168.2.201 192.168.2.201 192.168.2.200

An instinct for growth $\!\!\!\!^{^{\!\scriptscriptstyle{\mathsf{M}}}}$

The remote host is affected by a memory corruption vulnerability in SMB that may allow an attacker to execute arbitrary code or perform a denial of service against the remote host.	192.168.2.211					
SSL Version 2 and 3 Protocol Detection. Impact: The remote service accepts connections encrypted using SSL 2.0 and/or SSL 3.0. These versions of SSL are affected by several cryptographic flaws, including: - An insecure padding scheme with CBC ciphers. - Insecure session renegotiation and resumption schemes. An attacker can exploit these flaws to conduct man-in-the-middle attacks or to decrypt communications between the affected service and clients.	172.17.160.80 172.17.160.84 192.168.2.200	Criti	It is observed that the remote service encrypts traffic using a protocol with known weaknesses.	It is recommended to consult the application's documentation to disable SSL 2.0 and 3.0. Use TLS 1.2 (with approved cipher suites) or higher instead.	Op en	Open
Unsupported Web Server Detection Impact: According to its version, the remote web server is obsolete and no longer maintained by its vendor or provider. Lack of support implies that no new security patches for the product will be released by the vendor. As a result, it may contain security vulnerabilities.	192.168.2.160 192.168.2.161	Criti	It was observed that the remote web server is obsolete / unsupported.	It is recommended to remove the web server if it is no longer needed. Otherwise, upgrade to a supported version if possible or switch to another server.	Op en	Open



An instinct for growth $\!\!\!\!^{^{\!\scriptscriptstyle{\mathsf{M}}}}$

Ungunnariad	170 46 400 4	C=:4:	It was absenced	It is recommended to	0	Onen
Unsupported Windows OS (remote) Impact: The remote version of Microsoft Windows is either missing a service pack or is no longer supported. As a result, it is likely to contain security vulnerabilities.	172.16.160.4 172.17.160.4 172.17.160.78 172.17.160.86 172.17.160.86 192.168.2.160 192.168.2.161 192.168.2.200 192.168.2.201 192.168.2.210 192.168.2.211	Criti cal	It was observed that the remote version of Microsoft Windows is either missing a service pack or is no longer supported	It is recommended to upgrade to a supported service pack or operating system	Op en	Open
MS06-035: Vulnerability in Server Service Could Allow Remote Code Execution (917159) (uncredentialed check)	172.16.160.4 172.17.160.4 192.168.2.201	High	It was observed that an arbitrary code can be executed on the remote host due to a flaw in the 'Server' service.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003.	Op en	Open
Impact:						
The remote host is vulnerable to heap overflow in the 'Server' service that may allow an attacker to execute arbitrary code on the remote host with 'SYSTEM' privileges. In addition to this, the remote host is also affected by an information disclosure vulnerability in SMB that may allow an attacker to obtain portions of the memory of the remote host.						
MS12-020: Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check)	192.168.2.160 192.168.2.161 192.168.2.200	High	It was observed that the remote Windows host could allow arbitrary code execution.	It is recommended to implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by Microsoft.	Op en	Open
Impact: An arbitrary remote code vulnerability exists in the implementation of the						

Remote Desktop Protocol (RDP) on the remote Windows host. The vulnerability is due to the way that RDP accesses an object in memory that has been improperly initialized or has been deleted. If RDP has been enabled on the affected system, an unauthenticated, remote attacker could leverage this vulnerability to cause the system to execute arbitrary code by sending a sequence of specially crafted RDP packets to it.						
MS17-010: Security Update for Microsoft Windows SMB Server (4013389) (ETERNALBLUE) (ETERNALCHAMPIO N) (ETERNALROMANCE) (ETERNALSYNERGY) (WannaCry) (EternalRocks) (Petya) (uncredentialed check) Impact: An unauthenticated, remote attacker can exploit these vulnerabilities, via a specially crafted packet, to execute arbitrary code. (CVE-2017-0143, CVE-2017-0144, CVE-2017-0145, CVE-2017-0146, CVE-2017-0148) - An information disclosure vulnerability exists in Microsoft Server Message Block 1.0 (SMBv1) due to	172.16.160.4 172.17.160.4 172.17.160.78 172.17.160.86 192.168.2.160 192.168.2.200 192.168.2.201 192.168.2.211 192.168.2.211	High	It has been observed that device is not updated to the MS SMB security patch (MS17-010)	It is recommended to follow the below mentioned. Microsoft has released a set of patches for Windows Vista, 2008, 7, 2008 R2, 2012, 8.1, RT 8.1, 2012 R2, 10, and 2016. Microsoft has also released emergency patches for Windows operating systems that are no longer supported, including Windows XP, 2003, and 8. REFERENCE: https://learn.microsoft.com/en-us/security-updates/securitybulletins/2017/ms17-010	Op en	Open



improper handling of certain requests. An unauthenticated, remote attacker can exploit this, via a specially crafted packet, to disclose sensitive information. (CVE-2017-0147)						
Network Time Protocol Daemon (ntpd) monlist Command Enabled DoS. Impact: The version of ntpd running on the remote host is vulnerable to a DoS attack if the 'monlist' command is enabled. The 'monlist' command returns a list of recent hosts that have connected to the service. However, it is affected by a denial-of- service vulnerability in ntp_request.c that allows an unauthenticated, remote attacker to saturate network traffic to a specific IP address by using forged REQ_MON_GETLIST or REQ_MON_GETLIST or requests. Furthermore, an attacker can exploit this issue to conduct reconnaissance or distributed denial of service (DDoS)	172.17.160.84 192.168.2.201	High	It was observed that the remote network time server can be affected by a denial-of-service vulnerability.	It is recommended to upgrade to NTP version 4.2.7-p26 or later. Alternatively, add 'disable monitor' to the ntp.conf configuration file and restart the service. Otherwise, limit access to the affected service to trusted hosts, or contact the vendor for a fix.	Op en	Open
attacks. SMB NULL Session Authentication. Impact: The remote host is running and SMB protocol. It is possible to log into the browser or spoolss pipes using a NULL session (i.e.,	172.16.160.4 172.17.160.4 172.17.160.78 172.17.160.8 172.17.160.86 192.168.2.160 192.168.2.161 192.168.2.200 192.168.2.201 192.168.2.210 192.168.2.211	High	It is observed that it is possible to log into the remote host with a NULL session.	It is recommended to contact the product vendor for recommended solutions.	Op en	Open



with no login or password).						
Depending on the configuration, it may be possible for an unauthenticated, remote attacker to leverage this issue to get information about the remote host.						
SSL Certificate Signed Using Weak Hashing Algorithm Impact: These signature algorithms are known to be vulnerable to collision attacks. An attacker can exploit this to generate another certificate with the same digital signature, allowing an attacker to masquerade as the affected service.	172.17.160.80 172.17.160.84 192.168.2.200	High	It was observed that the remote service uses an SSL certificate chain that has been signed using a cryptographicall y weak hashing algorithm (e.g., MD2, MD4, MD5, or SHA1).	It is recommended to have the SSL certificate reissued.	Op en	Open
SSL Medium	172.17.160.80	High	It has been	It is recommended to	Ор	Open
Strength Cipher	172.17.160.84		observed that		en	
Strength Cipher Suites Supported (SWEET32)	172.17.160.84 192.168.2.200		observed that SSL is using medium strength encryption which	reconfigure the affected application, if possible, to avoid use of medium	•	
Suites Supported (SWEET32) Impact:			SSL is using medium strength encryption which can be easily	reconfigure the affected application, if possible, to	•	
Suites Supported (SWEET32) Impact: The remote host			SSL is using medium strength encryption which can be easily compromised if	reconfigure the affected application, if possible, to avoid use of medium strength ciphers.	•	
Suites Supported (SWEET32) Impact: The remote host supports the use of			SSL is using medium strength encryption which can be easily	reconfigure the affected application, if possible, to avoid use of medium	•	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer			SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References:	•	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength			SSL is using medium strength encryption which can be easily compromised if the attacker is on the same	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites	•	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is			SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in	•	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength			SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in GPO - Microsoft Remote	•	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to			SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in GPO - Microsoft Remote Desktop Services	•	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength. encryption if the			SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in GPO - Microsoft Remote	•	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength. encryption if the attacker is on the same			SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in GPO - Microsoft Remote Desktop Services	•	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength. encryption if the	192.168.2.200 192.168.3.5	Medi	SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical network.	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in GPO - Microsoft Remote Desktop Services	•	Open
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength. encryption if the attacker is on the same physical network. IP Forwarding Enabled.	192.168.2.200	Medi um	SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical network.	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in GPO - Microsoft Remote Desktop Services (spiceworks.com)	en	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength. encryption if the attacker is on the same physical network. IP Forwarding Enabled. Impact:	192.168.2.200 192.168.3.5		SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical network. It has been observed that IP forwarding is	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in GPO - Microsoft Remote Desktop Services (spiceworks.com)	en	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength. encryption if the attacker is on the same physical network. IP Forwarding Enabled. Impact: The remote host has IP	192.168.2.200 192.168.3.5		SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical network.	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in GPO - Microsoft Remote Desktop Services (spiceworks.com) It is recommended to follow the given steps below:	en	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength. encryption if the attacker is on the same physical network. IP Forwarding Enabled. Impact:	192.168.2.200 192.168.3.5		SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical network. It has been observed that IP forwarding is enabled on	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in GPO - Microsoft Remote Desktop Services (spiceworks.com) It is recommended to follow the given steps below: On Linux, you can	en	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength. encryption if the attacker is on the same physical network. IP Forwarding Enabled. Impact: The remote host has IP forwarding enabled. An attacker can exploit this to route packets	192.168.2.200 192.168.3.5		SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical network. It has been observed that IP forwarding is enabled on	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in GPO - Microsoft Remote Desktop Services (spiceworks.com) It is recommended to follow the given steps below: On Linux, you can disable IP forwarding by	en	
Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength. encryption if the attacker is on the same physical network. IP Forwarding Enabled. Impact: The remote host has IP forwarding enabled. An attacker can exploit	192.168.2.200 192.168.3.5		SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical network. It has been observed that IP forwarding is enabled on	reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in GPO - Microsoft Remote Desktop Services (spiceworks.com) It is recommended to follow the given steps below: On Linux, you can	en	



All illstillet for	g					
some firewalls / routers / NAC filtering.				echo 0 > /proc/sys/net/ipv4/ip_for ward On Windows, set the key 'IPEnableRouter' to 0 under HKEY_LOCAL_MACHI NE\System\CurrentCont rolSet\Services\Tcpip\Pa rameters On Mac OS X, you can disable IP forwarding by executing the command: sysctl -w net.inet.ip.forwarding=0 References: https://linuxconfig.org/ho w-to-turn-on-off-ip- forwarding-in-linux https://docs.oracle.com/ cd/E19957-01/805- 2901-		
Microsoft Windows EFSRPC NTLM Reflection Elevation of Privilege (PetitPotam) (Remote). Impact: An unauthenticated, remote attacker can exploit this, by sending a specially crafted EFSRPC request, to cause the affected host to connect to a malicious server. An attacker can then utilize an NTLM relay to impersonate the target host and authenticate	192.168.2.160 192.168.2.161 192.168.2.200	Medi um	It is observed that the remote host is affected by an NTLM reflection elevation of privilege vulnerability.	It is recommended to apply the updates supplied by the vendor. Optionally, refer to Microsoft's KB5005413 for mitigation guidance. RPC filters may also be implemented to block remote access to the interface UUIDs necessary for this exploit.	Op en	Open



			T		1	
against remote services.						
Microsoft Windows	192.168.2.200	Medi	It is observed	It is recommended to	Op	Open
SMB LsaQueryInformation Policy Function SID Enumeration Without Credentials		um	that it is possible to obtain the host SID for the remote host, without credentials.	prevent anonymous lookups of the host SID by setting the 'RestrictAnonymous' registry setting to an	en	
Impact:				appropriate value.		
By emulating the call to LsaQueryInformationP				References:		
olicy(), it was possible to obtain the host SID (Security Identifier), without credentials.				https://learn.microsoft.co m/en-us/previous- versions/tn- archive/bb418944(v=tec		
The host SID can then be used to get the list of local users.				hnet.10)?redirectedfrom =MSDN		
MS16-047: Security Update for SAM and LSAD Remote Protocols (3148527) (Badlock) (uncredentialed check)	192.168.2.160 192.168.2.161 192.168.2.200	Medi um	It has been observed that the remote Windows host is affected by an elevation of privilege vulnerability.	It is recommended to implement the Microsoft released set of patches for Windows Vista, 2008, 7, 2008 R2, 2012, 8.1, RT 8.1, 2012 R2, and 10.	Op en	Open
Impact: Ciphers that support encryption before MAC computation, and authenticated encryption modes such as GCM cannot be used with TLS 1.0. Hence an attacker can perform man-in-the-middle attack against the remote host.				References: http://badlock.org/		
Network Time Protocol (NTP) Mode 6 Scanner	172.17.160.84 192.168.2.201 192.168.3.1 192.168.3.2	Medi um	It has been observed that a remote NTP server responds	It is recommended to restrict NTP mode 6 queries.	Op en	Open
Impact: An unauthenticated, remote attacker could potentially exploit this, via a specially crafted mode 6 query, to cause	192.168.3.5 192.168.3.6		to mode 6 queries.	References: https://www.ibm.com/su pport/pages/ibm-aix- disable-ntp-mode-6-and- 7-queries		



a reflected denial of				https://community.cisco.		
service condition.				com/t5/other-data-		
				center-subjects/how-to-		
				restrict-ntp-mode-6-		
				queries/td-p/3335720		
NTP ntpd Mode 7	172.17.160.84	Medi	It is observed	It is recommended to	Op	Open
Error Response	192.168.2.201	um	that the remote	upgrade to NTP 4.2.4p8	en	
Packet Loop Remote			network time	/ 4.2.6 or later.		
DoS			service has a			
Impact:			denial-of-service vulnerability.			
ilipact.			vullierability.			
The version of ntpd						
running on the remote						
host has a denial-of-						
service vulnerability. It						
responds to mode 7						
error packets with its						
own mode 7 error packets. A remote						
attacker could exploit						
this by sending a mode						
7 error response with a						
spoofed IP header,						
setting the source and						
destination IP						
addresses to the IP						
address of the target.						
This would cause ntpd to respond to itself						
endlessly, consuming						
excessive amounts of						
CPU, resulting in a						
denial of service.						
Microsoft Windows		Medi		It is recommended to	Op	Open
Remote Desktop	192.168.2.161	um	remote version	10100 1110 400 01 002 40 4	en	
Protocol Server Man-	192.168.2.200		of the Remote Desktop	transport layer for this		
in-the-Middle			Protocol Server	service if supported,		
Weakness			(Terminal	or/and. Select the 'Allow		
			Service) is	connections only from		
			vulnerable to a	computers running		
			man-in-the-	Remote Desktop with		
			middle (MiTM)	Network Level		
Impact:			attack. The RDP	Authentication' setting if		
The MiTM attack of this			client makes no effort to validate	it is available.		
nature would allow the			the identity of the			
attacker to obtain any			server when	References:		
sensitive information			setting up	http://technet.microsoft.c		
transmitted, including			encryption.	om/en-		
	I			/library/22700010 222		
authentication				us/library/cc782610.asp		
authentication credentials.				$\frac{\text{us/iibrary/cc782610.asp}}{\underline{X}}$		



		1			1	
SMB Signing not	172.16.160.4	Medi	It has been	https://www.tenable.com/plugins/nessus/18405	Ор	Open
required Impact: Signing is not required on the remote SMB server. An unauthenticated, remote attacker can exploit this to conduct man-in-the-middle attacks against the SMB server.	172.17.160.4 172.17.160.78 172.17.160.8 172.17.160.86 192.168.2.160 192.168.2.161 192.168.2.201 192.168.2.210 192.168.2.211	um	observed that remote host does not require SMB Signing.	enable signing is on the remote SMB server. References: How to resolve SMB Signing not required Vulnerability - GISPP	en	
SSL / TLS Renegotiation Handshakes MiTM Plaintext Data Injection Impact:	172.17.160.80 172.17.160.84 192.168.2.200	Medi um	It is observed that the remote service allows insecure renegotiation of TLS / SSL connections.	It is recommended to contact the vendor for specific patch information	Op en	Open
An unauthenticated, remote attacker may be able to leverage this issue to inject an arbitrary amount of plaintext into the beginning of the application protocol stream, which could facilitate man-in-the-middle attacks if the service assumes that the sessions before and after renegotiation are from the same 'client' and merges them at the application layer.						
SSL Certificate Expiry Impact: Websites with expired certificates are prone to attacks by hackers or attackers.	172.17.160.80 172.17.160.84 192.168.2.200	Medi um	It is observed to when using an expired SSL certificate, there is a continuous risk to the encryption and mutual	It is recommended to Purchase or generate a new SSL certificate to replace the existing one. References: https://www.tenable.com/plugins/nessus/15901	Op en	Open



			authentication of	https://nvd.nist.gov/vuln/		
			website.	detail/CVE-2015-3886		
SSL Certificate with	172.17.160.80	Medi	It has been	Purchase or generate a	Op	Open
Wrong Hostname	172.17.160.84	um	observed that	proper SSL certificate for	en	Open
in ong mooniame	172.171100.01	uiii		' '	CII	
Impact:				this service.		
The 'commonName'			certificate for this			
			service is for a			
(CN) attribute of the			different host.			
SSL certificate						
presented for this						
service is for a different						
machine.						
SSL RC4 Cipher	172.17.160.80	Medi	It has been	It is recommended to	Op	Open
Suites Supported		um	observed that	reconfigure the affected	en	-
(Bar Mitzvah)	192.168.2.200		remote host is	application, if possible, to		
			using weak	avoid use of RC4		
Impact:			cipher suite.	ciphers. Consider using		
If plaintext is						
repeatedly encrypted				TLS 1.2 with AES-GCM		
(e.g., HTTP cookies),				suites subject to browser		
and an attacker is able				and web server support.		
				References:		
to obtain many (i.e. tens of millions)				SSL RC4 Cipher Suites		
				Supported (Bar Mitzvah)		
ciphertexts, the				(microsoft.com)		
attacker may be able to						
derive the plaintext.						
SSL Weak Cipher	172.17.160.80	Medi	It is observed	It is recommended to	Op	Open
Suites Supported	172.17.160.84	um	this is	Reconfigure the affected	en	
	192.168.2.200		considerably	application, if possible to		
Impact:			easier to exploit			
The attackers can			if the attacker is	ciphers.		
spoof the identity of the			on the same	References:		
victim. Unlike CA-			physical	How to Disable Weak		
issued certificates,			network.	SSL Protocols and		
			HIGIWOIN.			
self-signed certificates				Ciphers in IIS Wayne		
cannot be revoked.				Zimmerman's Blog		
The inability to quickly						
find and revoke private						
key associated with a						
self-signed certificate						
creates serious risk.						



SSL/TLS	172.17.160.80	Medi	It is observed	It is recommended to	Op	Open
EXPORT_RSA <=	172.17.160.84	um	that the remote	reconfigure the service	en	
512-bit Cipher Suites	192.168.2.200		host supports a	to remove support for		
Supported (FREAK)			set of weak	EXPORT_RSA cipher		
Impact:			ciphers.	suites.		
The remote host						
supports						
EXPORT_RSA cipher						
suites with keys less						
than or equal to 512						
bits. An attacker can factor a 512-bit RSA						
modulus in a short						
amount of time.						
amount of time.						
A man-in-the middle						
attacker may be able to						
downgrade the session						
to use EXPORT_RSA						
cipher suites (e.g.						
CVE-2015-0204).						
Thus, it is						
recommended to						
remove support for						
weak cipher suites.	4=0.4= 400.00				_	
SSLv3 Padding	172.17.160.80	Medi	It has been	It is recommended to	Op	Open
Oracle on	172.17.160.84	um	observed that	disable SSLv3. Services	en	
Downgraded Legacy	192.168.2.200		the remote host is vulnerable to	that must support SSLv3 should enable the TLS		
Encryption Vulnerability			padding oracle	Fallback SCSV		
(POODLE)			attack.	mechanism until SSLv3		
Impact:			attaorti	can be disabled.		
				References:		
An attacker can				How to fix POODLE		
perform a man-in-the-				vulnerability (SSL v3) in		
middle (MitM)				Windows - Windows		
information disclosure				VPS Hosting Blog -		
known as POODLE.				AccuWeb Hosting		
MitM attackers can						
decrypt a selected byte of a cipher text in as						
few as 256 tries if they						
are able to force a						
victim application to						
repeatedly send the						
same data over newly						
created SSL 3.0						
connections.						
Terminal Services	192.168.2.160	Medi	It has been	It is recommended to	Op	Open
Encryption Level is	192.168.2.161	um	observed that	Change RDP encryption	en	
Medium or Low	192.168.2.200		the remote	level to High & FIPS		
Immonto			Terminal	Compliant		
Impact:			Services is t	'		
An attacker can eavesdrop on the			configured to	References:		
eavesdrop on the communications more						
- COMMUNICATIONS MOTE	İ	l	l		İ	



easily and obtain screenshots and/or keystrokes.			use Medium cryptography.	https://techgenix.com/Windows_Terminal_Services/#:~:text=Medium%3A%20encrypts%20both%20the%20data%20sent%20from%20client,40%20bit%20key%2C%20depending%20on%20the%20client%20version.		
TLS Version 1.0 Protocol Detection Impact: An attacker can cause connection failures and they can trigger the use of TLS 1.0 to exploit vulnerabilities like BEAST (Browser Exploit Against SSL/TLS). Websites using TLS 1.0 will be considered noncompliant by PCI after 30 June 2018.	172.17.160.80 172.17.160.84 192.168.2.200	Medi um	It is observed to TLS 1.2 is more secure, an attacker can cause connection failures and they can trigger the use of TLS 1.0 to exploit vulnerabilities.	It is recommended to Enable support for TLS 1.2 and 1.3, and disable support for TLS 1.0. References: https://www.invicti.com/web-vulnerability-scanner/vulnerabilities/insecure-transportation-security-protocol-supported-tls-10/	Op en	Open
Unencrypted Telnet Server Impact: Using Telnet over an unencrypted channel is not recommended as logins, passwords, and commands are transferred in cleartext. This allows a remote, man-in-the-middle attacker to eavesdrop on a Telnet session to obtain credentials or other sensitive information and to modify traffic exchanged between a client and server. SSH is preferred over Telnet since it protects credentials from eavesdropping and can tunnel additional	172.16.200.163 172.17.200.163 192.168.3.1 192.168.3.2 192.168.3.5 192.168.3.6 192.168.3.9	Medi	It is observed that the remote Telnet server transmits traffic in cleartext.	It is recommended to disable the Telnet service and use SSH instead.	Op en	Open



-	T	1			ı	<u> </u>
data streams such as an X11 session.						
Multiple Ethernet Driver Frame Padding Information Disclosure (Etherleak) Impact: this information disclosure vulnerability may allow an attacker to collect sensitive information from the affected host provided he is on the same physical subnet as that host.	172.16.3.32 172.16.3.33 172.16.3.34 172.16.3.35 172.16.3.36 172.16.3.37 172.17.3.32 172.17.3.33 172.17.3.34 172.17.3.35 172.17.3.36 172.17.3.36	Low	It is observed that the remote host appears to leak memory in network packets.	contact the network device driver's vendor for	Op en	Open
SSL Certificate Chain Contains RSA Keys Less Than 2048 bits. Impact: According to industry standards set by the Certification Authority/Browser (CA/B) Forum, certificates issued after January 1, 2014 must be at least 2048 bits. Some browser SSL implementations may reject keys less than 2048 bits after January 1, 2014. Additionally, some SSL certificate vendors may revoke certificates less than 2048 bits before January 1, 2014.	192.168.2.200	Low	It was observed that at least one of the X.509 certificates sent by the remote host has a key that is shorter than 2048 bits	replace the certificate in the chain with the RSA key less than 2048 bits in length with a longer key, and reissue any	Op en	Open
SSL/TLS Diffie-Hellman Modulus <= 1024 Bits (Logjam) Impact: Through cryptanalysis, a third party may be able to find the shared secret in a short amount of time (depending on modulus size and attacker resources).	172.17.160.80 172.17.160.84 192.168.2.200	Low	It was observed that the remote host allows SSL/TLS connections with one or more Diffie-Hellman moduli less than or equal to 1024 bits.	It is recommended to reconfigure the service to use a unique Diffie-Hellman moduli of 2048 bits or greater.	Op en	Open



An instinct for growth[™]

This may allow an attacker to recover the plaintext or potentially violate the integrity of connections.						
SSL/TLS EXPORT_DHE <= 512-bit Export Cipher Suites Supported (Logjam) Impact: The remote host supports EXPORT_DHE cipher suites with keys less than or equal to 512 bits. Through cryptanalysis, a third party can find the shared secret in a short amount of time. A man-in-the middle attacker may be able to downgrade the session to use EXPORT_DHE cipher suites. Thus, it is recommended to remove support for weak cipher suites.	172.17.160.80 172.17.160.84 192.168.2.200	Low	It is observed that the remote host supports a set of weak ciphers.	It is recommended to reconfigure the service to remove support for EXPORT_DHE cipher suites.	Op en	Open

Asset Inventory detail

Inventory Overview

This section focuses on asset tracking, asset discovery and asset classification. These are the first steps for ensuring operational continuity, reliability and safety. They provide the user with a full context for security events and support routine procedures aimed at improving overall cyber hygiene. Creating an inventory of devices in the network, as well as understanding the relationships and connections between them, is a crucial component in network security.

Asset List DCS-1





Asset List DCS-2



Mapping of Vulnerabilities with Assets (DCS1)

Final Mapping of C&I Unit-3 Dept Assets:

Refer below excel file contains mapping of vulnerabilities & open ports with the assets, it provides the details of vulnerabilities observed in each asset.



Mapping of Vulnerabilities with Assets (DCS2)

Final Mapping of C&I Unit-3 Dept Assets:

Refer below excel file contains mapping of vulnerabilities & open ports with the assets, it provides the details of vulnerabilities observed in each asset.




Unit 4

Asset Classification

DCS 1 (BHEL Make)

The assessment was able to identify 83 all devices and discovered 48 vulnerabilities.

Based on the assessment, risk mitigation and remediation are needed to reduce the risk of nation-level threat vector and improve the cyber posture.






C&I - Unit -4 DCS 2 (Emerson Make)

The assessment was able to identify 143 all devices and discovered 96 vulnerabilities.

Based on the assessment, risk mitigation and remediation are needed to reduce the risk of nation-level threat vector and improve the cyber posture.



Vendors

C&I - Unit -4 DCS 1

undefined	Broadcom	Cisco	HP
44	5	3	3
LCFC(HeFei) Electr	PEGATRON	-	TRANSMITTON LTD.
3	1	5	19

C&I - Unit -4 DCS 2

undefined 83	Cisco 16	Dell Inc.	LCFC(HeFei) Electr 2
MICRO INDUSTRIES			
32			

Asset Types

C&I - Unit -4 DCS 1

- 70 computer	12	switch	1
---------------	----	--------	---


C&I - Unit -4 DCS 2

	1		1		1		1
-	125	computer	12	router	4	switch	2




Operating systems

C&I - Unit -4 DCS 1



C&I - Unit -4 DCS 2



Risk Vulnerability Score

C&I - Unit -4 DCS 1


GT Risk Assessment Report provides a comprehensive risk analysis related to network behaviour and assets. Based on overall assessment for **NTPC TANDA**, all network risk score is 6.7(Medium risk)



NAME	TYPE	OS/FIRMWARE	COUNT	SCORE DISTRIBUTION	SCOF	RE GROUPS (Lo	ow, Medium, High	n)
ws-c2950c-24	switch	Firmware: 12.1(22)ea8a	48		2	37	8	
OWSI	computer	Windows XP	686		29	463	194	
4OPSTN_2	computer	Windows XP	686		29	463	194	
4OPSTN_3	computer	Windows XP	686		29	463	194	
4ENGG	computer	Windows XP	686		29	463	194	
4LVS_1	computer	Windows XP	686		29	463	194	
3EWS	computer	Windows XP	686		29	463	194	
OWS2	computer	Windows XP	686		29	463	194	
3STORIAN	computer	Windows XP	686		29	463	194	
WCCBLRLAP660	computer	Windows XP SP2	1027		21	498	508	
4STORIAN_2	computer	Windows Server 2003 R2 SP2	341		2	240	99	
4STORIAN_1	computer	Windows Server 2003 SP1	52		1	35	16	
Assets witl	h confirn	ned CPEs						1
Assets witl	h Firmwa	are Discovered						124
Number of	f Hosts w	ith Vulnerabilities	5					1
Number of	f Vulnera	bilities						48
Vulnerabil	ity Avera	ge Score						6.7

C&I - Unit -4 DCS 2

GT Risk Assessment Report provides a comprehensive risk analysis related to network behaviour and assets. Based on overall assessment for **NTPC TANDA**, all network risk score is 6.7(Medium risk)





Vulnerabilities per type

C&I - Unit -4 DCS 1


Improper Neutralization of Input Du...: 6.3 %

Resource Management Errors: 6.3 %

Improper Restriction of Opera...: 10.4 %

Exposure of Sensitive Information to ...:

C&I - Unit -4 DCS 2



Top 30 Vulnerabilities on Network Devices

C&I - Unit -4 DCS 1

CVE	LABEL	CVE	CWE NAME	CVE CREATION TIME	TIME
CVE-2006- 4950	00:19:aa:f2:a5: 4e	10.0	Improper Input Validation	2006-09-23 10:07:00	2022-12-15 11:42:09
CVE-2017- 12240	00:19:aa:f2:a5: 4e	9.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-09-29 01:34:00	2022-12-15 11:42:09
CVE-2007- 2586	00:19:aaf2:a5: 4e	9.3	Incorrect Authorization	2007-05-10 00:19:00	2022-12-15 11:42:09
CVE-2007- 5552	00:19:aa:f2:a5: 4e	9.3	Numeric Errors	2007-10-18 20:17:00	2022-12-15 11:42:09
CVE-2017-6743	00:19:aa:f2:a5: 4e	8.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-07-17 21:29:00	2022-12-15 11:42:09
CVE-2019- 16009	00:19:aa:f2:a5: 4e	8.8	Cross-Site Request Forgery (CSRF)	2020-09-23 01:15:00	2022-12-15 11:42:09
CVE-2017- 3864	00:19:aa:f2:a5: 4e	8.6	Improper Input Validation	2017-03-22 19:59:00	2022-12-15 11:42:09
CVE-2016- 6380	00:19:aa:f2:a5: 4e	8.1	Improper Input Validation	2016-10-05 20:59:00	2022-12-15 11:42:09
CVE-2011-3279	00:19:aa:f2:a5: 4e	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 11:42:09
CVE-2009- 2051	00:19:aa:f2:a5: 4e	7.8	Improper Input Validation	2009-08-27 17:00:00	2022-12-15 11:42:09
CVE-2011-0946	00:19:aa:f2:a5: 4e	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 11:42:09
CVE-2013-1142	00:19:aa:f2:a5: 4e	7.8	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2013-03-28 23:55:00	2022-12-15 11:42:09
CVE-2021- 34699	00:19:aa:f2:a5: 4e	7.7	Interpretation Conflict	2021-09-23 03:15:00	2022-12-15 11:42:09
CVE-1999-0293	00:19:aa:f2:a5: 4e	7.5	Improper Input Validation	1998-01-01 05:00:00	2022-12-15 11:42:09
CVE-2017-3857	00:19:aa:f2:a5: 4e	7.5	Uncontrolled Resource Consumption	2017-03-22 19:59:00	2022-12-15 11:42:09
CVE-2016-1409	00:19:aa:f2:a5: 4e	7.5	Improper Input Validation	2016-05-29 22:59:00	2022-12-15 11:42:09
CVE-2022- 20724	00:19:aa:f2:a5: 4e	7.5	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2022-04-15 15:15:00	2022-12-15 11:42:09
CVE-2016-6415	00:19:aa:f2:a5: 4e	7.5	Exposure of Sensitive Information to an Unauthorized Actor	2016-09-19 01:59:00	2022-12-15 11:42:09
CVE-2016-6393	00:19:aa:f2:a5: 4e	7.5	Resource Management Errors	2016-10-05 20:59:00	2022-12-15 11:42:09
CVE-2016- 638-4	00:19:aa:f2:a5: 4e	7.5	Improper Input Validation	2016-10-05 17:59:00	2022-12-15 11:42:09
CVE-2019- 12655	00:19:aa:f2:a5: 4e	7.5	Buffer Copy without Checking Size of Input (Classic Buffer Overflow)	2019-09-25 21:15:00	2022-12-15 11:42:09
CVE-2003- 0647	00:19:aa:f2:a5: 4e	7.5	Improper Restriction of Operations within the Bounds of a Memory Buffer	2003-08-27 04:00:00	2022-12-15 11:42:09
CVE-2022- 20726	00:19:aa:f2:a5: 4e	7.5	Improper Neutralization of Input During Web Page Generation ('Cross-site Scripting')	2022-04-15 15:15:00	2022-12-15 11:42:09
CVE-2008- 4609	00:19:aa:f2:a5: 4e	7.1	Configuration	2008-10-20 17:59:00	2022-12-15 11:42:09
CVE-2008- 4963	00:19:aa:f2:a5: 4e	7.1	Improper Input Validation	2008-11-06 15:55:00	2022-12-15 11:42:09
CVE-2008-1151	00:19:aa:f2:a5: 4e	7.1	Resource Management Errors	2008-03-27 17:44:00	2022-12-15 11:42:09
CVE-2008-1150	00:19:aa:f2:a5: 4e	7.1	Resource Management Errors	2008-03-27 17:44:00	2022-12-15 11:42:09
CVE-2007-5551	00:19:aa:f2:a5: 4e	7.1	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-18 20:17:00	2022-12-15 11:42:09
CVE-2007- 5548	00:19:aa:f2:a5: 4e	6.9	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-18 20:17:00	2022-12-15 11:42:09
CVE-2008- 5230	00:19:aa:f2:a5: 4e	6.8	Cryptographic Issues	2008-11-25 23:30:00	2022-12-15 11:42:09



C&I - Unit -4 DCS 2

CVE	LABEL	CVE SCORE	CWE NAME	CVE CREATION TIME	TIME
CVE-2006- 4950	00:1cb1b253: 94	10.0	Improper Input Validation	2006-09-23 10:07:00	2022-12-15 22:34:31
CVE-2006- 4950	00:1cf9:fd:73:0 8	10.0	Improper Input Validation	2006-09-23 10:07:00	2022-12-15 22:50:46
CVE-2017- 12240	00:1cb1b2:53: 94	9.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-09-29 01:34:00	2022-12-15 22:34:31
CVE-2017- 12240	00:1cf9:fd:73:0 8	9.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-09-29 01:34:00	2022-12-15 22:50:46
CVE-2007- 2586	00:1cb1b253: 94	9.3	Incorrect Authorization	2007-05-10 00:19:00	2022-12-15 22:34:31
CVE-2007- 2586	00:1cf9:fd:73:0 8	9.3	Incorrect Authorization	2007-05-10 00:19:00	2022-12-15 22:50:46
CVE-2007- 5552	00:1cb1b253: 94	9.3	Numeric Errors	2007-10-18 20:17:00	2022-12-15 22:34:31
CVE-2007- 5552	00:1cf9:fd:73:0 8	9.3	Numeric Errors	2007-10-18 20:17:00	2022-12-15 22:50:46
CVE-2019- 16009	00:1cb1b253: 94	8.8	Crass-Site Request Forgery (CSRF)	2020-09-23 01:15:00	2022-12-15 22:34:31
CVE-2017- 6743	00:1cf9:fd:73:0 8	8.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-07-17 21:29:00	2022-12-15 22:50:46
CVE-2019- 16009	00:1cf9:fd:73:0 8	8.8	Crass-Site Request Forgery (CSRF)	2020-09-23 01:15:00	2022-12-15 22:50:46
CVE-2017- 6743	00:1cb1b253: 94	8.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-07-17 21:29:00	2022-12-15 22:34:31
CVE-2017- 3864	00:1cb1b253: 94	8.6	Improper Input Validation	2017-03-22 19:59:00	2022-12-15 22:34:31
CVE-2017- 3864	00:1cf9:fd:73:0 8	8.6	Improper Input Validation	2017-03-22 19:59:00	2022-12-15 22:50:46
CVE-2016- 6380	00:1cb1b253: 94	8.1	Improper Input Validation	2016-10-05 20:59:00	2022-12-15 22:34:31
CVE-2016- 6380	00:1cf9:fd:73:0 8	8.1	Improper Input Validation	2016-10-05 20:59:00	2022-12-15 22:50:46
CVE-2009- 2051	00:1cb1b253: 94	7.8	Improper Input Validation	2009-08-27 17:00:00	2022-12-15 22:34:31
CVE-2011-0946	00:1cb1b253: 94	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 22:34:31
CVE-2011-3279	00:1cbtb253: 94	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 22:34:31
CVE-2013-1142	00:1cb1b253: 94	7.8	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2013-03-28 23:55:00	2022-12-15 22:34:31
CVE-2011-0946	00:1cf9:fd:73:0 8	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 22:50:46
CVE-2011-3279	00:1cf9:fd:73:0 8	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-15 22:50:46
CVE-2009- 2051	00:1cf9:fd:73:0 8	7.8	Improper Input Validation	2009-08-27 17:00:00	2022-12-15 22:50:46
CVE-2013-1142	00:1cf9:fd:73:0 8	7.8	Concurrent Execution using Shared Resource with Improper Synchronization (Race Conditions)	2013-03-28 23:55:00	2022-12-15 22:50:46
CVE-2021- 34699	00:1cb1b253: 94	7.7	Interpretation Conflict	2021-09-23 03:15:00	2022-12-15 22:34:31
CVE-2021- 34699	00:1cf9:fd:73:0 8	7.7	Interpretation Conflict	2021-09-23 03:15:00	2022-12-15 22:50:46
CVE-2017-3857	00:1cb1b2:53: 94	7.5	Uncontrolled Resource Consumption	2017-03-22 19:59:00	2022-12-15 22:34:31
CVE-2019- 12655	00:1c:f9:fd:73:0 8	7.5	Buffer Copy without Checking Size of Input ('Classic Buffer Overflow')	2019-09-25 21:15:00	2022-12-15 22:50:46
CVE-2022- 20724	00:1cb1b253: 94	7.5	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2022-04-15 15:15:00	2022-12-15 22:34:31
CVE-1999- 0293	00:1cb1b253: 94	7.5	Improper Input Validation	1998-01-01 05:00:00	2022-12-15 22:34:31



Vulnerability summary

C&I - Unit -4 DCS 1

Malware detected	0
Different Operating Systems	6
Different Types of Technologies	8
Attempted Links to Public Internet	0
Multi-homed Assets	0
Different Firmware Versions	2
Clients Accessing SMB Shares	10
Insecure Protocol Links in the Environment	57

Clients accessing SMB Shares

FROM	то	PROTOCOL	TX PACKETS	TX BYTES
172.16.200.149	172.16.160.80	smb		
172.16.200.149	172.16.160.46	smb		
172.16.200.149	172.16.160.54	smb		
172.16.200.149	172.16.160.78	smb		
172.16.200.149	172.16.160.50	smb		
172.16.200.149	172.16.160.84	smb		
172.16.200.149	172.16.160.56	smb		
172.16.200.149	172.16.160.58	smb		
172.16.200.149	172.16.160.52	smb		
172.16.200.149	172.16.160.48	smb		

C&I - Unit -4 DCS 2

Malware detected	0
Different Operating Systems	6
Different Types of Technologies	5
Attempted Links to Public Internet	0
Multi-homed Assets	82
Different Firmware Versions	2
Clients Accessing SMB Shares	12
Insecure Protocol Links in the Environment	295

Clients accessing SMB Shares

FROM	то	PROTOCOL	TX PACKETS	TX BYTES
192.168.7.149	192.168.6.211	smb		
192.168.7.149	192.168.6.210	smb		
192.168.7.149	192.168.6.201	smb		
192.168.7.149	192.168.6.160	smb		
192.168.7.149	192.168.6.161	smb		
192.168.7.149	192.168.6.200	smb		
192.168.3.149	192.168.2.211	smb		
192.168.3.149	192.168.2.210	smb		
192.168.3.149	192.168.2.160	smb		
192.168.3.149	192.168.2.161	smb		
192.168.3.149	192.168.2.201	smb		
192.168.3.149	192.168.2.200	smb		



Devices Vulnerability Summary

Domain	Critical	High	Medium	Low	Total
Vulnerability Assessment	13	7	19	4	33
Re-validation(closed)	0	0	0	0	0
Re-validation(open)	13	7	19	4	33

Observation Summary

The chart given below represents the vulnerabilities found during network vulnerability testing:

Fig:1




Fig:2




Figure 1: Vulnerability Assessment Test Observations

Illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Figure 2: Vulnerability Assessment Test Observations- Revalidation

Illustrates the closure of Vulnerabilities based on the categorization i.e., Closed, Open.

Note:

Closed: Count considered having vulnerability in all the IP addresses as closed.

Open: Count considered having vulnerability in minimum one IP address as open/unreachable, it may have more different IP addresses which may have the same vulnerability as closed.



Vulnerability Assessment Test Observations

The below table illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Vulnerabilities &	Affected IP	Risk	Observations	Recommendations	Status	Revalidati
Impact						on status
Conficker Worm Detection (uncredentialed check) Impact: This worm has several capabilities which allow an attacker to execute arbitrary code on the remote operating system. The remote host might also be attempting to propagate the worm to third party hosts.	172.16.160.50 172.16.160.54 172.16.160.56 172.16.160.58 172.16.160.78 172.17.160.50 172.17.160.54 172.17.160.56 172.17.160.58	Criti cal	It was observed that the remote host seems to be infected by a variant of the Conficker worm.	It is recommended to update your Antivirus and perform a full scan of the remote operating system.	Open	Open
HP System Management Homepage Multiple Vulnerabilities (HPSBMU03593)	172.16.160.56 172.17.160.56	Criti cal	It is observed that the remote web server is affected by multiple vulnerabilities.	It is recommended to upgrade to HP System Management Homepage version 7.5.5 or later.	Open	Open
Impact: An unauthenticated, remote attacker can exploit this, via a saturation of partial HTTP requests, to cause a daemon outage. (CVE-2007-6750)						
An unauthenticated, remote attacker can exploit this, via a specially crafted tag, to inject arbitrary script code or HTML into the user's browser session. (CVE-2011-4969)						
A remote attacker can exploit this to cause the signature verification routine to crash, resulting in a denial of service condition. (CVE-2015-3194)						

A remote attacker can						
exploit this to cause a						
memory leak by						
triggering a decoding						
failure in a PKCS#7 or						
resulting in a denial of						
service. (CVE-2015-						
3195)						
An unauthenticated,						
remote attacker can						
exploit this, using a						
malicious SMB server						
and crafted length and						
offset values, to						
disclose sensitive						
memory information or						
to cause a denial-of-						
service condition.						
(CVE-2015-3237)						
A remote attacker can						
exploit this to corrupt						
memory, resulting in a						
denial-of-service						
condition or the						
execution of arbitrary						
code. (CVE-2016-						
0705)						
Microsoft IIS 6.0	192.168.6.160	Criti	It was observed	It is recommended to	Onon	Onen
					Open	Open
Unsupported Version	192.168.6.161	cal	that an	upgrade to a version		
Detection			unsupported	of Microsoft IIS that is		
			version of	currently supported.		
Impact:			Microsoft IIS is			
			running on the			
Lack of support implies			remote Windows			
that no new security			host.			
patches for the product						
will be released by the						
vendor. As a result, it is						
likely to contain						
security vulnerabilities.						
Microsoft RDP RCE	192.168.6.160	Criti	It was observed	It is recommended to	Open	Open
(CVE-2019-0708)	192.168.6.161		that the remote		Open	Орен
(BlueKeep)	132.100.0.101	cal	host is affected by	implement patches		
(uncredentialed				for Windows XP,		
`				2003, 2008, 7, and		
check)			execution	2008 r2 released by		
1.			vulnerability.	Microsoft.		
		1	İ	wholosoft.		
Impact:						
An unauthenticated,						
An unauthenticated, remote attacker can						
An unauthenticated, remote attacker can exploit this, via a series						
An unauthenticated, remote attacker can exploit this, via a series of specially crafted						
An unauthenticated, remote attacker can exploit this, via a series						
An unauthenticated, remote attacker can exploit this, via a series of specially crafted						



		1 -			T	T
Microsoft Windows Server 2003 Unsupported Installation Detection. Impact: Lack of support implies that no new security patches for the product will be released by the vendor. As a result, it is likely to contain security vulnerabilities. Furthermore, Microsoft is unlikely to investigate or acknowledge reports of vulnerabilities.	172.16.160.54 172.16.160.56 172.17.160.54 172.17.160.56 192.168.6.160 192.168.6.161 192.168.6.200	Criti	It is observed that the remote operating system is no longer supported.	It is recommended to upgrade to a version of Windows that is currently supported.	Open	Open
Microsoft Windows XP Unsupported Installation Detection. Impact: Lack of support implies that no new security patches for the product will be released by the vendor. As a result, it is likely to contain security vulnerabilities. Furthermore, Microsoft is unlikely to investigate or acknowledge reports of vulnerabilities.	172.16.160.48 172.16.160.50 172.16.160.52 172.16.160.58 172.16.160.78 172.17.160.48 172.17.160.50 172.17.160.52 172.17.160.58 192.168.6.201 192.168.6.210 192.168.6.211	Criti	It is observed that the remote operating system is no longer supported.	It is recommended to upgrade to a version of Windows that is currently supported.	Open	Open
MS05-027: Vulnerability in SMB Could Allow Remote Code Execution (896422) (uncredentialed check) Impact: The remote version of Windows contains a flaw in the Server Message Block (SMB) implementation that may allow an attacker to execute arbitrary code on the remote host. An attacker does not need to be	172.16.160.58 172.17.160.58 192.168.6.201	Criti	It is observed that an arbitrary code can be executed on the remote host due to a flaw in the SMB implementation.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003. Reference: https://learn.microsoft.com/en-us/security-updates/SecurityBulletins/2005/ms05-027	Open	Open



authenticated to exploit this flaw.						
MS06-040: Vulnerability in Server Service Could Allow Remote Code Execution (921883) (uncredentialed check)	172.16.160.54 172.16.160.58 172.17.160.54 172.17.160.58 192.168.6.201	Criti cal	It is observed that an arbitrary code can be executed on the remote host due to a flaw in the 'Server' service.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003.	Open	Open
Impact: The remote host is vulnerable to a buffer overrun in the 'Server' service that may allow an attacker to execute arbitrary code on the remote host with 'SYSTEM' privileges.				References: https://learn.microsof t.com/en-us/security- updates/SecurityBull etins/2006/ms06-040		
MS08-067: Microsoft Windows Server Service Crafted RPC Request Handling Remote Code Execution (958644) (ECLIPSEDWING) (uncredentialed check)	192.168.6.160 192.168.6.161 192.168.6.201 192.168.6.210 192.168.6.211	Criti cal	It is observed that the remote Windows host is affected by a remote code execution vulnerability.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003.	Open	Open
Impact: An unauthenticated, remote attacker can exploit this, via a specially crafted RPC request, to execute arbitrary code with 'System' privileges.						
MS09-001: Microsoft Windows SMB Vulnerabilities Remote Code Execution (958687) (uncredentialed check) Impact: The remote host is affected by a memory	172.16.160.48 172.16.160.50 172.16.160.52 172.16.160.54 172.16.160.56 172.16.160.58 172.16.160.78 172.17.160.48 172.17.160.50 172.17.160.52	Criti cal	It is observed that it is possible to crash the remote host due to a flaw in SMB.	It is recommended to update set of patches for Windows 2000, XP, 2003, Vista and 2008 provided by Microsoft	Open	Open



corruption vulnerability	172.17.160.56					
in SMB that may allow	172.17.160.58					
an attacker to execute	192.168.6.160					
arbitrary code or	192.168.6.161					
perform a denial of	192.168.6.200					
service against the	192.168.6.201					
remote host.	192.168.6.210					
	192.168.6.211					
SSL Version 2 and 3	172.16.160.56	Criti	It is observed that	It is recommended to	Open	Open
Protocol Detection.	172.16.160.80	cal	the remote service	consult the	•	•
	172.16.160.84	Jui	encrypts traffic	application's		
Impact:	172.17.160.56		using a protocol	documentation to		
	192.168.6.160		with known	disable SSL 2.0 and		
The remote service	192.168.6.161		weaknesses.	3.0.		
accepts connections	192.168.6.200		wcakiic33c3.	Use TLS 1.2 (with		
encrypted using SSL	192.100.0.200			· ·		
				approved cipher		
2.0 and/or SSL 3.0.				suites) or higher		
These versions of SSL				instead.		
are affected by several						
cryptographic flaws,						
including:						
- An insecure padding						
scheme with CBC						
ciphers.						
- Insecure session						
renegotiation and						
resumption schemes.						
rocamption conomics.						
An attacker can exploit						
these flaws to conduct						
man-in-the-middle						
attacks or to decrypt						
communications						
between the affected						
service and clients.	400 400 0 400				_	
Unsupported Web	192.168.6.160	Criti	It was observed	It is recommended to	Open	Open
Server Detection	192.168.6.161	cal	that the remote	remove the web		
			web server is	server if it is no longer		
Impact:			obsolete /	needed. Otherwise,		
According to its			unsupported.	upgrade to a		
version, the remote				1 0		
web server is obsolete				supported version if		
and no longer				possible or switch to		
maintained by its				another server.		
vendor or provider.						
Lack of support implies						
that no new security						
patches for the product						
will be released by the						
vendor. As a result, it						
may contain security						
vulnerabilities.						
vuirierabilities.		l			l	



Unsupported Windows OS (remote) Impact: The remote version of Microsoft Windows is either missing a service pack or is no longer supported. As a result, it is likely to contain security vulnerabilities.	172.16.160.48 172.16.160.50 172.16.160.52 172.16.160.54 172.16.160.56 172.16.160.78 172.17.160.48 172.17.160.50 172.17.160.52 172.17.160.54 172.17.160.56 172.17.160.58 192.168.6.160 192.168.6.200 192.168.6.201 192.168.6.210 192.168.6.211	Criti	It was observed that the remote version of Microsoft Windows is either missing a service pack or is no longer supported	It is recommended to upgrade to a supported service pack or operating system	Open	Open
MS06-035: Vulnerability in Server Service Could Allow Remote Code Execution (917159) (uncredentialed check)	172.16.160.54 172.16.160.58 172.17.160.54 172.17.160.58 192.168.6.201	High	It was observed that an arbitrary code can be executed on the remote host due to a flaw in the 'Server' service.	It is recommended to upgrade to the patches provided by Microsoft for Windows 2000, XP, and 2003.	Open	Open
Impact: The remote host is vulnerable to heap overflow in the 'Server' service that may allow an attacker to execute arbitrary code on the remote host with 'SYSTEM' privileges. In addition to this, the remote host is also affected by an information disclosure vulnerability in SMB that may allow an attacker to obtain portions of the memory of the remote host.						
MS12-020: Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check)	192.168.6.160 192.168.6.161	High	It was observed that the remote Windows host could allow arbitrary code execution.	It is recommended to implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by Microsoft.	Open	Open

Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop Protocol (RDP) on the remote Windows host. The vulnerability is due to the way that RDP accesses an object in memory that has been improperly initialized or has been deleted.						
If RDP has been enabled on the affected system, an unauthenticated, remote attacker could leverage this vulnerability to cause the system to execute arbitrary code by sending a sequence of specially crafted RDP packets to it.						
MS17-010: Security Update for Microsoft Windows SMB Server (4013389) (ETERNALBLUE) (ETERNALCHAMPIO N) (ETERNALROMANCE) (ETERNALSYNERGY) (WannaCry) (EternalRocks) (Petya) (uncredentialed check) Impact: An unauthenticated, remote attacker can exploit these vulnerabilities, via a specially crafted packet, to execute arbitrary code. (CVE-2017-0143, CVE-2017-0145, CVE-2017-0146, CVE-2017-0148)	172.16.160.48 172.16.160.50 172.16.160.52 172.16.160.54 172.16.160.58 172.16.160.78 172.17.160.48 172.17.160.50 172.17.160.52 172.17.160.54 172.17.160.56 172.17.160.58 192.168.6.160 192.168.6.200 192.168.6.201 192.168.6.210	High	It has been observed that device is not updated to the MS SMB security patch (MS17-010)	It is recommended to follow the below mentioned. Microsoft has released a set of patches for Windows Vista, 2008, 7, 2008 R2, 2012, 8.1, RT 8.1, 2012 R2, 10, and 2016. Microsoft has also released emergency patches for Windows operating systems that are no longer supported, including Windows XP, 2003, and 8. REFERENCE: https://learn.microsoft.com/en-us/security-updates/securitybulletins/2017/ms17-010	Open	Open

- An information						
disclosure vulnerability						
exists in Microsoft						
Server Message Block						
1.0 (SMBv1) due to						
improper handling of						
certain requests. An						
unauthenticated,						
remote attacker can						
exploit this, via a						
specially crafted						
packet, to disclose						
sensitive information.						
(CVE-2017-0147)						
Network Time	172.16.160.84	High	It was observed	It is recommended to	Open	Open
Protocol Daemon			that the remote	upgrade to NTP	•	•
(ntpd) monlist			network time	version 4.2.7-p26 or		
Command Enabled			server can be			
DoS.			affected by a	later. Alternatively,		
Impact:			denial-of-service	add 'disable monitor'		
The version of ntpd			vulnerability.	to the ntp.conf		
running on the remote			, and the second	configuration file and		
host is vulnerable to a				restart the service.		
DoS attack if the				Otherwise, limit		
'monlist' command is				access to the affected		
enabled. The 'monlist'						
command returns a list				service to trusted		
of recent hosts that				hosts, or contact the		
have connected to the				vendor for a fix.		
service. However, it is						
affected by a denial-of-						
service vulnerability in						
ntp_request.c that						
allows an						
unauthenticated,						
remote attacker to						
saturate network traffic						
to a specific IP address						
by using forged						
REQ_MON_GETLIST						
or						
REQ_MON_GETLIST						
_1 requests.						
Furthermore, an						
attacker can exploit						
this issue to conduct						
reconnaissance or						
distributed denial of						
service (DDoS)						
attacks.						
SMB NULL Session	172.16.160.48	High	It is observed that	It is recommended to	Open	Open
Authentication.	172.16.160.50		it is possible to log	contact the product		
Impact:	172.16.160.52		into the remote	vendor for		
The remote host is	172.16.160.54		host with a NULL	recommended		
running and SMB	172.16.160.56		session.	solutions.		
protocol. It is possible	172.16.160.58			องเนแงกอ.		
to log into the browser	172.16.160.78					



or spoolss pipes using a NULL session (i.e., with no login or password). Depending on the configuration, it may be possible for an unauthenticated, remote attacker to leverage this issue to get information about the remote host.						
SSL Certificate Signed Using Weak Hashing Algorithm Impact: These signature algorithms are known to be vulnerable to collision attacks. An attacker can exploit this to generate another certificate with the same digital signature, allowing an attacker to masquerade as the affected service.	172.16.160.80 172.16.160.84 192.168.6.160 192.168.6.161 192.168.6.200	High	It was observed that the remote service uses an SSL certificate chain that has been signed using a cryptographically weak hashing algorithm (e.g. MD2, MD4, MD5, or SHA1).	It is recommended to have the SSL certificate reissued.	Open	Open
SSL Medium Strength Cipher Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength encryption if the attacker is on the same physical network.	172.16.160.56 172.16.160.80 172.16.160.84 172.17.160.56 192.168.6.160 192.168.6.200	High	It has been observed that SSL is using medium strength encryption which can be easily compromised if the attacker is on the same physical network.	It is recommended to reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: [SOLVED] how to disable ssl medium strength cipher suites supported (sweet32) in GPO - Microsoft Remote Desktop Services (spiceworks.com)	Open	Open
IP Forwarding Enabled. Impact: The remote host has IP forwarding enabled. An attacker can exploit this to route packets	192.168.7.5 192.168.7.6	Medi um	It has been observed that IP forwarding is enabled on remote hosts	It is recommended to follow the given steps below: On Linux, you can disable IP forwarding by doing:	Open	Open



through the host and potentially bypass some firewalls / routers / NAC filtering.				echo 0 > /proc/sys/net/ipv4/ip_ forward On Windows, set the key 'IPEnableRouter' to 0 under HKEY_LOCAL_MAC HINE\System\Curren tControlSet\Services\ Tcpip\Parameters On Mac OS X, you can disable IP forwarding by executing the command: sysctl -w net.inet.ip.forwarding =0 References: https://linuxconfig.org/how-to-turn-on-off-ip-forwarding-in-linux https://docs.oracle.com/cd/E19957-01/805-2901-12/6j2p9gi08/index.html		
Microsoft Windows EFSRPC NTLM Reflection Elevation of Privilege (PetitPotam) (Remote). Impact: An unauthenticated, remote attacker can exploit this, by sending a specially crafted EFSRPC request, to cause the affected host to connect to a malicious server. An attacker can then	172.16.160.54 172.16.160.56 172.17.160.54 172.17.160.56 192.168.6.160 192.168.6.161 192.168.6.200	Medi um	It is observed that the remote host is affected by an NTLM reflection elevation of privilege vulnerability.	It is recommended to apply the updates supplied by the vendor. Optionally, refer to Microsoft's KB5005413 for mitigation guidance. RPC filters may also be implemented to block remote access to the interface UUIDs necessary for this exploit.	Open	Open



utilize an NTLM relay to impersonate the target host and authenticate against remote services.						
Microsoft Windows SMB LsaQueryInformation Policy Function SID Enumeration Without Credentials Impact:	192.168.6.200	Medi um	It is observed that it is possible to obtain the host SID for the remote host, without credentials.	It is recommended to prevent anonymous lookups of the host SID by setting the 'RestrictAnonymous' registry setting to an appropriate value.	Open	Open
By emulating the call to LsaQueryInformationP olicy(), it was possible to obtain the host SID (Security Identifier), without credentials.				References: https://learn.microsof t.com/en- us/previous- versions/tn-		
The host SID can then be used to get the list of local users.				archive/bb418944(v= technet.10)?redirecte dfrom=MSDN		
MS16-047: Security Update for SAM and LSAD Remote Protocols (3148527) (Badlock) (uncredentialed check) Impact:	172.16.160.56	Medi um	It has been observed that the remote Windows host is affected by an elevation of privilege vulnerability.	It is recommended to implement the Microsoft released set of patches for Windows Vista, 2008, 7, 2008 R2, 2012, 8.1, PT 2.4, 2010 R2, and	Open	Open
Ciphers that support encryption before MAC computation, and authenticated encryption modes such as GCM cannot be used with TLS 1.0. Hence an attacker can perform man-in-the-middle attack against the remote host.				RT 8.1, 2012 R2, and 10. References: http://badlock.org/		
Network Time Protocol (NTP) Mode 6 Scanner Impact: An unauthenticated, remote attacker could potentially exploit this, via a specially crafted mode 6 query, to cause	172.16.160.84 192.168.7.1 192.168.7.17 192.168.7.18 192.168.7.19 192.168.7.2 192.168.7.20 192.168.7.5 192.168.7.6	Medi um	It has been observed that a remote NTP server responds to mode 6 queries.	It is recommended to restrict NTP mode 6 queries. References: https://www.ibm.com/support/pages/ibm-aix-disable-ntp-	Open	Open



An instinct for growth[™]

a reflected denial of service condition.				mode-6-and-7-		
Service Condition.				<u>queries</u>		
				https://community.cis		
				co.com/t5/other-data-		
				center-subjects/how-		
				to-restrict-ntp-mode-		
				6-queries/td-		
				p/3335720		
NTP ntpd Mode 7	172.16.160.84	Medi	It is observed that		Open	Open
Error Response Packet Loop Remote		um	the remote network time	upgrade to NTP		
DoS			service has a	4.2.4p8 / 4.2.6 or		
			denial-of-service	later.		
Impact:			vulnerability.			
The version of ntpd						
running on the remote						
host has a denial-of- service vulnerability. It						
responds to mode 7						
error packets with its						
own mode 7 error						
packets. A remote attacker could exploit						
this by sending a mode						
7 error response with a						
spoofed IP header,						
setting the source and destination IP						
addresses to the IP						
address of the target.						
This would cause ntpd						
to respond to itself						
endlessly, consuming excessive amounts of						
CPU, resulting in a						
denial of service.	1=2 12 122 =2					
OpenSSL	172.16.160.56 172.17.160.56	Medi	It is observed that	It is recommended to	Open	Open
SSL_OP_NETSCAP E_REUSE_CIPHER	772.17.100.00	um	the remote host allows resuming	upgrade to OpenSSL 0.9.8q / 1.0.0.c or		
_CHANGE_BUG			SSL sessions with	later, or contact your		
Session Resume			a weaker cipher	vendor for a patch.		
Ciphersuite			than the one			
Downgrade Issue			originally			
Impact:			negotiated.			
an attacker that sees						
(i.e., by sniffing) the						
start of an SSL						
connection can						



manipulate the						
OpenSSL session						
cache to cause						
subsequent						
resumptions of that						
session to use a						
weaker cipher chosen						
by the attacker.						
Microsoft Windows	192.168.6.160	Medi	It is observed the	It is recommended to	Open	Open
Remote Desktop	192.168.6.161	um	remote version of	force the use of SSL	•	
Protocol Server Man-			the Remote	as a transport layer		
in-the-Middle			Desktop Protocol	for this service if		
Weakness			Server (Terminal	supported, or/and.		
Weakiless			Service) is	Select the 'Allow		
Impact			vulnerable to a	connections only		
Impact:				_		
The MiTM attack of this			man-in-the-middle	from computers		
nature would allow the			(MiTM) attack.	running Remote		
attacker to obtain any			The RDP client	Desktop with Network		
sensitive information			makes no effort to	Level Authentication'		
transmitted, including			validate the	setting if it is		
authentication			identity of the	available.		
credentials.			server when			
			setting up	References:		
			encryption.	http://technet.micros		
				oft.com/en-		
				us/library/cc782610.a		
				spx		
						
				https://www.tenable.c		
				om/plugins/nessus/1		
				8405		
				0403		
SMB Signing not	172.16.160.48	Medi	It has been	It is recommended to	Open	Open
required.	172.16.160.48		observed that	enable signing is on	Open	Obell
- cquireu.	172.16.160.50	um	remote host does	the remote SMB		
Impact:	172.16.160.52		not require SMB	server.		
Signing is not required	172.16.160.56		Signing.	References:		
on the remote SMB	172.16.160.58			How to resolve SMB		
server. An	172.16.160.78			Signing not required		
unauthenticated,	172.17.160.48			Vulnerability - GISPP		
remote attacker can	172.17.160.50			Variorability Offi		
exploit this to conduct	172.17.160.52					
man-in-the-middle	172.17.160.54					
attacks against the	172.17.160.56					
SMB server.	172.17.160.58 192.168.6.160					
	192.168.6.161					
	192.168.6.201					
	192.168.6.210					
	192.168.6.211					
<u> </u>		1	<u>i</u>	i	·	1



SSL / TLS Renegotiation Handshakes MiTM Plaintext Data Injection Impact: An unauthenticated, remote attacker may be able to leverage this	172.16.160.56 172.16.160.80 172.16.160.84 172.17.160.56 192.168.6.160 192.168.6.161 192.168.6.200	Medi um	It is observed that the remote service allows insecure renegotiation of TLS / SSL connections.	It is recommended to contact the vendor for specific patch information	Open	Open
issue to inject an arbitrary amount of plaintext into the beginning of the application protocol stream, which could facilitate man-in-the-middle attacks if the service assumes that the sessions before and after renegotiation are from the same 'client' and merges them at the application layer.						
SSL Certificate with Wrong Hostname Impact: The 'commonName' (CN) attribute of the SSL certificate presented for this service is for a different machine.	172.16.160.80 172.16.160.84	Medi um	It has been observed that the SSL certificate for this service is for a different host.	Purchase or generate a proper SSL certificate for this service.	Open	Open
SSL DROWN Attack Vulnerability (Decrypting RSA with Obsolete and Weakened eNcryption) Impact: This vulnerability exists due to a flaw in the Secure Sockets Layer Version 2 (SSLv2) implementation, and it allows captured TLS traffic to be decrypted. A man-in-the-middle attacker can exploit this to decrypt the TLS connection by utilizing previously	172.16.160.56 172.17.160.56	Medi um	It has been observed that the remote host may be affected by a vulnerability that allows a remote attacker to potentially decrypt captured TLS traffic.	Disable SSLv2 and export grade cryptography cipher suites. Ensure that private keys are not	Open	Open



172.16.160.56	Medi	It has been	It is recommended to	Open	Open
172.16.160.84 172.17.160.56 192.168.6.160 192.168.6.161	um	remote host is using weak cipher suite such as MD5	affected application, if possible, to avoid use of RC4 ciphers.		
192.168.6.200		and OnA-1.	1.2 with AES-GCM suites subject to browser and web server support.		
			References: https://www.rc4nomore.com/		
			http://cr.yp.to/talks/20 13.03.12/slides.pdf http://www.isg.rhul.ac .uk/tls/		
			https://www.imperva. com/docs/HII_Attacki ng_SSL_when_using _RC4.pdf		
172.16.160.80 172.16.160.84 192.168.6.160	Medi um	It was observed that the remote host supports the	It is recommended to reconfigure the affected application, if	Open	Open
192.168.6.161 192.168.6.200		use of SSL ciphers that offer weak encryption.	possible, to avoid the use of weak ciphers.		
172.16.160.80 172.16.160.84 192.168.6.160 192.168.6.161 192.168.6.200	Medi um	It is observed that the remote host supports a set of weak ciphers.	reconfigure the service to remove support for	Open	Open
			cipher suites.		
	172.16.160.80 172.16.160.84 172.17.160.56 192.168.6.160 192.168.6.200 172.16.160.80 172.16.160.84 192.168.6.200 172.16.160.84 192.168.6.161 192.168.6.160 192.168.6.160	172.16.160.80 172.16.160.84 172.17.160.56 192.168.6.161 192.168.6.200 172.16.160.80 172.16.160.84 192.168.6.161 192.168.6.161 192.168.6.161 192.168.6.160 192.168.6.160 192.168.6.161	172.16.160.80 172.16.160.84 172.17.160.56 192.168.6.161 192.168.6.200 Medi 172.16.160.84 192.168.6.160 192.168.6.161 192.168.6.160 192.168.6.160 192.168.6.160 192.168.6.160 192.168.6.161 192.168.6.200 Medi 172.16.160.84 192.168.6.200 Medi 172.16.160.84 192.168.6.160 192.168.6.160 192.168.6.160 192.168.6.160 192.168.6.160 192.168.6.160 192.168.6.160 192.168.6.160 192.168.6.161	172.16.160.80 172.16.160.84 172.17.160.56 192.168.6.160 192.168.6.200 172.16.86.6.200 172.16.160.84 172.17.160.56 192.168.6.161 192.168.6.200 172.16.160.80 172.16.160.	172.16.160.80 172.16.160.84 172.17.160.56 192.168.6.160 192.168.6.160 192.168.6.160 192.168.6.200 172.16.160.84 192.168.6.200 172.16.160.80



	1		r		I	
A man-in-the middle attacker may be able to downgrade the session to use EXPORT_RSA cipher suites (e.g., CVE-2015-0204). Thus, it is recommended to remove support for weak cipher suites.						
SSLv3 Padding Oracle on Downgraded Legacy Encryption Vulnerability (POODLE) Impact: MitM attackers can decrypt a selected byte of a cipher text in as few as 256 tries if they are able to force a victim application to repeatedly send the same data over newly created SSL 3.0 connections.	172.16.160.56 172.16.160.80 172.16.160.84 172.17.160.56 192.168.6.160 192.168.6.161 192.168.6.200	Medi um	It was observed that the remote host is affected by a man-in-the-middle (MitM) information disclosure vulnerability known as POODLE.	It is recommended to disable SSLv3. Services that must support SSLv3 should enable the TLS Fallback SCSV mechanism until SSLv3 can be disabled.	Open	Open
Terminal Services Encryption Level is Medium or Low Impact: An attacker can eavesdrop on the communications more easily and obtain screenshots and/or keystrokes.	192.168.6.160 192.168.6.161	Medi um	It has been observed that the remote Terminal Services is t configured to use Medium cryptography.	It is recommended to Change RDP encryption level to High & FIPS Compliant References: https://techgenix.com/Windows_Terminal_Services/#:~:text=Medium%3A%20encrypts%20both%20the%20data%20sent%20from%20client,40%20bit%20key%2C%20depending%20on%20the%20client%20version.	Open	Open
TLS Version 1.0 Protocol Detection Impact: An attacker can cause connection failures and	172.16.160.56 172.16.160.80 172.16.160.84 172.17.160.56 192.168.6.160 192.168.6.161 192.168.6.200	Medi um	It is observed to TLS 1.2 is more secure, an attacker can cause connection failures and they	It is recommended to Enable support for TLS 1.2 and 1.3, and disable support for TLS 1.0.	Open	Open



they can trigger the use			can trigger the use	References:		
of TLS 1.0 to exploit			of TLS 1.0 to	https://www.invicti.co		
vulnerabilities like			exploit	m/web-vulnerability-		
BEAST (Browser			vulnerabilities.	scanner/vulnerabilitie		
Exploit Against			vaniciabilities.	s/insecure-		
,						
SSL/TLS). Websites				transportation-		
using TLS 1.0 will be				security-protocol-		
considered non-				supported-tls-10/		
compliant by PCI after						
30 June 2018.						
Unencrypted Telnet	172.16.200.22	Medi	It is observed that	It is recommended to	Open	Open
Server	5	um	the remote Telnet		•	•
	172.17.200.22		server transmits	service and use SSH		
Impact:	5		traffic in cleartext.	instead.		
	192.168.7.1		tramo in ordanoxi.	motodd:		
Using Telnet over an	192.168.7.10					
unencrypted channel is	192.168.7.17 192.168.7.18					
not recommended as						
logins, passwords, and commands are	192.168.7.19 192.168.7.2					
transferred in cleartext.	192.168.7.20					
This allows a remote,	192.168.7.5					
man-in-the-middle	192.168.7.9					
attacker to eavesdrop	10211001110					
on a Telnet session to						
obtain credentials or						
other sensitive						
information and to						
modify traffic						
exchanged between a						
client and server.						
SSH is preferred over						
Telnet since it protects						
credentials from						
eavesdropping and						
can tunnel additional						
data streams such as						
an X11 session. SSL Certificate Chain	192.168.6.160	Low	It was shoomed	It is recommended to	Onon	Onon
Contains RSA Keys	192.168.6.161	Low	It was observed that at least one of		Open	Open
Less Than 2048 bits.	192.168.6.200		the X.509	in the chain with the		
			certificates sent	,		
Impact:			by the remote host			
According to industry			has a key that is	with a longer key, and		
standards set by the			shorter than 2048 bits	reissue any		
Certification Authority/Browser			פווט	certificates signed by the old certificate.		
(CA/B) Forum,				uno ola certificate.		
certificates issued after						
January 1, 2014 must						
be at least 2048 bits.						
Some browser SSL						
implementations may						
reject keys less than						

2048 bits after January						
1, 2014. Additionally, some SSL certificate vendors may revoke certificates less than						
2048 bits before January 1, 2014.						
SSL/TLS Diffie-Hellman Modulus <= 1024 Bits (Logjam) Impact: Through cryptanalysis, a third party may be able to find the shared secret in a short amount of time (depending on modulus size and attacker resources). This may allow an attacker to recover the plaintext or potentially violate the integrity of connections.	172.16.160.80 172.16.160.84 192.168.6.160 192.168.6.161 192.168.6.200	Low	It was observed that the remote host allows SSL/TLS connections with one or more Diffie-Hellman moduli less than or equal to 1024 bits.	It is recommended to reconfigure the service to use a unique Diffie-Hellman moduli of 2048 bits or greater.	Open	Open
SSL/TLS EXPORT_DHE <= 512-bit Export Cipher Suites Supported (Logjam)	172.16.160.80 172.16.160.84 192.168.6.160 192.168.6.161 192.168.6.200	Low	It is observed that the remote host supports a set of weak ciphers.	reconfigure the	Open	Open
Impact:				cipher suites.		
The remote host supports EXPORT_DHE cipher suites with keys less than or equal to 512 bits. Through cryptanalysis, a third party can find the shared secret in a short amount of time.						
1		•	ì	i e	1	1



Terminal Services	192.168.6.160	Low	It is observed the	It is recommended to	Open	Open
Encryption Level is	192.168.6.161		Client Compatible	change RDP		
not FIPS-140			setting encrypts	encryption level to:		
Compliant			data sent between	4. FIPS Compliant		
			the client and the			
Impact:			server at the	References:		
The attacker observed			maximum key	https://www.tenable.c		
the encryption setting			strength	om/plugins/nessus/3		
used by the remote			supported by the	<u>0218</u>		
Terminal Services after			client.			
the attacker easy to						
expose the all sensitive						
data						

Asset Inventory

Inventory Overview

This section focuses on asset tracking, asset discovery and asset classification. These are the first steps for ensuring operational continuity, reliability and safety. They provide the user with a full context for security events and support routine procedures aimed at improving overall cyber hygiene. Creating an inventory of devices in the network, as well as understanding the relationships and connections between them, is a crucial component in network security.

Asset List DCS-1



Asset List DCS-2



Mapping of Vulnerabilities with Assets (DCS1)

Final Mapping of C&I Unit-4 Dept Assets:

Refer the below excel file contains mapping of vulnerabilities & open ports with the assets, it provides the details of vulnerabilities observed in each asset.





Mapping of Vulnerabilities with Assets (DCS2)

Final Mapping of C&I Unit-4 Dept Assets:

Refer the below excel file contains mapping of vulnerabilities & open ports with the assets, it provides the details of vulnerabilities observed in each asset.




Unit -6

Asset classification

DCS 1 (BHEL Make)

The assessment was able to identify 143 all devices and discovered 86 vulnerabilities.


Based on the assessment, risk mitigation and remediation are needed to reduce the risk of nation-level threat vector and improve the cyber posture.



DCS 2 (Emerson Make)

The assessment was able to identify 111 all devices and discovered 38 vulnerabilities.

Based on the assessment, risk mitigation and remediation are needed to reduce the risk of nation-level threat vector and improve the cyber posture.





Vendors

DCS₁

undefined	Broadcom	Cisco	Hirschmann
101	6	3	3
Intel Corporate	LCFC(HeFei) Electr	TRANSMITTON LTD.	VMware, Inc.
26	2	1	1

DCS 2



Asset Types

DCS₁




DCS 2




Operating systems

DCS₁





DCS₂




Risk

Vulnerability Score

DCS₁

GT Risk Assessment Report provides a comprehensive risk analysis related to network behaviour and assets. Based on overall assessment for **NTPC TANDA**, all network risk score is 6.9 (Medium risk)






DCS₂

GT Risk Assessment Report provides a comprehensive risk analysis related to network behaviour and assets. Based on overall assessment for **NTPC TANDA**, all network risk score is 0.


NAME	TYPE	OS/FIRMWARE	COUNT	SCORE DISTRIBUTION	SCOR	E GROUPS (Lo	ow, Medium, High))
nessus	computer	Windows XP SP2	1065	والمتعدد	27	528	510	
DROP210	computer	Windows 7 SP1	2226		40	1 741	445	
DROP214	computer	Windows 7 SP1	2226		40	1 741	445	
DROP215	computer	Windows 7 SP1	2226		40	1 741	445	
DROP216	computer	Windows 7 SP1	2226	and the second	40	1 741	445	
DROP217	computer	Windows 7 SP1	2226		40	1 741	445	
DROP218	computer	Windows 7 SP1	2226		40	1 741	445	
DROP219	computer	Windows 7 SP1	2226		40	1 741	445	
DROP200	computer	Windows Server 2012 R2 Update 1	2151		46	1 696	409	
Assets \	with conf	firmed CPEs						
Assets ۱	with Firm	nware Discovered						13
Numbe	r of Host	s with Vulnerabilitie	s					
Numbe	r of Vuln	erabilities						3
/ulnera	bility Av	erage Score						

Vulnerabilities per type

DCS₁



DCS₂





Top 30 Vulnerabilities on Network Devices

DCS₁

CVE	LABEL	CVE SCORE	CWE NAME	CVE CREATION TIME	TIME
CVE-2017- 12240	2HMI- UPLINKA	9.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-09-29 01:34:00	2022-12-16 12:05:42
CVE-2007- 5552	2HMI- UPLINKA	9.3	Numeric Errors	2007-10-18 20:17:00	2022-12-16 12:05:42
CVE-2017-6743	2HMI- UPLINKA	8.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-07-17 21:29:00	2022-12-16 12:05:42
CVE-2019- 16009	2HMI- UPLINKA	8.8	Cross-Site Request Forgery (CSRF)	2020-09-23 01:15:00	2022-12-16 12:05:42
CVE-2020- 3225	2HMI- UPLINKA	8.6	Improper Input Validation	2020-06-03 18:15:00	2022-12-16 12:05:42
CVE-2017- 3864	2HMI- UPLINKA	8.6	Improper Input Validation	2017-03-22 19:59:00	2022-12-16 12:05:42
CVE-2019-1737	2HMI- UPLINKA	8.6	Allocation of Resources Without Limits or Throttling	2019-03-27 23:29:00	2022-12-16 12:05:42
CVE-2011-3279	2HMI- UPLINKA	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-16 12:05:42
CVE-2011-0946	2HMI- UPLINKA	7.8	Improper Input Validation	2011-10-03 23:55:00	2022-12-16 12:05:42
CVE-2013-1142	2HMI- UPLINKA	7.8	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2013-03-28 23:55:00	2022-12-16 12:05:42
CVE-2015-6278	2HMI- UPLINKA	7.8	Improper Input Validation	2015-09-28 02:59:00	2022-12-16 12:05:42
CVE-2009- 2051	2HMI- UPLINKA	7.8	Improper Input Validation	2009-08-27 17:00:00	2022-12-16 12:05:42
CVE-2020- 3200	2HMI- UPLINKA	7.7	Interpretation Conflict	2020-06-03 18:15:00	2022-12-16 12:05:42
CVE-2021- 34699	2HMI- UPLINKA	7.7	Interpretation Conflict	2021-09-23 03:15:00	2022-12-16 12:05:42
CVE-1999-0293	2HMI- UPLINKA	75	Improper Input Validation	1998-01-01 05:00:00	2022-12-16 12:05:42
CVE-2022- 20726	2HMI- UPLINKA	75	Improper Neutralization of Input During Web Page Generation ('Cross-site Scripting')	2022-04-15 15:15:00	2022-12-16 12:05:42
CVE-2022- 20724	2HMI- UPLINKA	75	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2022-04-15 15:15:00	2022-12-16 12:05:42
CVE-2020- 3230	2HMI- UPLINKA	75	Improper Input Validation	2020-06-03 18:15:00	2022-12-16 12:05:42
CVE-2019- 12655	2HMI- UPLINKA	75	Buffer Copy without Checking Size of Input ('Classic Buffer Overflow')	2019-09-25 21:15:00	2022-12-16 12:05:42
CVE-2017-3857	2HMI- UPLINKA	75	Uncontrolled Resource Consumption	2017-03-22 19:59:00	2022-12-16 12:05:42
CVE-2017- 12237	2HMI- UPLINKA	75	Uncontrolled Resource Consumption	2017-09-29 01:34:00	2022-12-16 12:05:42
CVE-2017- 12235	2HMI- UPLINKA	75	Improper Input Validation	2017-09-29 01:34:00	2022-12-16 12:05:42
CVE-2016-6415	2HMI- UPLINKA	75	Exposure of Sensitive Information to an Unauthorized Actor	2016-09-19 01:59:00	2022-12-16 12:05:42
CVE-2016-6393	2HMI- UPLINKA	75	Resource Management Errors	2016-10-05 20:59:00	2022-12-16 12:05:42
CVE-2016- 6384	2HMI- UPLINKA	75	Improper Input Validation	2016-10-05 17:59:00	2022-12-16 12:05:42
CVE-2016-1409	2HMI- UPLINKA	75	Improper Input Validation	2016-05-29 22:59:00	2022-12-16 12:05:42
CVE-2007-5551	2HMI- UPLINKA	7.1	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-18 20:17:00	2022-12-16 12:05:42
CVE-2008- 4609	2HMI- UPLINKA	7.1	Configuration	2008-10-20 17:59:00	2022-12-16 12:05:42
CVE-2008- 4963	2HMI- UPLINKA	7.1	Improper Input Validation	2008-11-0615:55:00	2022-12-16 12:05:42
CVE-2007- 5548	2HMI- UPLINKA	6.9	Improper Restriction of Operations within the Bounds of a Memory Buffer	2007-10-18 20:17:00	2022-12-16 12:05:42

DCS₂

<NONE>

Top 30 Vulnerabilities on Non-Switches DCS 2



CVE	LABEL	CVE SCORE	CWE NAME	CVE CREATION TIME	TIME
CVE-2016-1908	nessu s	9.8	Improper Authentication	2017-04-11 18:59:00	2022-12-16 13:01:39
CVE-2015-5600	nessu s	8.5	Permissions, Privileges, and Access Controls	2015-08-03 01:59:00	2022-12-16 13:01:39
CVE	LABEL	CVE SCORE	CWE NAME	CVE CREATION TIME	TIME
CVE-2019- 16905	nessu s	7.8	Integer Overflow or Wraparound	2019-10-09 20:15:00	2022-12-16 13:01:39
CVE-2020- 15778	nessu s	7.8	Improper Neutralization of Special Elements used in an OS Command (OS Command Injection)	2020-07-2414:15:00	2022-12-16 13:01:39
CVE-2015-8325	nessu s	7.8	Permissions, Privileges, and Access Controls	2016-05-01 01:59:00	2022-12-16 13:01:39
CVE-2016-10012	nessu s	7.8	Improper Restriction of Operations within the Bounds of a Memory Buffer	2017-01-05 02:59:00	2022-12-16 13:01:39
CVE-2016- 10708	nessu s	7.5	NULL Pointer Dereference	2018-01-21 22:29:00	2022-12-16 13:01:39
CVE-2014-1692	nessu s	7.5	Improper Restriction of Operations within the Bounds of a Memory Buffer	2014-01-29 16:02:05	2022-12-16 13:01:39
CVE-2016-6515	nessu s	7.5	Improper Input Validation	2016-08-07 21:59:00	2022-12-16 13:01:39
CVE-2010-4478	nessu s	7.5	Improper Authentication	2010-12-06 22:30:00	2022-12-16 13:01:39
CVE-2016- 10009	nessu s	7.3	Untrusted Search Path	2017-01-05 02:59:00	2022-12-16 13:01:39
CVE-2021- 28041	nessu s	7.1	Double Free	2021-03-05 21:15:00	2022-12-16 13:01:39
CVE-2016- 10010	nessu s	7.0	Permissions, Privileges, and Access Controls	2017-01-05 02:59:00	2022-12-16 13:01:39
CVE-2021-41617	nessu s	7.0	Permissions, Privileges, and Access Controls	2021-09-26 19:15:00	2022-12-16 13:01:39
CVE-2015-6564	nessu s	6.9	Permissions, Privileges, and Access Controls	2015-08-24 0159:00	2022-12-16 13:01:39
CVE-2019-6109	nessu s	6.8	Improper Encoding or Escaping of Output	2019-01-31 18:29:00	2022-12-16 13:01:39
CVE-2019-6110	nessu s	6.8	Inappropriate Encoding for Output Context	2019-01-31 18:29:00	2022-12-16 13:01:39
CVE-2016-0777	nessu s	6.5	Exposure of Sensitive Information to an Unauthorized Actor	2016-01-14 22:59:00	2022-12-16 13:01:39
CVE-2016-3115	nessu s	6.4	Permissions, Privileges, and Access Controls	2016-03-22 10:59:00	2022-12-16 13:01:39
CVE-2019-6111	nessu s	5.9	Improper Limitation of a Pathname to a Restricted Directory ('Path Traversal')	2019-01-31 18:29:00	2022-12-16 13:01:39
CVE-2016-6210	nessu s	5.9	Exposure of Sensitive Information to an Unauthorized Actor	2017-02-13 1759:00	2022-12-16 13:01:39
CVE-2020- 14145	nessu s	5.9	Observable Discrepancy	2020-06-29 18:15:00	2022-12-16 13:01:39
CVE-2014-2653	nessu s	5.8	Improper Input Validation	2014-03-27 10:55:00	2022-12-16 13:01:39
CVE-2016-10011	nessu s	5.5	Key Management Errors	2017-01-05 02:59:00	2022-12-16 13:01:39
CVE-2017- 15906	nessu s	5.3	Incorrect Permission Assignment for Critical Resource	2017-10-26 03:29:00	2022-12-16 13:01:39
CVE-2016- 20012	nessu s	5.3	Improper Input Validation	2021-09-15 20:15:00	2022-12-16 13:01:39
CVE-2018- 15473	nessu s	5.3	Concurrent Execution using Shared Resource with Improper Synchronization ('Race Condition')	2018-08-17 19:29:00	2022-12-16 13:01:39
CVE-2018-15919	nessu s	5.3	Exposure of Sensitive Information to an Unauthorized Actor	2018-08-28 08:29:00	2022-12-16 13:01:39
CVE-2018- 20685	nessu s	5.3	Incorrect Authorization	2019-01-10 21:29:00	2022-12-16 13:01:39
CVE-2010-5107	nessu s	5.0	Improper Input Validation	2013-03-07 2055:00	2022-12-16 13:01:39



Vulnerability summary

DCS₁

Malware detected	0
Different Operating Systems	6
Different Types of Technologies	7
Attempted Links to Public Internet	0
Multi-homed Assets	16
Different Firmware Versions	2
Clients Accessing SMB Shares	13
Insecure Protocol Links in the Environment	80

Clients accessing SMB Shares TX PACKETS TX BYTES 172.16.202.99 172.16.160.42 172.16.202.99 172.16.160.38 smb 172.16.202.99 172.16.160.37 smb 172.16.202.99 172.16.160.36 172.16.202.99 172.16.160.32 172.16.202.99 172.16.160.33 smb 172.16.202.99 172.16.160.41 172.16.202.99 172.16.160.40 172.16.160.39 172.16.202.99 smb 172.16.202.99 172.16.160.35 smb 172.16.202.99 172.16.160.34 smb 172.16.202.99 172.16.160.30 smb

DCS₂

Malware detected	0
Different Operating Systems	6
Different Types of Technologies	7
Attempted Links to Public Internet	0
Multi-homed Assets	0
Different Firmware Versions	1
Clients Accessing SMB Shares	11
Insecure Protocol Links in the Environment	193



Clients accessing SMB Shares							
FROM	то	PROTOCOL	TX PACKETS	TX BYTES			
192.168.4.200	192.168.5.149	smb					
192.168.5.149	192.168.4.218	smb					
192.168.5.149	192.168.4.200	smb					
192.168.5.149	192.168.4.215	smb					
192.168.5.149	192.168.4.214	smb					
192.168.5.149	192.168.4.216	smb					
192.168.5.149	192.168.4.210	smb					
192.168.5.149	192.168.4.160	smb					
192.168.5.149	192.168.4.219	smb					
192.168.5.149	192.168.4.217	smb					
192.168.5.149	192.168.4.161	smb					

Devices Vulnerability Summary

Domain	Critical	High	Medium	Low	Total
Vulnerability Assessment	4	8	18	7	37
Re-validation(closed)	0	0	0	0	0
Re-validation(open)	4	8	18	7	37

Observation Summary

The chart given below represents the vulnerabilities found during network vulnerability testing:

Fig:1




Fig:2



Figure 1: Vulnerability Assessment Test Observations

Illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.



Figure 2: Vulnerability Assessment Test Observations- Revalidation

Illustrates the closure of Vulnerabilities based on the categorization i.e., Closed, Open.

Note:

Closed: Count considered having vulnerability in all the IP addresses as closed.

Open: Count considered having vulnerability in minimum one IP address as open/unreachable, it may have more different IP addresses which may have the same vulnerability as closed.

Vulnerability Assessment Test Observations

The below table illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Vulnerabilities & /	Affected IP	Risk	Observations	Recommendations	Sta	Revalidati
Impact					tus	on status
Cisco IOS Cluster 17 Management 17 Protocol Telnet 17 Option Handling RCE 17 (cisco-sa-20170317- 17	72.16.202.50 72.16.202.51 72.16.202.55 72.17.202.50 72.17.202.51 72.17.202.55	Criti	It is observed that the remote device is missing a vendor-supplied security patch.	It is recommended to upgrade to the relevant fixed version referenced in Cisco bug ID CSCvd48893. Alternatively, as a workaround, disable the Telnet protocol for incoming connections.	Op en	Open



Microsoft RDP RCE (CVE-2019-0708) (BlueKeep) (uncredentialed check) Impact: An unauthenticated, remote attacker can exploit this, via a series of specially crafted requests, to execute arbitrary code.	172.16.160.30 172.16.160.33 172.16.160.34 172.16.160.35 172.17.160.30 172.17.160.33 172.17.160.34 172.17.160.35 192.168.4.214 192.168.4.218	Criti cal	It was observed that the remote host is affected by a remote code execution vulnerability.	It is recommended to implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by Microsoft.	Op en	Open
SSL Version 2 and 3 Protocol Detection Impact: An attacker can conduct man-in-the-middle attacks or to decrypt communications between the affected service and clients.	172.16.160.30 172.17.160.30	Criti	It has been observed that arbitrary commands can be run on this port.		Op en	Open
Unsupported Windows OS (remote) Impact: A system is unsupported when the developer is no longer issuing any software patches or security updates. From that point on, the operating system is stagnant.	172.16.160.30 172.16.160.31 172.16.160.32 172.16.160.33 172.16.160.34 172.16.160.35 172.16.160.36 172.16.160.37 172.16.160.38 172.16.160.40 172.16.160.41 172.16.160.42 172.17.160.30 172.17.160.31 172.17.160.32	Criti cal	It is observed the remote OS or service pack is no longer supported.	It is recommended to upgrade to a supported service pack or operating system. References: https://cve.mitre.org/cgi-bin/cvekey.cgi?keyword=windows	Op en	Open



	172.17.160.33					
	172.17.160.34					
	172.17.160.35					
	172.17.160.36					
	172.17.160.37					
	172.17.160.38					
	172.17.160.39					
	172.17.160.40					
	172.17.160.42					
	192.168.4.210					
	192.168.4.214					
	192.168.4.215					
	192.168.4.216					
	192.168.4.217					
	192.168.4.218					
	192.168.4.219					
Microsoft Windows	172.16.160.33	High	It was observed	"It is recommended to	Op	Open
SMBv1 Multiple	172.16.160.34	_	that the remote	apply the applicable	en	-
Vulnerabilities	172.16.160.35		Windows host has	security update for		
	172.16.160.37		Microsoft Server	your Windows		
Impact:	172.16.160.38		Message Block	*		
"The remote Windows	172.16.160.39		1.0 (SMBv1)	version:		
host has Microsoft	172.16.160.41		enabled.			
Server Message Block	172.17.160.33			- Windows Server		
1.0 (SMBv1) enabled.	172.17.160.34			2008 : KB4018466		
It is, therefore, affected	172.17.160.35			- Windows 7 :		
by multiple	172.17.160.37			KB4019264		
vulnerabilities:	172.17.160.38			- Windows Server		
- Multiple information	172.17.160.39			2008 R2 :		
disclosure						
vulnerabilities exist in				KB4019264		
Microsoft Server				- Windows Server		
Message Block 1.0				2012 : KB4019216		
(SMBv1) due to				- Windows 8.1 / RT		
improper handling of				8.1. : KB4019215		
SMBv1 packets. An				- Windows Server		
unauthenticated,				2012 R2 :		
remote attacker can				KB4019215		
exploit these vulnerabilities, via a				- Windows 10		
specially crafted						
SMBv1 packet, to				: KB4019474		
disclose sensitive				- Windows 10		
information. (CVE-				Version 1511 :		
2017-0267, CVE-2017-				KB4019473		
0268, CVE-2017-0270,				- Windows 10		
CVE-2017-0271, CVE-				Version 1607 :		
2017-0274, CVE-2017-				KB4019472		
0275, CVE-2017-0276)				- Windows 10		
- Multiple denial of						
service vulnerabilities				Version 1703 :		
exist in Microsoft				KB4016871		
Server Message Block				- Windows Server		
1.0 (SMBv1) due to				2016 : KB4019472"		
improper handling of						
requests. An						
unauthenticated,						

remote attacker can						
exploit these						
vulnerabilities, via a						
specially crafted SMB						
request, to cause the						
system to stop						
responding. (CVE-2017-0269, CVE-2017-						
0273, CVE-2017-0280)						
- Multiple remote						
code execution						
vulnerabilities exist in						
Microsoft Server						
Message Block 1.0						
(SMBv1) due to						
improper handling of						
SMBv1 packets. An unauthenticated,						
remote attacker can						
exploit these						
vulnerabilities, via a						
specially crafted						
SMBv1 packet, to						
execute arbitrary code.						
(CVE-2017-0272,						
CVE-2017-0277, CVE- 2017-0278, CVE-2017-						
0279)"						
MS12-020:	172.16.160.30	High	It was observed	It is recommended to	Op	Open
	1 172.10.100.30	HIGH	ili was observed	I IL IS IECUITITIETIAEA IO		Open
Vulnerabilities in	172.16.160.30	nigii	that the remote			Open
Vulnerabilities in Remote Desktop		nigii		implement patches	en	Орен
Vulnerabilities in Remote Desktop Could Allow Remote	172.17.160.30	nigii	that the remote Windows host could allow	implement patches for Windows XP,		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387)	172.17.160.30	riigii	that the remote Windows host could allow	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387)	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop Protocol (RDP) on the	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop Protocol (RDP) on the remote Windows host. The vulnerability is due to the way that RDP	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop Protocol (RDP) on the remote Windows host. The vulnerability is due to the way that RDP accesses an object in	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop Protocol (RDP) on the remote Windows host. The vulnerability is due to the way that RDP accesses an object in memory that has been	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop Protocol (RDP) on the remote Windows host. The vulnerability is due to the way that RDP accesses an object in memory that has been improperly initialized or	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop Protocol (RDP) on the remote Windows host. The vulnerability is due to the way that RDP accesses an object in memory that has been	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop Protocol (RDP) on the remote Windows host. The vulnerability is due to the way that RDP accesses an object in memory that has been improperly initialized or has been deleted.	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Open
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop Protocol (RDP) on the remote Windows host. The vulnerability is due to the way that RDP accesses an object in memory that has been improperly initialized or	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop Protocol (RDP) on the remote Windows host. The vulnerability is due to the way that RDP accesses an object in memory that has been improperly initialized or has been deleted. If RDP has been enabled on the affected system, an	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен
Vulnerabilities in Remote Desktop Could Allow Remote Code Execution (2671387) (uncredentialed check) Impact: An arbitrary remote code vulnerability exists in the implementation of the Remote Desktop Protocol (RDP) on the remote Windows host. The vulnerability is due to the way that RDP accesses an object in memory that has been improperly initialized or has been deleted. If RDP has been enabled on the	172.17.160.30	riigii	that the remote Windows host could allow arbitrary code	implement patches for Windows XP, 2003, 2008, 7, and 2008 r2 released by		Орен



leverage this vulnerability to cause the system to execute arbitrary code by sending a sequence of specially crafted RDP packets to it.						
MS17-010: Security Update for Microsoft Windows SMB Server (4013389) (ETERNALBLUE) (ETERNALCHAMPIO N) (ETERNALSYNERGY) (WannaCry) (EternalRocks) (Petya) (uncredentialed check) Impact: An unauthenticated, remote attacker can exploit these vulnerabilities, via a specially crafted packet, to execute arbitrary code. (CVE-2017-0143, CVE-2017-0144, CVE-2017-0145, CVE-2017-0148) - An information disclosure vulnerability exists in Microsoft Server Message Block 1.0 (SMBv1) due to improper handling of certain requests. An unauthenticated, remote attacker can exploit this, via a specially crafted packet, to disclose sensitive information. (CVE-2017-0147)	172.16.160.32 172.16.160.33 172.16.160.34 172.16.160.35 172.16.160.37 172.16.160.38 172.16.160.39 172.16.160.41 172.17.160.30 172.17.160.31 172.17.160.33 172.17.160.33 172.17.160.35 172.17.160.35 172.17.160.37 172.17.160.38	High	It has been observed that device is not updated to the MS SMB security patch (MS17-010)	It is recommended to follow the below mentioned. Microsoft has released a set of patches for Windows Vista, 2008, 7, 2008 R2, 2012, 8.1, RT 8.1, 2012 R2, 10, and 2016. Microsoft has also released emergency patches for Windows operating systems that are no longer supported, including Windows XP, 2003, and 8. REFERENCE: https://learn.microsoft.com/en-us/security-updates/securitybulletins/2017/ms17-010	Op en	Open
SNMP Agent Default Community Name (public) Impact: It is possible to obtain the default community	172.16.202.50 172.16.202.51 172.16.202.55 172.17.202.50 172.17.202.51 172.17.202.55	High	It was observed that the community's name of the remote SNMP	It is recommended to disable the SNMP service on the remote host if you do not use it.	Op en	Open



name of the remote SNMP server. An attacker may use this information to gain more knowledge about the remote host, or to change the configuration of the remote system (if the default community allows such modifications).			server can be guessed	Either filter incoming UDP packets going to this port, or change the default community string.		
SSH Protocol Version 1 Session Key Retrieval Impact: These protocols are not completely cryptographically safe so they should not be used.	172.16.202.50 172.16.202.51 172.16.202.55 172.17.202.50 172.17.202.51 172.17.202.55	High	It has been observed that the remote service offers an insecure cryptographic protocol.	It is recommended to disable compatibility with version 1 of the SSH protocol. References: https://community.cisco.com/t5/security-knowledge-base/guide-to-betterssh-security/ta-p/3133344 https://www.sonicwall.com/support/knowledge-base/how-to-fix-the-error-ssh-protocol-version-1-session-key-retrieval/1705054773 14897/	Op en	Open
SSL Certificate Signed Using Weak Hashing Algorithm Impact: An attacker can exploit this to generate another certificate with the same digital signature, allowing an attacker to masquerade as the affected service	172.16.160.30 172.16.160.33 172.16.160.34 172.16.160.35 172.17.160.30 172.17.160.33 172.17.160.35 192.168.4.210 192.168.4.214 192.168.4.215 192.168.4.216 192.168.4.217 192.168.4.218 192.168.4.218 192.168.4.219	High	It has been observed that SSL certificate is signed using SHA-1 With RSA Encryption.	It is recommended to sign SSL certificate using strong encryption algorithm such as SHA-512. References: https://tools.ietf.org/html/rfc3279	Op en	Open



SSL Medium Strength Cipher Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength encryption if the attacker is on the same physical network.	172.16.160.30 172.16.160.33 172.16.160.34 172.16.160.35 172.16.202.50 172.16.202.51 172.16.202.55 172.17.160.30 172.17.160.33 172.17.160.35 172.17.202.50 172.17.202.51 172.17.202.55 192.168.4.160 192.168.4.210 192.168.4.210 192.168.4.215 192.168.4.216 192.168.4.217 192.168.4.218 192.168.4.219	High	It has been observed that SSL is using medium strength encryption such as DES-CBC3-SHA which can be easily compromised if the attacker is on the same physical network.	It is recommended to reconfigure the affected application, if possible, to avoid use of medium strength ciphers. References: https://www.openssl.org/blog/blog/2016/08/24/sweet32/	Op en	Open
VNC Server	172.16.160.36	High	It is observed that	It is recommended to	Op	Open
Unauthenticated	172.16.160.38		the remote VNC	disable the No	en	
Access	172.16.160.39		server does not	Authentication		
Impact:	172.17.160.36 172.17.160.38 172.17.160.39		require authentication.	security type.		
The VNC server installed on the remote host allows an attacker to connect to the remote host as no authentication is required to access this service. The VNC server sometimes sends the connected user to the XDM login screen. Unfortunately, Nessus cannot identify this situation. in such a case, it is not possible to go further without valid credentials and this alert may be ignored.						
HTTP TRACE / TRACK Methods Allowed.	172.16.160.30 172.17.160.30	Medi um	It is observed that debugging functions are enabled on the remote web server.	It is recommended to disable these HTTP methods.	Op en	Open
The remote web server supports the TRACE			301701.			



					1	T
and/or TRACK methods. TRACE and TRACK are HTTP methods that are used to debug web server connections.						
Microsoft Windows EFSRPC NTLM Reflection Elevation of Privilege (PetitPotam) (Remote). Impact: An unauthenticated, remote attacker can exploit this, by sending a specially crafted EFSRPC request, to cause the affected host to connect to a malicious server. An attacker can then utilize an NTLM relay to impersonate the target host and authenticate against remote services.	192.168.4.200	Medi um	It is observed that the remote host is affected by an NTLM reflection elevation of privilege vulnerability.	It is recommended to apply the updates supplied by the vendor. Optionally, refer to Microsoft's KB5005413 for mitigation guidance. RPC filters may also be implemented to block remote access to the interface UUIDs necessary for this exploit.	Op en	Open
MS16-047: Security Update for SAM and LSAD Remote Protocols (3148527) (Badlock) (uncredentialed check) Impact: Ciphers that support encryption before MAC computation, and authenticated encryption modes such as GCM cannot be used with TLS 1.0. Hence an attacker can perform man-in-the- middle attack against the remote host.	172.16.160.30 172.16.160.31 172.16.160.32 172.17.160.30 172.17.160.31 172.17.160.32 192.168.4.218 192.168.4.219	Medi um	It has been observed that the remote Windows host is affected by an elevation of privilege vulnerability.	It is recommended to implement the Microsoft released set of patches for Windows Vista, 2008, 7, 2008 R2, 2012, 8.1, RT 8.1, 2012 R2, and 10. References: http://badlock.org/	Op en	Open
Network Time Protocol (NTP) Mode 6 Scanner Impact: An unauthenticated, remote attacker could potentially exploit this, via a specially crafted	172.16.202.50 172.16.202.51 172.16.202.55 172.17.202.50 172.17.202.51 172.17.202.55	Medi um	It has been observed that a remote NTP server responds to mode 6 queries.	It is recommended to restrict NTP mode 6 queries. References: https://www.ibm.com/support/pages/ibm-aix-disable-ntp-	Op en	Open



mode 6 query, to cause a reflected denial of service condition.				mode-6-and-7- queries https://community.cis co.com/t5/other-data- center-subjects/how- to-restrict-ntp-mode- 6-queries/td- p/3335720		
Microsoft Windows Remote Desktop Protocol Server Manin-the-Middle Weakness Impact: The MiTM attack of this nature would allow the attacker to obtain any sensitive information transmitted, including authentication credentials.	172.16.160.30 172.16.160.33 172.16.160.34 172.16.160.35 172.17.160.30 172.17.160.34 172.17.160.35 192.168.4.200 192.168.4.214 192.168.4.218	Medium	It is observed the remote version of the Remote Desktop Protocol Server (Terminal Service) is vulnerable to a man-in-the-middle (MiTM) attack. The RDP client makes no effort to validate the identity of the server when setting up encryption.	It is recommended to force the use of SSL as a transport layer for this service if supported, or/and. Select the 'Allow connections only from computers running Remote Desktop with Network Level Authentication' setting if it is available. References: http://technet.microsoft.com/enus/library/cc782610.aspx https://www.tenable.com/plugins/nessus/18405	Op en	Open
SMB Signing not required. Impact: Signing is not required on the remote SMB server. An unauthenticated, remote attacker can exploit this to conduct man-in-the-middle attacks against the SMB server.	172.16.160.30 172.16.160.31 172.16.160.32 172.16.160.33 172.16.160.34 172.16.160.35 172.16.160.36 172.16.160.37 172.16.160.38 172.16.160.39 172.16.160.40 172.16.160.41 172.16.160.42 172.17.160.30 172.17.160.31 172.17.160.32 172.17.160.33	Medi um	It has been observed that remote host does not require SMB Signing.	It is recommended to enable signing is on the remote SMB server. References: How to resolve SMB Signing not required Vulnerability - GISPP	Op en	Open



	172.17.160.34 172.17.160.35 172.17.160.36 172.17.160.37 172.17.160.39 172.17.160.40 172.17.160.42 192.168.4.160 192.168.4.210 192.168.4.214 192.168.4.215 192.168.4.215 192.168.4.216 192.168.4.217 192.168.4.217 192.168.4.218 192.168.4.219					
SNMP 'GETBULK' Reflection DDoS Impact: A remote attacker can use this SNMP server to conduct a reflected distributed denial of service attack on an arbitrary remote host.	172.16.202.50 172.16.202.51 172.17.202.50 172.17.202.51 172.17.202.55	Medi um	It was observed that the remote SNMP daemon is affected by a vulnerability that allows a reflected distributed denial of service attack.	It is recommended to disable the SNMP service on the remote host if you do not use it. Otherwise, restrict and monitor access to this service, and consider changing the default 'public' community string.	Op en	Open
SSL Certificate Chain Contains Weak RSA Keys. Impact: At least one of the X.509 certificates sent by the remote host has a key that is shorter than 1024 bits. Such keys are considered weak due to advances in available computing power decreasing the time required to factor cryptographic keys. Some SSL implementations, notably Microsoft's, may consider this SSL chain to be invalid due to the length of one or more of the RSA keys it contains.	172.16.202.50 172.16.202.51 172.16.202.55 172.17.202.50 172.17.202.51 172.17.202.55	Medi	It is observed that the X.509 certificate chain used by this service contains certificates with RSA keys shorter than 1024 bits.	It is recommended to replace the certificate in the chain with the weak RSA key with a stronger key, and reissue any certificates it signed	Op en	Open



SSL Certificate with Wrong Hostname. Impact: The 'commonName' (CN) attribute of the SSL certificate presented for this service is for a different machine.	192.168.4.160 192.168.4.161 192.168.4.200 192.168.4.210 192.168.4.214 192.168.4.215 192.168.4.216 192.168.4.217 192.168.4.218 192.168.4.218	Medi um	The SSL certificate for this service is for a different host.	Purchase or generate a proper SSL certificate for this service.	Op en	Open
SSL DROWN Attack Vulnerability (Decrypting RSA with Obsolete and Weakened eNcryption) Impact: This vulnerability exists due to a flaw in the Secure Sockets Layer Version 2 (SSLv2) implementation, and it allows captured TLS traffic to be decrypted. A man-in-the-middle attacker can exploit this to decrypt the TLS connection by utilizing previously captured traffic and weak cryptography along with a series of specially crafted connections to an SSLv2 server that uses the same private key.	172.16.160.30 172.17.160.30	Medi um	It has been observed that the remote host may be affected by a vulnerability that allows a remote attacker to potentially decrypt captured TLS traffic.	It is recommended to Disable SSLv2 and export grade cryptography cipher suites. Ensure that private keys are not used anywhere with server software that supports SSLv2 connections. References: https://drownattack.com/drown-attack-paper.pdf	Op en	Open
SSL RC4 Cipher Suites Supported (Bar Mitzvah) Impact: If plaintext is repeatedly encrypted (e.g., HTTP cookies), and an attacker is able to obtain many (i.e., tens of millions) ciphertexts, the attacker may be able to derive the plaintext.	172.16.160.30 172.16.160.33 172.16.160.34 172.16.160.35 172.16.202.50 172.16.202.51 172.16.202.55 172.17.160.30 172.17.160.33 172.17.160.35 172.17.202.50 172.17.202.51 172.17.202.55 192.168.4.160 192.168.4.210 192.168.4.214	Medi um	It has been observed that remote host is using weak cipher suite such as MD5 and SHA-1.	It is recommended to reconfigure the affected application, if possible, to avoid use of RC4 ciphers. Consider using TLS 1.2 with AES-GCM suites subject to browser and web server support. References: http://cr.yp.to/talks/20 13.03.12/slides.pdf http://www.isg.rhul.ac .uk/tls/	Op en	Open



	192.168.4.215					
	192.168.4.216			https://www.imperva.		
	192.168.4.217			com/docs/HII Attacki		
	192.168.4.218			ng_SSL_when_using		
	192.168.4.219			_RC4.pdf		
SSL Weak Cipher	172.16.160.30	Medi	It was observed	It is recommended to	Op	Open
Suites Supported.	172.16.202.50	um	that the remote	reconfigure the	en	
• •	172.16.202.51		host supports the	affected application, if		
Impact:	172.16.202.55		use of SSL	possible, to avoid the		
This is considerably	172.17.160.30		ciphers that offer	use of weak ciphers.		
easier to exploit if the	172.17.202.50		weak encryption.	use of weak cipilers.		
attacker is on the same	172.17.202.51					
physical network.	172.17.202.55				_	
SSL/TLS	172.16.160.30	Medi	It is observed that	It is recommended to	Op	Open
EXPORT_RSA <=	172.17.160.30	um	the remote host	reconfigure the	en	
512-bit Cipher Suites			supports a set of	service to remove		
Supported (FREAK)			weak ciphers.	support for		
Impact:				EXPORT_RSA		
The remote host				cipher suites.		
supports						
EXPORT_RSA cipher						
suites with keys less						
than or equal to 512						
bits. An attacker can						
factor a 512-bit RSA						
modulus in a short						
amount of time.						
A man-in-the middle						
attacker may be able to						
downgrade the session						
to use EXPORT_RSA						
cipher suites (e.g.						
CVE-2015-0204).						
Thus, it is						
recommended to						
remove support for						
weak cipher suites.	1=0 (5 : 5 : 5 : 5			1.1		
SSLv3 Padding	172.16.160.30	Medi	It was observed	It is recommended to	Op	Open
Oracle on	172.17.160.30	um	that the remote	disable SSLv3.	en	
Downgraded Legacy Encryption			host is affected by a man-in-the-	Services that must		
Vulnerability			middle (MitM)	support SSLv3		
(POODLE)			information	should enable the		
()			disclosure	TLS Fallback SCSV		
Impact:			vulnerability	mechanism until		
MitM attackers can			known as	SSLv3 can be		
decrypt a selected byte			POODLE.	disabled.		
of a cipher text in as						
few as 256 tries if they						
are able to force a						
victim application to						
repeatedly send the						
same data over newly						



created SSL 3.0 connections.						
Terminal Services Doesn't Use Network Level Authentication (NLA) Only Impact: An attacker can cause connection failures and they can trigger the use of TLS 1.0 to exploit vulnerabilities like BEAST (Browser Exploit Against SSL/TLS). Websites using TLS 1.0 will be considered non- compliant by PCI after 30 June 2018.	172.16.160.30 172.16.160.33 172.16.160.34 172.16.160.35 172.17.160.30 172.17.160.33 172.17.160.35 192.168.4.200 192.168.4.214 192.168.4.218	Medium	It is observed in addition to improving authentication, NLA also helps protect the remote computer from malicious users and software by completing user authentication before a full RDP connection is established.	It is recommended to enable Network Level Authentication (NLA) on the remote RDP server. This is generally done on the 'Remote' tab of the 'System' settings on Windows. References: https://appuals.com/fix-the-remote-computer-requires-network-level-authentication/	Op en	Open
Terminal Services Encryption Level is Medium or Low Impact: An attacker can eavesdrop on the communications more easily and obtain screenshots and/or keystrokes.	172.16.160.30 172.16.160.33 172.16.160.34 172.16.160.35 172.17.160.30 172.17.160.33 172.17.160.35 192.168.4.200 192.168.4.214 192.168.4.218	Medi um	It has been observed that the remote Terminal Services is t configured to use Medium cryptography.	It is recommended to Change RDP encryption level to High & FIPS Compliant References: https://techgenix.com/Windows Terminal/Services/#:~:text=Medium%3A%20encrypts%20both%20the%20data%20sent%20from%20client,40%20bit%20key%2C%20depending%20on%20the%20client%20version.	Op en	Open
TLS Version 1.1 Protocol Deprecated Impact: Ciphers that support encryption before MAC computation, and authenticated	192.168.4.160 192.168.4.161 192.168.4.200 192.168.4.210 192.168.4.214 192.168.4.215 192.168.4.216 192.168.4.217	Medi um	It has been observed that remote host supports version 1.1.	It is recommended to enable support for	Op en	Open



				.		
encryption modes such				TLS Version 1.0		
as GCM cannot be				<u>Protocol</u> <u>Detection</u>		
used with TLS 1.1.				(tableau.com)		
Hence an attacker can						
perform man-in-the-						
middle attack against						
the remote host.						
Unencrypted Telnet	172.16.202.50	Medi	It is observed that	It is recommended to	Op	Open
Server	172.16.202.51	um	the remote Telnet	isable the Telnet	en	•
	172.16.202.55		server transmits	service and use SSH		
Impact:	172.17.202.50		traffic in cleartext.	instead.		
	172.17.202.51		tramo in olcarioxi.	motodd.		
Using Telnet over an	172.17.202.55					
unencrypted channel is						
not recommended as						
logins, passwords, and						
commands are						
transferred in cleartext. This allows a remote,						
man-in-the-middle						
attacker to eavesdrop						
on a Telnet session to						
obtain credentials or						
other sensitive						
information and to						
modify traffic						
exchanged between a						
client and server.						
SSH is preferred over						
Telnet since it protects						
credentials from						
eavesdropping and						
can tunnel additional						
data streams such as						
an X11 session.						
SSH Server CBC	172.16.202.50	Low	It has been	It is recommended to	Op	Open
Mode Ciphers	172.16.202.51		observed that	disable CBC mode	en	O P O
Enabled	172.16.202.55		remote host is	cipher encryption,	0	
	172.17.202.50		using CBC Mode	and enable CTR or		
Impact:	172.17.202.51		Cipher. The			
•	172.17.202.55		following Cipher	GCM cipher mode		
The SSH server is			Block Chaining	encryption.		
configured to support			(CBC) algorithms			
Cipher Block Chaining			are supported:			
(CBC) encryption. This			0.1	References:		
may allow an attacker			3des-cbc	openssl - How to		
to recover the plaintext			aes128-cbc	disable CBC-mode		
message from the			aes256-cbc	ciphers - Information		
ciphertext.				Security Stack		
				Exchange		
				<u></u>		



SSH Weak Key Exchange Algorithms Enabled Impact: An attacker can easily exploit the remote SSH server that is configured to allow weak key exchange algorithms.	172.16.202.50 172.16.202.51 172.16.202.55 172.17.202.50 172.17.202.51 172.17.202.55	Low	It has been observed that remote host allow weak key exchange algorithms. The following are weak key exchange algorithms that are enabled: diffie-hellmangroup-exchangesha1 diffie-hellmangroup1-sha1	It is recommended to disable the weak key exchange algorithms. References: SSH Weak Key Exchange Algorithms Enabled - Virtue Security	Op en	Open
SSH Weak MAC Algorithms Enabled Impact: An attacker may try to exploit the host as the remote SSH server is configured to allow key exchange algorithms which are considered weak.	172.16.202.50 172.16.202.51 172.16.202.55 172.17.202.50 172.17.202.51 172.17.202.55	Low	It has been observed that the remote SSH server is configured to allow key exchange algorithms which are considered weak.	It is recommended to contact the vendor or consult product documentation to disable the weak algorithms. References: Disable SSH Weak MAC Algorithms in Linux - DbAppWeb.com	Op en	Open
SSL Certificate Chain Contains RSA Keys Less Than 2048 bits Impact: An attacker can easily perform brute force in order to decrypt the encryption with key size shorter than 2048 bits.	172.16.160.30 172.17.160.30	Low	It has been observed that 2048-bit RSA key provides 112-bit of security.	It is recommended to replace the certificate in the chain with the RSA key less than 2048 bits in length with a longer key, and reissue any certificates signed by the old certificate. References: https://community.hpe.com/t5/Integrity-Servers/SSL-Certificate-Chain-Contains-RSA-Keys-Less-Than-2048-bits-for/td-p/6440854#.Yuj7nHZBw2w	Op en	Open



SSL/TLS Diffie-Hellman Modulus <= 1024 Bits (Logjam) Impact: Through cryptanalysis, a third party may be able to find the shared secret in a short amount of time (depending on modulus size and attacker resources). This may allow an attacker to recover the plaintext or potentially violate the integrity of connections.	172.16.160.30 172.16.160.33 172.16.160.34 172.16.160.35 172.16.202.50 172.16.202.51 172.16.202.55 172.17.160.30 172.17.160.33 172.17.160.35 172.17.202.50 172.17.202.51	Low	It has been observed that the remote host allows SSL/TLS connections with one or more Diffie-Hellman moduli less than or equal to 1024 bits.	It is recommended to reconfigure the service to use a unique Diffie-Hellman moduli of 2048 bits or greater. References: https://www.ibm.com/mysupport/s/question/0D50z00005q4LjCCAU/ssltls-diffiehellman-modulus-1024-bits-logjam?language=enUS	Op en	Open
SSL/TLS EXPORT_DHE <= 512-bit Export Cipher Suites Supported (Logjam) Impact: The remote host supports EXPORT_DHE cipher suites with keys less than or equal to 512 bits. Through cryptanalysis, a third party can find the shared secret in a short amount of time. A man-in-the middle attacker may be able to downgrade the session	172.16.160.30 172.17.160.30	Low	It is observed that the remote host supports a set of weak ciphers.	It is recommended to reconfigure the service to remove support for EXPORT_DHE cipher suites.	Op en	Open
to use EXPORT_DHE cipher suites. Thus, it is recommended to remove support for weak cipher suites. Terminal Services Encryption Level is not FIPS-140 Compliant Impact: The attacker observed the encryption setting	172.16.160.30 172.16.160.33 172.16.160.34 172.16.160.35 172.17.160.30 172.17.160.33 172.17.160.34 172.17.160.35 192.168.4.200	Low	It is observed the Client Compatible setting encrypts data sent between the client and the server at the maximum key	It is recommended to change RDP encryption level to: 4. FIPS Compliant References: Federal Information Processing Standard	Op en	Open



An instinct for growth


used by the remote	192.168.4.214	strength	(FIPS) 140 Validation	
Terminal Services after	192.168.4.218	supported by the	- Windows security	
the attacker easy to		client.	Microsoft Learn	
expose the all sensitive				
data.				

Asset Inventory

Inventory Overview

This section focuses on asset tracking, asset discovery and asset classification. These are the first steps for ensuring operational continuity, reliability and safety. They provide the user with a full context for security events and support routine procedures aimed at improving overall cyber hygiene. Creating an inventory of devices in the network, as well as understanding the relationships and connections between them, is a crucial component in network security.

Asset List DCS-1



Asset List DCS-2



Mapping of Vulnerabilities with Assets (DCS1)

Final Mapping of C&I Unit-6 Dept Assets:

Refer below excel file contains mapping of vulnerabilities & open ports with the assets, it provides the details of vulnerabilities observed in each asset.





Mapping of Vulnerabilities with Assets (DCS2)

Final Mapping of C&I Unit-6 Dept Assets:

Refer **below** excel file contains mapping of vulnerabilities & open ports with the assets, it provides the details of vulnerabilities observed in each asset.



Recommendations:

- 14. It is recommended to update the firewall to the latest firmware version.
- 15. Disable ping (ICMP) response on WAN port.
- 16. Disable UPnP (Universal plug-and-play).
- 17. Disable IDENT (i.e., port 113).
- 18. Disable remote management of the firewall.
- 19. The setting for a firewall policy should be as specific as possible. Do not use 0.0.0.0 as an address.
- 20. Regularly check for incoming/outgoing traffic security policy.
- 21. Allow only HTTPS access to the GUI and SSH access to the CLI.
- 22. Set up two-factor authentication for administrator.
- 23. Modify administrator account lockout duration and threshold values.
- 24. It is recommended that all management access from the internet is turned off.
- 25. Ensure that your SNMP setting are using SNMPv3 with encryption.
- 26. All firewall policies should be reviewed every 3 months.



Station LAN Vulnerability Summary

Domain	Critical	High	Medium	Low	Total
Vulnerability Assessment	3	1	3	1	8
Re-validation(closed)	0	0	0	0	0
Re-validation(open)	3	1	3	1	8

Observation Summary

The chart given below represents the vulnerabilities found during network vulnerability testing:

Fig:1




Fig:2




Figure 1: Vulnerability Assessment Test Observations

Illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Figure 2: Vulnerability Assessment Test Observations- Revalidation

Illustrates the closure of Vulnerabilities based on the categorization i.e., Closed, Open.

Note:

Closed: Count considered having vulnerability in all the IP addresses as closed.

Open: Count considered having vulnerability in minimum one IP address as open/unreachable, it may have more different IP addresses which may have the same vulnerability as closed.

Vulnerability Assessment Test Observations



The below table illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Vulnerabilities &	Affected	Risk	Observations	Recommendations	Sta	Revalidat
Impact	Devices				tus	ion
						Status
SSL Version 2 and 3	172.17.160.152	Critical	It was observed	It is recommended to	Op	Open
Protocol Detection			that the remote	consult the	en	
Impost			service accepts	application's		
Impact:			connections encrypted using	documentation to		
The flaws are as			SSL 2.0 and/or	disable SSL 2.0 and		
follows:			SSL 3.0. These	3.0. Use TLS 1.2		
- An insecure padding			versions of SSL	(with approved cipher		
scheme with CBC			are affected by	suites) or higher		
ciphers Insecure session			several	instead.		
renegotiation and			cryptographic flaws			
resumption schemes.				Reference:		
An attacker can exploit				Luce II		
these flaws to conduct				https://www.imperialv		
man-in-the-middle attacks or to decrypt				iolet.org/2014/10/14/ poodle.html		
communications				poodie.num		
between the affected				https://www.openssl.		
service and clients.				org/~bodo/ssl-		
				poodle.pdf		
Unsupported	172.17.160.152	Critical	It is observed	It is recommended to	Op	Open
Windows OS (remote)			the remote OS or	upgrade to a	en	
, ,			service pack is no	supported service		
Impact:			longer supported.	pack or operating		
A system is				system.		
unsupported when the				References:		
developer is no longer				https://www.tenable.c		
issuing any software				om/plugins/nessus/1		
patches or security				08797		
updates. From that						
point on, the operating				https://cve.mitre.org/		
system is stagnant.				<u>cgi-</u>		
				bin/cvekey.cgi?keyw		
				<u>ord=windows</u>		
Unsupported Web	172.17.160.152	Critical	It is observed the	It is recommended to	Op	Open
Server Detection	172.17.100.102	Critical	remote web	remove the web	en	Open
OGIVEI DELECTION			server is obsolete	server if it is no longer	CII	
Impact:			and no longer	needed. Otherwise,		
Web Server is put			maintained by its	upgrade to a		
longer the attacker			vendor or	supported version if		
easy to attack the web			provider.	possible or switch to		
1				another server.		
server and expose the						



				Hansana anta al MAZI		
				Unsupported Web		
				Server Detection		
				<u>Tenable®</u>		
001 Ma l'ann 04 ann 11	470 47 400 450	T.P. a.L.	11	14.1	0	0
SSL Medium Strength Cipher Suites	172.17.160.152 172.17.160.153	High	It was observed	It is recommended to	Op	Open
Cipher Suites Supported	172.17.160.153		that the remote service supports	reconfigure the	en	
(SWEET32)	172.17.100.154		the use of medium	affected application		
(01122102)	1121101100100		strength SSL	to use strong cipher		
Impact:			ciphers.	suited and to avoid		
The remote host				use of		
supports the use of				medium strength		
SSL ciphers that offer				ciphers.		
medium strength						
encryption.				References:		
				https://www.openssl.		
				org/blog/blog/2016/0		
				<u>8/24/sweet32/</u>		
				https://sweet32.info		
SMB Signing not	172.17.160.152	Medium	It was observed	It is recommended to	Op	Open
required.	172.17.160.153		that signing is not	enforce message	en	
I	172.17.160.154		required on the	signing in the host's		
Impact: An unauthenticated,	172.18.160.50		remote SMB server.	configuration. On		
remote attacker can			Server.	Windows, this is		
exploit this to conduct				found in the policy		
man-in-the-middle				setting 'Microsoft		
attacks against the				network server:		
SMB server.				Digitally sign		
				communications		
				(always)'. On Samba,		
				the setting is called		
				'server signing'.		
				References:		
				http://technet.micros		
				oft.com/en-		
				us/library/cc731957.a		
				spx		
TLS Version 1.1	172.17.160.154	Medium	It was observed	It is recommended	Op	Open
Protocol Deprecated	172.18.160.50		that the emote	enable support for	en	
			service accepts	TLS 1.2 and/or 1.3,		
Impact:			connections	and disable support		
TLS 1.1 lacks support for current and			encrypted using TLS 1.1	for TLS 1.1.		
recommended cipher			113 1.1			
suites. Ciphers that				References:		
support encryption						
before MAC						



		I	I			<u> </u>
authenticated encryption modes such as GCM cannot be used with TLS 1.1				https://datatracker.iet f.org/doc/html/rfc899 6		
Terminal Services Doesn't Use Network Level Authentication (NLA) Only Impact: An attacker can cause connection failures and they can trigger the use of TLS 1.0 to exploit vulnerabilities like BEAST (Browser Exploit Against SSL/TLS).	172.17.160.152 172.17.160.153 172.17.160.154 172.18.160.50	Medium	It was observed in addition to improving authentication, NLA also helps protect the remote computer from malicious users and software by completing user authentication before a full RDP connection is established.	It is recommended to enable Network Level Authentication (NLA) on the remote RDP server. This is generally done on the 'Remote' tab of the 'System' settings on Windows. References: https://docs.microsoft.com/en-us/previous-versions/windows/it-pro/windows-server-2008-R2-and-2008/cc732713(v=ws.11)	Op en	Open
SSL Certificate Chain Contains RSA Keys Less Than 2048 bits. Impact: At least one of the X.509 certificates sent by the remote host has a key that is shorter than 2048 bits. According to industry standards set by the Certification Authority/Browser (CA/B) Forum, certificates issued after January 1, 2014, must be at least 2048 bits.	172.17.160.152	Low	It is observed a 2048-bit RSA key provides 112-bit of security. Given that TLS certificates are valid for two years maximum (soon to be decreased to one), 2048-bit RSA key length fulfills the NIST recommendation until late in this decade.	It is recommended to replace the certificate in the chain with the RSA key less than 2048 bits in length with a longer key, and reissue any certificates signed by the old certificate. References: https://community.hp e.com/t5/Integrity- Servers/SSL- Certificate-Chain- Contains-RSA-Keys- Less-Than-2048-bits- for/td- p/6440854#.Yuj7nHZ Bw2w	Op en	Open




Electrical Department

SAS Network

Asset classification

The assessment was able to identify 101 all devices and discovered 0 vulnerabilities.

Based on the assessment, risk mitigation and remediation are needed to reduce the risk of nation-level threat vector and improve the cyber posture.




Vendors

undefined	LCFC(HeFei) Electr	NR ELECTRIC CO.,	PEGATRON
76	2	2	9
RuggedCom Inc.	Toradex AG	VMware, Inc.	

Asset Types



Operating systems






Risk

Vulnerability Score

GT Risk Assessment Report provides a comprehensive risk analysis related to network behaviour and assets. Based on overall assessment for **NTPC TANDA**, all network risk score is 0.



Vulnerability summary

Malware detected	0
Different Operating Systems	5
Different Types of Technologies	10
Attempted Links to Public Internet	0
Multi-homed Assets	6
Different Firmware Versions	1
Clients Accessing SMB Shares	13
Insecure Protocol Links in the Environment	55

Clients accessing SMB Shares

FROM	то	PROTOCOL	TX PACKETS	TX BYTES
192.168.1.1	192.168.1.101	smb		
192.168.1.22	192.168.1.101	smb		
192.168.1.101	192.168.1.67	smb		
192.168.1.101	192.168.1.21	smb		
192.168.1.101	192.168.1.37	smb		
192.168.1.101	192.168.1.22	smb		
192.168.1.101	192.168.1.1	smb		
192.168.1.101	192.168.1.23	smb		
192.168.1.101	192.168.1.20	smb		
192.168.1.21	192.168.1.101	smb		
192.168.1.67	192.168.1.101	smb		
192.168.1.20	192.168.1.101	smb		
192.168.1.37	192.168.1.101	smb		



Revalidation

Devices Vulnerability Summary

Switches

Domain	Critical	High	Medium	Low	Total
Vulnerability Assessment	1	1	6	0	8
Re-validation(closed)	0	0	0	0	0
Re-validation(open)	1	1	6	0	8

Servers

Domain	Critical	High	Medium	Low	Total
Vulnerability Assessment	0	0	5	0	5
Re-validation(closed)	0	0	0	0	0
Re-validation(open)	0	0	5	0	5

Workstations

Domain	Critical	High	Medium	Low	Total
Vulnerability Assessment	0	1	6	0	7
Re-validation(closed)	0	0	0	0	0
Re-validation(open)	0	1	6	0	7

LDGCW

Domain	Critical	High	Medium	Low	Total
Vulnerability Assessment	4	5	13	1	23
Re-validation(closed)	0	0	0	0	0
Re-validation(open)	4	5	13	1	23



Switches

Observation Summary

The chart given below represents the vulnerabilities found during network vulnerability testing:

Fig:1




Fig:2




Figure 1: Vulnerability Assessment Test Observations

Illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Figure 2: Vulnerability Assessment Test Observations- Revalidation

Illustrates the closure of Vulnerabilities based on the categorization i.e., Closed, Open.

Note:

Closed: Count considered having vulnerability in all the IP addresses as closed.

Open: Count considered having vulnerability in minimum one IP address as open/unreachable, it may have more different IP addresses which may have the same vulnerability as closed.



Vulnerability Assessment Test Observations

The below table illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Vulnerabilities &	Affected	Risk	Observations	Recommendations	Sta	Revalidat
Impact	Devices				tus	ion status
SSL/TLS Deprecated Ciphers Unsupported Impact: It allows an attacker to recover the plaintext or potentially violate the integrity of connections.	192.168.1.16 192.168.1.17 192.168.1.38 192.168.1.7	Criti	It was observed that the remote host has open SSL/TLS ports which advertise deprecated cipher suites. The ciphers contained in these suites are no longer supported by most major ssl libraries such as OpenSSL, NSS, Mbed TLS, and wolfSSL and, as such, should not be used for secure communication.	It is recommended to upgrade to a cipher suite which does not contain deprecated ciphers.	Op en	Open
SSL Certificate Signed Using Weak Hashing Algorithm Impact: An attacker can exploit this to generate another certificate with the same digital signature, allowing an attacker to masquerade as the affected service	192.168.1.16 192.168.1.17 192.168.1.38 192.168.1.7	High	It has been observed that SSL certificate is signed using SHA-1 With RSA Encryption.	It is recommended to sign SSL certificate using strong encryption algorithm such as SHA-512. References: https://tools.ietf.org/html/rfc3279	Op en	Open
SSL Certificate Cannot Be Trusted Impact: If the remote host is a public host in production, any break in the chain makes it more difficult for users to verify the authenticity and identity of the web	192.168.1.16 192.168.1.17 192.168.1.38 192.168.1.7	Medi um	It has been observed that remote host is using untrusted SSL certificate. SSL certificate expired on Jan 01 00:00:00 2020 GMT	It is recommended to purchase or generate a proper SSL certificate for this service. References: https://www.itu.int/rec/T-REC-X.509/en	Op en	Open



conver This said						
server. This could make it easier to carry out man-in-the-middle attacks against the remote host.				https://en.wikipedia.o rg/wiki/X.509		
SSL Certificate Chain Contains RSA Keys Less Than 2048 bits. Impact: An attacker can perform man-in-the-middle attack. This can lead to sensitive data loss.	192.168.1.16 192.168.1.17 192.168.1.38 192.168.1.7	Medi um	It was observed that the X.509 certificates sent by the remote host has a key that is shorter than 2048 bits. According to industry standards set by the Certification Authority/Browser (CA/B) Forum, /certificates issued after January 1, 2014, must be at least 2048 bits.	It is recommended to replace the certificate in the chain with the RSA key less than 2048 bits in length with a longer key, and reissue any certificates signed by the old certificate.	Op en	Open
SSL Self-Signed Certificate Impact: If the remote host is a public host in production, this nullifies the use of SSL as anyone could establish a man-in-the-middle attack against the remote host.	192.168.1.16 192.168.1.17 192.168.1.38 192.168.1.7	Medi um	It has been observed that remote host is using SSL Self-Signed Certificate.	It is recommended to purchase or generate a proper SSL certificate for this service. References: https://confluence.atlassian.com/bitbucketserverkb/resolvingsl-self-signed-certificate-errors-806029899.html	Op en	Open
SSL Weak Cipher Suites Supported Impact: The attackers can spoof the identity of the victim. Unlike CAissued certificates, self-signed certificates cannot be revoked. The inability to quickly find and revoke private key associated with a	192.168.1.16 192.168.1.17 192.168.1.38 192.168.1.7	Medi um	It is observed this is considerably easier to exploit if the attacker is on the same physical network.	It is recommended to Reconfigure the affected application, if possible, to avoid the use of weak ciphers. References: How to Disable Weak SSL Protocols and Ciphers in IIS Wayne Zimmerman's Blog	Op en	Open



self-signed certificate creates serious risk. TLS Version 1.1 Protocol Detection Impact: Ciphers that support encryption before MAC computation, and authenticated encryption modes such as GCM cannot be used with TLS 1.1. Hence an attacker can perform man-in-the-middle attack against the remote host.	192.168.1.16 192.168.1.17 192.168.1.38 192.168.1.7	Medi um	It has been observed that remote host supports TLS version 1.1.	enable support for	Op en	Open
Unencrypted Telnet Server Impact: An attacker may eavesdrop on a Telnet session and obtain credentials or other sensitive information. Use of SSH is preferred nowadays as it protects credentials from eavesdropping and can tunnel additional data streams such as the X11 session.	192.168.1.16 192.168.1.17 192.168.1.38 192.168.1.7	Medi um	It is observed SSH is preferred over Telnet since it protects credentials from eavesdropping and can tunnel additional data streams such as an X11 session.		Op en	Open



Servers

Observation Summary

The chart given below represents the vulnerabilities found during network vulnerability testing:

Fig:1




Fig:2




Figure 1: Vulnerability Assessment Test Observations

Illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Figure 2: Vulnerability Assessment Test Observations- Revalidation

Illustrates the closure of Vulnerabilities based on the categorization i.e., Closed, Open.

Note:

Closed: Count considered having vulnerability in all the IP addresses as closed.

Open: Count considered having vulnerability in minimum one IP address as open/unreachable, it may have more different IP addresses which may have the same vulnerability as closed.



Vulnerability Assessment Test Observations

The below table illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Vulnerabilities & Impact	Affected Devices	Risk	Observations	Recommendations	Sta tus	Revalid ation Status
SMB Signing not required. Impact: Signing is not required on the remote SMB server. An unauthenticated, remote attacker can exploit this to conduct man-in-the-middle attacks against the SMB server.	192.168.1.23	Medi um	It has been observed that remote host does not require SMB Signing.	It is recommended to enable signing is on the remote SMB server. References: How to resolve SMB Signing not required Vulnerability - GISPP	Op en	Open
Impact: If the remote host is a public host in production, any break in the chain makes it more difficult for users to verify the authenticity and identity of the web server. This could make it easier to carry out man-in-the-middle attacks against the remote host.	192.168.1.23	Medi um	It has been observed that remote host is using untrusted SSL certificate. SSL certificate expired on Jan 01 00:00:00 2020 GMT	It is recommended to purchase or generate a proper SSL certificate for this service. References: https://www.itu.int/rec//T-REC-X.509/en https://en.wikipedia.org/wiki/X.509	Op en	Open
SSL Certificate with Wrong Hostname Impact: It allows an attacker to perform man-in-the-middle attack.	192.168.1.23	Medi um	It was observed that the 'commonName' (CN) attribute of the SSL certificate presented for this service is for a different machine.	It is recommended to purchase or generate a proper SSL certificate for this service. References: https://www.tenable.com/plugins/nessus/45411	Op en	Open



SSL Self-Signed Certificate Impact: If the remote host is a public host in production, this nullifies the use of SSL as anyone could establish a man-in-the-middle attack against the remote host.	192.168.1.23	Medi um	It has been observed that remote host is using SSL Self-Signed Certificate.	It is recommended to purchase or generate a proper SSL certificate for this service. References: https://confluence.atlassian.com/bitbucketserverkb/resolvingsl-self-signed-certificate-errors-806029899.html	Op en	Open
TLS Version 1.1 Protocol Deprecated / Detection Impact: An attacker may perform man-in-the-middle attack. As of March 31, 2020, Endpoints that are not enabled for TLS 1.2 and higher will no longer function properly with major web browsers and major vendors.	192.168.1.23	Medium	It was observed that the service accepts connections encrypted using TLS 1.1. TLS 1.1 lacks support for current and recommended cipher suites. It was observed that the service accepts connections encrypted using TLS 1.0. TLS 1.0 has a number of cryptographic design flaws. Modern implementations of TLS 1.0 mitigate these problems, but newer versions of TLS like 1.2 and 1.3 are designed against these flaws and should be used whenever possible.	It is recommended to enable support for TLS 1.2 and/or 1.3, and disable support for TLS 1.1.	Op en	Open



Workstation

Observation Summary

The chart given below represents the vulnerabilities found during network vulnerability testing:

Fig:1




Fig:2




Figure 1: Vulnerability Assessment Test Observations

Illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Figure 2: Vulnerability Assessment Test Observations- Revalidation

Illustrates the closure of Vulnerabilities based on the categorization i.e., Closed, Open.

Note:

Closed: Count considered having vulnerability in all the IP addresses as closed.

Open: Count considered having vulnerability in minimum one IP address as open/unreachable, it may have more different IP addresses which may have the same vulnerability as closed.



Vulnerability Assessment Test Observations

The below table illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Vulnerabilities & Impact	Affected Devices	Risk	Observations	Recommendations	Sta tus	Revalid ation status
SMB Server DOUBLEPULSAR Backdoor / Implant Detection (EternalRocks) Impact: The implant allows an unauthenticated, remote attacker to use SMB as a covert channel to exfiltrate data, launch remote commands, or execute arbitrary code.	192.168.1.20 192.168.1.21 192.168.1.22 192.168.1.37	High	It was observed that presence of DOUBLEPULSAR on the remote Windows host. DOUBLEPULSAR is one of multiple Equation Group SMB implants and backdoors disclosed on 2017/04/14 by a group known as the Shadow Brokers.	It is recommended to remove the DOUBLEPULSAR backdoor / implant and disable SMBv1.	Op en	Open
Network Time Protocol (NTP) Mode 6 Scanner Impact: An unauthenticated, remote attacker could potentially exploit this, via a specially crafted mode 6 query, to cause a reflected denial of service condition.	192.168.1.20	Medi um	It was observed that the remote NTP server responds to mode 6 queries. Devices that respond to these queries have the potential to be used in NTP amplification attacks.	It is recommended to restrict NTP mode 6 queries.	Op en	Open
SMB Signing not required. Impact: Signing is not required on the remote SMB server. An unauthenticated, remote attacker can exploit this to conduct man-in-the-middle attacks against the SMB server.	192.168.1.23	Medi um	It has been observed that remote host does not require SMB Signing.	It is recommended to enable signing is on the remote SMB server. References: How to resolve SMB Signing not required Vulnerability - GISPP	Op en	Open
SSL Certificate Cannot Be Trusted Impact: If the remote host is a public host in production, any break in the chain	192.168.1.23	Medi um	It has been observed that remote host is using untrusted SSL certificate. SSL certificate expired	It is recommended to purchase or generate a proper SSL certificate for this service.	Op en	Open



makes it more difficult for users to verify the authenticity and identity of the web server. This could make it easier to carry out man-in-the-middle attacks against the remote host.			on Jan 01 00:00:00 2020 GMT	References: https://www.itu.int/rec /T-REC-X.509/en https://en.wikipedia.org/wiki/X.509		
SSL Certificate with Wrong Hostname Impact: It allows an attacker to perform man-in-the-middle attack	192.168.1.23	Medi um	It was observed that the 'commonName' (CN) attribute of the SSL certificate presented for this service is for a different machine.	It is recommended to purchase or generate a proper SSL certificate for this service. References: https://www.tenable.com/plugins/nessus/45411	Op en	Open
SSL Self-Signed Certificate Impact: If the remote host is a public host in production, this nullifies the use of SSL as anyone could establish a man-in-the-middle attack against the remote host.	192.168.1.23	Medi um	It has been observed that remote host is using SSL Self-Signed Certificate.	It is recommended to purchase or generate a proper SSL certificate for this service. References: https://confluence.atlassian.com/bitbucketserverkb/resolvingssl-self-signed-certificate-errors-806029899.html	Op en	Open
TLS Version 1.1 Protocol Deprecated / Detection Impact: An attacker may perform man-in-the-middle attack. As of March 31, 2020, Endpoints that are not enabled for TLS 1.2 and higher will no longer function properly with major web browsers and major vendors.	192.168.1.23	Medi um	It was observed that the service accepts connections encrypted using TLS 1.1. TLS 1.1 lacks support for current and recommended cipher suites. It was observed that the service accepts connections encrypted using TLS 1.0. TLS 1.0 has a number of cryptographic design flaws. Modern implementations of TLS 1.0 mitigate	It is recommended to enable support for TLS 1.2 and/or 1.3, and disable support for TLS 1.1.	Op en	Open



these problems, but newer versions of TLS like 1.2 and 1.3 are designed against these flaws and should be used whenever possible.

LDGCW

Observation Summary

The chart given below represents the vulnerabilities found during network vulnerability testing:

Fig:1




Fig:2




Figure 1: Vulnerability Assessment Test Observations

Illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Figure 2: Vulnerability Assessment Test Observations- Revalidation

Illustrates the closure of Vulnerabilities based on the categorization i.e., Closed, Open.

Note:

Closed: Count considered having vulnerability in all the IP addresses as closed.

Open: Count considered having vulnerability in minimum one IP address as open/unreachable, it may have more different IP addresses which may have the same vulnerability as closed.



Vulnerability Assessment Test Observations

The below table illustrates the distribution of observations of Vulnerability testing based on the risk categorization i.e., Critical, High, Medium, and Low.

Vulnerabilities & Impact	Affected Devices	Risk	Observations	Recommendations	Sta tus	Revali dation Status
Microsoft RDP RCE (CVE-2019-0708) (BlueKeep) (uncredentialed check) Impact: An unauthenticated, remote attacker can exploit this, via a series of specially crafted requests, to execute arbitrary code.	192.168.1.1	Criti cal	It was observed that remote host is affected by a remote code execution vulnerability in Remote Desktop Protocol (RDP).	that Microsoft has released a set of patches for Windows	Op en	Open
SSL Version 2 and 3 Protocol Detection Impact: An attacker can conduct man-in-the-middle attacks or to decrypt communications between the affected service and clients.	192.168.1.1	Criti	It has been observed that devices are using SSL version 2.0 and 3.0.	It is recommended to disable SSL 2.0 and 3.0. Use TLS 1.2 with higher cipher suites listed below. TLS_ECDHE_RSA_WITH_AES_128_CB C_SHA256 (secp256k1) - A TLS_ECDHE_RSA_WITH_AES_128_GC M_SHA256 (secp256k1) - A TLS_ECDHE_RSA_WITH_AES_256_CB C_SHA384 (secp256k1) - A TLS_ECDHE_RSA_WITH_AES_256_GC M_SHA384 (secp256k1) - A 2 References: https://www.imperialviolet.org/2014/10/14/poodle.html	Op en	Open



Unsupported Web Server Detection Impact: Web Server is put longer the attacker easy to attack the web server and expose the sensitive data.	192.168.1.1	Criti	It is observed the remote web server is obsolete and no longer maintained by its vendor or provider.	It is recommended to remove the web server if it is no longer needed. Otherwise, upgrade to a supported version if possible or switch to another server. References: https://www.tenable.com/plugins/nessus/34460 https://cve.mitre.org/cgi-bin/cvekey.cgi?keyword=apache+httpcore+4.4.3 https://cwe.mitre.org/data/definitions/447.html	Op en	Open
Unsupported Windows OS (remote) Impact: An attacker easy to attack the web server and expose the sensitive data.	192.168.1.1	Criti	It was observed that remote version of Microsoft Windows is either missing a service pack or is no longer supported. As a result, it is likely to contain security vulnerabilities.	It is recommended to upgrade to a supported service pack or operating system	Op en	Open
MS14-066: Vulnerability in Schannel Could Allow Remote Code Execution (2992611) (uncredentialed check) Impact: An attacker can exploit this issue by sending specially crafted packets to a Windows server.	192.168.1.1	High	It was observed that remote Windows host is affected by a remote code execution vulnerability due to improper processing of packets by the Secure Channel (Schannel) security package.	that Microsoft has released a set of patches for Windows 2003, Vista, 2008, 7,	Op en	Open



An instinct for growth $^{^{\mathsf{T}}}$

MS17-010: Security Update for Microsoft Windows SMB Server (4013389) (ETERNALBLUE) (ETERNALCHAMPION) (ETERNALSYNERGY) (WannaCry) (EternalRocks) (Petya) (uncredentialed check) Impact: Successful exploitation of this vulnerability leads to Remote code execution. Also, this may lead to installation of ransomware, malwares, crypto-jacking, or any other worm-like software's.	192.168.1.1	High	It was observed that he remote Windows host is affected by the remote code execution vulnerability.	It is recommended to install the patches for Windows Vista, 2008, 7, 2008 R2, 2012, 8.1, RT 8.1, 2012 R2, 10, and 2016. Microsoft has also released emergency patches for Windows operating systems that are no longer supported, including Windows XP, 2003, and 8. It is also recommended for unsupported Windows operating systems, e.g., Windows XP, Microsoft recommends that users discontinue the use of SMBv1. SMBv1 lacks security features that were included in later SMB versions. SMBv1 can be disabled by following the vendor instructions provided in Microsoft. Additionally, it is recommending that users block SMB directly by blocking TCP port 445 on all network boundary devices. For SMB over the NetBIOS API, block TCP ports 137 / 139 and UDP ports 137 / 138 on all network boundary devices.	Op en	Open
Network Time Protocol Daemon (ntpd) read_mru_list() Remote DoS Impact: An unauthenticated, remote attacker can exploit this, via a specially crafted NTP	192.168.1.1	High	It was observed that remote NTP server is affected by a denial of service vulnerability due to improper validation of mrulist queries.	upgrade to NTP	Op en	Open



mrulist query packet, to terminate the ntpd process.						
SSL Certificate Signed Using Weak Hashing Algorithm Impact: An attacker can exploit this to generate another certificate with the same digital signature, allowing an attacker to masquerade as the affected service.	192.168.1.1	High	It has been observed that SSL certificate is signed using SHA-1 With RSA Encryption.	It is recommended to sign SSL certificate using strong encryption algorithm such as SHA-512. References: https://tools.ietf.org/httml/rfc3279	Op en	Open
SSL Medium Strength Cipher Suites Supported (SWEET32) Impact: The remote host supports the use of SSL ciphers that offer medium strength encryption that it is considerably easier to circumvent medium strength encryption if the attacker is on the same physical network.	192.168.1.1	High	It has been observed that SSL is using medium strength encryption such as DES-CBC3-SHA which can be easily compromised if the attacker is on the same physical network.	It is recommended to reconfigure the affected application if possible, to avoid use of medium strength ciphers. References: https://www.openssl.org/blog/blog/2016/08/24/sweet32/	Op en	Open
MS13-006: Vulnerability in Microsoft Windows Could Allow Security Feature Bypass (2785220) (uncredentialed check) Impact: An attacker can inject specially crafted content into an SSL/TLS session, which could allow an attacker to bypass security features of SSLv3 and TLS protocols in order to intercept communications.	192.168.1.1	Medi um	It was observed that remote host contains a flaw in the handling of SSL version 3 (SSLv3) and TLS (Transport Layer Security) protocols.	It was recommended that Microsoft has released a set of patches for Windows Vista, 2008, 7, 2008 R2, 8, and 2012. For other SSL/TLS implementations, contact the vendor for updates.	Op en	Open



MS16-047: Security Update for SAM and LSAD Remote Protocols (3148527) (Badlock) (uncredentialed check) Impact: A man-in-the-middle attacker able to intercept communications between a client and a server hosting a SAM database can exploit this to force the authentication level to downgrade, allowing the attacker to impersonate an authenticated user and access the SAM database.	192.168.1.1	Medi um	It was observed that remote Windows host is affected by an elevation of privilege vulnerability in the Security Account Manager (SAM) and Local Security Authority (Domain Policy) (LSAD) protocols due to improper	It is recommended to Microsoft has released a set of patches for Windows Vista, 2008, 7, 2008 R2, 2012, 8.1, RT 8.1, 2012 R2, and 10.	Op en	Open
Network Time Protocol (NTP) Mode 6 Scanner Impact: An unauthenticated, remote attacker could potentially exploit this, via a specially crafted mode 6 query, to cause a reflected denial of service condition.	192.168.1.1	Medi um	It was observed that the remote NTP server responds to mode 6 queries. Devices that respond to these queries have the potential to be used in NTP amplification attacks.	It is recommended to restrict NTP mode 6 queries.	Op en	Open
Remote Desktop Protocol Server Man- in-the-Middle Weakness Impact: A MiTM attack of this nature would allow the attacker to obtain any sensitive information transmitted, including authentication credentials.	192.168.1.1	Medi um	It was observed that the remote version of the Remote Desktop Protocol Server (Terminal Service) is vulnerable to a man-in-the-middle (MiTM) attack. The RDP client makes no effort to validate the identity of the server when setting up encryption. An attacker with the ability to intercept traffic from the RDP server can establish encryption with the client	layer for this service if supported, or/and - On Microsoft Windows operating	Op en	Open



			and server without			
			being detected.	http://www.nessus.or		
				g/u?8033da0d		
SMB Signing not	192.168.1.1	Medi	It has been observed	It is recommended to	05	Onon
SMB Signing not required.	192.100.1.1		that remote host does	enable signing is on	Op	Open
required:		um	not require SMB	the remote SMB	en	
Impact:			Signing.	server.		
impuoti			Olgrinig.	References:		
Signing is not required				How to resolve SMB		
on the remote SMB				Signing not required		
server. An				Vulnerability - GISPP		
unauthenticated,				vullerability - GISPP		
remote attacker can						
exploit this to conduct						
man-in-the-middle						
attacks against the SMB						
server.						
SSL Certificate Cannot	192.168.1.1	Medi	It has been observed	It is recommended to	Op	Open
Be Trusted	134.100.1.1	um	that remote host is		en	Ohen
20 1140104		uiii		purchase or generate	en	
Impact:			using untrusted SSL	a proper SSL		
1			certificate. SSL	certificate for this		
If the remote host is a			certificate expired on	service.		
public host in production,			Jan 01 00:00:00 2020			
any break in the chain			GMT	References:		
makes it more difficult for				https://www.itu.int/rec		
users to verify the				/T-REC-X.509/en		
authenticity and identity						
of the web server. This				https://en.wikipedia.o		
could make it easier to carry out man-in-the-				rg/wiki/X.509		
middle attacks against						
the remote host.						
SSL DROWN Attack	192.168.1.1	Medi	It was observed hat	It is recommended to	Op	Open
Vulnerability		um	remote host supports	Disable SSLv2 and	en	
(Decrypting RSA with			SSLv2 and therefore	export grade		
Obsolete and			may be affected by a	cryptography cipher		
Weakened eNcryption)			vulnerability that	suites. Ensure that		
Process and			allows a cross-	private keys are not		
Impact:			protocol Bleichenbacher	used anywhere with		
A man-in-the-middle			padding oracle attack	server software that		
attacker can exploit this			known as DROWN	supports SSLv2		
to decrypt the TLS			(Decrypting RSA with	connections.		
connection by utilizing			Obsolete and	CONNECTIONS.		
previously			Weakened			
captured traffic and			eNcryption). This			
weak cryptography			vulnerability exists			
along with a series of			due to a flaw in the			
specially crafted			Secure Sockets			
connections to an SSLv2			Layer Version 2			
server that uses the			(SSLv2)			
same			implementation, and			
private key.			it allows captured			
	<u> </u>					



			TLS traffic to be decrypted.			
SSL RC4 Cipher Suites Supported (Bar Mitzvah) Impact: If plaintext is repeatedly encrypted (e.g., HTTP cookies), and an attacker is able to obtain many (i.e., tens of millions) ciphertexts, the attacker may be able to derive the plaintext.	192.168.1.1	Medi um	It has been observed that remote host is using weak cipher suite.	It is recommended to reconfigure the affected application, if possible, to avoid use of RC4 ciphers. Consider using TLS 1.2 with AES-GCM suites subject to browser and web server support. References: SSL RC4 Cipher Suites Supported (Bar Mitzvah) (microsoft.com)	Op en	Open
SSL Self-Signed Certificate Impact: If the remote host is a public host in production, this nullifies the use of SSL as anyone could establish a man-in-the-middle attack against the remote host.	192.168.1.1	Medi um	It has been observed that remote host is using SSL Self-Signed Certificate.	It is recommended to purchase or generate a proper SSL certificate for this service. References: https://confluence.atlassian.com/bitbucketserverkb/resolvingssl-self-signed-certificate-errors-806029899.html	Op en	Open
SSLv3 Padding Oracle on Downgraded Legacy Encryption Vulnerability (POODLE) Impact: An attacker can perform a man-in-the-middle (MitM) information disclosure known as POODLE. MitM attackers can decrypt a selected byte of a cipher text in as few as 256 tries if they are able to force a victim application to repeatedly send the same data over newly created SSL 3.0 connections.	192.168.1.1	Medi um	It has been observed that the remote host is vulnerable to padding oracle attack.	Services that must	Op en	Open



Terminal Services Doesn't Use Network Level Authentication (NLA) Only Impact: An attacker can cause connection failures and they can trigger the use of TLS 1.0 to exploit vulnerabilities like BEAST (Browser Exploit Against SSL/TLS). Websites using TLS 1.0 will be considered non- compliant by PCI after 30 June 2018.	192.168.1.1	Medi um	It is observed in addition to improving authentication, NLA also helps protect the remote computer from malicious users and software by completing user authentication before a full RDP connection is established.	It is recommended to enable Network Level Authentication (NLA) on the remote RDP server. This is generally done on the 'Remote' tab of the 'System' settings on Windows. References: https://appuals.com/fix-the-remote-computer-requires-network-level-authentication/	Op en	Open
Terminal Services Encryption Level is Medium or Low Impact: The Using weak cryptography with this service may allow an attacker to eavesdrop on the communications more easily and obtain screenshots and/or keystrokes.	192.168.1.1	Medi um	It is observed the Client Compatible setting encrypts data sent between the client and the server at the maximum key strength supported by the client.	Change RDP encryption level to one of: 3. High 4. FIPS Compliant References: https://techgenix.com/Windows_Terminal_Services/#:~:text=Medium%3A%20encrypts%20both%20the%20data%20sent%20from%20client,40%20bit%20key%2C%20depending%20on%20the%20client%20version.	Op en	Open
TLS Version 1.0 Protocol Detection Impact: An attacker can cause connection failures and they can trigger the use of TLS 1.0 to exploit vulnerabilities like BEAST (Browser Exploit Against SSL/TLS). Websites using TLS 1.0 will be considered non-	192.168.1.1	Medi um	It is observed to TLS 1.2 is more secure, an attacker can cause connection failures and they can trigger the use of TLS 1.0 to exploit vulnerabilities.		Op en	Open



compliant by PCI after 30 June 2018.						
Terminal Services Encryption Level is not FIPS-140 Compliant Impact: The attacker observed the encryption setting used by the remote Terminal Services after the attacker easy to expose the all sensitive data.	192.168.1.1	Low	It is observed the Client Compatible setting encrypts data sent between the client and the server at the maximum key strength supported by the client.	It is recommended to change RDP encryption level to: 4. FIPS Compliant References: https://www.tenable.com/plugins/nessus/30218	Op en	Open

Asset Inventory

Inventory Overview

This section focuses on asset tracking, asset discovery and asset classification. These are the first steps for ensuring operational continuity, reliability and safety. They provide the user with a full context for security events and support routine procedures aimed at improving overall cyber hygiene. Creating an inventory of devices in the network, as well as understanding the relationships and connections between them, is a crucial component in network security.

Electrical Asset List



Final Mapping of Electrical Dept Assets:

Refer below excel file contains mapping of vulnerabilities & open ports with the assets, it provides the details of vulnerabilities observed in each asset.





Recommendations

- All unwanted ports & services running on the systems should be disabled. During this process, it is always good to check the effect on running SCADA system performance (with the help of SCADA vendor). System availability is more important in OT environment.
- Unused ports of network/OT devices such as switch should be disabled.
- Device control and application control policy for OT environment should be implemented.
- Upgradation of system OS should be carried out and the systems should be on latest OS.
- Upgradation of Network Device Firmware should be carried out are regular intervals and should be on latest Firmware.
- Antivirus definitions and OS patch update rule should be defined and implemented.
- Monitor and implement security controls for the communication involving DCS systems (System PC and PLC) which are having the data flow between DCS systems and third-party sources / devices for security checks (with the support of vendor). This will add another layer of security in third party communication involving TCP/IP, OPC, Modbus, etc between DCS systems and third-party sources / devices.

Disclaimer: The audit / assessment has been performed (Point in Time Basis) against most of the technical security controls. It is important to note that tests are valid as on the date of testing. New issues / vulnerabilities are being discovered daily hence it is recommended to conduct proactive assessment periodically and ensure any new changes introduced on the systems/ environment should undergo a comprehensive security assessment to identify and mitigate new threats.

End Of Document

DOOSAN

Technical Annexure – 4X110 MW SKODA Machine Upgrade of control system TCP/TPS Siemens Simatic PCS7

DOOSAN Škoda Power

Due to the obsolescence and future unavailability of ET200M modules (phase-out status), we recommend replacing the I/O peripherals with ET200SP-HA I/O peripherals with redundant communication bus PROFINET instead of the current communication bus PROFIBUS-DP.

In connection with the possible installation of the I/O peripheral ET200SP-HA with PROFINET communication, it is also necessary to replace the CPU unit CPU-414-4H with a modern type CPU 410-H which supports PROFINET communication.

In addition, the ET200M and CPU-414-4H do not meet the requirements of the cyber security standard IEC 62443.

1.2. Recommended hardware upgrade of automation station (For 4 units)

DSPW recommend the complete replacing of the existing I/O peripherals ET200M with modern I/O peripherals ET200SP-HA I/O with redundant communication bus PROFINET in the following configuration include replacing of all CPU units CPU-414-4-H by CPU 410-H.

- 10 pcs of processor modules CPU 410-5H incl. the relevant synchr. modules
- 7 pcs of ET200SP-HA interface module IM155-6 PN incl. bus adapters
- 14 pcs of ET200SP-HA digital input module (32x DI, 24Vdc)
- 14 pcs of ET200SP-HA digital output module (32x DO, 24Vdc, 0,5A)
- 14 pcs of ET200SP-HA analog input module (8x AI U/I/TC/4xRTD 2-/3-/4-wire)
- 14 pcs of ET200SP-HA fast multi I/O and counter module (4xAI,8xAO,10xDI/DO)
- 12 pcs of ET200SP-HA carrier module for 8 I/O modules
- 36 pcs of ET200SP-HA terminal block, 32 push-in terminals
- 12 pcs of ET200SP-HA terminal block, 16 push-in terminals

1.3. Recommended upgrade of engineering and operator station (For 4 units)

Hardware delivery (computers):

- 1 pcs of engineering station, notebook DELL Precission, Win 11, WM Player V17
- 8 pcs of operator stations computers SIEMENS IPC 647E, Win10 LTSC 2019
- 16 pcs of monitor DELL Professional P2222H, 22"
- 8x keyboard
- 8x mouse

Software delivery (licences)

- 1 pcs of PCS7 Upgrade Package Engineering from v. 7.1 to v. 8.2
- 1 pcs of PCS7 Upgrade Package Engineering from v. 8.x to v. 9.1
- 8 pcs of PCS7 Upgrade Package OS Server from v. 7.1 to v. 8.2
- 8 pcs of PCS7 Upgrade Package OS Server from v. 8.x to v. 9.1
- 8 pcs of PCS7 Upgrade Softnet-IE S7 Lean

1.4. Related services in the factory (invelt-elektro s.r.o., Pilsen, CZ)

- 8x installation and setting of system upgrade PCS7 (v.7.1 v.9.1) for new OS IPC647E
- 1x installation and setting of system upgrade PCS7 (v.7.1 v.9.1) for new engineering

Prepared by: Sandeep Kumar Page 3/4 Date: 08.07.2024 Rev.0

DOOSAN

Technical Annexure – 4X110 MW SKODA Machine Upgrade of control system TCP/TPS Siemens Simatic PCS7



stations (notebook DELL Precission).

- 4x upgrade of process software application PCS7 for automation station
- 8x complete implementation of upgrade process software application into PCS7 v.9.1 in OS IPC647E
- Hardware design modification for ET200M by ET200SP-HA replacement
- Preassembly of I/O peripherals of ET200SP-HA
- Trial and testing of ES, OS, CPU, I/O peripherals ET200SP-HA

1.5. Related services On-Site (NTPC- Tanda) – Supervision only (Assembly in Client Scope)

- Installation of 8 pcs CPU modules CPU410 inside control system cabinets in exchange for existing ones CPU 414-4H
- Installation of 12 racks of I/O peripheral ET200SP-HA inside control system cabinets in exchange of existing ones ET200M
- Reconnection of connectors of I/O modules of ET200SP-HA inside control system cabinets according to modified hardware design
- Connection of communication bus PROFINET inside control system cabinets according to modified hardware design
- Hardware installation of new operator stations
- Verification and testing of communication buses PROFINET, ETHERNET
- Complete testing of system functions of the control system after the upgrade implementation incl. SAT test

All activities of the System Expert (DSPW/INVELT) technicians on the site are billed at an hourly rate include related travel and accommodation costs.

2. Delivery date:

8-10 months after ordering

3. Delivery conditions:

FCA SITE according to the international rules INCOTERMS 2020.

Deliveries will be packed in packaging for oversee transport – wooden boxes.

4. Counter Obligation:

- The control system of the relevant TG available for upgrade, under voltage
- Ensuring of entrances and entrances to the NTPC Tanda complex
- Provision of electrical installation works remain in Client Scope

Prepared by: Sandeep Kumar Page 4/4 Date: 08.07.2024 Rev.0

ANNEXURE-R7



भारत हेवी इलेक्ट्रिकल्स लिमिटेड

Bharat Heavy Electricals Limited

(A GOVERNMENT OF INDIA UNDERTAKING)
ELECTRONICS DIVISION

ार.के. तिवारी

K. TIWARI ECUTIVE DIRECTOR

PHONE: OFF: 080-26989000

FAX: 080-26742780

e-mail: rktiwari@bheledn.co.in P. B. No. 2606, MYSORE ROAD

BANGALORE - 560 026

EDN/CE/SM/DPU/NTPC 9th September 2015

Dear Shri Venkateshwara Rao,

Sub: Processor upgrades (DPU4E to DPU4F) in BHEL's maxDNA C&I systems at various NTPC Projects – reg.

I am pleased to inform that BHEL-EDn has very closely partnered with NTPC in meeting the C&I system requirements of various projects through our maxDNA based controls. As a part of our continuous product development, innovation and commitment to offer the latest controls, we have come out with superior processor DPU4F and the same is currently being supplied to NTPC projects with good response. As a consequence of this development and due to component obsolescence, we have phased out DPU4E processors and withdrawn spares and services support. However, we are presently supplying and supporting the latest processor DPU4F with compatible HMIs and associated software.

In view of this, I strongly suggest that the processor upgrades may please be implemented for all the units of NTPC projects using DPU4E, by which we can ensure continuous availability of your plants and thereby extend the life cycle of C&I systems. In this context I would like to inform you that we have already implemented processor upgrades at NTPC- Rihand (Unit-3).

I request you to examine the above and advice all the NTPC project sites to consider for procurement of processor upgrades (DPU4E to DPU4F) at the earliest with the help of EDN.

S.CS)

You may instruct the concerned officials to interact with our Mr.G A Saravanan, AGM (Ph:080-26989241 & 09972249827, email:saravananga@bheledn.co.in) on the above subject.

With warm regards.

Yours sincerely,

(R.K. TIWARI)

Shri Y Venkateshwara Rao, Executive Director (Operation Services) National Thermal Power Corporation Ltd., Engineering Office Complex (EOC), Sector 24, Noida – 201 301.



ANNEXURE-R8



Date: April 18, 2023

Subject: Autrosafe Detectors Phase Out

Dear Sir/Madam,

Please note that all Autrosafe detector variants (Smoke/Heat/Multi) below are now obsolete and are no longer manufactured.

- 116-BDH-200
- 116-BDH-300
- 116-BDH-500
- 116-BHH-200
- 116-BHH-300
- 116-BHH-500
- 116-BHH-220
- 116-BHH-320
- 116-BHH-520

Our new AutroGuard protector V-430 and V-530 variants are available as replacements for the above detectors

Please do not hesitate to contact me for further clarifications.

Kind Regards,

Oussama El Khatib

Oussama

Regional Sales Manager Global Land

Tel +44 0 1784262836 | Mobile +44 0 7553229381

Oussama.elkhatib@carrier.com www.autronicafire.com

RE: Regarding budgetary offer for Screw terminal 140xts00200 for modicon quantum

Deepak Kumar < Deepak3.Kumar@se.com >

Tue 8/6/2024 8:39 PM

To:VISHWAS <VISHWASSINGH@NTPC.CO.IN>

Cc:Suresh Kumar <SURESHKUMAR02@NTPC.CO.IN>;Alok Mandliya <ALOKMANDLIYA@NTPC.CO.IN>;Tushar Johari <Tushar.Johari@se.com>;Amit Kumar Arya <AmitKumar.Arya@non.se.com>;Renugopan.Arunagiri <renugopan.arunagiri@se.com>

0 5 attachments (1 MB)

SESIPL PLC Spare Offer to NTPC, Tanda_R00_06-08-2024.pdf; Quantum EoC - Customer Letter_Signed.pdf; Annexure-3 End Use Statement (EUS). version Feb 2018.docx; Annexure-1 Simplified T&Cs -Supply of Equipment and Services v1.5.pdf; Annexure-2 Schneider Principles of Responsibility.pdf;

CAUTION: This Email has been sent from outside the Organization. Unless you trust the sender, Don't click links or open attachments as it may be a Phishing email, which can steal your Information and compromise your Computer.

Dear Sir,

Please ignore my previous mail.

Referring to your below mail and our telephonic discussion, please find attached our techno-commercial proposal for supply of PLC spare. You are requested to release the Purchase Order to our company on below address:

Schneider Electric Systems India Private Limited (NTPC Vendor Code: 1040064)

Tamarai Tech Park, SP Plot# 16-19 and 20A,

Thiru Vi Ka Industrial Estate, Guindy,

Chennai - 600032, Tamil Nadu, India

Being OEM, we would also like to inform you that our installed Quantum PLC starting with 140CPU series has already crossed End-of Commercialization in Year 01-Dec-2018 and will reach end-of-service by 01-Dec-2026. Therefore, kindly initiate the PLC upgradation phase-by-phase before end-of-service period to avail our continued service support. As per our telephonic discussion, we are attaching our EoC Letter for your kind reference and record.

In case of any queries/clarifications, please feel free to contact the undersigned

Thanks & Best Regards,

Deepak Kumar
General Manager - Sales
Automation Solutions & Services
Industry 4.0 | Digital Solutions

IMPACT company
bridging progress and sustainability for all

Learn more

Schneider Electric Systems India Pvt. Ltd.
Mobile: 9717361325
Customer Care: 18001030011 / 18004194272
Email: deepak3.kumar@se.com

UMPACT company
bridging progress and sustainability for all

Life Is On Schneider

PElectric

General

From: VISHWAS VISHWASSINGH@NTPC.CO.IN Sent: Tuesday, August 6, 2024 4:41 PM To: Deepak Kumar <u>Deepak3.Kumar@se.com</u>

Cc: Suresh Kumar SURESHKUMAR02@NTPC.CO.IN; Alok Mandliya ALOKMANDLIYA@NTPC.CO.IN

Subject: Regarding budgetary offer for Screw terminal 140xts00200 for modicon quantum

Dear Sir

Kindly provide budgetary offer for modicon quantum Screw terminal 140xts00200 for 3 quantity.

यह आपकी जानकारी और आवश्यक कार्रवाई के लिए है।

This is for your kind inf. and necessary action at your end please.

धन्यवाद/Thanks.

भवदीय/Regards

विश्वास सिंह/Vishwas Singh

प्रबंधक/Manager एनटीपीसी टांडा सुपर थर्मल पावर स्टेशन

NTPC Tanda Super Thermal Power Station

विद्युत नगर, टांडा, उत्तर प्रदेश 224238

Vidyut Nagar, Tanda, Uttar Pradesh 224238

Mob. (मोबाइल)-7250687370/9473196703

Please don't print this e-mail unless you really need to..... Please Save tree.

कृपया इस ई-मेल को तब तक न छापें जब तक आपको वास्तव में इसकी आवश्यकता न हो....... कृपया पेड़ बचाएं।

DISCLAIMER: This Email contains PRIVILEGED AND CONFIDENTIAL INFORMATION intended solely for the use of the addressee(s). If you are not the intended recipient do not copy, disclose or distribute this mail. Further, remove it from your system & please notify to administrator at <a href="mailto:ma

ANNEXURE-R9



Schneider Electric

Subject: Modicon Quantum EoC (End of Commercialization)

Over the past 20 years, technological advancements in industrial automation have brought higher performance processors with more memory, better performance, and enhanced capabilities. In plant environments, these advancements translate to increased productivity, efficiency, security and sustainability. Schneider Electric has taken full advantage of these technological advancements to provide you with a PAC to address your needs now and into the future.

Important information about the future of Modicon range of processors

We have a great opportunity to take advantage of these new technologies, which is why we have developed the Modicon M580 ePAC. Introduced in 2013, this latest generation of Programmable Automation Controller has been designed to replace the Quantum range.

On December 1, 2018, Modicon Quantum processor has reached end of active sales.

Modicon PAC Range	End of Commercialization	End of Service
Quantum CPU (140CPU*)	December 1, 2018	December 1, 2026

We strongly recommend you take this opportunity to take a look at the Modicon M580 ePAC platform and how it helps you address your current and future needs. We also have a strong service offer to ease the modernization and ensure access to products during your planned transition period.

Modicon M580 addresses your needs now and into the future

Awarded the 2015 Engineers' Choice by Control Engineering, the Modicon M580 is one of the highest performance processors in the industry with increased power and greater connectivity. We understand the importance of having an open yet secure processor. The Modicon M580 has cyber security built into its core. Independently certified by global third-party organization to mitigate operational technology (OT) threats and vulnerabilities. The increased capabilities of the Modicon M580 help you improve operational efficiency and maintenance for the life of your control systems.

Efficient, low risk upgrades

Automation is often at the heart of the industrial process. That's why we have developed a range of tools and techniques to make it as efficient as possible for customers to upgrade from our legacy CPUs to our latest controllers. With more than 20 years of experience, we can provide you with smooth, step by step upgrade paths to our latest platforms. We have worked hard to make sure that the Modicon M580 will make the most of your existing automation investment. It minimizes the time and cost it takes to upgrade due to its compatibility with existing Quantum I/O plus software utilities available to import your existing application programs. The Modicon M580 platform is designed to continue leveraging the innovative benefits of the range to help you with your future upgrade plans.

Schneider Electric is committed to supporting your business.

Yours Sincerely,



Schneider Electric Systems India Private Limited.

Tamarai Tech Park, SP Plot # 16-19 & 20A, Thiru Vi Ka Industrial Estate, Inner Ring Road, Guindy, Chennai - 600032

ANNEXURE-R10

RE: NTPC, TANDA/Regarding upgradation of ILK make pneumatic actuator with SMART Positioners in NTPC TANDA STAGE#1.

sparenorth < sparenorth@ilpgt.com>

Mon 8/12/2024 2:25 PM

To:BIKRAM KUMAR <BIKRAMKUMAR@NTPC.CO.IN>;madhu@ilpgt.com <madhu@ilpgt.com>
Cc:ARENDRA KUMAR ARYA <ARENDRAARYA@NTPC.CO.IN>;Suresh Kumar <SURESHKUMAR02@NTPC.CO.IN>

1 attachments (590 KB)

NTPC TANDA MOM.PDF;

CAUTION: This Email has been sent from outside the Organization. Unless you trust the sender, Don't click links or open attachments as it may be a Phishing email, which can steal your Information and compromise your Computer.

ILP/OR-4810765/NS

Dear Sir,

Please refer the attached MOM dated 25/03/2023 regarding up-gradation of IL Make Pneumatic Actuators installed at various units of NTPC.

As per the MOM we have already executed purchase order number 4000313775 for Spares required for upgrading of FD/PA IGV Fan IGV, ID Fan Scoop and Fuel Oil control Valves for UNIT # 2.

Since the existing Actuators and Positioners Mounted are of Obsolete Model, it is suggested to upgrade the Actuators of the balance 3 units also.

With Regards सादर,

MADHU मध्

Sr.Engineer (Commercial) वरिष्ठ अभियंता (वाणिज्य)

Instrumentation Limited इंस्ट्रमेंटेशन लिमिटेड

PALAKKAD - 678623 (Kerala)पालकाड

PIN CODE- 678623 (केरल)

PH: 0491-2566844

Mob:9496946766/8921602300 E Mail: sparenorth@ilpgt.com

GeM Seller ID विक्रेता आईडी - E5FF20001308318

For Complaints visit - सेवा शिकायतों के लिए कृपया देखें https://www.ilpgt.com/html/complaints.php

IL's official Youtube channel https://youtube.com/channel/UCTyfGXgalO0eD2GvDnqLfQQ

IL's official Twitter handle https://twitter.com/limited unit?t=LPGTT-gz1ov1yJ26FCKI2g&s=03

From: BIKRAM KUMAR [mailto:BIKRAMKUMAR@NTPC.CO.IN]

Sent: 03 February 2023 09:05

To: <u>sparenorth@ilpgt.com</u>; <u>madhu@ilpgt.com</u> **Cc:** ARENDRA KUMAR ARYA; Suresh Kumar

Subject: Regarding upgradation of ILK make pneumatic actuator with SMART Positioners in NTPC TANDA STAGE#1.

Sir,

Basic Information Regarding Cast basalt



Basalt is basically a volcanic rock that possesses perfect characteristics including resistance to abrasion as well as corrosion.

The process of **basalt casting** starts with discerning quarrying of the rock. It is then melted at 1280°C and then casted in the form of moulds and cylinders. The **basalt castings** that are produced are then exposed to a cycle of heat treatment. They are placed in kilns for the production of basalt in a recrystallized form. The product contains various **cast basalt properties** like inertness in it. This inertness is inherited from the parent material. It is homogenous, non porous and denser as compared to the raw form. Amazing qualities of abrasion resistance are acquired by the processed form of basalt after going through the process of **basalt casting**.

Basalt casts are considered the best lining materials for industries dealing with abrasion resistance. The other application areas of **basalt casts** are bends, lining pipers and trenches.

Application Areas of Basalt Casting

- Because of the specialized cast basalt properties, they can be used in thermal power stations for the manufacture of hoppers, bottom ash, bends, pipelines, trenches, coal piping, dust lines, disposal slurries etc.
- Cast basalt is also used in cement plants for making air separators, chain conveyor, silica hoppers, nozzles, coal hoppers, cement hoppers, cyclones, raw mill ducts, chutes, thick slurry lines, mixers, grate cooler housing, coal ventury etc.
- Steel plants also make exceptional use of basalt casting materials. They use if for making lime bunkers, coke breeze, telescopic pipers, cyclones, sieves, floatation cells, coke sorting units, sinter plant cyclones, iron slurry line, granulated slag, thick slurry lines, hot mill flume, flow conveyors etc.
- Furthermore, coal washeries make effective use of cast basalt for the manufacture of media sumps, coal transportation, coal
 washing plans, cyclones, conveyor pipes, floatation cells, centrifuges etc.

Cast Basalt Properties

- · Cast basalt is resistant to abrasion.
- It is resistant to many chemicals.
- Cast basalt can be easily cast in various shapes including flat, hexagonal and radial tiles or cylinders. They can also be made up into special castings and different circular pipelines can be made of it.

Some Technical Properties of Cast Basalt

- Cast basalt gets polished up when more material is passed over it. This reduces friction in it and improves the service that it renders.
- Cast basalt is considered the best for abrasion. A basalt pipe has a stronger strength as compared with that of a bare pipe. Its external effect of strength is higher than the raw form.
- Another important feature of cast basalt is that it is resistant to chemicals including alkalis and acids. As it is resistant to chemicals; therefore, it is resistant to corrosion as well.
- Cast basalt tiles can be easily found in a regular size of 200x200x30 mm. The weight of a regular shaped cast basalt tile is 78 kg/sq m. The pipes and bends that contain lining of cast basalt possess a size of 40-1100 NB.
- The maximum temperature that can be withstood by cast basalt is 450°C.
- The life span of an average pipe made up of cast basalt lining is more as compared with that of cast iron. It is 3-4 times more than the wear of cast iron.

Cast basalt is a durable, resistant, and reliable and widely used manufacturing material being used in variant construction projects and industries. The linings made from cast basalt are strong and have long lasting effects. This is why most of the industries prefer using cast basalt linings in most of their manufacturing operations.



ANNEXURE-R12

CONDITION ASSESSMENT STUDY OF CONCRETE STRUCTURES OF NTPC TANDA

FOR

NTPC TANDA, UTTAR PRADESH



REPORT OF CLARIFLOCATORS-1, 2 CDR/SP-6325 APRIL 2024

Centre for Construction Development and Research
NATIONAL COUNCIL FOR CEMENT AND BUILDING MATERIALS
Old Bombay Road, Near Raidurgh Police Station, Hyderabad-500104

	ad, Near Raidurgh Police Station	n, Hyderabad-500104
Prepared By A. Bharath	to disease	
Checked By Adarsh Kumar N.S	Lasel	
Approved By B S Rao	STERSE	4/27
Electronic File Ref: CDR-2/F:/Report/SP-6325	Report No. NCB/CDR/	No. of Pages/Appendices



1.0 INTRODUCTION

NTPC Tanda, Uttar Pradesh approached National Council for Cement and Building Materials (NCB). To carry out condition assessment study of Clariflocators-1, 2 using Non Destructive Evaluation Technique including preparation of Quantities (BOQ), Cost Estimation for repair and restoration at NTPC Tanda. NCB took up the work as per PO No: 4000269971-026-1035 Dated 31.12.2021

Scope of works

- a) To carry out condition assessment using Non Destructive Evaluation Technique including repair methodology, preparation of quantities (BOQ), Cost estimate of Clariflocators-1, 2 at NTPC Tanda, Uttar Pradesh.
- i) Visual observations of Clariflocators-1, 2: To collect data of distress on RCC members of Clariflocators shall be carried out up to safely accessible heights which were made accessible for testing. Visual observation data will be supplemented by photographs and other pertinent information wherever available.
- ii) To conduct experimental investigation by Non Destructive Testing technique on the selected representative RCC members at different locations of the Clariflocators-1,2
 - a. Quality assessment of selected RCC members using Rebound Hammer testing technique as per IS 516 (Part 5/Sec 4):2020
 - b. Quality assessment of selected RCC members using Ultrasonic Pulse Velocity testing technique as per IS: IS: 516 (Part V) 2019
 - c. Determination of equivalent cube compressive strength of concrete in RCC structure using concrete core extraction & testing technique as per IS: 456-2000 & IS: 516-1959.
 - d. Assessment of Carbonation depth of the extracted concrete cores.
 - e. Determine the corrosion status of reinforcement steel using Half-cell potential survey as per IS: 516 (PART 5, SECTION 2) 2021 on few selected safely accessible RCC Members.
 - f. Determination of concrete cover thickness in RCC members using Ferro scanning technique at identified & safely accessible location.



- g. Chemical Analysis to determine Chloride content, Sulphate content and pH value of Concrete Powder Samples in laboratory.
- iii) Analysis and interpretation of test results/data obtained in (i) & (ii) above.
- iv) Recommendations on remedial measures using indigenously available compatible repair materials. Preparation of BOQ covering selected items for repair including rate analysis & preparation of specifications and methodology for carrying out effective repair shall also be provided.
- v) The report covering (i) to (iv) above.

2.0 DATA PROVIDED BY SPONSOR

• Year of Construction of the subject structure was around 1990

3.0 INVESTIGATION CARRIED OUT BY NCB

To collect the data of distress on RCC members of Clariflocators at NTPC, TANDA, Uttar Pradesh, and Visual observation survey was carried out jointly by NCB team and the concerned NTPC officials during the visits for condition assessment from 06th September to 10th September 2022.

3.1 Rebound Hammer Testing (RHT) As Per IS 516 (Part 5/Sec 4):2020

Rebound hammer testing technique was used for assessing the likely surface compressive strength of concrete. Basic principle of rebound hammer test is given below.

When the plunger of rebound hammer is pressed against the surface of the concrete, the spring-controlled mass rebounds and the extent of such rebound depends upon the surface hardness of concrete. The surface hardness and therefore the rebound are taken to be related to the compressive strength of the concrete. The rebound is read off along a graduated scale and is designated as the rebound number or rebound index. It is also to be noted that rebound indices are indicative of compressive strength of concrete to a limited depth from the surface. If the concrete in a particular member has internal micro cracking, flaws or heterogeneity across the cross-section, rebound hammer indices will not indicate the same. IS: 516 (Part 5/Sec 4): 2020 states, "As such, the estimation of strength of concrete by rebound hammer method cannot be held to be very accurate and probable accuracy of prediction of concrete strength in a structure is ±25 percent." However, the test should only be used as indication of the probable compressive strength of concrete.



The test was carried out using a Schmidt's Rebound Hammer on randomly selected accessible Mill foundations at NTPC Tanda, Uttar Pradesh. The members which were tested were made accessible. So the testing done on accessible members represents other members also. The surfaces at the chosen locations were thoroughly cleaned with carborandum stone/grinding stone and readings were taken around each point. The average of the readings becomes the rebound index at that point of observation.

3.2 Ultrasonic Pulse Velocity (UPV) Method As per IS: 516 (Part V) – 2018.

UPV is a non-destructive evaluation method for assessing the quality of concrete; density, homogeneity and uniformity. Basic principle of UPV method is given below.

In this method, an ultrasonic pulse of longitudinal vibrations is produced by an electro-acoustical transducer which is held in contact with one surface of the concrete member under test. After traversing a known path length of the member, the pulse of vibrations is converted into an electric signal by a second electro-acoustical transducer, and an electric timing circuit enables the transit time of the pulse to be measured, from which the pulse velocity is calculated. For the present investigation, the pulse velocity measurements were obtained by direct transmission of ultrasonic pulses through the concrete, i.e. by "cross probing" & "Surface probing". For this purpose, the transducers were held on opposite faces of the beam and columns.

The Ultrasonic Pulse Velocity in concrete is mainly related to its density and modulus of elasticity. This in turn depends upon the materials and mix proportions used in making concrete as well as methods of placing, compaction and curing of concrete. If the concrete is not thoroughly compacted, or if there is segregation of concrete during placing or there are internal cracks or flaws, the pulse velocity will be lower, although the same materials and mix proportions are used.

The underlying principle of assessing the quality of concrete from UPV method is that, comparatively higher pulse velocities are obtained when the 'quality' of concrete in terms of density, homogeneity and uniformity is good. In case of concrete of poorer quality, lower velocities are obtained.

On this basis, guidelines have been evolved for characterizing the quality of concrete in structures in terms of ultrasonic pulse velocity. Such guideline reproduced from IS: 516 (Part V) – 2018.



3.3 Concrete Core Testing

Concrete cores of 60-mm diameter were extracted from different structural members identified, to estimate equivalent cube compressive strength of the structure. Equivalent cube strength does not indicate 28 days' standard cube strength rather it represents the in-situ cube strength, and is compared vis-à-vis strength used in design calculation with safety of the structure under load in mind.

There are a number of parameters, which influence the measured compressive strengths. Such parameters include size (diameter) of the specimen, length-to-diameter ratio, direction of drilling, method of capping, drilling operations, moisture conditions of cores at the time of testing etc. Many of these parameters have been standardized.

The second set of variables relates to the intrinsic difference that exists between the concrete in structure and in standard laboratory controlled specimens, the core specimens representing the former. Such intrinsic differences are due to inherent differences that may occur in mixing constituents, degree of compaction, extent of curing and temperature condition in two cases. The procedure for sampling, preparing, testing and calculating the equivalent compressive strength with corrections are given in **IS: 516-2018.**

The net effect of all these parameters is that the strength of concrete cores is in general lower than those of laboratory controlled specimens, for this reason **IS: 456-2000** (Code of Practice for Plain and Reinforced Concrete)consider that concrete in the area represented by a core test is adequate if" the average equivalent cube strength of the cores is equal to at least 85 percent of the specified for the corresponding age and if no single core has strength lower than 75 percent of the specified value".

3.4 Carbonation Test

Carbonation is the formation of calcium carbonate (CaCO₃) by chemical reactions in concrete. When CO₂penetrates into the hardened concrete, it reacts with portlandite [Portlandite is a mineral formed during the curing of concrete, calcium hydroxide Ca (OH)₂] in the presence of moisture forming CaCO₃. The rate of carbonation depends mainly on the relative humidity, the concentration of CO₂, the penetration pressure and the temperature of the environment where concrete is placed.

As carbon dioxide enters the concrete from the environment, it reacts with calcium hydroxide present in the concrete and depending upon the quality of concrete it reduces the



alkalinity of the pore fluids, depassivating ferric oxide layer on reinforcing bar which in turn initiates the process of corrosion in reinforcement.

To determine the depth of carbonation, concrete is exposed and sprayed with a pH indicator (solutions of 1%phenolphthalein in 70% ethyl alcohol). The demarcation between the region, which turns into magenta (dark pink colour) and the region showing no change in colour indicate the carbonation front.

Carbonation measurements were recorded immediately after the cores specified in col. 3.4 were extracted.

3.5 Half-Cell Potential (HCP) Measurements

This test method covers the estimation of electrical Half Cell Potential of uncoated reinforcing steel, to determine corrosion activity using reference electrode copper; copper sulphate half-cell. It is not possible to expose all the reinforcements in the structural element and observe the extent of corrosion. So, this method has been very convenient to assess the condition of the entire length of a member by exposing a portion of the reinforcement at a suitable location, which measures the half-cell potential on the entire length, by placing the reference electrode on the wet concrete surface.

The Half-Cell Potential measurement is based on the principal of the corrosion, being an electro-chemical process, induces certain voltage to the reinforcement steel that is corroding. The wetting of the concrete is required to make the portion between the concrete surface and the reinforcing bar as electrolytes.

A criterion for assessment for corrosion of steel is given as under IS: 516 (Part 5, Section 2)-2021 below.

- ➤ If potentials over an area are more positive than -200 mV, there is a greater than 90% probability that no reinforcing steel corrosion is occurring in that area at the time of measurement.
- ➤ If potentials over an area are in the range of -200 mV to -350 mV, corrosion activity of the reinforcing steel in that area is uncertain.
- ➤ If potentials over an area are more negative than -350 mV, there is a greater than 90% probability that reinforcing steel corrosion is occurring in that area at the time of measurement.



Adequate numbers of accessible RCC members were selected from various locations to conduct Half-Cell Potential test.

3.6 Concrete Cover Study

Concrete cover depth to reinforcing bars shall be done by using Ferro Scanner instrument on safe & accessible locations. This instrument detects the reinforcing bars and mesh, to measure their cover depth and determine the bar diameter. The instrument is based on the magnetic technique and is calibrated for different purposes. The cover depth is important from the point of view of estimation of initiation of corrosion of reinforcing bars.

For a longitudinal reinforcing bar in a Column nominal cover shall in any case not be less than 40mm or less than the diameter of such bar as per clause 26.4.2.1 of IS: 456-2000. Nominal cover to meet durability requirement for footing, minimum cover shall be 50mm as per clause 26.4.2.2 of IS: 456-2000.

Minimum values of nominal cover of normal weight aggregate concrete to be provided to all reinforcement including links to meet specified period of fire resistance shall be as per Table 16A of IS:456-2000.

Minimum values for the nominal cover of normal weight aggregate concrete which should be provided all reinforcement including links depending of exposure condition shall be as per the Table 5 of IS: 456-2000.

3.7 Chemical Analysis

Corrosion of reinforcing steel due to chlorides in concrete is one of the most common environmental attacks that lead to deterioration of concrete structures. Whenever there is chloride in concrete there is an increased risk of corrosion of embedded metal. Chloride content is then expressed in kg per cubic meter of concrete and compared with the values of limits of chloride contents of concrete (**Table 7 of IS: 456–2000**).

Sulphates (SO₃) are present in most cements and in some aggregates; excessive amounts of water-soluble sulphate from these or other mix constituents can cause expansion and disruption of concrete. To prevent it, **IS:** 456-2000 clause-8.2.5.3 states that the total water-soluble sulphate content of the concrete mix, expressed as SO₃, should not exceed 4 percent by mass of the cement in the mix. The sulphate content should be calculated as the total from the various constituents of the mix.



The pH value of the concrete should be above 11.5 to maintain alkalinity of concrete surrounding the embedded steel. A reduction in the pH value of concrete indicates loss of passive layer around the reinforcement which protects the steel from distress.

For analyzing Chloride content and pH of concrete, concrete powder samples were extracted from 0-25mm, 25-50mm depths at identified locations and then tested as per IS:14959(Part 2) -2001 (Determination of water soluble and acid soluble Chlorides in Mortar and Concrete – Method of Test).

Adequate numbers of accessible RCC members were selected from various locations to extract concrete powders for chemical test.

4.0 RESULTS AND DISCUSSION

4.1. Visual Observations

Visual observations and testing carried out at Different levels of Clariflocators. Distress was found in the form of cracks, Honeycombs and Seepage of Water through concrete surface. Colour deterioration, spalling of Concrete was noticed at few locations of Clariflocators. The visual observations and photographs are shown in Annexure I.

4.2. Rebound Hammer Testing:

Rebound Hammer testing was carried out on various identified RCC (Reinforced Cement Concrete) members of Clariflocators-1, 2 using random sampling technique the results of surface compressive strength obtained by Rebound Hammer testing are given in Table 2 to 17.

Surface Compressive strength results of concrete as obtained on different hardened concrete surfaces of RCC Members are summarized as:

- 1) Surface compressive strength of concrete obtained Clariflocator-1 East side wall by Rebound Hammer Testing is found with an average surface compressive strength of 31.75 N/mm² (Refer Table 2).
- 2) Surface compressive strength of concrete obtained on Clariflocator-1 West side wall by Rebound Hammer Testing is found with an average surface compressive strength of **34.80 N/mm**² (Refer Table 3).



- 3) Surface compressive strength of concrete obtained on Clariflocator-1 South side wall by Rebound Hammer Testing is found with an average surface compressive strength **34.16 N/mm²** (Refer Table 4).
- 4) Surface compressive strength of concrete obtained on Clariflocator-1 North side wall by Rebound Hammer Testing is found with an average surface compressive strength of 33.95 N/mm² (Refer Table 5).
- 5) Surface compressive strength of concrete obtained on Clariflocator-1 North East side wall by Rebound Hammer Testing is found with an average surface compressive strength of **36.07 N/mm²** (Refer Table 6).
- 6) Surface compressive strength of concrete obtained on Clariflocator-1 South West side wall by Rebound Hammer Testing is found with an average surface compressive strength of **33.66 N/mm**² (Refer Table 7).
- 7) Surface compressive strength of concrete obtained on Clariflocator-1 North West side wall by Rebound Hammer Testing is found with an average surface compressive strength of **31.97 N/mm²** (Refer Table 8).
- 8) Surface compressive strength of concrete obtained on Clariflocator-1 North West side wall by Rebound Hammer Testing is found with an average surface compressive strength of **35.64 N/mm²** (Refer Table 9).
- 9) Surface compressive strength of concrete obtained on Clariflocator-2 North side wall by Rebound Hammer Testing is found with an average surface compressive strength of 32.81 N/mm² (Refer Table 10).
- 10) Surface compressive strength of concrete obtained on Clariflocator-2 South side wall by Rebound Hammer Testing is found with an average surface compressive strength of 33.10 N/mm² (Refer Table 11).
- 11) Surface compressive strength of concrete obtained on Clariflocator-2 East side wall by Rebound Hammer Testing is found with an average surface compressive strength of 33.73 N/mm² (Refer Table 12).
- 12) Surface compressive strength of concrete obtained on Clariflocator-2 West side wall by Rebound Hammer Testing is found with an average surface compressive strength of 32.74 N/mm² (Refer Table 13).



- 13) Surface compressive strength of concrete obtained on Clariflocator-2 North East side wall by Rebound Hammer Testing is found with an average surface compressive strength of 33.03 N/mm² (Refer Table 14).
- 14) Surface compressive strength of concrete obtained on Clariflocator-2 South West side wall by Rebound Hammer Testing is found with an average surface compressive strength of **32.96 N/mm²** (Refer Table 15).
- 15) Surface compressive strength of concrete obtained on Clariflocator-2 North West side wall by Rebound Hammer Testing is found with an average surface compressive strength of 33.66 N/mm² (Refer Table 16).
- **16)** Surface compressive strength of concrete obtained on Clariflocator-2 North West side wall by Rebound Hammer Testing is found with an average surface compressive strength of **34.09** N/mm² (Refer Table 17).

4.3 Ultrasonic Pulse Velocity Testing (UPV):

The Ultrasonic Pulse Velocity testing was conducted on Clariflocators for #1, 2 in the presence of concerned engineering team of NTPC Tanda. The results of the UPV values obtained on various RCC members are as follows:

- 1) The UPV measurements were taken using Surface probing technique on the Clariflocator-1 East side wall are in the range of **3.77 to 4.6 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018(Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table -19).
- 2) The UPV measurements were taken using Cross probing technique on the Clariflocator-1 West side wall are in the range of 3.62 to 4.09 km/sec. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be GOOD (Table 20).
- 3) The UPV measurements were taken using Cross probing technique on the Clariflocator-1 South side wall are in the range of **3.64 to 4.27 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 21).
- 4) The UPV measurements were taken using Cross probing technique on the Clariflocator-1 North side wall are in the range of 3.58 to 4.13 km/sec. When these values are



- compared with the velocity criteria of IS: 516 (Part V) -2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 5) The UPV measurements were taken using Cross probing technique on the Clariflocator-1 North East side wall are in the range of **3.56 to 4.08 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 23).
- 6) The UPV measurements were taken using Surface probing technique on the Clariflocator-1 South West side wall are in the range of **3.54 to 3.98 km/sec**. When these values are compared with the velocity criteria of IS:516 (Part V)–2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 24).
- 7) The UPV measurements were taken using Surface probing technique on the Clariflocator-1 North West side wall are in the range of **3.55 to 3.98 km/sec**. When these values are compared with the velocity criteria of IS:516 (Part V)–2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 25).
- 8) The UPV measurements were taken using Surface probing technique on the Clariflocator-1 North West side wall are in the range of **3.51 to 3.88 km/sec**. When these values are compared with the velocity criteria of IS:516 (Part V)–2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 26).
- 9) The UPV measurements were taken using Surface probing technique on the Clariflocator-2 North side wall are in the range of **3.98 to 4.66km/sec**. When these values are compared with the velocity criteria of IS:516 (Part V)–2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 27).
- 10) The UPV measurements were taken using Cross probing technique on the Clariflocator-2 North side wall are in the range of **3.61 to 4.19 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 28).
- 11) The UPV measurements were taken using Cross probing technique on the Clariflocator-2 East side wall are in the range of **3.59 to 4.08 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 29).



- 12) The UPV measurements were taken using Cross probing technique on the Clariflocator-2 West side wall are in the range of **3.64 to 4.02 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 30).
- 13) The UPV measurements were taken using Cross probing technique on the Clariflocator-2 North East side wall are in the range of **3.73 to 4.08 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 31).
- 14) The UPV measurements were taken using Surface probing technique on the Clariflocator-2 South West side wall are in the range of **4.06 to 4.41 km/sec**. When these values are compared with the velocity criteria of IS:516 (Part V)–2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 32).
- 15) The UPV measurements were taken using Surface probing technique on the Clariflocator-2 North West side wall are in the range of **3.86 to 4.26 km/sec**. When these values are compared with the velocity criteria of IS:516 (Part V)–2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 33).
- 16) The UPV measurements were taken using Surface probing technique on the Clariflocator-2 North West side wall are in the range of **3.89 to 4.22 km/sec**. When these values are compared with the velocity criteria of IS: 516(Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 34).

4.4 Concrete Core Testing:

Corresponding to the 60mm concrete core extracted by random sampling technique covering different locations of Clariflocators- 1, 2 in power plant of NTPC Tanda and tested at NCCBM laboratory Hyderabad, the equivalent cube compressive strength of concrete RCC members are shown in Tables- 40, 41. In total, 28 nos. of concrete cores were extracted from different members of the Clariflocators all are found to be testable either due to short length of the cores.

The test results indicate that the equivalent cube compressive strength values for



Clariflocator-1

- 1. Clariflocator-1 East side wall is found to be 48.30 N/mm²
- 2. Clariflocator-1 West side wall is found to be 64.63 N/mm2
- 3. Clariflocator-1 South side wall is found to be 31.00 N/mm2
- 4. Clariflocator-1 North side wall is found to be 47.00 N/mm2
- 5. Clariflocator-1 North East side wall is found to be 33.41 N/mm2
- 6. Clariflocator-1 South West side wall is found to be 39.13 N/mm2
- 7. Clariflocator-1 North West side wall is found to be 33.26 N/mm2
- 8. Clariflocator-1 North West side wall is found to be 36.80 N/mm2

Clariflocator-2

- 1. Clariflocator-2 North side wall is found to be **35.49 N/mm2**
- 2. Clariflocator-2 South side wall is found to be 31.93 N/mm2
- 3. Clariflocator-2 East side wall is found to be 25.53 N/mm2
- 4. Clariflocator-2 West side wall is found to be 34.32 N/mm2
- 5. Clariflocator-2 North East side wall is found to be **37.92 N/mm2**
- 6. Clariflocator-2 South West side wall is found to be 35.34 N/mm2
- 7. Clariflocator-2 North West side wall is found to be **36.34 N/mm2**
- 8. Clariflocator-2 North West side wall is found to be 32.87 N/mm2

In total, 16 nos tested cores all of them found to have equivalent cube compressive strength more than specified characteristic compressive strength of M25 grade concrete (which is produced in Table- 40,41).

4.5 Concrete Cover:

The concrete cover depth to rebars in RCC members is measured with Ferro-scanner and a measuring tape/scale in the places where concrete is exposed and accessible for direct measurement. Nominal cover to reinforcement to meet durability requirement is given in **IS-456: Table 16-clause 26.4.2** (Also reproduced in Table-35), the measured cover to reinforcement steel in the selected RCC members are given in Table 36,37.

Clariflocator-1

1. The Concrete cover to Reinforcing bars of Clariflocator-1 East side wall during testing using Ferro scanner meter is found with an average of **50 mm**.



- 2. The Concrete cover to Reinforcing bars of Clariflocator-1 West side wall during testing using Ferro scanner meter is found with an average of **54 mm**.
- 3. The Concrete cover to Reinforcing bars of Clariflocator-1 South side wall during testing using Ferro scanner meter is found with an average of **57 mm**.
- 4. The Concrete cover to Reinforcing bars of Clariflocator-1 North side wall during testing using Ferro scanner meter is found with an average of **56 mm**.
- 5. The Concrete cover to Reinforcing bars of Clariflocator-1 North East side wall during testing using Ferro scanner meter is found with an average of **52 mm**.
- 6. The Concrete cover to Reinforcing bars of Clariflocator-1 South West side wall during testing using Ferro scanner meter is found with an average of **53 mm**.
- 7. The Concrete cover to Reinforcing bars of Clariflocator-1 North West side wall during testing using Ferro scanner meter is found with an average of **57 mm**.
- 8. The Concrete cover to Reinforcing bars of Clariflocator-1 North West side wall during testing using Ferro scanner meter is found with an average of **54 mm**.

Clariflocator-2

- 1. The Concrete cover to Reinforcing bars of Clariflocator-2 North side wall during testing using Ferro scanner meter is found with an average of **51 mm**.
- 2. The Concrete cover to Reinforcing bars of Clariflocator-2 South side wall during testing using Ferro scanner meter is found with an average of **52 mm**.
- 3. The Concrete cover to Reinforcing bars of Clariflocator-2 East side wall during testing using Ferro scanner meter is found with an average of **58 mm**.
- 4. The Concrete cover to Reinforcing bars of Clariflocator-2 West side wall during testing using Ferro scanner meter is found with an average of **57 mm**.
- 5. The Concrete cover to Reinforcing bars of Clariflocator-2 North East side wall during testing using Ferro scanner meter is found with an average of **52 mm**.
- 6. The Concrete cover to Reinforcing bars of Clariflocator-2 South West side wall during testing using Ferro scanner meter is found with an average of **55 mm**.
- 7. The Concrete cover to Reinforcing bars of Clariflocator-2 North West side wall during testing using Ferro scanner meter is found with an average of **54 mm**.
- 8. The Concrete cover to Reinforcing bars of Clariflocator-2 North West side wall during testing using Ferro scanner meter is found with an average of **55 mm**.



The Concrete cover within the specified limits to meet durability requirement as per IS: 456-2000 (Refer Table 16 of IS: 456-2000) which is Reproduced in Table 35.

4.6 Carbonation:

Table-38,39 shows test results of carbonation testing done on 16 nos. of Concrete Cores extracted from various representative concrete samples. The results indicate that the values of depth of carbonation in all different locations of Clariflocators-1, 2 are found to be **0-8**mm, on RCC members.

Based on the above carbonation study carried on different selected RCC members at several locations the carbonation depth is found to be within the concrete cover region.

4.7 Half-Cell Potential Test:

Half-cell potential (HCP) measurements using copper, copper-sulfate half-cell technique as per IS: 516 (Part 5, Section 2)-2021 (Standard test method for corrosion potentials of uncoated reinforcing steel in concrete) were taken at site to ascertain corrosion status of reinforcing bars of various locations of Clariflocators-1, 2 at NTPC TANDA. The measurements were done on different locations randomly selected locations and comprising of representative samples of for the structure.

Test results (refer Table- 43,44) when compared with the corrosion criteria as per ASTM C-876 (Table-42) indicate that probability of corrosion is found to be in "90% Possibility of no corrosion".

4.8 Chemical Analysis:

The chemical analysis of water and powdered samples extracted from different elements of Clariflocators-1, 2 collecting by random sampling technique. This covered chloride content, sulphate content per cum of concrete as well pH value of powdered samples. The test results as obtained in NCCBM laboratory are shown in Table- 45,46. Analysis of interpretation of test results given as under:

1) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-1 East side wall was found with an average value of **0.09 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3)



- content by mass of the cement in mix with an average value of **1.57%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.3** which is within the specified limit to resist the corrosion.
- 2) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-1 West side wall was found with an average value of **0.13 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.58%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.46** which is within the specified limit specified limit to resist the corrosion.
- 3) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-1 South side wall was found with an average value of **0.16 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.44%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.52** which is within the specified limit to resist the corrosion.
- 4) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-1 North side wall was found with an average value of **0.14 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.5%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.54** which is within the specified limit to resist the corrosion.
- 5) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-1 North East side wall was found with an average value of **0.18 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.5%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of



pH value is found with an average of 11.55 is within the specified limit to resist the corrosion.

- 6) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-2 North side wall was found with an average value of **0.13 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.62%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.35** which is within the specified limit to resist the corrosion.
- 7) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-2 South side wall was found with an average value of **0.15 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.58%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.48** which is within the specified limit to resist the corrosion.
- 8) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-2 East side wall was found with an average value of **0.16 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.44%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.57** is within the specified limit to resist the corrosion.
- 9) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-2 West side wall was found with an average value of **0.15 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.5%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.58** which is within the specified limit to resist the corrosion.
- 10) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-2 North East side wall was found with an average value of **0.17** kg/m³ is



within the permissible limit of 0.6 kg/m3 (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.47%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.57** which is within the specified limit to resist the corrosion.

5.0 Conclusions:

The following Conclusions can be broadly made from the testing results Clariflocators-,1,2:

- i) Based on visual observations carried out in the Clariflocators-,1,2 locations Distress was found in the form of cracks, Honey combs and Seepage of Water on concrete surface. Colour deterioration, Peeling of Concrete was developing at few locations.
- ii) Based on Rebound hammer test surface hardness and likely compressive strength found satisfactory and meeting the required limits as per data furnished by the client.
- iii) Based on Ultrasonic Pulse Velocity (random sampling technique) to find quality and homogeneity of concrete on RCC members, the results were found to be good quality of concrete.
- iv) The equivalent cube compressive strength of the core samples extracted from the Clariflocators-1, 2 is found meeting more than the required limit for M25 Grade of concrete.
- v) Carbonation is found 0-8mm after 30 years 'whereas concrete cover of RCC members is found to vary from 51 58 mm and found within the limits of concrete cover region.
- vi) Based on the Half-Cell potential measurements done by random sampling technique at various locations and visual observations of Clariflocators-1, 2 given an initiation signal of either in "90% Possibility of no corrosion".
- vii) The amount of Acid soluble chloride content and soluble sulphates in the concrete of Clariflocators-1, 2 is within the specified limits for all the samples and pH values for few of tested samples slightly less than 11.5 as per (IS: 456-2000& IS: 3025 -1984).



6.0 Recommendations

The following steps shall be taken to repair the cracks & strengthening of Clariflocators-1, 2:

i) Chipping:

Cover concrete around the horizontal, vertical cracks & spalling of concrete shall be chipped off to the depth up to 40mm on RCC walls. The chipping in the spalled portion of the Shells and RCC Walls shall be limited up to the cover region. Chipping of loose/hollow sounding concrete can be done by striking the doubtful surfaces with 2 lb. hammer.

ii) Treatment for Cracks:

- a. The cracks are to be widened by cutting V-grooves of 10mm x 10mm size and sealed with approved epoxy repair mortar.
- b. After the sealing, 12mm dia galvanized steel injection nipples are to be inserted in the crack area and also wherever honeycombing is found by drilling holes of required diameter up to the depth of 30 80 mm at required spacing (generally 350 mm staggered spacing). The drilled holes must be made dust free by blowing compressed air and should be sealed after the insertion of the nozzle with approved adhesive and allowed to cure.
- c. After the nipples are injected and cured, grouting in the proportion recommended by the manufacturer into the cracks/honeycombed area of concrete/masonry shall be done using suitable gun/pump at required pressure. Once the grouting work is finished, the extruding nipples can be cut-off after the curing period.

iii) Reinforcement Corrosion Treatment:

Wherever reinforcing rebar is found corroded in RCC walls

- a) Remove the rust by manually or suitable means to make corroded reinforcing bars rust free.
- b) Provide and apply corrosion protection using 2 coats of anticorrosive Zn rich epoxy phenolic rebar protection system of approved brand on the exposed old reinforcement by brush with interval of 24 hours between coats and corrosion protection of exposed old reinforcing bars.



c) Provide and apply concrete penetrating corrosion inhibitor (CPCI) of approved brand over the entire finished surface are obtained after removal of distressed concrete in 2 coats @ of 4m²/ltr/coat approximately.

iv) Bond Coat:

After chipping off the concrete cover, provide and apply structural grade two component epoxy bond coat prior to application of any type of mortar conforming to ASTM C - 881 -13 Type - II tested as per ASTM C -882-13 to ensure bond between old and new concrete by brush application. (Material manufacture from SYNORGANIC /BASF/SIKA/FOSRAC/KRISHNA Conchem/Pidilite or equivalent)

v) Making up lost section with Polymer Modified Mortar (PMM):

For repair of patches having, apply average 40mm PMM in 2-3 layers using SBR Latex conforming to ASTM C-1059-13 Type-I in damaged areas (1 Cement-3 part graded cleaned river sand + 20 % latex by weight of cement) with 0.35 w/c ratio, in 10-15 mm thick layers by applying bond coat between successive/each. (Material manufacture either from SYNORGANIC/BASF/SIKA/FOSRAC or equivalent)

vi) Protective coating:

Before applying the protective coating on RCC walls and the outer wall surface shall be cleaned by scrubbing with hard steel brush to remove loose particles, disintegrated concrete, deposited smoke and dust particles etc. The scrubbed surface is cleaned by air blowing and then dries it completely. Apply min. 2 coats of two part high performance moisture compatible corrosion resistant coating material (base and curing agent) of approved manufacturer over prepared surface, using not less than theoretical consumption as per the manufacturer's specification. Total dry film thickness (DFT) including primer will be 300 - 400 microns.



Note:

- 1. Before taking up any repair work, the dryness of substrate concrete must be ensured for effective application of several repair materials. Remove oil, grease, wax, Cement laitance, loose particles and other contaminants by shot blasting, scarifying or mechanically wire brushing followed by vacuum cleaning from the substrate concrete.
- 2. During repair works of Clariflocators-1,2 measures should be taken up in accordance with relevant safety standards and safety guidelines of Occupational safety & Health Administration (OSHA) for construction, arrangement like safety nets/platforms should be done.

•••••

ANNEXURE-R13

CONDITION ASSESSMENT STUDY OF CONCRETE STRUCTURES OF NTPC TANDA

FOR

NTPC TANDA, UTTAR PRADESH



FINAL REPORT OF MILL FOUNDATION CDR/SP-6325 FEBRUARY 2024

Centre for Construction Development and Research
NATIONAL COUNCIL FOR CEMENT AND BUILDING MATERIALS
Old Bombay Road, Near Raidurgh Police Station, Hyderabad-500104

Prepared By
A. Bharath
Adarsh Kumar N.S

Approved By
B S Rao

Report No. NCB/CDR/
No. of Pages/Appendices

CDR-2/F:/Report/SP-6325



1.0 INTRODUCTION

Scope of works

- a) To carry out condition assessment using Non Destructive Evaluation Technique including repair methodology, preparation of quantities (BOQ), Cost estimate of Mill foundations for units #1, 2, 3 & 4 at NTPC Tanda, Uttar Pradesh.
- i) Visual observations of Mill foundations for units #1, 2, 3 & 4: To collect data of distress on RCC members of Mill foundations shall be carried out up to safely accessible heights which were made accessible for testing. Visual observation data will be supplemented by photographs and other pertinent information wherever available.
- ii) To conduct experimental investigation by Non Destructive Testing technique on the selected representative RCC members at different locations of the RCC Mill foundations for units #1, 2, 3 & 4:
 - a. Quality assessment of selected RCC members using Rebound Hammer testing technique as per IS 516 (Part 5/Sec 4):2020
 - b. Quality assessment of selected RCC members using Ultrasonic Pulse Velocity testing technique as per IS: IS: 516 (Part V) 2019
 - c. Determination of equivalent cube compressive strength of concrete in RCC structure using concrete core extraction & testing technique as per IS: 456-2000 & IS: 516-1959.
 - d. Assessment of Carbonation depth of the extracted concrete cores.
 - e. Determine the corrosion status of reinforcement steel using Half-cell potential survey as per IS: 516 (PART 5, SECTION 2) 2021 on few selected safely accessible RCC Members.
 - f. Determination of concrete cover thickness in RCC members using Ferro scanning technique at identified & safely accessible location.
 - g. Chemical Analysis to determine Chloride content, Sulphate content and pH value of Concrete Powder Samples in laboratory.
- iii) Analysis and interpretation of test results/data obtained in (i) & (ii) above.



- iv) Recommendations on remedial measures using indigenously available compatible repair materials. Preparation of BOQ covering selected items for repair including rate analysis & preparation of specifications and methodology for carrying out effective repair shall also be provided.
- v) The report covering (i) to (iv) above.

2.0 DATA PROVIDED BY SPONSOR

• Year of Construction of the subject structure was around 1990

3.0 INVESTIGATION CARRIED OUT BY NCB

To collect the data of distress on RCC members of Mill foundations at NTPC, TANDA, Uttar Pradesh, and Visual observation survey was carried out jointly by NCB team and the concerned NTPC officials during the visits for condition assessment from 06th September to 09th September 2022.

3.1 Rebound Hammer Testing (RHT) As Per IS 516 (Part 5/Sec 4):2020

Rebound hammer testing technique was used for assessing the likely surface compressive strength of concrete. Basic principle of rebound hammer test is given below.

When the plunger of rebound hammer is pressed against the surface of the concrete, the spring-controlled mass rebounds and the extent of such rebound depends upon the surface hardness of concrete. The surface hardness and therefore the rebound are taken to be related to the compressive strength of the concrete. The rebound is read off along a graduated scale and is designated as the rebound number or rebound index. It is also to be noted that rebound indices are indicative of compressive strength of concrete to a limited depth from the surface. If the concrete in a particular member has internal micro cracking, flaws or heterogeneity across the cross-section, rebound hammer indices will not indicate the same. IS: 516 (Part 5/Sec 4): 2020 states, "As such, the estimation of strength of concrete by rebound hammer method cannot be held to be very accurate and probable accuracy of prediction of concrete strength in a structure is ±25 percent." However, the test should only be used as indication of the probable compressive strength of concrete.

The test was carried out using a Schmidt's Rebound Hammer on randomly selected accessible Mill foundations at NTPC Tanda, Uttar Pradesh. The members which were tested were made accessible. So the testing done on accessible members represents other members also.



The surfaces at the chosen locations were thoroughly cleaned with carborandum stone/grinding stone and readings were taken around each point. The average of the readings becomes the rebound index at that point of observation.

3.2 Ultrasonic Pulse Velocity (UPV) Method As per IS: 516 (Part V) – 2018.

UPV is a non-destructive evaluation method for assessing the quality of concrete; density, homogeneity and uniformity. Basic principle of UPV method is given below.

In this method, an ultrasonic pulse of longitudinal vibrations is produced by an electro-acoustical transducer which is held in contact with one surface of the concrete member under test. After traversing a known path length of the member, the pulse of vibrations is converted into an electric signal by a second electro-acoustical transducer, and an electric timing circuit enables the transit time of the pulse to be measured, from which the pulse velocity is calculated. For the present investigation, the pulse velocity measurements were obtained by direct transmission of ultrasonic pulses through the concrete, i.e. by "cross probing" & "Surface probing". For this purpose, the transducers were held on opposite faces of the beam and columns.

The Ultrasonic Pulse Velocity in concrete is mainly related to its density and modulus of elasticity. This in turn depends upon the materials and mix proportions used in making concrete as well as methods of placing, compaction and curing of concrete. If the concrete is not thoroughly compacted, or if there is segregation of concrete during placing or there are internal cracks or flaws, the pulse velocity will be lower, although the same materials and mix proportions are used.

The underlying principle of assessing the quality of concrete from UPV method is that, comparatively higher pulse velocities are obtained when the 'quality' of concrete in terms of density, homogeneity and uniformity is good. In case of concrete of poorer quality, lower velocities are obtained.

On this basis, guidelines have been evolved for characterizing the quality of concrete in structures in terms of ultrasonic pulse velocity. Such guideline reproduced from IS: 516 (Part V) – 2018.

3.3 Concrete Core Testing

Concrete cores of 60-mm diameter were extracted from different structural members identified, to estimate equivalent cube compressive strength of the structure. Equivalent cube strength does not indicate 28 days' standard cube strength rather it represents the in-situ cube



strength, and is compared vis-à-vis strength used in design calculation with safety of the structure under load in mind.

There are a number of parameters, which influence the measured compressive strengths. Such parameters include size (diameter) of the specimen, length-to-diameter ratio, direction of drilling, method of capping, drilling operations, moisture conditions of cores at the time of testing etc. Many of these parameters have been standardized.

The second set of variables relates to the intrinsic difference that exists between the concrete in structure and in standard laboratory controlled specimens, the core specimens representing the former. Such intrinsic differences are due to inherent differences that may occur in mixing constituents, degree of compaction, extent of curing and temperature condition in two cases. The procedure for sampling, preparing, testing and calculating the equivalent compressive strength with corrections are given in **IS: 516-2018.**

The net effect of all these parameters is that the strength of concrete cores is in general lower than those of laboratory controlled specimens, for this reason **IS: 456-2000** (Code of Practice for Plain and Reinforced Concrete)consider that concrete in the area represented by a core test is adequate if" the average equivalent cube strength of the cores is equal to at least 85 percent of the specified for the corresponding age and if no single core has strength lower than 75 percent of the specified value".

3.4 Carbonation Test

Carbonation is the formation of calcium carbonate (CaCO₃) by chemical reactions in concrete. When CO₂penetrates into the hardened concrete, it reacts with portlandite [Portlandite is a mineral formed during the curing of concrete, calcium hydroxide Ca (OH)₂] in the presence of moisture forming CaCO₃. The rate of carbonation depends mainly on the relative humidity, the concentration of CO₂, the penetration pressure and the temperature of the environment where concrete is placed.

As carbon dioxide enters the concrete from the environment, it reacts with calcium hydroxide present in the concrete and depending upon the quality of concrete it reduces the alkalinity of the pore fluids, depassivating ferric oxide layer on reinforcing bar which in turn initiates the process of corrosion in reinforcement.

To determine the depth of carbonation, concrete is exposed and sprayed with a pH indicator (solutions of 1%phenolphthalein in 70% ethyl alcohol). The demarcation between the



region, which turns into magenta (dark pink colour) and the region showing no change in colour indicate the carbonation front.

Carbonation measurements were recorded immediately after the cores specified in col. 3.4 were extracted.

3.5 Half-Cell Potential (HCP) Measurements

This test method covers the estimation of electrical Half Cell Potential of uncoated reinforcing steel, to determine corrosion activity using reference electrode copper; copper sulphate half-cell. It is not possible to expose all the reinforcements in the structural element and observe the extent of corrosion. So, this method has been very convenient to assess the condition of the entire length of a member by exposing a portion of the reinforcement at a suitable location, which measures the half-cell potential on the entire length, by placing the reference electrode on the wet concrete surface.

The Half-Cell Potential measurement is based on the principal of the corrosion, being an electro-chemical process, induces certain voltage to the reinforcement steel that is corroding. The wetting of the concrete is required to make the portion between the concrete surface and the reinforcing bar as electrolytes.

A criterion for assessment for corrosion of steel is given as under IS: 516 (Part 5, Section 2)-2021 below.

- ➤ If potentials over an area are more positive than -200 mV, there is a greater than 90% probability that no reinforcing steel corrosion is occurring in that area at the time of measurement.
- ➤ If potentials over an area are in the range of -200 mV to -350 mV, corrosion activity of the reinforcing steel in that area is uncertain.
- ➤ If potentials over an area are more negative than -350 mV, there is a greater than 90% probability that reinforcing steel corrosion is occurring in that area at the time of measurement.

Adequate numbers of accessible RCC members were selected from various locations to conduct Half-Cell Potential test.

3.6 Concrete Cover Study

Concrete cover depth to reinforcing bars shall be done by using Ferro Scanner instrument on safe & accessible locations. This instrument detects the reinforcing bars and mesh, to measure



their cover depth and determine the bar diameter. The instrument is based on the magnetic technique and is calibrated for different purposes. The cover depth is important from the point of view of estimation of initiation of corrosion of reinforcing bars.

For a longitudinal reinforcing bar in a Column nominal cover shall in any case not be less than 40mm or less than the diameter of such bar as per clause 26.4.2.1 of IS: 456-2000. Nominal cover to meet durability requirement for footing, minimum cover shall be 50mm as per clause 26.4.2.2 of IS: 456-2000.

Minimum values of nominal cover of normal weight aggregate concrete to be provided to all reinforcement including links to meet specified period of fire resistance shall be as per Table 16A of IS:456-2000.

Minimum values for the nominal cover of normal weight aggregate concrete which should be provided all reinforcement including links depending of exposure condition shall be as per the Table 5 of IS: 456-2000.

3.7 Chemical Analysis

Corrosion of reinforcing steel due to chlorides in concrete is one of the most common environmental attacks that lead to deterioration of concrete structures. Whenever there is chloride in concrete there is an increased risk of corrosion of embedded metal. Chloride content is then expressed in kg per cubic meter of concrete and compared with the values of limits of chloride contents of concrete (**Table 7 of IS: 456–2000**).

Sulphates (SO₃) are present in most cements and in some aggregates; excessive amounts of water-soluble sulphate from these or other mix constituents can cause expansion and disruption of concrete. To prevent it, **IS:** 456-2000 clause-8.2.5.3 states that the total water-soluble sulphate content of the concrete mix, expressed as SO₃, should not exceed 4 percent by mass of the cement in the mix. The sulphate content should be calculated as the total from the various constituents of the mix.

The pH value of the concrete should be above 11.5 to maintain alkalinity of concrete surrounding the embedded steel. A reduction in the pH value of concrete indicates loss of passive layer around the reinforcement which protects the steel from distress.

For analyzing Chloride content and pH of concrete, concrete powder samples were extracted from 0-20mm, 20-40mm & 40-60mm depths at identified locations and then tested as



per IS:14959(Part 2) -2001 (Determination of water soluble and acid soluble Chlorides in Mortar and Concrete – Method of Test).

Adequate numbers of accessible RCC members were selected from various locations to extract concrete powders for chemical test.

4.0 RESULTS AND DISCUSSION

4.1. Visual Observations

Visual observations and testing carried out at Different levels of Mill foundations. Minor distress was found in the form of cracks, Honey Combs and surface voids on concrete surface. Whitish color powdered deposition of salts and efflorescence was developing at few locations of Mill foundations. The visual observations and photographs are shown in Annexure I.

4.2. Rebound Hammer Testing

Rebound Hammer testing was carried out on various identified RCC (Reinforced Cement Concrete) members of Mill foundations for units #1, 2, 3 & 4using random sampling technique the results of surface compressive strength obtained by Rebound Hammer testing are given in Table 2 to 25.

Surface Compressive strength results of concrete as obtained on different hardened concrete surfaces of RCC Members are summarized as:

- 1) Surface compressive strength of concrete obtained Mill Foundation-1A by Rebound Hammer Testing is found with an average surface compressive strength of **28.22 N/mm²** (Refer Table 2).
- 2) Surface compressive strength of concrete obtained on Mill foundation-1B by Rebound Hammer Testing is found with an average surface compressive strength of **27.79 N/mm²** (Refer Table 3).
- 3) Surface compressive strength of concrete obtained on Mill foundation-1C by Rebound Hammer Testing is found with an average surface compressive strength 29.35 N/mm² (Refer Table 4).



- 4) Surface compressive strength of concrete obtained on Mill foundation-1D by Rebound Hammer Testing is found with an average surface compressive strength of 27.79 N/mm² (Refer Table 5).
- 5) Surface compressive strength of concrete obtained on Mill Foundation-1E by Rebound Hammer Testing is found with an average surface compressive strength of **27.08 N/mm²** (Refer Table 6).
- 6) Surface compressive strength of concrete obtained on Mill Foundation -1F by Rebound Hammer Testing is found with an average surface compressive strength of **28.07 N/mm²** (Refer Table 7).
- 7) Surface compressive strength of concrete obtained on Mill Foundation-1G by Rebound Hammer Testing is found with an average surface compressive strength of **27.79 N/mm²** (Refer Table 8).
- 8) Surface compressive strength of concrete obtained on Mill foundation-2A by Rebound Hammer Testing is found with an average surface compressive strength of **28.64** N/mm² (Refer Table 9).
- 9) Surface compressive strength of concrete obtained on Mill Foundation-2B by Rebound Hammer Testing is found with an average surface compressive strength of **28.85 N/mm²** (Refer Table 10).
- 10) Surface compressive strength of concrete obtained on Mill Foundation-2C by Rebound Hammer Testing is found with an average surface compressive strength of **31.97 N/mm²** (Refer Table 11).
- 11) Surface compressive strength of concrete obtained on Mill Foundation-2D by Rebound Hammer Testing is found with an average surface compressive strength of **30.69 N/mm²** (Refer Table 12).
- 12) Surface compressive strength of concrete obtained on Mill Foundation-2E by Rebound Hammer Testing is found with an average surface compressive strength of **31.19 N/mm²** (Refer Table 13).
- 13) Surface compressive strength of concrete obtained on Mill Foundation-2F by Rebound Hammer Testing is found with an average surface compressive strength of **32.60 N/mm²** (Refer Table 14).



- 14) Surface compressive strength of concrete obtained on Mill Foundation-2G by Rebound Hammer Testing is found with an average surface compressive strength of **32.74** N/mm² (Refer Table 15).
- 15) Surface compressive strength of concrete obtained on Mill Foundation-3A by Rebound Hammer Testing is found with an average surface compressive strength of **34.09 N/mm²** (Refer Table 16).
- 16) Surface compressive strength of concrete obtained on Mill Foundation-3B by Rebound Hammer Testing is found with an average surface compressive strength of 33.66 N/mm² (Refer Table 17).
- 17) Surface compressive strength of concrete obtained on Mill Foundation-3C by Rebound Hammer Testing is found with an average surface compressive strength of 33.66 N/mm² (Refer Table 18).
- **18)** Surface compressive strength of concrete obtained on Mill Foundation-3D by Rebound Hammer Testing is found with an average surface compressive strength of **33.80 N/mm²** (Refer Table 19).
- 19) Surface compressive strength of concrete obtained on Mill Foundation-3E by Rebound Hammer Testing is found with an average surface compressive strength of 32.74 N/mm² (Refer Table 20).
- **20)** Surface compressive strength of concrete obtained on Mill Foundation-3F by Rebound Hammer Testing is found with an average surface compressive strength of **32.32 N/mm²** (Refer Table 21).
- 21) Surface compressive strength of concrete obtained on Mill Foundation-3G by Rebound Hammer Testing is found with an average surface compressive strength of 33.24 N/mm² (Refer Table 22).
- 22) Surface compressive strength of concrete obtained on Mill Foundation-4A by Rebound Hammer Testing is found with an average surface compressive strength of 33.52 N/mm² (Refer Table 23).
- 23) Surface compressive strength of concrete obtained on Mill Foundation-4B by Rebound Hammer Testing is found with an average surface compressive strength of 33.38 N/mm² (Refer Table 24).



24) Surface compressive strength of concrete obtained on Mill Foundation-4C by Rebound Hammer Testing is found with an average surface compressive strength of 36.56 N/mm² (Refer Table 25).

4.3 Ultrasonic Pulse Velocity Testing (UPV):

The Ultrasonic Pulse Velocity testing was conducted on Mill foundations for units #1, 2, 3 & 4 in the presence of concerned engineering team of NTPC Tanda. The results of the UPV values obtained on various RCC members are as follows:

- 1) The UPV measurements were taken using Surface probing technique on the Mill Foundation -1A are in the range of **3.55 to 4.02km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018(Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table -27).
- 2) The UPV measurements were taken using Surface probing technique on the Mill Foundation -1Bare in the range of **3.54 to 4.09 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 28).
- 3) The UPV measurements were taken using Surface probing technique on the Mill Foundation -1 Care in the range of 3.58 to 4.10 km/sec. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be GOOD (Table 29).
- 4) The UPV measurements were taken using Cross probing technique on the Mill Foundation -1Dare in the range of **3.80 to 4.60 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 30).
- 5) The UPV measurements were taken using Cross probing technique on the Mill Foundation -1Eare in the range of **3.99 to 4.88 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 31).



- 6) The UPV measurements were taken using Cross probing technique on the Mill Foundation -1 Fare in the range of **4.21 to 4.86 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 32).
- 7) The UPV measurements were taken using Surface probing technique on the Mill Foundation -1 Gare in the range of **3.71 to 4.62 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 33).
- 8) The UPV measurements were taken using Surface probing technique on the Mill Foundation -2Aare in the range of **3.86 to 4.32 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 34).
- 9) The UPV measurements were taken using Surface probing technique on the Mill Foundation -2Bare in the range of **3.84 to 4.33 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 35).
- 10) The UPV measurements were taken using Surface probing technique on the Mill Foundation -2Care in the range of 3.75 to 4.23 km/sec. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be GOOD (Table 36).
- 11) The UPV measurements were taken using Cross probing technique on the Mill Foundation -2Dare in the range of **3.93 to 4.47 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 37).
- 12) The UPV measurements were taken using Cross probing technique on the Mill Foundation -2Eare in the range of **3.91 to 4.49 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 38).
- 13) The UPV measurements were taken using Surface probing technique on the Mill Foundation -2Fare in the range of 3.75 to 4.44 km/sec. When these values are compared



- with the velocity criteria of IS: 516 (Part V) -2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 39).
- 14) The UPV measurements were taken using Surface probing technique on the Mill Foundation -2Gare in the range of **3.62 to 4.48 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 40).
- 15) The UPV measurements were taken using Surface probing technique on the Mill Foundation -3Aare in the range of **3.75 to 4.22 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 41).
- 16) The UPV measurements were taken using Surface probing technique on the Mill Foundation -3Bare in the range of **3.86 to 4.67 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 42).
- 17) The UPV measurements were taken using Surface probing technique on the Mill Foundation -3Care in the range of **3.68 to 4.25 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 43).
- 18) The UPV measurements were taken using Cross probing technique on the Mill Foundation -3Dare in the range of **3.94 to 4.58 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 44).
- 19) The UPV measurements were taken using Cross probing technique on the Mill Foundation -3Eare in the range of **3.56 to 4.58 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 45).
- 20) The UPV measurements were taken using Cross probing technique on the Mill Foundation -3Fare in the range of **3.96 to 4.53 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 46).



- 21) The UPV measurements were taken using Surface probing technique on the Mill Foundation -3Gare in the range of **3.74 to 4.04 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 47).
- 22) The UPV measurements were taken using Surface probing technique on the Mill Foundation -4Aare in the range of **3.67 to 4.08 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 48).
- 23) The UPV measurements were taken using Surface probing technique on the Mill Foundation -4Bare in the range of **3.69 to 4.18 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 49).
- 24) The UPV measurements were taken using Cross probing technique on the Mill Foundation -4Care in the range of **3.51 to 3.91 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 50).

4.4 Concrete Core Testing

Corresponding to the 60mm concrete core extracted by random sampling technique covering different locations of Mill foundations for units #1, 2, 3 & 4in power plant of NTPC Tanda and tested at NCCBM laboratory Hyderabad, the equivalent cube compressive strength of concrete RCC members are shown in Table 54. In total, 28 nos. of concrete cores were extracted from different members of the Mill foundations all are found to be testable either due to short length of the cores.

The test results indicate that the equivalent cube compressive strength values for

- 1. Mill Foundation -1A is found to be 30.01 N/mm²
- 2. Mill Foundation -1B is found to be 16.85N/mm2
- 3. Mill Foundation -1C is found to be 20.28 N/mm2
- 4. Mill Foundation -1D is found to be 16.51N/mm2
- 5. Mill Foundation -1E is found to be 13.22N/mm2
- 6. Mill Foundation-1Fis found to be 29.93N/mm2



- 7. Mill Foundation -1Gis found to be 26.40N/mm2
- 8. Mill Foundation -2Ais found to be 46.19N/mm2
- 9. Mill Foundation -2Bis found to be 32.42N/mm2
- 10. Mill Foundation -2Cis found to be 24.12N/mm2
- 11. Mill Foundation -2Dis found to be 24.70N/mm2
- 12. Mill Foundation -2Eis found to be 27.19N/mm2
- 13. Mill Foundation -2F is found to be 30.81N/mm2
- 14. Mill Foundation -2Gis found to be 25.62N/mm2
- 15. Mill Foundation -3A is found to be 33.13N/mm2
- 16. Mill Foundation -3Bis found to be 19.85N/mm2
- 17. Mill Foundation -3C is found to be 18.50 N/mm2
- 18. Mill Foundation -3D is found to be 39.35N/mm2
- 19. Mill Foundation -3E is found to be29.18N/mm2
- 20. Mill Foundation -3F is found to be 22.77N/mm2
- 21. Mill Foundation -3G is found to be 28.18N/mm2
- 22. Mill Foundation -4A is found to be 28.95N/mm2
- 23. Mill Foundation -4B is found to be 22.59N/mm2
- 24. Mill Foundation -4C is found to be 28.20 N/mm2
- 25. Mill Foundation -4D is found to be35.40N/mm2
- 26. Mill Foundation -4E is found to be 34.66N/mm2
- 27. Mill Foundation -4F is found to be35.19N/mm2
- 28. Mill Foundation -4G is found to be38.85N/mm2

In total, 28 nos. tested cores 25 of them found to have equivalent cube compressive strength more than specified characteristic compressive strength of M25 grade concrete (which is produced in Table 54).

4.5 Concrete Cover

The concrete cover depth to rebars in RCC members is measured with Ferro-scanner and a measuring tape/scale in the places where concrete is exposed and accessible for direct measurement. Nominal cover to reinforcement to meet durability requirement is given in **IS-456**:



Table 16-clause 26.4.2 (Also reproduced in Table-51), the measured cover to reinforcement steel in the selected RCC members are given in Table 52.

- 1. The Concrete cover to Reinforcing bars of Mill Foundation -1Aduring testing using Ferro scanner meter is found with an average of **62 mm**.
- 2. The Concrete cover to Reinforcing bars of Mill Foundation -1Bduring testing using Ferro scanner meter is found with an average of **48 mm**.
- 3. The Concrete cover to Reinforcing bars of Mill Foundation -1Cduring testing using Ferro scanner meter is found with an average of **57 mm**.
- 4. The Concrete cover to Reinforcing bars of Mill Foundation -1Dduring testing using Ferro scanner meter is found with an average of **51 mm**.
- 5. The Concrete cover to Reinforcing bars of Mill Foundation -1Eduring testing using Ferro scanner meter is found with an average of **62 mm**.
- 6. The Concrete cover to Reinforcing bars of Mill Foundation -1Fduring testing using Ferro scanner meter is found with an average of **72 mm**.
- 7. The Concrete cover to Reinforcing bars of Mill Foundation -1Gduring testing using Ferro scanner meter is found with an average of **74 mm**.
- 8. The Concrete cover to Reinforcing bars of Mill Foundation -2Aduring testing using Ferro scanner meter is found with an average of **65 mm**.
- 9. The Concrete cover to Reinforcing bars of Mill Foundation -2Bduring testing using Ferro scanner meter is found with an average of **65 mm**.
- 10. The Concrete cover to Reinforcing bars of Mill Foundation -2Cduring testing using Ferro scanner meter is found with an average of **69 mm**.
- 11. The Concrete cover to Reinforcing bars of Mill Foundation -2Dduring testing using Ferro scanner meter is found with an average of **66 mm**.
- 12. The Concrete cover to Reinforcing bars of Mill Foundation -2Eduring testing using Ferro scanner meter is found with an average of **70 mm**.
- 13. The Concrete cover to Reinforcing bars of Mill Foundation -2Fduring testing using Ferro scanner meter is found with an average of **71 mm**.
- 14. The Concrete cover to Reinforcing bars of Mill Foundation -2Gduring testing using Ferro scanner meter is found with an average of **70 mm**.



- 15. The Concrete cover to Reinforcing bars of Mill Foundation -3Aduring testing using Ferro scanner meter is found with an average of **62 mm**.
- 16. The Concrete cover to Reinforcing bars of Mill Foundation -3B during testing using Ferro scanner meter is found with an average of **75 mm**.
- 17. The Concrete cover to Reinforcing bars of Mill Foundation -3C during testing using Ferro scanner meter is found with an average of **69 mm**.
- 18. The Concrete cover to Reinforcing bars of Mill Foundation -3D during testing using Ferro scanner meter is found with an average of 77 mm.
- 19. The Concrete cover to Reinforcing bars of Mill Foundation -3E during testing using Ferro scanner meter is found with an average of **68 mm**.
- 20. The Concrete cover to Reinforcing bars of Mill Foundation -3F during testing using Ferro scanner meter is found with an average of **69 mm**.
- 21. The Concrete cover to Reinforcing bars of Mill Foundation -3G during testing using Ferro scanner meter is found with an average of **77 mm**.
- 22. The Concrete cover to Reinforcing bars of Mill Foundation -4A during testing using Ferro scanner meter is found with an average of **67 mm**.
- 23. The Concrete cover to Reinforcing bars of Mill Foundation -4B during testing using Ferro scanner meter is found with an average of **74 mm**.
- 24. The Concrete cover to Reinforcing bars of Mill Foundation -4C during testing using Ferro scanner meter is found with an average of **67 mm**.
- 25. The Concrete cover to Reinforcing bars of Mill Foundation -4D during testing using Ferro scanner meter is found with an average of **73 mm**.
- 26. The Concrete cover to Reinforcing bars of Mill Foundation -4E during testing using Ferro scanner meter is found with an average of **69 mm**.
- 27. The Concrete cover to Reinforcing bars of Mill Foundation -4F during testing using Ferro scanner meter is found with an average of **67 mm**.
- 28. The Concrete cover to Reinforcing bars of Mill Foundation -4G during testing using Ferro scanner meter is found with an average of **69 mm**.

The Concrete cover within the specified limits to meet durability requirement as per IS: 456-2000 (Refer Table 16 of IS: 456-2000) which is Reproduced in Table 51.



4.6 Carbonation

Table-53shows test results of carbonation testing done on 28 nos. of Concrete Cores extracted from various representative concrete samples. The results indicate that the values of depth of carbonation in all different locations of Mill foundation for the unit's #1, 2, 3 & 4 are found to be **0-16**mm, on RCC members.

Based on the above carbonation study carried on different selected RCC members at several locations the carbonation depth is found to be within the concrete cover region.

4.7 Half-Cell Potential Test

Half-cell potential (HCP) measurements using copper, copper-sulfate half-cell technique as per IS: 516 (Part 5, Section 2)-2021 (Standard test method for corrosion potentials of uncoated reinforcing steel in concrete) were taken at site to ascertain corrosion status of reinforcing bars of various locations of Mill foundation for the unit's #1, 2, 3 & 4 at NTPC TANDA. The measurements were done on different locations randomly selected locations and comprising of representative samples of for the structure.

Test results (refer Table-56) when compared with the corrosion criteria as per ASTM C-876 (Table-55) indicate that probability of corrosion is found to be in "90% Possibility of no corrosion" & "Transit state of corrosion".

4.8 Chemical Analysis

The chemical analysis of water and powdered samples extracted from different elements of Mill foundation for the unit's #1, 2, 3 & 4 collecting by random sampling technique. This covered chloride content, sulphate content per cum of concrete as well pH value of powdered samples. The test results as obtained in NCCBM laboratory are shown in Table- 57. Analysis of interpretation of test results given as under:

1) Based on the results obtained from laboratory the range of chloride content in the Mill foundation Unit-1A was found with an average value of **0.35 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.38%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.65** which is slightly more than the specified limit to resist the corrosion.



- 2) Based on the results obtained from laboratory the range of chloride content in the Mill foundation Unit-1C was found with an average value of **0.28 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **2.22%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.5** which is slightly more than the specified limit to resist the corrosion.
- 3) Based on the results obtained from laboratory the range of chloride content in the Mill foundation Unit-1E was found with an average value of **0.32 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **2.2%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.46** which is slightly less than the specified limit to resist the corrosion.
- 4) Based on the results obtained from laboratory the range of chloride content in the Mill foundation Unit-1G was found with an average value of **0.22 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.62%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.60** which is slightly less than the specified limit to resist the corrosion.
- 5) Based on the results obtained from laboratory the range of chloride content in the Mill foundation Unit-2B was found with an average value of **0.31 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.44%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.64**which is slightly less than the specified limit to resist the corrosion.
- 6) Based on the results obtained from laboratory the range of chloride content in the Mill foundation Unit-2D was found with an average value of **0.16 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.88%** which is within the permissible



limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.65**which is slightly less than the specified limit to resist the corrosion.

- 7) Based on the results obtained from laboratory the range of chloride content in the Mill foundation Unit-2F was found with an average value of **0.26 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.7%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.7**which is slightly less than the specified limit to resist the corrosion.
- 8) Based on the results obtained from laboratory the range of chloride content in the Mill foundation Unit-3A was found with an average value of **0.21 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **2.7%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.2**which is slightly less than the specified limit to resist the corrosion.
- 9) Based on the results obtained from laboratory the range of chloride content in the Mill foundation Unit-3C was found with an average value of **0.49 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.88%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.3**which is slightly less than the specified limit to resist the corrosion.
- 10) Based on the results obtained from laboratory the range of chloride content in the Mill foundation Unit-3G was found with an average value of **0.08 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **2.54%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.63** which is slightly less than the specified limit to resist the corrosion.



- 11) Based on the results obtained from laboratory the range of chloride content in the Mill foundation Unit-4B was found with an average value of **0.13 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **3.0%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.58**which is slightly less than the specified limit to resist the corrosion.
- 12) Based on the results obtained from laboratory the range of chloride content in the Mill foundation Unit-4D was found with an average value of **0.17 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **3.02%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.45**which is slightly less than the specified limit to resist the corrosion.

5.0 Conclusions:

The following Conclusions can be broadly made from the testing results Mill foundation for the unit's #1, 2, 3 & 4:

- i) Based on visual observations carried out in the Mill foundations, Minor distress was found in the form of cracks, Honey Comb and surface voids on concrete surface. Whitish color powdered deposition of salts and efflorescence was developing at few locations.
- ii) Based on Rebound hammer test surface hardness and likely compressive strength found satisfactory and meeting the required limits as per data furnished by the client.
- iii) Based on Ultrasonic Pulse Velocity (random sampling technique) to find quality and homogeneity of concrete on RCC members, the results were found to be good quality of concrete.
- iv) The equivalent cube compressive strength of the core samples extracted from the Mill foundation for the unit's #1, 2, 3 & 4 is found meeting more than the required limit for M25 Grade of concrete.



- v) Carbonation is found 0-16 mm after 30 years 'whereas concrete cover of RCC members is found to vary from 48 77 mm and found within the limits of concrete cover region.
- vi) Based on the Half-Cell potential measurements done by random sampling technique at various locations and visual observations of Mill foundation for the unit's #1, 2, 3 & 4 given an initiation signal of either in "90% Possibility of no corrosion "&" Transit state of corrosion".
- vii) The amount of Acid soluble chloride content and soluble sulphates in the concrete of Mill foundation for the unit's #1, 2, 3 & 4 is within the specified limits for all the samples and pH values for few of tested samples slightly less than 11.5 as per (IS: 456-2000& IS: 3025-1984).

6.0 Recommendations

The following steps shall be taken to repair the cracks & strengthening of Mill foundations:

i) Chipping:

Cover concrete around the horizontal, vertical cracks & spalling of concrete shall be chipped off to the depth up to 40mm on RCC walls. The chipping in the spalled portion of the Shells and RCC Walls shall be limited up to the cover region. Chipping of loose/hollow sounding concrete can be done by striking the doubtful surfaces with 2 lb. hammer.

ii) Treatment for Cracks:

- a. The cracks are to be widened by cutting V-grooves of 10mm x 10mm size and sealed with approved epoxy repair mortar.
- b. After the sealing, 12mm dia galvanized steel injection nipples are to be inserted in the crack area and also wherever honeycombing is found by drilling holes of required diameter up to the depth of 30 80 mm at required spacing (generally 350 mm staggered spacing). The drilled holes must be made dust free by blowing compressed air and should be sealed after the insertion of the nozzle with approved adhesive and allowed to cure.



c. After the nipples are injected and cured, grouting in the proportion recommended by the manufacturer into the cracks/honeycombed area of concrete/masonry shall be done using suitable gun/pump at required pressure. Once the grouting work is finished, the extruding nipples can be cut-off after the curing period.

iii) Reinforcement Corrosion Treatment:

Wherever reinforcing rebar is found corroded in RCC walls

- a) Remove the rust by manually or suitable means to make corroded reinforcing bars rust free.
- b) Provide and apply corrosion protection using 2 coats of anticorrosive Zn rich epoxy phenolic rebar protection system of approved brand on the exposed old reinforcement by brush with interval of 24 hours between coats and corrosion protection of exposed old reinforcing bars.
- c) Provide and apply concrete penetrating corrosion inhibitor (CPCI) of approved brand over the entire finished surface are obtained after removal of distressed concrete in 2 coats @ of 4m²/ltr/coat approximately.

iv) Bond Coat:

After chipping off the concrete cover, provide and apply structural grade two component epoxy bond coat prior to application of any type of mortar conforming to ASTM C - 881 -13 Type - II tested as per ASTM C -882-13 to ensure bond between old and new concrete by brush application. (Material manufacture from STP/BASF/SIKA/FOSRAC/KRISHNA Conchem/Pidilite or equivalent)

v) Making up lost section with Polymer Modified Mortar (PMM):

For repair of patches having, apply average 40mm PMM in 2-3 layers using SBR Latex conforming to ASTM C-1059-13 Type-I in damaged areas (1 Cement-3 part graded cleaned river sand + 20 % latex by weight of cement) with 0.35 w/c ratio, in 10-15 mm thick layers by applying bond coat between successive/each. (Material manufacture either from STP/BASF/SIKA/FOSRAC or equivalent)

vi) Fiber Wrapping (Single layer):

Strengthening structural elements with single layer of nonmetallic composite fiber wrapping system (TYFO Fiber wrap of M/s FYFE & Co., GOLD BOND 1893 of M/s



Krishna Conchem Products Pvt. Ltd OR EQUIVALENT) comprise of two layers of unidirectional E -glass fiber wrap (900 GSM) and compatible epoxy saturant, by wet layup system including,

Surface preparation: Grinding/ moulding concrete substrate, cleaning it with wire brush removing oil, laitance if present, rounding sharp edges to min 25 mm radius etc. complete.

Profiling: Applying compatible primer on prepared substrate, Filling the holes and uneven surface with thixotropic putty etc. complete Wrapping:

Wrapping: The fiber sheet to structural element at desired orientation using tamping roller to avoid any air voids etc. repeat the same procedure for multiple layer with the interval of 8 hrs.

Sand pasting: Applying second coat of saturant after min. 12 hrs., rectify air voids if any paste the river sand on it to make surface rough to take further finishes and plastering the surface after complete curing using 10 mm thick PMM (PMM to be paid extra), to give uniform finish. All complete as per direction of Engineer-In-Charge.

vi) Protective coating:

Before applying the protective coating on RCC walls and the outer wall surface shall be cleaned by scrubbing with hard steel brush to remove loose particles, disintegrated concrete, deposited smoke and dust particles etc. The scrubbed surface is cleaned by air blowing and then dries it completely. Apply min. 2 coats of two part high performance moisture compatible corrosion resistant coating material (base and curing agent) of approved manufacturer over prepared surface, using not less than theoretical consumption as per the manufacturer's specification. Total dry film thickness (DFT) including primer will be 300 - 400 microns.



Note:

- 1. Before taking up any repair work, the dryness of substrate concrete must be ensured for effective application of several repair materials. Remove oil, grease, wax, Cement laitance, loose particles and other contaminants by shot blasting, scarifying or mechanically wire brushing followed by vacuum cleaning from the substrate concrete.
- 2. During repair works of Mill foundations measures should be taken up in accordance with relevant safety standards and safety guidelines of Occupational safety & Health Administration (OSHA) for construction, arrangement like safety nets/platforms should be done.

• • • • • • • •

CONDITION ASSESSMENT STUDY OF CONCRETE STRUCTURES OF NTPC TANDA

FOR

NTPC TANDA, UTTAR PRADESH



REPORT OF TG UNIT#1 CDR/SP-6325 APRIL 2024

Centre for Construction Development and Research
NATIONALCOUNCILFORCEMENTANDBUILDINGMATERIALS
Old Bombay Road, Near Raidurgh Police Station, Hyderabad-500104

Duananad Du	Old Bolliony 110m	. 1	,	
Prepared By	A. Bharath	for dasse		
Checked By	Adarsh Kumar N.S	charel		
ApprovedBy	BSRao	8x 10/4/24		
ElectronicFileRef: CDR/F:/Report/SP-6325		Report No. NCB/CDR/	No. of Pages/Appendices	



1.0 INTRODUCTION

NTPC Tanda, Uttar Pradesh approached National Council for Cement and Building Materials (NCB). To carry out condition assessment study of Turbine Generator (TG) unit#1 using Non Destructive Evaluation Technique including preparation of Quantities (BOQ), Cost Estimation for repair and restoration at NTPC Tanda. NCB took up the work as per PO No: 4000269971-026-1035 Dated 31.12.2021

Scope of works

- a) To carry out condition assessment using Non-Destructive Evaluation Technique including Repair Methodology, preparation of Quantities (BOQ), Cost Estimate of Turbine Generator (TG) unit#1 at NTPC Tanda.
- i) Visual observations of Turbine Generator (TG) unit#1: In this study visual observation indicating any sign of distress in members shall be carried out up to safely accessible heights. Visual observation data will be supplemented by photographs and other pertinent information wherever available.
- ii) To conduct experimental investigation by Non-Destructive Testing technique on the selected representative members of each cell at different locations of the TG Unit#1:
 - a. Quality assessment of selected members using Rebound Hammer testing technique as per IS: 516-2020 (Part-V, Sec-IV).
 - b. Quality assessment of selected members using Ultrasonic Pulse Velocity testing technique as per IS: IS: 516 (Part V) -2018
 - c. Determination of equivalent cube compressive strength of concrete in structure using concrete core extraction & testing technique as per IS: 456-2000 & IS: 516-2018.
 - d. Assessment of Carbonation depth of the extracted concrete cores.
 - e. Determine the corrosion status of reinforcement steel using Half-cell potential survey as per ASTM C876 on few selected safely accessible Members.
 - f. Determination of concrete cover thickness in members using Ferro scanning technique at identified & safely accessible location.

CONDITION ASSESSMENT STUDY OF CONCRETE STRUCTURES OF NTPC TANDA

FOR

NTPC TANDA, UTTAR PRADESH



FINAL REPORT OF CHIMNEY UNIT#1&2 CDR/SP-6325 MARCH 2024

Centre for Construction Development and Research
NATIONAL COUNCIL FOR CEMENT AND BUILDING MATERIALS
Old Bombay Road, Near Raidurgh Police Station, Hyderabad-500104

Old Bombay Road Prepared By A. Bharath	I, Near Raidurgh Police Station, Hyderabad-500104		
Checked By Adarsh Kumar N.S			
Approved By B S Rao	9	SY: 06/83/24.	
Electronic File Ref: CDR-2/F:/Report/SP-6325	Report No. NCB/CDR/	No. of Pages/Appendices	



1.0 INTRODUCTION

NTPC Tanda, Uttar Pradesh approached National Council for Cement and Building Materials (NCB). To carry out condition assessment study of RCC Chimney unit#1&2 using Non Destructive Evaluation Technique including preparation of Quantities (BOQ), Cost Estimation for repair and restoration of RCC Chimney Unit#1&2 at NTPC Tanda. The structures were constructed around the year 1995. NCB took up the work as per PO No: 4000245388-026-1026 Dated 24.9.2020

Scope of works

- a) To carry out condition assessment using Non-Destructive Evaluation Technique including Repair Methodology, preparation of Quantities (BOQ), Cost Estimate of RCC Chimney Unit#1&2 at NTPC Tanda, Uttar Pradesh
- i) Visual observations of RCC chimney Unit#1&2: In this study visual observation indicating any sign of distress in RCC members shall be carried out up to safely accessible heights. Visual observation data will be supplemented by photographs and other pertinent information wherever available.
- ii) To conduct experimental investigation by Non-Destructive Testing technique on the selected representative RCC members of each cell at different locations of the RCC Chimney:
 - a. Quality assessment of selected RCC members using Rebound Hammer testing technique as per IS: 516 (Part V, Sec-IV) 2020.
 - b. Quality assessment of selected RCC members using Ultrasonic Pulse Velocity testing technique as per IS: IS: 516 (Part V, Sec-I) 2018
 - c. Determination of equivalent cube compressive strength of concrete in RCC structure using concrete core extraction & testing technique as per IS: 456-2000 & IS: 516-2018.
 - d. Assessment of Carbonation depth of the extracted concrete cores.
 - e. Determine the corrosion status of reinforcement steel using Half-cell potential survey as per ASTM C876 on few selected safely accessible RCC Members.
 - f. Determination of concrete cover thickness in RCC members using Ferro scanning technique at identified & safely accessible location.

CONDITION ASSESSMENT STUDY OF CONCRETE STRUCTURES OF NTPC TANDA

FOR

NTPC TANDA, UTTAR PRADESH



REPORT OF CLARIFLOCATORS-1, 2 CDR/SP-6325 APRIL 2024

Centre for Construction Development and Research
NATIONAL COUNCIL FOR CEMENT AND BUILDING MATERIALS
Old Bombay Road, Near Raidurgh Police Station, Hyderabad-500104

	Olu Dollibay K	oau, Mear Kaluurgii Folice Statio	a, Hyderabad-500104
Prepared By	A. Bharath	for Laxah	
Checked By	Adarsh Kumar N.S	Larel	
Approved By	B S Rao	SY- 25/24/24	
Electronic File Ref: CDR-2/F:/Report/SP-6325		Report No. NCB/CDR/	No. of Pages/Appendices



1.0 INTRODUCTION

NTPC Tanda, Uttar Pradesh approached National Council for Cement and Building Materials (NCB). To carry out condition assessment study of Clariflocators-1, 2 using Non Destructive Evaluation Technique including preparation of Quantities (BOQ), Cost Estimation for repair and restoration at NTPC Tanda. NCB took up the work as per PO No: 4000269971-026-1035 Dated 31.12.2021

Scope of works

- a) To carry out condition assessment using Non Destructive Evaluation Technique including repair methodology, preparation of quantities (BOQ), Cost estimate of Clariflocators-1, 2 at NTPC Tanda, Uttar Pradesh.
- i) Visual observations of Clariflocators-1, 2: To collect data of distress on RCC members of Clariflocators shall be carried out up to safely accessible heights which were made accessible for testing. Visual observation data will be supplemented by photographs and other pertinent information wherever available.
- ii) To conduct experimental investigation by Non Destructive Testing technique on the selected representative RCC members at different locations of the Clariflocators-1,2
 - a. Quality assessment of selected RCC members using Rebound Hammer testing technique as per IS 516 (Part 5/Sec 4):2020
 - b. Quality assessment of selected RCC members using Ultrasonic Pulse Velocity testing technique as per IS: IS: 516 (Part V) 2019
 - c. Determination of equivalent cube compressive strength of concrete in RCC structure using concrete core extraction & testing technique as per IS: 456-2000 & IS: 516-1959.
 - d. Assessment of Carbonation depth of the extracted concrete cores.
 - e. Determine the corrosion status of reinforcement steel using Half-cell potential survey as per IS: 516 (PART 5, SECTION 2) 2021 on few selected safely accessible RCC Members.
 - f. Determination of concrete cover thickness in RCC members using Ferro scanning technique at identified & safely accessible location.



- g. Chemical Analysis to determine Chloride content, Sulphate content and pH value of Concrete Powder Samples in laboratory.
- iii) Analysis and interpretation of test results/data obtained in (i) & (ii) above.
- iv) Recommendations on remedial measures using indigenously available compatible repair materials. Preparation of BOQ covering selected items for repair including rate analysis & preparation of specifications and methodology for carrying out effective repair shall also be provided.
- v) The report covering (i) to (iv) above.

2.0 DATA PROVIDED BY SPONSOR

• Year of Construction of the subject structure was around 1990

3.0 INVESTIGATION CARRIED OUT BY NCB

To collect the data of distress on RCC members of Clariflocators at NTPC, TANDA, Uttar Pradesh, and Visual observation survey was carried out jointly by NCB team and the concerned NTPC officials during the visits for condition assessment from 06th September to 10th September 2022.

3.1 Rebound Hammer Testing (RHT) As Per IS 516 (Part 5/Sec 4):2020

Rebound hammer testing technique was used for assessing the likely surface compressive strength of concrete. Basic principle of rebound hammer test is given below.

When the plunger of rebound hammer is pressed against the surface of the concrete, the spring-controlled mass rebounds and the extent of such rebound depends upon the surface hardness of concrete. The surface hardness and therefore the rebound are taken to be related to the compressive strength of the concrete. The rebound is read off along a graduated scale and is designated as the rebound number or rebound index. It is also to be noted that rebound indices are indicative of compressive strength of concrete to a limited depth from the surface. If the concrete in a particular member has internal micro cracking, flaws or heterogeneity across the cross-section, rebound hammer indices will not indicate the same. IS: 516 (Part 5/Sec 4): 2020 states, "As such, the estimation of strength of concrete by rebound hammer method cannot be held to be very accurate and probable accuracy of prediction of concrete strength in a structure is ±25 percent." However, the test should only be used as indication of the probable compressive strength of concrete.



The test was carried out using a Schmidt's Rebound Hammer on randomly selected accessible Mill foundations at NTPC Tanda, Uttar Pradesh. The members which were tested were made accessible. So the testing done on accessible members represents other members also. The surfaces at the chosen locations were thoroughly cleaned with carborandum stone/grinding stone and readings were taken around each point. The average of the readings becomes the rebound index at that point of observation.

3.2 Ultrasonic Pulse Velocity (UPV) Method As per IS: 516 (Part V) – 2018.

UPV is a non-destructive evaluation method for assessing the quality of concrete; density, homogeneity and uniformity. Basic principle of UPV method is given below.

In this method, an ultrasonic pulse of longitudinal vibrations is produced by an electro-acoustical transducer which is held in contact with one surface of the concrete member under test. After traversing a known path length of the member, the pulse of vibrations is converted into an electric signal by a second electro-acoustical transducer, and an electric timing circuit enables the transit time of the pulse to be measured, from which the pulse velocity is calculated. For the present investigation, the pulse velocity measurements were obtained by direct transmission of ultrasonic pulses through the concrete, i.e. by "cross probing" & "Surface probing". For this purpose, the transducers were held on opposite faces of the beam and columns.

The Ultrasonic Pulse Velocity in concrete is mainly related to its density and modulus of elasticity. This in turn depends upon the materials and mix proportions used in making concrete as well as methods of placing, compaction and curing of concrete. If the concrete is not thoroughly compacted, or if there is segregation of concrete during placing or there are internal cracks or flaws, the pulse velocity will be lower, although the same materials and mix proportions are used.

The underlying principle of assessing the quality of concrete from UPV method is that, comparatively higher pulse velocities are obtained when the 'quality' of concrete in terms of density, homogeneity and uniformity is good. In case of concrete of poorer quality, lower velocities are obtained.

On this basis, guidelines have been evolved for characterizing the quality of concrete in structures in terms of ultrasonic pulse velocity. Such guideline reproduced from IS: 516 (Part V) – 2018.



3.3 Concrete Core Testing

Concrete cores of 60-mm diameter were extracted from different structural members identified, to estimate equivalent cube compressive strength of the structure. Equivalent cube strength does not indicate 28 days' standard cube strength rather it represents the in-situ cube strength, and is compared vis-à-vis strength used in design calculation with safety of the structure under load in mind.

There are a number of parameters, which influence the measured compressive strengths. Such parameters include size (diameter) of the specimen, length-to-diameter ratio, direction of drilling, method of capping, drilling operations, moisture conditions of cores at the time of testing etc. Many of these parameters have been standardized.

The second set of variables relates to the intrinsic difference that exists between the concrete in structure and in standard laboratory controlled specimens, the core specimens representing the former. Such intrinsic differences are due to inherent differences that may occur in mixing constituents, degree of compaction, extent of curing and temperature condition in two cases. The procedure for sampling, preparing, testing and calculating the equivalent compressive strength with corrections are given in **IS: 516-2018.**

The net effect of all these parameters is that the strength of concrete cores is in general lower than those of laboratory controlled specimens, for this reason **IS: 456-2000** (Code of Practice for Plain and Reinforced Concrete)consider that concrete in the area represented by a core test is adequate if" the average equivalent cube strength of the cores is equal to at least 85 percent of the specified for the corresponding age and if no single core has strength lower than 75 percent of the specified value".

3.4 Carbonation Test

Carbonation is the formation of calcium carbonate (CaCO₃) by chemical reactions in concrete. When CO₂penetrates into the hardened concrete, it reacts with portlandite [Portlandite is a mineral formed during the curing of concrete, calcium hydroxide Ca (OH)₂] in the presence of moisture forming CaCO₃. The rate of carbonation depends mainly on the relative humidity, the concentration of CO₂, the penetration pressure and the temperature of the environment where concrete is placed.

As carbon dioxide enters the concrete from the environment, it reacts with calcium hydroxide present in the concrete and depending upon the quality of concrete it reduces the



alkalinity of the pore fluids, depassivating ferric oxide layer on reinforcing bar which in turn initiates the process of corrosion in reinforcement.

To determine the depth of carbonation, concrete is exposed and sprayed with a pH indicator (solutions of 1%phenolphthalein in 70% ethyl alcohol). The demarcation between the region, which turns into magenta (dark pink colour) and the region showing no change in colour indicate the carbonation front.

Carbonation measurements were recorded immediately after the cores specified in col. 3.4 were extracted.

3.5 Half-Cell Potential (HCP) Measurements

This test method covers the estimation of electrical Half Cell Potential of uncoated reinforcing steel, to determine corrosion activity using reference electrode copper; copper sulphate half-cell. It is not possible to expose all the reinforcements in the structural element and observe the extent of corrosion. So, this method has been very convenient to assess the condition of the entire length of a member by exposing a portion of the reinforcement at a suitable location, which measures the half-cell potential on the entire length, by placing the reference electrode on the wet concrete surface.

The Half-Cell Potential measurement is based on the principal of the corrosion, being an electro-chemical process, induces certain voltage to the reinforcement steel that is corroding. The wetting of the concrete is required to make the portion between the concrete surface and the reinforcing bar as electrolytes.

A criterion for assessment for corrosion of steel is given as under IS: 516 (Part 5, Section 2)-2021 below.

- ➤ If potentials over an area are more positive than -200 mV, there is a greater than 90% probability that no reinforcing steel corrosion is occurring in that area at the time of measurement.
- ➤ If potentials over an area are in the range of -200 mV to -350 mV, corrosion activity of the reinforcing steel in that area is uncertain.
- ➤ If potentials over an area are more negative than -350 mV, there is a greater than 90% probability that reinforcing steel corrosion is occurring in that area at the time of measurement.



Adequate numbers of accessible RCC members were selected from various locations to conduct Half-Cell Potential test.

3.6 Concrete Cover Study

Concrete cover depth to reinforcing bars shall be done by using Ferro Scanner instrument on safe & accessible locations. This instrument detects the reinforcing bars and mesh, to measure their cover depth and determine the bar diameter. The instrument is based on the magnetic technique and is calibrated for different purposes. The cover depth is important from the point of view of estimation of initiation of corrosion of reinforcing bars.

For a longitudinal reinforcing bar in a Column nominal cover shall in any case not be less than 40mm or less than the diameter of such bar as per clause 26.4.2.1 of IS: 456-2000. Nominal cover to meet durability requirement for footing, minimum cover shall be 50mm as per clause 26.4.2.2 of IS: 456-2000.

Minimum values of nominal cover of normal weight aggregate concrete to be provided to all reinforcement including links to meet specified period of fire resistance shall be as per Table 16A of IS:456-2000.

Minimum values for the nominal cover of normal weight aggregate concrete which should be provided all reinforcement including links depending of exposure condition shall be as per the Table 5 of IS: 456-2000.

3.7 Chemical Analysis

Corrosion of reinforcing steel due to chlorides in concrete is one of the most common environmental attacks that lead to deterioration of concrete structures. Whenever there is chloride in concrete there is an increased risk of corrosion of embedded metal. Chloride content is then expressed in kg per cubic meter of concrete and compared with the values of limits of chloride contents of concrete (**Table 7 of IS: 456–2000**).

Sulphates (SO₃) are present in most cements and in some aggregates; excessive amounts of water-soluble sulphate from these or other mix constituents can cause expansion and disruption of concrete. To prevent it, **IS:** 456-2000 clause-8.2.5.3 states that the total water-soluble sulphate content of the concrete mix, expressed as SO₃, should not exceed 4 percent by mass of the cement in the mix. The sulphate content should be calculated as the total from the various constituents of the mix.



The pH value of the concrete should be above 11.5 to maintain alkalinity of concrete surrounding the embedded steel. A reduction in the pH value of concrete indicates loss of passive layer around the reinforcement which protects the steel from distress.

For analyzing Chloride content and pH of concrete, concrete powder samples were extracted from 0-25mm, 25-50mm depths at identified locations and then tested as per IS:14959(Part 2) -2001 (Determination of water soluble and acid soluble Chlorides in Mortar and Concrete – Method of Test).

Adequate numbers of accessible RCC members were selected from various locations to extract concrete powders for chemical test.

4.0 RESULTS AND DISCUSSION

4.1. Visual Observations

Visual observations and testing carried out at Different levels of Clariflocators. Distress was found in the form of cracks, Honeycombs and Seepage of Water through concrete surface. Colour deterioration, spalling of Concrete was noticed at few locations of Clariflocators. The visual observations and photographs are shown in Annexure I.

4.2. Rebound Hammer Testing:

Rebound Hammer testing was carried out on various identified RCC (Reinforced Cement Concrete) members of Clariflocators-1, 2 using random sampling technique the results of surface compressive strength obtained by Rebound Hammer testing are given in Table 2 to 17.

Surface Compressive strength results of concrete as obtained on different hardened concrete surfaces of RCC Members are summarized as:

- 1) Surface compressive strength of concrete obtained Clariflocator-1 East side wall by Rebound Hammer Testing is found with an average surface compressive strength of 31.75 N/mm² (Refer Table 2).
- 2) Surface compressive strength of concrete obtained on Clariflocator-1 West side wall by Rebound Hammer Testing is found with an average surface compressive strength of 34.80 N/mm² (Refer Table 3).



- 3) Surface compressive strength of concrete obtained on Clariflocator-1 South side wall by Rebound Hammer Testing is found with an average surface compressive strength 34.16 N/mm² (Refer Table 4).
- 4) Surface compressive strength of concrete obtained on Clariflocator-1 North side wall by Rebound Hammer Testing is found with an average surface compressive strength of 33.95 N/mm² (Refer Table 5).
- 5) Surface compressive strength of concrete obtained on Clariflocator-1 North East side wall by Rebound Hammer Testing is found with an average surface compressive strength of **36.07 N/mm²** (Refer Table 6).
- 6) Surface compressive strength of concrete obtained on Clariflocator-1 South West side wall by Rebound Hammer Testing is found with an average surface compressive strength of **33.66 N/mm²** (Refer Table 7).
- 7) Surface compressive strength of concrete obtained on Clariflocator-1 North West side wall by Rebound Hammer Testing is found with an average surface compressive strength of **31.97 N/mm²** (Refer Table 8).
- 8) Surface compressive strength of concrete obtained on Clariflocator-1 North West side wall by Rebound Hammer Testing is found with an average surface compressive strength of **35.64 N/mm²** (Refer Table 9).
- 9) Surface compressive strength of concrete obtained on Clariflocator-2 North side wall by Rebound Hammer Testing is found with an average surface compressive strength of 32.81 N/mm² (Refer Table 10).
- 10) Surface compressive strength of concrete obtained on Clariflocator-2 South side wall by Rebound Hammer Testing is found with an average surface compressive strength of 33.10 N/mm² (Refer Table 11).
- 11) Surface compressive strength of concrete obtained on Clariflocator-2 East side wall by Rebound Hammer Testing is found with an average surface compressive strength of 33.73 N/mm² (Refer Table 12).
- 12) Surface compressive strength of concrete obtained on Clariflocator-2 West side wall by Rebound Hammer Testing is found with an average surface compressive strength of 32.74 N/mm² (Refer Table 13).



- 13) Surface compressive strength of concrete obtained on Clariflocator-2 North East side wall by Rebound Hammer Testing is found with an average surface compressive strength of **33.03 N/mm**² (Refer Table 14).
- 14) Surface compressive strength of concrete obtained on Clariflocator-2 South West side wall by Rebound Hammer Testing is found with an average surface compressive strength of **32.96 N/mm²** (Refer Table 15).
- 15) Surface compressive strength of concrete obtained on Clariflocator-2 North West side wall by Rebound Hammer Testing is found with an average surface compressive strength of 33.66 N/mm² (Refer Table 16).
- **16)** Surface compressive strength of concrete obtained on Clariflocator-2 North West side wall by Rebound Hammer Testing is found with an average surface compressive strength of **34.09** N/mm² (Refer Table 17).

4.3 Ultrasonic Pulse Velocity Testing (UPV):

The Ultrasonic Pulse Velocity testing was conducted on Clariflocators for #1, 2 in the presence of concerned engineering team of NTPC Tanda. The results of the UPV values obtained on various RCC members are as follows:

- 1) The UPV measurements were taken using Surface probing technique on the Clariflocator-1 East side wall are in the range of **3.77 to 4.6 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018(Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table -19).
- 2) The UPV measurements were taken using Cross probing technique on the Clariflocator-1 West side wall are in the range of 3.62 to 4.09 km/sec. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be GOOD (Table 20).
- 3) The UPV measurements were taken using Cross probing technique on the Clariflocator-1 South side wall are in the range of **3.64 to 4.27 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 21).
- 4) The UPV measurements were taken using Cross probing technique on the Clariflocator-1 North side wall are in the range of 3.58 to 4.13 km/sec. When these values are



- compared with the velocity criteria of IS: 516 (Part V) -2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 5) The UPV measurements were taken using Cross probing technique on the Clariflocator-1 North East side wall are in the range of **3.56 to 4.08 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 23).
- 6) The UPV measurements were taken using Surface probing technique on the Clariflocator-1 South West side wall are in the range of **3.54 to 3.98 km/sec**. When these values are compared with the velocity criteria of IS:516 (Part V)–2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 24).
- 7) The UPV measurements were taken using Surface probing technique on the Clariflocator-1 North West side wall are in the range of **3.55 to 3.98 km/sec**. When these values are compared with the velocity criteria of IS:516 (Part V)–2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 25).
- 8) The UPV measurements were taken using Surface probing technique on the Clariflocator-1 North West side wall are in the range of **3.51 to 3.88 km/sec**. When these values are compared with the velocity criteria of IS:516 (Part V)–2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 26).
- 9) The UPV measurements were taken using Surface probing technique on the Clariflocator-2 North side wall are in the range of **3.98 to 4.66km/sec**. When these values are compared with the velocity criteria of IS:516 (Part V)–2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 27).
- 10) The UPV measurements were taken using Cross probing technique on the Clariflocator-2 North side wall are in the range of **3.61 to 4.19 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 28).
- 11) The UPV measurements were taken using Cross probing technique on the Clariflocator-2 East side wall are in the range of **3.59 to 4.08 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 29).



- 12) The UPV measurements were taken using Cross probing technique on the Clariflocator-2 West side wall are in the range of **3.64 to 4.02 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 30).
- 13) The UPV measurements were taken using Cross probing technique on the Clariflocator-2 North East side wall are in the range of **3.73 to 4.08 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 31).
- 14) The UPV measurements were taken using Surface probing technique on the Clariflocator-2 South West side wall are in the range of **4.06 to 4.41 km/sec**. When these values are compared with the velocity criteria of IS:516 (Part V)–2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 32).
- 15) The UPV measurements were taken using Surface probing technique on the Clariflocator-2 North West side wall are in the range of **3.86 to 4.26 km/sec**. When these values are compared with the velocity criteria of IS:516 (Part V)–2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 33).
- 16) The UPV measurements were taken using Surface probing technique on the Clariflocator-2 North West side wall are in the range of **3.89 to 4.22 km/sec**. When these values are compared with the velocity criteria of IS: 516(Part V) 2018 (Also reproduced in Table 18), the overall quality of concrete is assessed to be **GOOD** (Table 34).

4.4 Concrete Core Testing:

Corresponding to the 60mm concrete core extracted by random sampling technique covering different locations of Clariflocators- 1, 2 in power plant of NTPC Tanda and tested at NCCBM laboratory Hyderabad, the equivalent cube compressive strength of concrete RCC members are shown in Tables- 40, 41. In total, 28 nos. of concrete cores were extracted from different members of the Clariflocators all are found to be testable either due to short length of the cores.

The test results indicate that the equivalent cube compressive strength values for



Clariflocator-1

- 1. Clariflocator-1 East side wall is found to be 48.30 N/mm²
- 2. Clariflocator-1 West side wall is found to be 64.63 N/mm2
- 3. Clariflocator-1 South side wall is found to be 31.00 N/mm2
- 4. Clariflocator-1 North side wall is found to be 47.00 N/mm2
- 5. Clariflocator-1 North East side wall is found to be 33.41 N/mm2
- 6. Clariflocator-1 South West side wall is found to be 39.13 N/mm2
- 7. Clariflocator-1 North West side wall is found to be 33.26 N/mm2
- 8. Clariflocator-1 North West side wall is found to be 36.80 N/mm2

Clariflocator-2

- 1. Clariflocator-2 North side wall is found to be **35.49 N/mm2**
- 2. Clariflocator-2 South side wall is found to be 31.93 N/mm2
- 3. Clariflocator-2 East side wall is found to be 25.53 N/mm2
- 4. Clariflocator-2 West side wall is found to be 34.32 N/mm2
- 5. Clariflocator-2 North East side wall is found to be **37.92 N/mm2**
- 6. Clariflocator-2 South West side wall is found to be 35.34 N/mm2
- 7. Clariflocator-2 North West side wall is found to be **36.34 N/mm2**
- 8. Clariflocator-2 North West side wall is found to be 32.87 N/mm2

In total, 16 nos tested cores all of them found to have equivalent cube compressive strength more than specified characteristic compressive strength of M25 grade concrete (which is produced in Table- 40,41).

4.5 Concrete Cover:

The concrete cover depth to rebars in RCC members is measured with Ferro-scanner and a measuring tape/scale in the places where concrete is exposed and accessible for direct measurement. Nominal cover to reinforcement to meet durability requirement is given in **IS-456: Table 16-clause 26.4.2** (Also reproduced in Table-35), the measured cover to reinforcement steel in the selected RCC members are given in Table 36,37.

Clariflocator-1

1. The Concrete cover to Reinforcing bars of Clariflocator-1 East side wall during testing using Ferro scanner meter is found with an average of **50 mm**.



- 2. The Concrete cover to Reinforcing bars of Clariflocator-1 West side wall during testing using Ferro scanner meter is found with an average of **54 mm**.
- 3. The Concrete cover to Reinforcing bars of Clariflocator-1 South side wall during testing using Ferro scanner meter is found with an average of **57 mm**.
- 4. The Concrete cover to Reinforcing bars of Clariflocator-1 North side wall during testing using Ferro scanner meter is found with an average of **56 mm**.
- 5. The Concrete cover to Reinforcing bars of Clariflocator-1 North East side wall during testing using Ferro scanner meter is found with an average of **52 mm**.
- 6. The Concrete cover to Reinforcing bars of Clariflocator-1 South West side wall during testing using Ferro scanner meter is found with an average of **53 mm**.
- 7. The Concrete cover to Reinforcing bars of Clariflocator-1 North West side wall during testing using Ferro scanner meter is found with an average of **57 mm**.
- 8. The Concrete cover to Reinforcing bars of Clariflocator-1 North West side wall during testing using Ferro scanner meter is found with an average of **54 mm**.

Clariflocator-2

- 1. The Concrete cover to Reinforcing bars of Clariflocator-2 North side wall during testing using Ferro scanner meter is found with an average of **51 mm**.
- 2. The Concrete cover to Reinforcing bars of Clariflocator-2 South side wall during testing using Ferro scanner meter is found with an average of **52 mm**.
- 3. The Concrete cover to Reinforcing bars of Clariflocator-2 East side wall during testing using Ferro scanner meter is found with an average of **58 mm**.
- 4. The Concrete cover to Reinforcing bars of Clariflocator-2 West side wall during testing using Ferro scanner meter is found with an average of **57 mm**.
- 5. The Concrete cover to Reinforcing bars of Clariflocator-2 North East side wall during testing using Ferro scanner meter is found with an average of **52 mm**.
- 6. The Concrete cover to Reinforcing bars of Clariflocator-2 South West side wall during testing using Ferro scanner meter is found with an average of **55 mm**.
- 7. The Concrete cover to Reinforcing bars of Clariflocator-2 North West side wall during testing using Ferro scanner meter is found with an average of **54 mm**.
- 8. The Concrete cover to Reinforcing bars of Clariflocator-2 North West side wall during testing using Ferro scanner meter is found with an average of **55 mm**.



The Concrete cover within the specified limits to meet durability requirement as per IS: 456-2000 (Refer Table 16 of IS: 456-2000) which is Reproduced in Table 35.

4.6 Carbonation:

Table-38,39 shows test results of carbonation testing done on 16 nos. of Concrete Cores extracted from various representative concrete samples. The results indicate that the values of depth of carbonation in all different locations of Clariflocators-1, 2 are found to be **0-8**mm, on RCC members.

Based on the above carbonation study carried on different selected RCC members at several locations the carbonation depth is found to be within the concrete cover region.

4.7 Half-Cell Potential Test:

Half-cell potential (HCP) measurements using copper, copper-sulfate half-cell technique as per IS: 516 (Part 5, Section 2)-2021 (Standard test method for corrosion potentials of uncoated reinforcing steel in concrete) were taken at site to ascertain corrosion status of reinforcing bars of various locations of Clariflocators-1, 2 at NTPC TANDA. The measurements were done on different locations randomly selected locations and comprising of representative samples of for the structure.

Test results (refer Table- 43,44) when compared with the corrosion criteria as per ASTM C-876 (Table-42) indicate that probability of corrosion is found to be in "90% Possibility of no corrosion".

4.8 Chemical Analysis:

The chemical analysis of water and powdered samples extracted from different elements of Clariflocators-1, 2 collecting by random sampling technique. This covered chloride content, sulphate content per cum of concrete as well pH value of powdered samples. The test results as obtained in NCCBM laboratory are shown in Table- 45,46. Analysis of interpretation of test results given as under:

1) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-1 East side wall was found with an average value of **0.09 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3)



content by mass of the cement in mix with an average value of **1.57%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.3** which is within the specified limit to resist the corrosion.

- 2) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-1 West side wall was found with an average value of **0.13 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.58%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.46** which is within the specified limit specified limit to resist the corrosion.
- 3) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-1 South side wall was found with an average value of **0.16 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.44%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.52** which is within the specified limit to resist the corrosion.
- 4) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-1 North side wall was found with an average value of **0.14 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.5%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.54** which is within the specified limit to resist the corrosion.
- 5) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-1 North East side wall was found with an average value of **0.18 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.5%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of



pH value is found with an average of 11.55 is within the specified limit to resist the corrosion.

- 6) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-2 North side wall was found with an average value of **0.13 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.62%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.35** which is within the specified limit to resist the corrosion.
- 7) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-2 South side wall was found with an average value of **0.15 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.58%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.48** which is within the specified limit to resist the corrosion.
- 8) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-2 East side wall was found with an average value of **0.16 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.44%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.57** is within the specified limit to resist the corrosion.
- 9) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-2 West side wall was found with an average value of **0.15 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.5%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.58** which is within the specified limit to resist the corrosion.
- 10) Based on the results obtained from laboratory the range of chloride content in the Clariflocators-2 North East side wall was found with an average value of **0.17** kg/m³ is



within the permissible limit of 0.6 kg/m3 (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix with an average value of **1.47%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found with an average of **11.57** which is within the specified limit to resist the corrosion.

5.0 Conclusions:

The following Conclusions can be broadly made from the testing results Clariflocators-,1,2:

- i) Based on visual observations carried out in the Clariflocators-,1,2 locations Distress was found in the form of cracks, Honey combs and Seepage of Water on concrete surface. Colour deterioration, Peeling of Concrete was developing at few locations.
- ii) Based on Rebound hammer test surface hardness and likely compressive strength found satisfactory and meeting the required limits as per data furnished by the client.
- iii) Based on Ultrasonic Pulse Velocity (random sampling technique) to find quality and homogeneity of concrete on RCC members, the results were found to be good quality of concrete.
- iv) The equivalent cube compressive strength of the core samples extracted from the Clariflocators-1, 2 is found meeting more than the required limit for M25 Grade of concrete.
- v) Carbonation is found 0-8mm after 30 years 'whereas concrete cover of RCC members is found to vary from 51 58 mm and found within the limits of concrete cover region.
- vi) Based on the Half-Cell potential measurements done by random sampling technique at various locations and visual observations of Clariflocators-1, 2 given an initiation signal of either in "90% Possibility of no corrosion".
- vii) The amount of Acid soluble chloride content and soluble sulphates in the concrete of Clariflocators-1, 2 is within the specified limits for all the samples and pH values for few of tested samples slightly less than 11.5 as per (IS: 456-2000& IS: 3025 -1984).



6.0 Recommendations

The following steps shall be taken to repair the cracks & strengthening of Clariflocators-1, 2:

i) Chipping:

Cover concrete around the horizontal, vertical cracks & spalling of concrete shall be chipped off to the depth up to 40mm on RCC walls. The chipping in the spalled portion of the Shells and RCC Walls shall be limited up to the cover region. Chipping of loose/hollow sounding concrete can be done by striking the doubtful surfaces with 2 lb. hammer.

ii) Treatment for Cracks:

- a. The cracks are to be widened by cutting V-grooves of 10mm x 10mm size and sealed with approved epoxy repair mortar.
- b. After the sealing, 12mm dia galvanized steel injection nipples are to be inserted in the crack area and also wherever honeycombing is found by drilling holes of required diameter up to the depth of 30 80 mm at required spacing (generally 350 mm staggered spacing). The drilled holes must be made dust free by blowing compressed air and should be sealed after the insertion of the nozzle with approved adhesive and allowed to cure.
- c. After the nipples are injected and cured, grouting in the proportion recommended by the manufacturer into the cracks/honeycombed area of concrete/masonry shall be done using suitable gun/pump at required pressure. Once the grouting work is finished, the extruding nipples can be cut-off after the curing period.

iii) Reinforcement Corrosion Treatment:

Wherever reinforcing rebar is found corroded in RCC walls

- a) Remove the rust by manually or suitable means to make corroded reinforcing bars rust free.
- b) Provide and apply corrosion protection using 2 coats of anticorrosive Zn rich epoxy phenolic rebar protection system of approved brand on the exposed old reinforcement by brush with interval of 24 hours between coats and corrosion protection of exposed old reinforcing bars.



c) Provide and apply concrete penetrating corrosion inhibitor (CPCI) of approved brand over the entire finished surface are obtained after removal of distressed concrete in 2 coats @ of 4m²/ltr/coat approximately.

iv) Bond Coat:

After chipping off the concrete cover, provide and apply structural grade two component epoxy bond coat prior to application of any type of mortar conforming to ASTM C - 881 -13 Type - II tested as per ASTM C -882-13 to ensure bond between old and new concrete by brush application. (Material manufacture from SYNORGANIC /BASF/SIKA/FOSRAC/KRISHNA Conchem/Pidilite or equivalent)

v) Making up lost section with Polymer Modified Mortar (PMM):

For repair of patches having, apply average 40mm PMM in 2-3 layers using SBR Latex conforming to ASTM C-1059-13 Type-I in damaged areas (1 Cement-3 part graded cleaned river sand + 20 % latex by weight of cement) with 0.35 w/c ratio, in 10-15 mm thick layers by applying bond coat between successive/each. (Material manufacture either from SYNORGANIC/BASF/SIKA/FOSRAC or equivalent)

vi) Protective coating:

Before applying the protective coating on RCC walls and the outer wall surface shall be cleaned by scrubbing with hard steel brush to remove loose particles, disintegrated concrete, deposited smoke and dust particles etc. The scrubbed surface is cleaned by air blowing and then dries it completely. Apply min. 2 coats of two part high performance moisture compatible corrosion resistant coating material (base and curing agent) of approved manufacturer over prepared surface, using not less than theoretical consumption as per the manufacturer's specification. Total dry film thickness (DFT) including primer will be 300 - 400 microns.



Note:

- 1. Before taking up any repair work, the dryness of substrate concrete must be ensured for effective application of several repair materials. Remove oil, grease, wax, Cement laitance, loose particles and other contaminants by shot blasting, scarifying or mechanically wire brushing followed by vacuum cleaning from the substrate concrete.
- 2. During repair works of Clariflocators-1,2 measures should be taken up in accordance with relevant safety standards and safety guidelines of Occupational safety & Health Administration (OSHA) for construction, arrangement like safety nets/platforms should be done.

• • • • • • • •



- g. Chemical Analysis to determine Chloride content, Sulphate content and pH value of Concrete Powder Samples in laboratory.
- iii) Analysis and interpretation of test results/data obtained in (i) & (ii) above.
- iv) Recommendations on remedial measures using indigenously available compatible repair materials. Preparation of BOQ covering selected items for repair including rate analysis & preparation of specifications and methodology for carrying out effective repair shall also be provided.
- v) The report covering (i) to (iv) above.

2.0 DATA PROVIDED BY SPONSOR

• Year of Construction of the subject structure was around 1995.

3.0 INVESTIGATION CARRIED OUT BY NCB

3.1 Visual Observations

To collect the data of distress on RCC members of RCC Chimney Unit#1&2 at NTPC, Tanda, Uttar Pradesh, Visual observation survey was carried out jointly by NCB team and the concerned NTPC officials during the visits for condition assessment from 26th March to 01st April 2023.

3.2 Rebound Hammer Testing (RHT) As Per IS: 516 (Part V, Sec-IV) – 2020

Rebound hammer testing technique was used for assessing the likely surface compressive strength of concrete. Basic principle of rebound hammer test is given below.

When the plunger of rebound hammer is pressed against the surface of the concrete, the spring-controlled mass rebounds and the extent of such rebound depends upon the surface hardness of concrete. The surface hardness and therefore the rebound are taken to be related to the compressive strength of the concrete. The rebound is read off along a graduated scale and is designated as the rebound number or rebound index. It is also to be noted that rebound indices are indicative of compressive strength of concrete to a limited depth from the surface. If the concrete in a particular member has internal micro cracking, flaws or heterogeneity across the cross-section, rebound hammer indices will not indicate the same. **IS: 516 (Part V, Sec-IV) – 2020 states,** "As such, the estimation of strength of concrete by rebound hammer method cannot be held to be very accurate and probable accuracy of prediction of concrete strength in a structure is ±25 percent." However, the test should only be used as indication of the probable compressive strength of concrete.



The test was carried out using a Schmidt's Rebound Hammer on randomly selected accessible RCC Chimney at NTPC Tanda, Uttar Pradesh. The members which were tested were made accessible, so the testing done on accessible RCC members. The surfaces at the chosen locations were thoroughly cleaned with carborandum stone/grinding stone and readings were taken around each point. The average of the readings becomes the rebound index at that point of observation.

3.3 Ultrasonic Pulse Velocity (UPV) Method as per as per IS: 516 (Part V, Sec-I) – 2018.

UPV is a non-destructive evaluation method for assessing the quality of concrete; density, homogeneity and uniformity. Basic principle of UPV method is given below.

In this method, an ultrasonic pulse of longitudinal vibrations is produced by an electro-acoustical transducer which is held in contact with one surface of the concrete member under test. After traversing a known path length of the member, the pulse of vibrations is converted into an electric signal by a second electro-acoustical transducer, and an electric timing circuit enables the transit time of the pulse to be measured, from which the pulse velocity is calculated. For the present investigation, the pulse velocity measurements were obtained by direct transmission of ultrasonic pulses through the concrete, i.e. by "cross probing". For this purpose, the transducers were held on opposite faces of the beam and columns.

The Ultrasonic Pulse Velocity in concrete is mainly related to its density and modulus of elasticity. This in turn depends upon the materials and mix proportions used in making concrete as well as methods of placing, compaction and curing of concrete. If the concrete is not thoroughly compacted, or if there is segregation of concrete during placing or there are internal cracks or flaws, the pulse velocity will be lower, although the same materials and mix proportions are used.

The underlying principle of assessing the quality of concrete from UPV method is that, comparatively higher pulse velocities are obtained when the 'quality' of concrete in terms of density, homogeneity and uniformity is good. In case of concrete of poorer quality, lower velocities are obtained.

On this basis, guidelines have been evolved for characterizing the quality of concrete in structures in terms of ultrasonic pulse velocity. Such guideline is given in Table 25, which is reproduced from IS: 516 (Part V, Sec-I) – 2018.



3.4 Concrete Core Testing

Concrete cores of 60-mm diameter were extracted from different structural members identified, to estimate equivalent cube compressive strength of the structure. Equivalent cube strength does not indicate 28 days' standard cube strength rather it represents the in-situ cube strength, and is compared vis-à-vis strength used in design calculation with safety of the structure under load in mind.

There are a number of parameters, which influence the measured compressive strengths. Such parameters include size (diameter) of the specimen, length-to-diameter ratio, direction of drilling, method of capping, drilling operations, moisture conditions of cores at the time of testing etc. Many of these parameters have been standardized.

The second set of variables relates to the intrinsic difference that exists between the concrete in structure and in standard laboratory-controlled specimens, the core specimens representing the former. Such intrinsic differences are due to inherent differences that may occur in mixing constituents, degree of compaction, extent of curing and temperature condition in two cases. The procedure for sampling, preparing, testing and calculating the equivalent compressive strength with corrections are given in **IS: 516-2018.**

The net effect of all these parameters is that the strength of concrete cores is in general lower than those of laboratory controlled specimens, for this reason **IS: 456-2000** (Code of Practice for Plain and Reinforced Concrete) consider that concrete in the area represented by a core test is adequate if the average equivalent cube strength of the cores is equal to at least 85 percent of the specified for the corresponding age and if no single core has strength lower than 75 percent of the specified value".

3.5 Carbonation Test

Carbonation is the formation of calcium carbonate (CaCO₃) by chemical reactions in concrete. When CO₂ penetrates into the hardened concrete, it reacts with portlandite [Portlandite is a mineral formed during the curing of concrete, calcium hydroxide Ca(OH)₂] in the presence of moisture forming CaCO₃. The rate of carbonation depends mainly on the relative humidity, the concentration of CO₂, the penetration pressure and the temperature of the environment where concrete is placed.

As carbon dioxide enters the concrete from the environment, it reacts with calcium hydroxide present in the concrete and depending upon the quality of concrete it reduces the alkalinity of the



pore fluids, depassivating ferric oxide layer on reinforcing bar which in turn initiates the process of corrosion in reinforcement.

To determine the depth of carbonation, concrete is exposed and sprayed with a pH indicator (solutions of 1%phenolphthalein in 70%ethyl alcohol). The demarcation between the region, which turns into magenta (dark pink colour) and the region showing no change in colour indicate the carbonation front.

Carbonation measurements were recorded immediately after the cores specified in col. 3.4 were extracted.

3.6 Half-Cell Potential (HCP) Measurements

This test method covers the estimation of electrical Half Cell Potential of uncoated reinforcing steel, to determine corrosion activity using reference electrode copper; copper sulphate half-cell. It is not possible to expose all the reinforcements in the structural element and observe the extent of corrosion. So, this method has been very convenient to assess the condition of the entire length of a member by exposing a portion of the reinforcement at a suitable location, which measures the half-cell potential on the entire length, by placing the reference electrode on the wet concrete surface.

The Half-Cell Potential measurement is based on the principal of the corrosion, being an electro-chemical process, induces certain voltage to the reinforcement steel that is corroding. The wetting of the concrete is required to make the portion between the concrete surface and the reinforcing bar as electrolytes.

A criterion for assessment for corrosion of steel is given as under ASTM C-876 below.

- ➤ If potentials over an area are more positive than -200 mV, there is a greater than 90% probability that no reinforcing steel corrosion is occurring in that area at the time of measurement.
- ➤ If potentials over an area are in the range of -200 mV to -350 mV, corrosion activity of the reinforcing steel in that area is uncertain.
- ➤ If potentials over an area are more negative than -350 mV, there is a greater than 90% probability that reinforcing steel corrosion is occurring in that area at the time of measurement.

Adequate numbers of accessible RCC members were selected from various locations to conduct Half-Cell Potential test.



3.7 Concrete Cover Study

Concrete cover depth to reinforcing bars shall be done by using Ferro Scanner instrument on safe & accessible locations. This instrument detects the reinforcing bars and mesh, to measure their cover depth and determine the bar diameter. The instrument is based on the magnetic technique and is calibrated for different purposes. The cover depth is important from the point of view of estimation of initiation of corrosion of reinforcing bars.

For a longitudinal reinforcing bar in a Column nominal cover shall in any case not be less than 40mm or less than the diameter of such bar as per clause 26.4.2.1 of IS: 456-2000. Nominal cover to meet durability requirement for footing, minimum cover shall be 50mm as per clause 26.4.2.2 of IS: 456-2000.

Minimum values of nominal cover of normal weight aggregate concrete to be provided to all reinforcement including links to meet specified period of fire resistance shall be as per Table 16A of IS:456-2000.

Minimum values for the nominal cover of normal weight aggregate concrete which should be provided all reinforcement including links depending of exposure condition shall be as per the Table 5 of IS: 456-2000.

3.8 Chemical Analysis

Corrosion of reinforcing steel due to chlorides in concrete is one of the most common environmental attacks that lead to deterioration of concrete structures. Whenever there is chloride in concrete there is an increased risk of corrosion of embedded metal. Chloride content is then expressed in kg per cubic meter of concrete and compared with the values of limits of chloride contents of concrete (**Table 7 of IS: 456–2000**).

Sulphates (SO₃) are present in most cements and in some aggregates; excessive amounts of water-soluble sulphate from these or other mix constituents can cause expansion and disruption of concrete. To prevent it, **IS:** 456-2000 clause-8.2.5.3 states that the total water-soluble sulphate content of the concrete mix, expressed as SO₃, should not exceed 4 percent by mass of the cement in the mix. The sulphate content should be calculated as the total from the various constituents of the mix.



The pH value of the concrete should be above 11.5 to maintain alkalinity of concrete surrounding the embedded steel. A reduction in the pH value of concrete indicates loss of passive layer around the reinforcement which protects the steel from distress.

For analyzing Chloride content and pH of concrete, concrete powder samples were extracted from 0-25mm, 25-50mm depths at identified locations and then tested as per IS:14959(Part 2) -2001 (Determination of water soluble and acid soluble Chlorides in Mortar and Concrete – Method of Test).

Adequate numbers of accessible RCC members were selected from various locations to extract concrete powders for chemical test.

4.0 RESULTS AND DISCUSSION

4.1. Visual Observations

The height of the RCC chimney of Unit- is 120m. Visual observations and testing carried out at 1.5m, 10m, 18m, 100m height. Distress, Signs of cracks, spalling of concrete and exposure of reinforcement observed on the chimney at different heights. Distress and Honey comb observed at a few locations of Interior and exterior walls. The visual observations and photographs are shown Annexure 1.

4.2. Rebound Hammer Testing

Rebound Hammer testing was carried out on various identified RCC (Reinforced Cement Concrete) members of Chimney (up to 120 m) using random sampling technique, The results of surface compressive strength obtained by Rebound Hammer testing are given in Table 2 to 21. Surface Compressive strength results of concrete as obtained on different hardened concrete surfaces of RCC Members are summarized as:

- 1) Surface compressive strength of concrete obtained on Chimney wall, S-E, Out Side at 1.5m level by Rebound Hammer Testing is found to vary from 38.26 N/mm² to 42.79 N/mm² with an average surface compressive strength of 40.81 N/mm² (Refer Table 2).
- 2) Surface compressive strength of concrete obtained on Chimney wall, S-W, Inside at 1.5 m level by Rebound Hammer Testing is found to vary from 39.39 N/mm² to 42.79 N/mm² with an average surface compressive strength of 40.67 N/mm² (Refer Table 3).



- 3) Surface compressive strength of concrete obtained on Chimney wall, N-W, north, inside at 1.5 m level by Rebound Hammer Testing is found to vary from 36.56 N/mm² to 42.22 N/mm² with an average surface compressive strength 39.96 N/mm² (Refer Table 4).
- 4) Surface compressive strength of concrete obtained on Chimney wall, N-W, outside at 1.5 m level by Rebound Hammer Testing is found to vary from 38.83 N/mm² to 42.79 N/mm² with an average surface compressive strength of 41.09 N/mm² (Refer Table 5).
- 5) Surface compressive strength of concrete obtained on Chimney wall, East side Near stack yard, Outside at 1.5 m level by Rebound Hammer Testing is found to vary from 36.56 N/mm² to 39.96 N/mm² with an average surface compressive strength of 38.97 N/mm² (Refer Table 6).
- 6) Surface compressive strength of concrete obtained on Chimney wall, N-E, outside at 1.5 m level by Rebound Hammer Testing is found to vary from 39.96 N/mm² to 42.22 N/mm² with an average surface compressive strength of 40.81 N/mm² (Refer Table 7).
- 7) Surface compressive strength of concrete obtained on Chimney wall, South side, outside at 1.5 m level Rebound Hammer Testing is found to vary from 39.39 N/mm² to 42.22 N/mm² with an average surface compressive strength of 40.67 N/mm² (Refer Table 8).
- 8) Surface compressive strength of concrete obtained on Chimney wall, N-E, outside at 1.5 m level by Rebound Hammer Testing is found to vary from 36.56 N/mm² to 42.22 N/mm² with an average surface compressive strength of 39.54 N/mm² (Refer Table 9).
- 9) Surface compressive strength of concrete obtained on Chimney wall, North side, outside at 1.5 m level by Rebound Hammer Testing is found to vary from 37.70 N/mm² to 41.66N/mm² with an average surface compressive strength of 39.68 N/mm² (Refer Table 10).
- 10) Surface compressive strength of concrete obtained on Chimney wall, N-W, Out Side at 1.5 m level by Rebound Hammer Testing is found to vary from 38.26 N/mm² to 42.22 N/mm² with an average surface compressive strength of 40.24 N/mm² (Refer Table 11).
- 11) Surface compressive strength of concrete obtained on Chimney wall, S-E, outside at 10m level by Rebound Hammer Testing is found to vary from 39.39 N/mm² to 42.22 N/mm² with an average surface compressive strength of 40.67 N/mm² (Refer Table 12).
- 12) Surface compressive strength of concrete obtained on Chimney wall, N-W, outside at 10 m level by Rebound Hammer Testing is found to vary from 39.39 N/mm² to 43.36 N/mm² with an average surface compressive strength of 41.23 N/mm² (Refer Table 13).



- 13) Surface compressive strength of concrete obtained on Chimney wall, South side, outside at 10 m level by Rebound Hammer Testing is found to vary from 39.39 N/mm² to 41.66 N/mm² with an average surface compressive strength of 40.67 N/mm² (Refer Table 14).
- 14) Surface compressive strength of concrete obtained on Chimney wall, North side, outside at 10 m level by Rebound Hammer Testing is found to vary from 37.70 N/mm² to 40.53N/mm² with an average surface compressive strength of 39.11 N/mm² (Refer Table 15).
- 15) Surface compressive strength of concrete obtained on Chimney wall, S-E, outside at 10 m level by Rebound Hammer Testing is found to vary from 38.83 N/mm² to 40.53 N/mm² with an average surface compressive strength of 39.68 N/mm² (Refer Table 16).
- 16) Surface compressive strength of concrete obtained on Chimney wall, West side, Outside at 18 m level by Rebound Hammer Testing is found to vary from 38.83 N/mm² to 40.53N/mm² with an average surface compressive strength of 39.82 N/mm² (Refer Table 17).
- 17) Surface compressive strength of concrete obtained on Chimney wall, South side, outside at 18m level by Rebound Hammer Testing is found to vary from 39.39N/mm² to 41.66N/mm² with an average surface compressive strength of 40.24 N/mm² (Refer Table 18).
- 18) Surface compressive strength of concrete obtained on Chimney wall, East side, Outside at 18m level by Rebound Hammer Testing is found to vary from 39.39 N/mm² to 42.22 N/mm² with an average surface compressive strength of 41.09 N/mm² (Refer Table 19).
- 19) Surface compressive strength of concrete obtained on Chimney wall, West side, Outside at 18m level by Rebound Hammer Testing is found to vary from 39.96 N/mm² to 41.09 N/mm² with an average surface compressive strength of 40.67 N/mm² (Refer Table 20).
- 20) Surface compressive strength of concrete obtained on Chimney wall, N-W, outside at 18m level by Rebound Hammer Testing is found to vary from 38.83 N/mm² to 40.53 N/mm² with an average surface compressive strength of 39.54 N/mm² (Refer Table 21).

4.3 Ultrasonic Pulse Velocity Testing (UPV):

The **Ultrasonic Pulse Velocity** testing was conducted on RCC Chimney in the presence of concerned engineering team of NTPC. The results of the UPV values obtained on various RCC members are as follows:

1) The UPV measurements were taken using Surface probing technique on the Chimney wall, S-E, Out Side at 1.5 m level are in the range of **4.05 to 4.33km/sec**. When these values are



- compared with the velocity criteria of IS: 516 (Part V) -2018 (Also reproduced in Table 23), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 2) The UPV measurements were taken using surface probing technique on the Chimney wall, S-W, Inside at 1.5 m level are in the range of **4.05 to 4.32km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 24), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 3) The UPV measurements were taken using Surface probing technique on the Chimney wall, N-W, north, inside at 1.5 m level are in the range of **3.89 to 4.34km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 25), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 4) The UPV measurements were taken using cross probing technique on the Chimney wall, Entrance at 1.5 m level are in the range of **3.94 to 4.14km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 26), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 5) The UPV measurements were taken using Surface probing technique on the Chimney wall, East side near stack yard, Outside at 1.5 m level is in the range of **3.96 to 4.31km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 6) The UPV measurements were taken using Surface probing technique on the Chimney wall, N-E, Outside at 1.5 m level is in the range of **3.97to 4.26km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 28), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 7) The UPV measurements were taken using Surface probing technique on the Chimney wall, South side, outside at 1.5 m level are in the range of **4.04 to 4.34km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 29), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 8) The UPV measurements were taken using Surface probing technique on the Chimney wall, N-E, Outside at 1.5 m level is in the range of **3.94 to 4.35km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 30), the overall quality of concrete is assessed to be **GOOD** (Table 22).



- 9) The UPV measurements were taken using surface probing technique on the Chimney wall, North side, outside at 1.5 m level is in the range of **3.93 to 4.29km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 31), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 10) The UPV measurements were taken using surface probing technique on the Chimney wall, N-W, Out Side at 1.5 m level is in the range of **3.91to 4.06km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 32), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 11) The UPV measurements were taken using surface probing technique on the Chimney wall, S-E, Outside at 10m level are in the range of **3.96 to 4.22km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 33), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 12) The UPV measurements were taken using surface probing technique on the Chimney wall, N-W, Outside at 10m level are in the range of **3.92 to 4.29km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 34), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 13) The UPV measurements were taken using surface probing technique on the Chimney wall, South side, Outside at 10m level are in the range of **4.01to 4.23km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 35), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 14) The UPV measurements were taken using surface probing technique on the Chimney wall, North side, outside at 10m level are in the range of **3.96 to 4.26km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 36), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 15) The UPV measurements were taken using surface probing technique on the Chimney wall, S-E, Outside at 10m level are in the range of **3.94 to 4.26km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 37), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 16) The UPV measurements were taken using surface probing technique on the Chimney wall, West side, Outside at 18 m level are in the range of **4.13 to 4.28km/sec**. When these values



- are compared with the velocity criteria of IS: 516(Part V) 2018 (Also reproduced in Table 38), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 17) The UPV measurements were taken using surface probing technique on the Chimney wall, South side, outside at 18 m level are in the range of **3.94 to 4.25km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 39), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 18) The UPV measurements were taken using surface probing technique on the Chimney wall, East side, Outside at 18 m level are in the range of **4.04 to 4.29km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 40), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 19) The UPV measurements were taken using surface probing technique on the Chimney wall, West side, Outside at 18 m level are in the range of **3.94 to 4.29km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 41), the overall quality of concrete is assessed to be **GOOD** (Table 22).
- 20) The UPV measurements were taken using surface probing technique on the Chimney wall, N-W, Outside at 18m level are in the range of **3.97to 4.25km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 42), the overall quality of concrete is assessed to be **GOOD** (Table 22).

4.4 Concrete Core Testing

Corresponding to the 60mm concrete core extracted by random sampling technique covering different locations of Chimney UNIT #1&2 in NTPC Tanda and tested at NCB laboratory Hyderabad, the equivalent cube compressive strength of concrete of RCC Chimney are shown in Table 46. In total, 15 concrete cores were extracted from different members of the RCC Chimney.

The test results indicate that the equivalent cube compressive strength values for

- 1. RCC Chimney wall, S-E, Out Side at 1.5 m level is found to 30.65 N/mm²
- ^{2.} RCC Chimney wall, S-W, Inside at 1.5 m level is found to 34.08 N/mm²
- 3. RCC Chimney wall, N-W, north, inside at 1.5 m level is found to 29.26 N/mm²
- 4. RCC Chimney wall, N-W, Outside at 1.5 m level is found to 27.84 N/mm²
- 5. RCC Chimney wall, Eastside Near stack yard, Outside at 1.5m level is found to 26.01 N/mm²
- ^{6.} RCC Chimney wall, East , N-E, Outside at 1.5 m level is found to 28.83 N/mm²



- 7. RCC Chimney wall, North side, Outside at 1.5 m level is found to 25.20 N/mm²
- 8. RCC Chimney wall, South side, Outside at 1.5 m level is found to 31.86 N/mm²
- 9. RCC Chimney wall, S-E, Outside at 10m level is found to 26.48 N/mm²
- ^{10.} RCC Chimney wall, N-W, Outside at 10 m level is found to 21.64 N/mm²
- ^{11.} RCC Chimney wall, , South side, Outside at 10 m level is found to 29.01 N/mm²
- 12. RCC Chimney wall, North side, outside at 10 m level is found to 30.35 N/mm²
- ^{13.} RCC Chimney wall, West side, Outside at 18 m level is found to 27.93 N/mm²
- ^{14.} RCC Chimney wall, South side, Outside at 18 m level is found to 27.41 N/mm²
- 15. RCC Chimney wall, East side, Outside at 18 m level is found to 29.31 N/mm²

In total, 15 nos. tested cores all of them found to have equivalent cube compressive strength more than specified characteristic compressive strength of M25 grade concrete (which is reproduced in Table 46).

4.5 Concrete Cover

The concrete cover depth to rebars in RCC members is measured with Ferro-scanner and a measuring tape/scale in the places where concrete is exposed and accessible for direct measurement. Nominal cover to reinforcement to meet durability requirement is given in **IS-456: Table 16-clause 26.4.2**, the measured cover to reinforcement steel in the selected RCC members are given in Table 44.

- The Concrete cover to Reinforcing bars of RCC Chimney wall, S-E, Out Side at 1.5 m level during testing using Ferro scanner meter is found to vary from 68mm-78mm (average 72 mm)
- The Concrete cover to Reinforcing bars of RCC Chimney wall, S-W, Inside at 1.5 m level during testing using Ferro scanner meter is found to vary from 62mm-76mm (average 70 mm)
- 3. The Concrete cover to Reinforcing bars of RCC Chimney wall, N-W, north, inside at 1.5 m level during testing using Ferro scanner meter is found to vary from 66mm-72mm (average 70 mm)



- 4. The Concrete cover to Reinforcing bars of RCC Chimney wall, N-W, Outside at 1.5 m level during testing using Ferro scanner meter is found to vary from 66mm-72mm (average 69 mm)
- 5. The Concrete cover to Reinforcing bars of RCC Chimney wall, East side Near stack yard, Outside at 1.5 m level during testing using Ferro scanner meter is found to vary from **64mm**–**72mm** (average **68 mm**)
- 6. The Concrete cover to Reinforcing bars of RCC Chimney wall, N-E, Outside at 1.5 m level during testing using Ferro scanner meter is found to vary from **68mm–74mm** (average **69 mm**)
- 7. The Concrete cover to Reinforcing bars of RCC Chimney wall, North side, Outside at 1.5 m level during testing using Ferro scanner meter is found to vary from **68mm-74mm** (average **71 mm**)
- 8. The Concrete cover to Reinforcing bars of RCC Chimney wall, South side, Outside at 1.5 m level during testing using Ferro scanner meter is found to vary from 66mm-74mm (average 70 mm)
- 9. The Concrete cover to Reinforcing bars of RCC Chimney wall, S-E, Outside at 10m level during testing using Ferro scanner meter is found to vary from 66mm-74mm (average 70 mm)
- 10. The Concrete cover to Reinforcing bars of RCC Chimney wall, N-W, Outside at 10 m level during testing using Ferro scanner meter is found to vary from 66mm-72mm (average 69 mm)
- 11. The Concrete cover to Reinforcing bars of RCC Chimney wall, South side, Outside at 10 m level during testing using Ferro scanner meter is found to vary from **70mm–76mm** (average **72 mm**)
- 12. The Concrete cover to Reinforcing bars of RCC Chimney wall, North side, outside at 10 m level during testing using Ferro scanner meter is found to vary from **68mm-72mm** (average **71 mm**)
- 13. The Concrete cover to Reinforcing bars of RCC Chimney wall, West side, Outside at 18 m level during testing using Ferro scanner meter is found to vary from **68mm–74mm** (average **71 mm**)



- 14. The Concrete cover to Reinforcing bars of RCC Chimney wall, South side, Outside at 18 m level during testing using Ferro scanner meter is found to vary from **68mm–74mm** (average **70 mm**)
- 15. The Concrete cover to Reinforcing bars of RCC Chimney wall, East side, Outside at 18 m level during testing using Ferro scanner meter is found to vary from **68mm-74mm** (average **71 mm**)

The Concrete cover within the specified limits to meet durability requirement as per IS: 456-2000 (Refer Table 16 of IS: 456-2000) which is Reproduced in Table 43

4.6 Carbonation

Table- 45 shows test results of carbonation testing done on 15 no. Concrete Cores extracted from various representative concrete samples. The results indicate that the values of depth of carbonation in all different locations of RCC Chimney are varying from **0-8 mm**.

Based on the above carbonation study carried on different selected RCC members at several locations the carbonation depth is found to be within the concrete cover region.

4.7 Half-Cell Potential Test

Half-cell potential (HCP) measurements using copper, copper-sulfate half-cell technique as per ASTM C-876 (Standard test method for corrosion potentials of uncoated reinforcing steel in concrete) were taken at site to ascertain corrosion status of reinforcing bars of various locations of RCC Chimney unit #1&2 NTPC Tanda. The measurements were done on different locations randomly selected locations and comprising of representative samples for the structure.

Test results (refer Table- 48) when compared with the corrosion criteria as per ASTM C-876 (Table-47) indicate that probability of corrosion is found to be in "Transit State".

4.8 Chemical Analysis

The chemical analysis of water and powdered samples extracted from different elements of RCC Chimney collecting by random sampling technique. This covered chloride content, sulphate content per cum of concrete as well pH value of powdered samples. The test results as obtained in NCB laboratory are shown in Table- 49. Analysis of interpretation of test results given as under:



- 1) Based on the results obtained from laboratory the range of chloride content in the Chimney wall, S-E, Out Side at 1.5 m level was found to vary from 0.216 kg/m³ to 0.192 kg/m³ with an average value of **0.204 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content is found to be vary from 2.48% to 2.36% by mass of the cement in mix with an average of **2.42%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found to vary from 11.34 to 11.28 with an average of **11.31** which is less than the specified limit to resist the corrosion.
- 2) Based on the results obtained from laboratory the range of chloride content in the Chimney wall, S-W, Inside at 1.5 m level was found to vary from 0.192 kg/m³ to 0.216 kg/m³ with an average value of **0.204 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content is found to be vary from 2.08% to 2.16% by mass of the cement in mix with an average of **2.12%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found to vary from 11.32 to 11.08 with an average of **11.20** which is less than the specified limit to resist the corrosion.
- 3) Based on the results obtained from laboratory the range of chloride content in the Chimney wall, N-W, north, inside at 1.5 m level was found to vary from 0.192 kg/m³ to 0.168 kg/m³ with an average value of **0.18 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content is found to be vary from 2.32% to 2.72% by mass of the cement in mix with an average of **2.52%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found to vary from 11.20 to 11.06 with an average of **11.13** which is less than the specified limit to resist the corrosion.
- 4) Based on the results obtained from laboratory the range of chloride content in the Chimney wall, N-W, Outside at 1.5 m level was found to vary from 0.192 kg/m³ to 0.120 kg/m³ with an average value of **0.156 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content is found to be vary from 2.56% to 2.64% by mass of the cement in mix with an average of **2.60%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found to vary from 11.10 to 11.30 with an average of **11.20** which is less than the specified limit to resist the corrosion.



- 5) Based on the results obtained from laboratory the range of chloride content in the Chimney wall, East side Near stack yard, Outside at 1.5 m level was found to vary from 0.192 kg/m³ to 0.144 kg/m³ with an average value of **0.168 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content is found to be vary from 2.72% to 2.48% by mass of the cement in mix with an average of **2.60%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found to vary from 11.25 to 11.36 with an average of **11.30** which is less than the specified limit to resist the corrosion.
- 6) Based on the results obtained from laboratory the range of chloride content in the Chimney wall, N-E, Outside at 1.5 m level was found to vary from 0.216 kg/m³ to 0.192 kg/m³ with an average value of **0.204 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content is found to be vary from 2.24% to 2.64% by mass of the cement in mix with an average of **2.44%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found to vary from 11.32 to 11.42 with an average of **11.37** which is less than the specified limit to resist the corrosion.
- 7) Based on the results obtained from laboratory the range of chloride content in the Chimney wall, N-W, Outside at 10 m level was found to vary from 0.192 kg/m³ to 0.168 kg/m³ with an average value of **0.180 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content is found to be vary from 2.16% to 2.48% by mass of the cement in mix with an average of **2.32%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found to vary from 11.46 to 11.38 with an average of **11.42** which is less than the specified limit to resist the corrosion.
- 8) Based on the results obtained from laboratory the range of chloride content in the Chimney wall, South side, Outside at 10 m level was found to vary from 0.216 kg/m³ to 0.192 kg/m³ with an average value of **0.204 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content is found to be vary from 2.24% to 2.28% by mass of the cement in mix with an average of **2.26%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found to vary from 11.28 to 11.36 with an average of **11.32** which is less than the specified limit to resist the corrosion.



- 9) Based on the results obtained from laboratory the range of chloride content in the Chimney wall, West side, Outside at 18m level was found to vary from 0.168 kg/m³ to 0.216 kg/m³ with an average value of **0.192 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content is found to be vary from 2.72% to 2.48% by mass of the cement in mix with an average of **2.60%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found to vary from 11.24 to 11.32 with an average of **11.28** which is less than the specified limit to resist the corrosion.
- 10) Based on the results obtained from laboratory the range of chloride content in the Chimney wall, East side, Outside at 18 m level was found to vary from 0.096 kg/m³ to 0.168 kg/m³ with an average value of **0.132 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content is found to be vary from 2.72% to 2.24% by mass of the cement in mix with an average of **2.48%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value is found to vary from 11.06 to 11.20 with an average of **11.13** which is less than the specified limit to resist the corrosion.

5.0 Conclusions:

The following Conclusions can be broadly made from the testing results:

- i) Based on Ultrasonic Pulse Velocity, Rebound Hammer testing & Core testing done on representative samples (random sampling technique) on RCC members, the results have given Good quality of concrete. The compressive strength of the samples extracted from the Chimney is found meeting the required limit for M25 Grade of concrete. Also, distress in the form of cracks, spalling of concrete and exposure of reinforcing rebar in some locations of RCC Chimney due to some issues which cannot be overlooked.
- ii) Based on the Half-Cell potential measurements done by random sampling technique at various locations and visual observations of RCC Chimney given an initiation signal of corrosion and indicate that probability of corrosion is found to be in "Transit State". Carbonation is found 0-8 mm after 25 years' exposure to existing environment where as concrete cover of RCC members are found to vary from 68 72 mm.



- iii) The amount of Soluble Sulphates in the concrete of RCC members is within the specified limits and chloride content in the concrete is also within the specified limit and pH values are lower than the specified limit in all RCC members.
- iv) The chemical test results of water sample shows that the Organic matter, Sulphate content, Chloride content, Inorganic content and pH value are within the permissible limits pH value are lower than the specified limit in all RCC members as per (IS:456-2000& IS: 3025-1984).

6.0 Recommendations

The following steps shall be taken to repair the cracks & strengthening of RCC Chimney:

Part I: Providing Total Platform system (Scaffolding):

Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm diameter M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S.clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer in- In charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding.

Part-II: Repair and Strengthening:

i) <u>Chipping:</u> Cover concrete around the horizontal, vertical cracks & spalling of concrete shall be chipping off to the depth up to 40mm on RCC walls. The chipping in the spalled portion of the Shells and RCC Walls shall be limited up to the cover region. Chipping of loose/hollow sounding concrete can be done by striking the doubtful surfaces with 2 lb hammer.

ii) Treatment for Cracks:

Filling of Cracks: The cracks/voids are to be widened by cutting V-grooves of 10mm
 x 10mm size and sealed with approved epoxy repair mortar.



- After the sealing, 12mm dia galvanized steel injection nipples are to be inserted in the crack area and also wherever honeycombing is found by drilling holes of required diameter up to the depth of 60 120 mm at required spacing (generally 350 mm staggered spacing). The drilled holes must be made dust free by blowing compressed air and should be sealed after the insertion of the nozzle with approved adhesive and allowed to cure.
- After the nipples are injected and cured, grouting in the proportion recommended by the manufacturer into the cracks/honeycombed area of concrete/masonry shall be done using suitable gun/pump at required pressure. Once the grouting work is finished, the extruding nipples can be cut-off after the curing period.
- **iii)** Reinforcement Corrosion Treatment: Wherever reinforcing rebar is found corroded in RCC walls
 - a) Remove the rust by manually or suitable means to make corroded reinforcing bars rust free.
 - b) Provide and apply corrosion protection using 2 coats of anticorrosive Zn rich epoxy phenolic rebar protection system of approved brand on the exposed old reinforcement by brush with interval of 24 hours between coats and corrosion protection of exposed old reinforcing bars.
 - c) Provide and apply concrete penetrating corrosion inhibitor (CPCI) of approved brand over the entire finished surface are obtained after removal of distressed concrete in 2 coats @ of 4m²/ltr/coat approximately.
- iv) <u>Bond Coat:</u> After chipping off the concrete cover, provide and apply structural grade two component epoxy bond coat prior to application of any type of mortar conforming to ASTM C 881 -13 Type II tested as per ASTM C -882-13 to ensure bond between old and new concrete by brush application. (Material manufacture from STP/BASF/SIKA/FOSRAC/KRISHNA Conchem/Pidilite or equivalent)
- v) Making up lost section with Polymer Modified Mortar (PMM): For repair of patches having, apply average 40mm PMM in 2-3 layers using SBR Latex conforming to ASTM C-1059-13 Type-I in damaged areas (1 Cement-3 part graded cleaned river sand + 20 % latex by weight of cement) with 0.35 w/c ratio, in 10-15 mm thick layers by applying bond coat between successive/each. (Material manufacture either from STP/BASF/SIKA/FOSRAC or equivalent)



- vi) <u>Protective coating:</u> Before applying the protective coating on RCC walls and the outer wall surface shall be cleaned by scrubbing with hard steel brush to remove loose particles, disintegrated concrete, deposited smoke and dust particles etc. The scrubbed surface is cleaned by air blowing and then dries it completely. Apply a silane siloxane priming coat as primer compatible to substrate (Cementitious). Over it, applying two or more coats of ready mixed anti carbonation UV resistant acrylic polymer-based water proofing coatings (having minimum 60% solid content) with broad brush or roller over prepared surface, using not less than theoretical Consumption as per the manufacturer's specification and direction of Engineer In Charge (time gap between two coats of coating shall be not less than 8 hrs). Total dry film thickness (DFT) including primer will be 225 240 microns.
 - vi) For the top 15m part of the chimney, providing protective coating, in signal red and white bands (2 bands) with contractor's supply of Epoxy-phenolic IP Net paints including priming coat, intermediate coat and polyurethane top coat with paints from approved firms after surface preparation. Total dry film thickness (DFT) including primer will be 185 215 microns, all complete as per direction of Engineer-In-Charge.

Note:

- 1. Before taking up any repair work, the dryness of substrate concrete must be ensured for effective application of several repair materials. Remove oil, grease, wax, Cement laitance, loose particles and other contaminants, scarifying or mechanically wire brushing followed by air jet from the substrate concrete.
- 2. During repair works of chimney measures should be taken up in accordance with relevant safety standards and safety guidelines of Occupational safety & Health Administration (OSHA) for construction, arrangement like safety nets/platforms should be done.
- 3. The extraction of concrete cores, chemical analysis samples and other tests shall be carried out up to height wherever safe access is provided as taking the equipment for the extraction of concrete cores at higher reaches would not be possible due to very less width of the platforms available at different heights.

......



- g. Chemical Analysis to determine Chloride content, Sulphate content and pH value of Concrete Powder Samples in laboratory.
- iii) Analysis and interpretation of test results/data obtained in (i) & (ii) above.
- iv) Recommendations on remedial measures using indigenously available compatible repair materials. Preparation of BOQ covering selected items for repair including rate analysis & preparation of specifications and methodology for carrying out effective repair shall also be provided.
- v) The report covering (i) to (iv) above.

2.0 DATA PROVIDED BY SPONSOR

• Year of Construction of the subject structure was around 1988.

3.0 INVESTIGATION CARRIED OUT BY NCB

3.1 Visual Observations

To collect the data of distress on members of TG Unit#1 at NTPC, Tanda. Visual observation survey was carried out jointly by NCB team and the concerned NTPC officials during the visits for condition assessment from 08th May 2023 to 17th May 2023.

3.2 Rebound Hammer Testing (RHT) As Per IS: 516-2020 (Part-V, Sec-IV).

Rebound hammer testing technique was used for assessing the likely surface compressive strength of concrete. Basic principle of rebound hammer test is given below.

When the plunger of rebound hammer is pressed against the surface of the concrete, the spring-controlled mass rebounds and the extent of such rebound depends upon the surface hardness of concrete. The surface hardness and therefore the rebound are taken to be related to the compressive strength of the concrete. The rebound is read off along a graduated scale and is designated as the rebound number or rebound index. It is also to be noted that rebound indices are indicative of compressive strength of concrete to a limited depth from the surface. If the concrete in a particular member has internal micro cracking, flaws or heterogeneity across the cross-section, rebound hammer indices will not indicate the same. **IS:** 516(Part 5)-2020 **Section 4 states,** "As such, the estimation of strength of concrete by rebound hammer method cannot be held to be very accurate and probable accuracy of prediction of concrete strength in a structure is ± 25 percent." However, the test should only be used as indication of the probable compressive strength of concrete.



The test was carried out using a Schmidt's Rebound Hammer on randomly selected accessible TG Unit#1 at NTPC, Tanda. The members which were tested were made accessible, so the testing done on accessible members. The surfaces at the chosen locations were thoroughly cleaned with carborandum stone/grinding stone and readings were taken around each point. The average of the readings becomes the rebound index at that point of observation.

3.3 Ultrasonic Pulse Velocity (UPV) Method as per IS: 516 (Part V) – 2018.

UPV is a non-destructive evaluation method for assessing the quality of concrete; density, homogeneity and uniformity. Basic principle of UPV method is given below.

In this method, an ultrasonic pulse of longitudinal vibrations is produced by an electro-acoustical transducer which is held in contact with one surface of the concrete member under test. After traversing a known path length of the member, the pulse of vibrations is converted into an electric signal by a second electro-acoustical transducer, and an electric timing circuit enables the transit time of the pulse to be measured, from which the pulse velocity is calculated. For the present investigation, the pulse velocity measurements were obtained by direct transmission of ultrasonic pulses through the concrete, i.e. by "cross probing". For this purpose, the transducers were held on opposite faces of the beam and columns.

The Ultrasonic Pulse Velocity in concrete is mainly related to its density and modulus of elasticity. This in turn depends upon the materials and mix proportions used in making concrete as well as methods of placing, compaction and curing of concrete. If the concrete is not thoroughly compacted, or if there is segregation of concrete during placing or there are internal cracks or flaws, the pulse velocity will be lower, although the same materials and mix proportions are used.

The underlying principle of assessing the quality of concrete from UPV method is that, comparatively higher pulse velocities are obtained when the 'quality' of concrete in terms of density, homogeneity and uniformity is good. In case of concrete of poorer quality, lower velocities are obtained.

On this basis, guidelines have been evolved for characterizing the quality of concrete in structures in terms of ultrasonic pulse velocity. Such guidelines reproduced from **IS: 516 (Part V) – 2018.**



3.4 Concrete Core Testing

Concrete cores of 60-mm diameter were extracted from different structural members identified, to estimate equivalent cube compressive strength of the structure. Equivalent cube strength does not indicate 28 days' standard cube strength rather it represents the in-situ cube strength, and is compared vis-à-vis strength used in design calculation with safety of the structure under load in mind.

There are a number of parameters, which influence the measured compressive strengths. Such parameters include size (diameter) of the specimen, length-to-diameter ratio, direction of drilling, method of capping, drilling operations, moisture conditions of cores at the time of testing etc. Many of these parameters have been standardized.

The second set of variables relates to the intrinsic difference that exists between the concrete in structure and in standard laboratory-controlled specimens, the core specimens representing the former. Such intrinsic differences are due to inherent differences that may occur in mixing constituents, degree of compaction, extent of curing and temperature condition in two cases. The procedure for sampling, preparing, testing and calculating the equivalent compressive strength with corrections are given in **IS: 516-2018**.

The net effect of all these parameters is that the strength of concrete cores is in general lower than those of laboratory controlled specimens, for this reason **IS: 456-2000** (Code of Practice for Plain and Reinforced Concrete) consider that concrete in the area represented by a core test is adequate if" the average equivalent cube strength of the cores is equal to at least 85 percent of the specified for the corresponding age and if no single core has strength lower than 75 percent of the specified value".

3.5 Carbonation Test

Carbonation is the formation of calcium carbonate (CaCO₃) by chemical reactions in concrete. When CO₂ penetrates into the hardened concrete, it reacts with portlandite [Portlandite is a mineral formed during the curing of concrete, calcium hydroxide Ca(OH)₂] in the presence of moisture forming CaCO₃. The rate of carbonation depends mainly on the relative humidity, the concentration of CO₂, the penetration pressure and the temperature of the environment where concrete is placed.

As carbon dioxide enters the concrete from the environment, it reacts with calcium hydroxide present in the concrete and depending upon the quality of concrete it reduces the



alkalinity of the pore fluids, depassivating ferric oxide layer on reinforcing bar which in turn initiates the process of corrosion in reinforcement.

To determine the depth of carbonation, concrete is exposed and sprayed with a pH indicator (solutions of 1% phenolphthalein in 70% ethyl alcohol). The demarcation between the region, which turns into magenta (dark pink colour) and the region showing no change in colour indicate the carbonation front.

Carbonation measurements were recorded immediately after the cores specified in col. 3.4 were extracted.

3.6 Half-Cell Potential (HCP) Measurements

This test method covers the estimation of electrical Half Cell Potential of uncoated reinforcing steel, to determine corrosion activity using reference electrode copper; copper sulphate half-cell. It is not possible to expose all the reinforcements in the structural element and observe the extent of corrosion. So, this method has been very convenient to assess the condition of the entire length of a member by exposing a portion of the reinforcement at a suitable location, which measures the half-cell potential on the entire length, by placing the reference electrode on the wet concrete surface.

The Half-Cell Potential measurement is based on the principal of the corrosion, being an electro-chemical process, induces certain voltage to the reinforcement steel that is corroding. The wetting of the concrete is required to make the portion between the concrete surface and the reinforcing bar as electrolytes.

A criterion for assessment for corrosion of steel is given as under ASTM C-876 below.

- ➤ If potentials over an area are more positive than -200 mV, there is a greater than 90% probability that no reinforcing steel corrosion is occurring in that area at the time of measurement.
- ➤ If potentials over an area are in the range of -200 mV to -350 mV, corrosion activity of the reinforcing steel in that area is uncertain.
- ➤ If potentials over an area are more negative than -350 mV, there is a greater than 90% probability that reinforcing steel corrosion is occurring in that area at the time of measurement.

Adequate numbers of accessible members were selected from various locations to conduct Half-Cell Potential test.



3.7 Concrete Cover Study

Concrete cover depth to reinforcing bars shall be done by using Ferro Scanner instrument on safe & accessible locations. This instrument detects the reinforcing bars and mesh, to measure their cover depth and determine the bar diameter. The instrument is based on the magnetic technique and is calibrated for different purposes. The cover depth is important from the point of view of estimation of initiation of corrosion of reinforcing bars.

For a longitudinal reinforcing bar in a Column nominal cover shall in any case not be less than 40mm or less than the diameter of such bar as per clause 26.4.2.1 of IS: 456-2000. Nominal cover to meet durability requirement for footing, minimum cover shall be 50mm as per clause 26.4.2.2 of IS: 456-2000.

Minimum values of nominal cover of normal weight aggregate concrete to be provided to all reinforcement including links to meet specified period of fire resistance shall be as per Table 16A of IS:456-2000.

Minimum values for the nominal cover of normal weight aggregate concrete which should be provided all reinforcement including links depending of exposure condition shall be as per the Table 5 of IS: 456-2000.

3.8 Chemical Analysis

Corrosion of reinforcing steel due to chlorides in concrete is one of the most common environmental attacks that lead to deterioration of concrete structures. Whenever there is chloride in concrete there is an increased risk of corrosion of embedded metal. Chloride content is then expressed in kg per cubic meter of concrete and compared with the values of limits of chloride contents of concrete (**Table 7 of IS: 456–2000**).

Sulphates (SO₃) are present in most cements and in some aggregates; excessive amounts of water-soluble sulphate from these or other mix constituents can cause expansion and disruption of concrete. To prevent it, **IS:** 456-2000 clause-8.2.5.3 states that the total water-soluble sulphate content of the concrete mix, expressed as SO₃, should not exceed 4 percent by mass of the cement in the mix. The sulphate content should be calculated as the total from the various constituents of the mix.

The pH value of the concrete should be above 11.5 to maintain alkalinity of concrete surrounding the embedded steel. A reduction in the pH value of concrete indicates loss of passive layer around the reinforcement which protects the steel from distress.



For analyzing Chloride content and pH of concrete, concrete powder samples were extracted from 0-25mm, 25-50mm depths at identified locations and then tested as per IS:14959(Part 2) -2001 (Determination of water soluble and acid soluble Chlorides in Mortar and Concrete – Method of Test).

Adequate numbers of accessible members were selected from various locations to extract concrete powders for chemical test.

4.0 RESULTS AND DISCUSSION

4.1. Visual Observations

The height of the TG-Unit#1 is 18m. Visual observations and testing carried out at 4m, 8.5m, 18m, and height. Distress, Signs of cracks, surface voids and exposure of steel reinforcement bars observed on the TG-Unit#1 at different heights. Distress and Honeycomb observed at a few locations of Interior and exterior RCC members. The visual observations and photographs are shown **Annexure 1**.

4.2. Rebound Hammer Testing-Completed values

Rebound Hammer testing was carried out on various identified (Reinforced Cement Concrete) members of TG-Unit#1 using random sampling technique. The results of surface compressive strength obtained by Rebound Hammer testing are given in Table 2 to 26. Surface Compressive strength results of concrete as obtained on different hardened concrete surfaces of Members are summarized as:

- 1) Surface compressive strength of concrete obtained on TG-Unit#1, Turbine Pedestal at West side by Rebound Hammer Testing is found to vary from 38.83 N/mm² to 41.09 N/mm² with an average surface compressive strength of 39.96 N/mm² (Refer Table 2).
- 2) Surface compressive strength of concrete obtained on TG-Unit#1, Turbine Pedestal at East side by Rebound Hammer Testing is found to vary from 38.83 N/mm² to 42.22 N/mm² with an average surface compressive strength of 39.68 N/mm² (Refer Table 3).
- 3) Surface compressive strength of concrete obtained on TG-Unit#1, Turbine Pedestal at East side by Rebound Hammer Testing is found to vary from 38.83 N/mm² to 41.66 N/mm² with an average surface compressive strength 40.10 N/mm² (Refer Table 4).
- 4) Surface compressive strength of concrete obtained on TG-Unit#1, Turbine Pedestal at West side by Rebound Hammer Testing is found to vary from 39.39 N/mm² to 41.09 N/mm² with an average surface compressive strength of 39.68 N/mm² (Refer Table 5).



- 5) Surface compressive strength of concrete obtained on TG-Unit#1, Turbine bottom level at West side by Rebound Hammer Testing is found to vary from 38.83 N/mm² to 40.53 N/mm² with an average surface compressive strength of 39.82 N/mm² (Refer Table 6).
- 6) Surface compressive strength of concrete obtained on TG-Unit#1, A6 Column by Rebound Hammer Testing is found to vary from **38.26** N/mm² to **40.53** N/mm² with an average surface compressive strength of **39.68** N/mm² (Refer Table 7).
- 7) Surface compressive strength of concrete obtained on TG-Unit#1, A5 Column @4m by Rebound Hammer Testing is found to vary from 39.39N/mm² to 40.53N/mm² with an average surface compressive strength of 39.82N/mm² (Refer Table 8).
- 8) Surface compressive strength of concrete obtained on TG-Unit#1, A2 Column by Rebound Hammer Testing is found to vary from 39.39 N/mm² to 42.22 N/mm² with an average surface compressive strength of 40.24 N/mm² (Refer Table 9).
- 9) Surface compressive strength of concrete obtained on TG-Unit#1, A3 Column @4m by Rebound Hammer Testing is found to vary from 38.83 N/mm² to 41.66 N/mm² with an average surface compressive strength of 39.96 N/mm² (Refer Table 10).
- 10) Surface compressive strength of concrete obtained on TG-Unit#1, at B5 Column @6m by Rebound Hammer Testing is found to vary from 38.26 N/mm² to 41.66 N/mm² with an average surface compressive strength of 39.82 N/mm² (Refer Table-11).
- 11) Surface compressive strength of concrete obtained on TG-Unit#1, at B1 Column @6m by Rebound Hammer Testing is found to vary from 39.39 N/mm² to 41.09 N/mm² with an average surface compressive strength of 40.24 N/mm² (Refer Table 12).
- 12) Surface compressive strength of concrete obtained on TG-Unit#1, at B1 Column @8.5m by Rebound Hammer Testing is found to vary from 38.26 N/mm² to 42.22 N/mm² with an average surface compressive strength of 40.10 N/mm² (Refer Table 13).
- 13) Surface compressive strength of concrete obtained on TG-Unit#1, at B1 Column @8.5m by Rebound Hammer Testing is found to vary from 39.39 N/mm² to 42.22 N/mm² with an average surface compressive strength of 40.38 N/mm² (Refer Table 14).
- 14) Surface compressive strength of concrete obtained TG-Unit#1, at A4 Column @4m by Rebound Hammer Testing is found to vary from 37.70 N/mm² to 41.66 N/mm² with an average surface compressive strength of 39.54 N/mm² (Refer Table 15).



- 15) Surface compressive strength of concrete obtained on TG-Unit#1, A1 Column @8.5m by Rebound Hammer Testing is found to vary from **38.26** N/mm² to **42.22** N/mm² with an average surface compressive strength of **39.96**N/mm² (Refer Table 16).
- 16) Surface compressive strength of concrete obtained on TG-Unit#1, A5 Column @8.5m by Rebound Hammer Testing is found to vary from **38.83** N/mm² to **41.09** N/mm² with an average surface compressive strength of **39.82** N/mm² (Refer Table 17).
- 17) Surface compressive strength of concrete obtained on TG-Unit#1, A3 Column by Rebound Hammer Testing is found to vary from **38.26** N/mm² to **41.66** N/mm² with an average surface compressive strength of **39.96** N/mm² (Refer Table 18).
- 18) Surface compressive strength of concrete obtained on TG-Unit#1, A4 Column by Rebound Hammer Testing is found to vary from **38.26** N/mm² to **41.09** N/mm² with an average surface compressive strength of **39.68** N/mm² (Refer Table 19).
- 19) Surface compressive strength of concrete obtained on TG-Unit#1, B5 Column by Rebound Hammer Testing is found to vary from **37.13** N/mm² to **42.79** N/mm²with an average surface compressive strength of **39.96** N/mm² (Refer Table 20).
- 20) Surface compressive strength of concrete obtained on TG-Unit#1, A1-B1 Beam 12.5m level by Rebound Hammer Testing is found to vary from 37.13 N/mm² to 41.09 N/mm² with an average surface compressive strength of 39.82 N/mm² (Refer Table 21).
- 21) Surface compressive strength of concrete obtained on TG-Unit#1, B1 Column 12.5m level by Rebound Hammer Testing is found to vary from **38.83** N/mm² to **42.22** N/mm² with an average surface compressive strength of **40.10** N/mm² (Refer Table 22).
- 22) Surface compressive strength of concrete obtained on TG-Unit#1, A7-B7 Beam 8.5m level by Rebound Hammer Testing is found to vary from 37.13 N/mm² to 42.22 N/mm² with an average surface compressive strength of 39.25 N/mm² (Refer Table 23).
- 23) Surface compressive strength of concrete obtained on TG-Unit#1, A1 Column 12.5m level by Rebound Hammer Testing is found to vary from 40.53 N/mm² to 41.09 N/mm² with an average surface compressive strength of 40.95 N/mm² (Refer Table 24).
- 24) Surface compressive strength of concrete obtained on TG-Unit#1, A6-B6 Beam 12.5m level by Rebound Hammer Testing is found to vary from **38.26** N/mm² to **39.96** N/mm² with an average surface compressive strength of **39.39** N/mm² (Refer Table 25).



25) Surface compressive strength of concrete obtained on TG-Unit#1, A2-B2 Beam 12.5m level by Rebound Hammer Testing is found to vary from **39.39** N/mm² to **40.53** N/mm² with an average surface compressive strength of **39.96** N/mm² (Refer Table 26).

4.3. Ultrasonic Pulse Velocity Testing (UPV):

The **Ultrasonic Pulse Velocity** testing was conducted on TG-Unit#1 in the presence of concerned engineering team of NTPC. The results of the UPV values obtained on various members are as follows:

- 1) The UPV measurements were taken using cross probing technique on the TG-Unit#1, A1 Column are in the range of **3.86 to 4.38 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018(Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table -28).
- 2) The UPV measurements were taken using surface probing technique on the TG-Unit#1, A2 Column are in the range of **3.98 to 4.22 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018(Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 29).
- 3) The UPV measurements were taken using surface probing technique on the TG-Unit#1, B3 Column are in the range of **4.03 to 4.26 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018(Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 30).
- 4) The UPV measurements were taken using Surface probing technique on the TG-Unit#1, C1 Column are in the range of **3.94 to 4.19 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018(Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table -31).
- 5) The UPV measurements were taken using Surface probing technique on the TG-Unit#1, B2 Column @8 m is in the range of **4.03 to 4.22 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018(Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table -32).
- 6) The UPV measurements were taken using surface probing technique on the TG-Unit#1, A1 Column @8 m is in the range of **4.02 to 4.24km/sec**. When these values are compared



- with the velocity criteria of IS: 516 (Part V) -2018(Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table -33).
- 7) The UPV measurements were taken using surface probing technique on the TG-Unit#1, C1 Column @8 m is in the range of **3.97 to 4.15 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018(Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table -34).
- 8) The UPV measurements were taken using Cross probing technique on the TG-Unit#1, C1 Column @8 m is in the range of **3.77 to 3.88 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018(Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table -35).
- 9) The UPV measurements were taken using Cross probing technique on the TG-Unit#1, B2 Column @8 m is in the range of **3.78 to 3.83 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table -36).
- 10) The UPV measurements were taken using Cross probing technique on the TG-Unit#1, B2 Column @8 m is in the range of **3.80 to 3.91 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 37).
- 11) The UPV measurements were taken using Cross probing technique on the TG-Unit#1, B1 Column @6m are in the range of **3.81 to 4.16 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 38).
- 12) The UPV measurements were taken using Cross probing technique on the TG-Unit#1, B1 Column @8.5m are in the range of **3.77 to 3.97 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 39).
- 13) The UPV measurements were taken using Surface probing technique on the TG-Unit#1, B1 Column @8.5m are in the range of **3.96 to 4.15 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 40).



- 14) The UPV measurements were taken using cross probing technique on the TG-Unit#1, A4 Column @4m are in the range of **3.85 to 3.92 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 41).
- 15) The UPV measurements were taken using Surface probing technique on the TG-Unit#1, A1 Column @8.5m are in the range of **3.98 to 4.22 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 42).
- 16) The UPV measurements were taken using surface probing technique on the TG-Unit#1, A5 Column @8.5m are in the range of **3.98 to 4.23 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 43).
- 17) The UPV measurements were taken using surface probing technique on the TG-Unit#1, A3 Column are in the range of **3.98 to 4.23 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 44).
- 18) The UPV measurements were taken using Surface probing technique on the TG-Unit#1, A4 Column are in the range of **3.98 to 4.13 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 45).
- 19) The UPV measurements were taken using surface probing technique on the TG-Unit#1, B5 Column are in the range of **3.98 to 4.22 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 46).
- 20) The UPV measurements were taken using surface probing technique on the TG-Unit#1, A1-B1 Beam 12.5m level are in the range of **3.98 to 4.11 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 47).
- 21) The UPV measurements were taken using Cross probing technique on the TG-Unit#1, B1 Column 12.5m level are in the range of **3.80 to 3.88 km/sec**. When these values are



- compared with the velocity criteria of IS: 516 (Part V) -2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 48).
- 22) The UPV measurements were taken using Cross probing technique on the TG-Unit#1, A7-B7 Beam 8.5m level are in the range of **3.80 to 4.17 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 49).
- 23) The UPV measurements were taken using surface probing technique on the TG-Unit#1, A1 Column 12.5m level are in the range of **3.95 to 4.25 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) 2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 50).
- 24) The UPV measurements were taken using surface probing technique on the TG-Unit#1, A6-B6 Beam 12.5m level are in the range of **4.00 to 4.30 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) –2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 51).
- 25) The UPV measurements were taken using surface probing technique on the TG-Unit#1, A2-B2 Beam 12.5m level are in the range of **4.00 to 4.24 km/sec**. When these values are compared with the velocity criteria of IS: 516 (Part V) –2018 (Also reproduced in Table 27), the overall quality of concrete is assessed to be **GOOD** (Table 52).

4.4 Concrete Core Testing

Corresponding to the 60mm concrete core extracted by random sampling technique covering different locations of TG-Unit#1 in NTPC Tanda tested at NCB laboratory Hyderabad, the equivalent cube compressive strength of concrete of TG-Unit#1 are shown in Table 56. In total, 12 concrete cores were extracted from different members of the TG-Unit#1 and were tested.

The test results indicate that the equivalent cube compressive strength values for

- 1. TG-Unit#1, A1 Column is found to be 32.04 N/mm²
- 2. TG-Unit#1, A2 Column @6m is found to be 31.58 N/mm²
- 3. TG-Unit#1, B3 Column @4m is found to be 27.30 N/mm²
- 4. TG-Unit#1, C1 Column @8m is found to be 29.98 N/mm²
- 5. TG-Unit#1, B2 Column @8m is found to be 25.27 N/mm²
- 6. TG-Unit#1, A1 Column @8m is found to be 25.75 N/mm²



- 7. TG-Unit#1, C1 Column @8m is found to be 21.45 N/mm²
- 8. TG-Unit#1, C1 Column @8 m level is found to be 22.76 N/mm²
- 9. TG-Unit#1, B2 Column @8m level is found to be 33.60 N/mm²
- 10. TG-Unit#1, B2 Column @8m level is found to be 22.71 N/mm²
- 11. TG-Unit#1, A1 Column @12.5m level is found to be 27.88 N/mm²
- 12. TG-Unit#1, B2 Column @12.5m level is found to be 23.56 N/mm²

In total, 12 nos. tested cores all of them found to have equivalent cube compressive strength more than specified characteristic compressive strength of M25 grade concrete.

4.5 Concrete Cover

The concrete cover depth to rebars in members is measured with Ferro-scanner and a measuring tape/scale in the places where concrete is exposed and accessible for direct measurement. Nominal cover to reinforcement to meet durability requirement is given in **IS-456: Table 16-clause 26.4.2**, the measured cover to reinforcement steel in the selected members are given in Table 54.

- 1. The Concrete cover to Reinforcing bars of TG-Unit#1, A3 Column @4m during testing using Ferro scanner meter is found with an average of **82mm**.
- 2. The Concrete cover to Reinforcing bars TG-Unit#1, A2 Column @6m during testing using Ferro scanner meter is found with an average of **83mm**.
- 3. The Concrete cover to Reinforcing bars of TG-Unit#1, B1 Column @4m during testing using Ferro scanner meter is found with an average of **81mm**.
- 4. The Concrete cover to Reinforcing bars of TG-Unit#1, B2 Column @8.5m during testing using Ferro scanner meter is found with an average of **84mm**.
- 5. The Concrete cover to Reinforcing bars of TG-Unit#1, A6 Column @8.5m during testing using Ferro scanner meter is found with an average of **83mm**.
- 6. The Concrete cover to Reinforcing bars of TG-Unit#1, A3 Column @8.5m during testing using Ferro scanner meter is found to with an average of **82mm**.
- 7. The Concrete cover to Reinforcing bars of TG-Unit#1, B5 Column @8.5m during testing using Ferro scanner meter is found with an average of **81mm**.
- 8. The Concrete cover to Reinforcing bars of TG-Unit#1, B1 Column 8.5m level during testing using Ferro scanner meter is found with an average of **81mm**.



- 9. The Concrete cover to Reinforcing bars of TG-Unit#1, A5 Column @8.5m level during testing using Ferro scanner meter is found with an average of **82mm**.
- 10. The Concrete cover to Reinforcing bars of TG-Unit#1, A3 Column @12.5m level during testing using Ferro scanner meter is found with an average of **83mm**.
- 11. The Concrete cover to Reinforcing bars of TG-Unit#1, A1 Column 12.5m level during testing using Ferro scanner meter is found with an average of **80mm**.
- 12. The Concrete cover to Reinforcing bars of TG-Unit#1, B2 Column @12.5m level during testing using Ferro scanner meter is found with an average of **84mm**.

The Concrete cover within the specified limits to meet durability requirement as per IS: 456-2000 (Refer Table 16 of IS: 456-2000) which is Reproduced in Table 53.

4.6 Carbonation

Table-55 shows test results of carbonation testing done on 12 no. Concrete Cores extracted from various representative concrete samples. The results indicate that the values of depth of carbonation in all different locations of TG-Unit#1 were found in between **0-10 mm**.

Based on the above carbonation study carried on different selected members at several locations the carbonation depth is found to be within the concrete cover region.

4.7 Half-Cell Potential Test

Half-cell potential (HCP) measurements using copper, copper-sulfate half-cell technique as per ASTM C-876 (Standard test method for corrosion potentials of uncoated reinforcing steel in concrete) were taken at site to ascertain corrosion status of reinforcing bars of various locations of RCC members in TG-Unit#1 NTPC Tanda. The measurements were done on different locations randomly selected locations and comprising of representative samples for the structure.

Test results (refer Table-58) when compared with the corrosion criteria as per ASTM C-876 (Table-57) indicate that probability of corrosion is found to be in 'Transit State'.

4.8 Chemical Analysis

The chemical analysis of water and powdered samples extracted from different elements of RCC members in TG-Unit#1 NTPC Tanda, collecting by random sampling technique. This covered chloride content, sulphate content per cum of concrete as well pH value of powdered



samples. The test results as obtained in NCB laboratory are shown in Table- 59. Analysis of interpretation of test results given as under:

- Based on the results obtained from laboratory the range of chloride content in the A3 Column @4m of TG-Unit#1 was found to vary from 0.192 kg/m³ to 0.216 kg/m³ with an average value of **0.204 kg/m³** is within the permissible limit of 0.6 kg/m3 (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix was found to vary from 2.20 % to 2.48% with an average of **2.34%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value was found to vary from 11.55 to 11.64 with an average of **11.60** which is more than the specified limit to resist the corrosion.
- 2) Based on the results obtained from laboratory the range of chloride content in the A2 Column @6m of TG-Unit#1 was found to vary from 0.168kg/m³ to 0.192 kg/m³ with an average value of **0.18 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix was found to vary from 2.08 % to 2.64% with an average of **2.36%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value was found to vary from 11.26 to 11.15 with an average of **11.20** which is slightly less than the specified limit to resist the corrosion.
- 3) Based on the results obtained from laboratory the range of chloride content in the B1 Column @4m of TG-Unit#1 was found to vary from 0.216 kg/m³ to 0.168 kg/m³ with an average value of **0.19 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS: 456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix was found to vary from 2.16 % to 2.64% with an average of **2.40%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value was found to vary from 11.45 to 11.14 with an average of **11.30** which is less than the specified limit to resist the corrosion.
- 4) Based on the results obtained from laboratory the range of chloride content in the B2 Column @8.5m of TG-Unit#1 was found to vary from 0.192 kg/m³ to 0.168 kg/m³ with an average value of **0.18 kg/m³** is within the permissible limit of 0.6 kg/m3 (As per IS:456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix was found to vary from 2.72 % to 2.88% with an average of **2.80%** which is within the permissible limit of 4%



- (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value was found to vary from 11.22 to 11.12 with an average of **11.17** which is less than the specified limit to resist the corrosion.
- Based on the results obtained from laboratory the range of chloride content in the A6 Column @8.5m of TG-Unit#1 was found to vary from 0.192 kg/m³ to 0.216 kg/m³ with an average value of **0.20kg/m³** is within the permissible limit of 0.6 kg/m3 (As per IS:456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix was found to vary from 2.24% to 2.84% with an average of **2.54%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value was found to vary from 11.25 to 11.09 with an average of **11.17** which is less than the specified limit to resist the corrosion.
- 6) Based on the results obtained from laboratory the range of chloride content in the A3 Column @8.5m of TG-Unit#1 was found to vary from 0.192 kg/m³ to 0.168 kg/m³ with an average value of **0.18kg/m³** is within the permissible limit of 0.6 kg/m3 (As per IS:456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix was found to vary from 2.36 % to 2.72% with an average of **2.54%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value was found to vary from 11.34 to 11.14 with an average of **11.24** which is less than the specified limit to resist the corrosion.
- 7) Based on the results obtained from laboratory the range of chloride content in the B5 Column @8.5m of TG-Unit#1 was found to vary from 0.192 kg/m³ to 0.216 kg/m³ with an average value of **0.20 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS:456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix was found to vary from 2.76 % to 2.72% with an average of **2.74%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value was found to vary from 11.28 to 11.06 with an average of **11.17** which is less than the specified limit to resist the corrosion.
- 8) Based on the results obtained from laboratory the range of chloride content in the A3 Column @12.5m level of TG-Unit#1 was found to vary from 0.168 kg/m³ to 0.216 kg/m³ with an average value of **0.19 kg/m³** is within the permissible limit of 0.6 kg/m3 (As per IS:456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix was found to



vary from 2.28 % to 2.32% with an average of **2.30%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value was found to vary from 11.29 to 11.10 with an average of **11.19** which is less than the specified limit to resist the corrosion.

- 9) Based on the results obtained from laboratory the range of chloride content in the B2 Column @12.5m level of TG-Unit#1 was found to vary from 0.168 kg/m³ to 0.192 kg/m³ with an average value of **0.18 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS:456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix was found to vary from 2.56 % to 2.36% with an average of **2.46%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value was found to vary from 11.41 to 11.21 with an average of **11.31** which is less than the specified limit to resist the corrosion.
- Based on the results obtained from laboratory the range of chloride content in the A3 Column @12.5m level of TG-unit#5 was found to vary from 0.192 kg/m³ to 0.144 kg/m³ with an average value of **0.17 kg/m³** is within the permissible limit of 0.6 kg/m³ (As per IS:456-2000 Table 7). The range of Sulphate (SO3) content by mass of the cement in mix was found to vary from 2.76 % to 2.80% with an average of **2.78%** which is within the permissible limit of 4% (As per clause-8.2.5.3 of IS: 456-2000). The range of pH value was found to vary from 11.23 to 10.88 with an average of **11.05** which is less than the specified limit to resist the corrosion.

5.0 Conclusions:

The following Conclusions can be broadly made from the testing results:

- i) Based on Rebound hammer testing to evaluate the average likely surface hardness on RCC members, the results were found satisfactory and it varies in between 39-40.
- ii) Based on Ultrasonic Pulse Velocity to evaluate Quality of concrete on RCC members, the results were found to vary between Good Quality of concrete.
- iii) The compressive strength of the concrete core samples extracted from the TG-Unit#1 were found meeting the required compressive strength more than specified characteristic compressive strength of M25 grade concrete.



- iv) Carbonation is found 0-10mm after 35 years' exposure to existing environment where as concrete cover of members is found to vary from 80 84mm.
- v) Based on the Half-Cell potential measurements done by random sampling technique at various locations and visual observations of TG-Unit#1 indicate that probability of corrosion is found to be in "Transit State".
- vi) The amount of Soluble Sulphates in the concrete of members is within the specified limits and chloride content in the concrete is also within the specified limit and pH values are slightly lower than the specified limit in all members.
- vii) Distress and deterioration in the form of minor cracks, Honey combs, surface voids and corrosion of steel reinforcement were noticed visually at few locations of TG-Unit#1.

6.0 Recommendations

The following steps shall be taken to repair the cracks & strengthening of TG-Unit#1:

Part I: Scaffolding:

Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challis, MS clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it thereafter .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer in charge. The elevation area of the scaffolding shall be measured for payment purpose.

Part-II: Repair and Strengthening:

i) <u>Chipping:</u>

Cover concrete around the horizontal, vertical cracks shall be chipped off to the depth up to 40mm on RCC members. The chipping in the spalled portion of the columns and beams shall be limited up to the cover region. Chipping of



loose/hollow sounding concrete can be done by striking the doubtful surfaces with 2 lb hammer.

ii) Treatment for Cracks& Honeycombing:

- a. The cracks are to be widened by cutting V-grooves of 10mm x 10mm size and sealed with approved epoxy repair mortar.
- b. After the sealing, 12mm dia galvanized steel injection nipples are to be inserted in the crack area and also wherever honeycombing is found by drilling holes of required diameter up to the depth of 50 120 mm at required spacing (generally 350 mm staggered spacing). The drilled holes must be made dust free by blowing compressed air and should be sealed after the insertion of the nozzle with approved adhesive and allowed to cure.
- c. After the nipples are injected and cured, grouting in the proportion recommended by the manufacturer into the cracks/honeycombed area of concrete/masonry shall be done using suitable gun/pump at required pressure. Once the grouting work is finished, the extruding nipples can be cut-off after the curing period.

iii) Reinforcement Corrosion Treatment:

Wherever reinforcing rebar is found corroded in RCC members

- a) Remove the rust by manually or suitable means to make corroded reinforcing bars rust free.
- b) Provide and apply corrosion protection using 2 coats of anticorrosive Zn rich epoxy phenolic rebar protection system of approved brand on the exposed old reinforcement by brush with interval of 24 hours between coats and corrosion protection of exposed old reinforcing bars.
- c) Provide and apply concrete penetrating corrosion inhibitor (CPCI) of approved brand over the entire finished surface are obtained after removal of distressed concrete in 2 coats @ of 4m²/ltr/coat approximately.

iv) Bond Coat:

After chipping off the concrete cover, provide and apply structural grade two component epoxy bond coat prior to application of any type of mortar conforming to ASTM C - 881 -13 Type - II tested as per ASTM C -882-13 to ensure bond



between old and new concrete by brush application. (Material manufacture either from Sinorganic/BASF/SIKA/FOSRAC/KRISHNA Conchem/Pidilite or equivalent)

v) Making up lost section with Polymer Modified Mortar (PMM):

For repair of patches having, apply average 40mm PMM in 2-3 layers using SBR Latex conforming to ASTM C-1059-13 Type-I in damaged areas (1 Cement-3 part graded cleaned river sand + 15 % latex by weight of cement) with 0.35 w/c ratio, in 15-20 mm thick layers by applying bond coat between successive/each. (Material manufacture either from Sinorganic/BASF/SIKA/FOSRAC or equivalent)

vi) **Protective coating:**

Before applying the protective coating on concrete surface as well as the internal exposed areas all platforms shall be cleaned by scrubbing with hard steel brush to remove loose particles, disintegrated concrete, deposited smoke and dust particles etc. The scrubbed surface is cleaned by air blowing and then dries it completely. Apply min. 2 coats of two-part high-performance moisture compatible corrosion resistant coating material (base and curing agent) of approved manufacturer over prepared surface, using not less than theoretical consumption as per the manufacturer's specification. Total dry film thickness (DFT) including primer will be 300-400 microns.

Note:

- 1. Before taking up any repair work, the dryness of substrate concrete must be ensured for effective application of several repair materials. Remove oil, grease, wax, Cement laitance, loose particles and other contaminants, scarifying or mechanically wire brushing followed by air jet from the substrate concrete.
- 2. During repair works of TG-Unit#1 measures should be taken up in accordance with relevant safety standards and safety guidelines of Occupational safety & Health Administration (OSHA) for construction, arrangement like safety nets/platforms should be done.

• • • • • • • • •

ANNEXURE-R14

(Computer No. 5220)



भारत सरकार
Government of India
विद्युत मंत्रालय
Ministry of Power
केंद्रीय विद्युत प्राधिकरण
Central Electricity Authority
तापीय अभियांत्रिकी एवं प्रौद्योगिकी विकास प्रभाग
Thermal Engineering & Technology Development

सेवा में / To.

सभी ताप विद्युत उत्पादन संयंत्र / All Thermal Power Generating Plants/Utilities

विषय/Subject: Safety Advisory to all Thermal Power Generating Utilities.

महोदय/महोदया / Sir/Madam,

You may be aware that Hon'ble National Green Tribunal vide its Order dated 22.12.2020 in O.A. No. 108/2020 with O.A. No. 130/2020 had directed that "Secretaries, Ministry of Power and Coal, Government of India, in coordination with such other Departments/ Institutions, as may be necessary, to undertake Safety Audits of similarly placed thermal power stations throughout the country expeditiously preferably within six months to avoid recurrence of such incidents in future".

In compliance to the aforesaid order, a Safety Audit Committee under the chairmanship of the undersigned was constituted by Central Electricity Authority (CEA) comprising representatives from Ministry of Coal, Central Boiler Board (CBB), Director General Fire Safety (DGFS), NTPC Ltd., NLC India Limited (NLCIL), Bharat Heavy Electrical Limited (BHEL) and other experts. The above Committee carried out the safety audit of different coal/lignite based Thermal Power plants across the country during the period of August to November 2021.

A safety advisory based on the broad deficiencies observed during above safety audits of the thermal power stations is enclosed at Annexure-I for your kind information and needful actions. However, safety of plant and personnel is not limited to these findings only. Utilities/plants may also continue to take regular safety measures as per the extant Rules and Regulations in this regard.

संलग्नक/Enclosure: यथोपरि/As above

भवदीय/Yours Sincerely

(धीरज कुमार श्रीवास्तव / Dhiraj Kumar Srivastava)

मुख्य अभियंता / Chief Engineer

Annexure-I

Safety Advisory to all Thermal Power Generating Utilities

(A) General Safety and Fire Safety

- Implement the requisite provisions of (1) Central Electricity Authority (Safety Requirements for Construction, Operation and Maintenance of Electrical Plants and Electric Lines) Regulations, 2011 (2) Central Electricity Authority (Measures relating to Safety and Electric Supply) Regulations, 2010 (3) Statutory requirement under Factories Act and other related Acts such as Manufacture, Storage, and Import of Hazardous Chemicals (MSIHC) Rules, 1989 entrusted functions and Response Rules (4) IS:1646 Code of Practice for Fire safety of buildings (general): Electrical installations (5) IS:3034 Fire safety of industrial buildings: Electrical generating and Distributing stations Code of Practice.
- 2. Internal Safety Audits must be carried out once a year through cross functional teams/ internal trained staff and records must be maintained. Further, External Safety Audit must be carried out through registered Agencies at a regular periodicity of 2 years and Action Taken Report (ATR) must be prepared & monitored to ensure early closing of pending recommendations.
- Ensure a separate budget head in its overall budget provisions to adequately fund safety related activities. Detailed safety manual complying with the statutory requirements and manufacturers' recommendations must be available with power plant.
- 4. Safety awareness drives must be conducted amongst plant personnel as well as the employees deployed by the Contractors, periodically for the compliance of provisions of safety manuals and to imbibe the safety culture.
- 5. The safety officer shall be appointed and safety committee shall be constituted by thermal power plant as per the statutory requirement. Plants shall hold Safety Committee meetings regularly and Head of Plant shall chair these meetings. The output of these Safety Committee meetings should be implemented.
- 6. Ensure that 'Safety Performance' KPA (Key Performance Area) for employees is linked with Annual Performance Assessment for officers at various levels to instill a safety-compliant behavior.
- 7. Keep an updated inventory of safety related PPEs and also provide the tasks specific PPE kits to all the workers/ staff.
- 8. All major/ minor accidents must be properly investigated and analyzed to find the Root Cause of incident/accident.
- 9. Implement procedures for reporting of accidents by the concerned Power Station to CEA in line with the provisions of the CEA safety regulations.

- 10. Emergency Response Disaster Management Plan (ERDMP) both On-site & Off-site shall be prepared by all power plants.
- 11. Ensure that a functional proper Public Address system is in place and also 'Walkie/ Talkie' should be mandatorily adopted in the power plants.
- 12. Plants must be compliant/ certified as per ISO: 45001 'Occupational Health & Safety Management System'.
- 13. Ensure that all fire safety procedures are followed and fire-fighting system, its operation, installations are well maintained and upkeep of various subcomponents is reviewed at regular intervals to make sure their proper response during emergencies. These shall include but not be limited to the following:
 - Fire Water pump house must be maintained in proper healthy condition.
 There should be no obstructions in the pathways and approaches to equipment should be hindrance free.
 - ii. All fire hydrant pumps and jockey pumps must be maintained in healthy condition. The Fire Hydrant pumps need to be operated in 'AUTO MODE' & Sequential starting system should be in place. The reliability & availability of the Pumps are to be checked at frequent intervals and recorded.
 - iii. Fire-fighting crew along with some identified regular employees must go through hands-on firefighting training including rescue and disaster handling to enhance effectiveness of firefighting & safety crew.
 - iv. Manual call points (MCPs) must be provided at all the strategic locations of the power stations and must be integrated with the Fire Control Room for effective monitoring and to ensure timely & quick response from firefighting crew.
 - v. Mock drills should be conducted at regular intervals and also at odd hours for various emergencies scenarios & debriefing session should be conducted after each mock drill. The gaps observed are to be analyzed and mitigation measures need to be taken. These details should be recorded in a register.
 - vi. Fire Marshalls/ firefighting crew should be trained for actual emergencies scenarios.
 - vii. Each Power Station shall have a Fire Emergency Plan formulated so as to facilitate organized actions (in case of fire) by employees at various levels, during day as well as night and shall also contain the instructions on fire prevention measures and the firefighting organization.
 - viii. Fireboxes with hose reels at fire hydrant points must be available.
 - ix. Non-sparking tools and flame-proof electric fittings should be mandatorily used at all places where flammable materials like oils and gases are stored/ are in use. Also, static electric charge dissipater should

be provided at the entry gate of such systems which are prone to catch fire easily.

- 14. Emergency exit path marking should be made available for safe evacuation of working personnel during emergency conditions. Emergency telephone numbers must be prominently displayed at prominent locations in the plant, such as at TG floor, Unit Control Room & emergency exit points etc. Display of DO's & DON'Ts should be done in large fonts for better visibility. All such Display Boards should have a DC backlit display.
- 15. Lock Out & Tag Out (LOTO) system for maintenance management should be fully implemented for safe operation of the power plants and a proper Permit to Work (PTW) system must be followed and there should be seamless integration between LOTO & PTW System (and also to ERP system, if available). Proper Job Safety Analysis (JSA) should be carried out before issuance of each PTW.
- 16. Accumulated and unwanted scrap/ dismantled machinery etc. should be removed from working areas such as boiler structure, TG floor etc. and stored at designated places. Measures should be taken to remove wild vegetation growth in switchyard.
- 17. Excessive accumulation of coal/ lignite dust in some of the vulnerable areas like Crusher house, transfer points, coal/ lignite Bunker house, etc. must be avoided.
- 18. Preventive measures such as anti-corrosion painting and regular maintenance should be done for support structures and various equipment.
- 19. Rotating parts of various equipment should be covered with proper guards.
- 20. SOPs for various plant equipment to be prepared and made available to working personnel.

(B) Boiler, Turbine and Generator (BTG) Safety

- 1. As per IBR Regulations, periodic Remnant Life Assessment (RLA) should be carried out.
- 2. Annual overhauling, Capital overhauling and Renovation & Modernization works must be done on time as these prevent equipment failures. Overhauling work should be monitored comprehensively.
- 3. The boilers must be operated by Boiler Operating Engineers (BOEs) in compliance with the provisions of IBR. Utilities with shortage of BOEs are advised to take immediate and urgent steps to ensure that sufficient number of engineers should be qualified BOEs.
- 4. Boilers having box type column-beam structure are prone to accumulation of coal/ash dust if there are openings in the boiler structure. Coal dust accumulated in such confined structure may lead to fire/explosion. All such openings in such kind of structure must be closed. Also, cleaning must be ensured before closure.

- 5. Thermal insulation of Boiler, Turbine, associated sub-systems and all other critical equipment & lines must be ensured and maintained in good health. Regular thermal survey for surface temperature should be done. It is recommended to do insulation of.
- 6. Pulverized fuel leakage in mills, pipes, joints etc., if any, should be arrested on immediate basis.
- 7. The closeness of steam lines with other components/structure of Boiler or adjacent civil structure must be avoided.
- 8. All Boiler expansion indicators must be fitted properly to measure vertical movement as well as horizontal movement.
- 9. Mandatorily carry-out tool tagging to have effective inventory management and thus ensure timely availability of all tools & tackles. Tagging and marking date of last load testing of all O&M tools & tackles must be ensured.
- 10. Illumination measurement should be carried out as per IS:6665 and it needs to be improved in the plants wherever necessary.
- 11. Take measures to ensure that ambient noise levels around equipment like Turbine-Generator, Boiler etc. auxiliaries are in desired limits.
- 12. Regular ash level monitoring in ESP hoppers must be done by providing Ash Level Indicators (ALI). Timely steps must be taken for regular evacuation of ash. Also, ensure that ash hopper heaters are in healthy condition so that fluidity of ash is not hampered.
- 13. Safety Valves and Electromatic Relief Valves (ERVs) must be maintained in healthy condition and operative.
- 14. Vibration levels of machines such as TG set, fans, pumps, etc. must be monitored on regular basis and machines should not run beyond the recommended vibration limits prescribed by OEM.
- 15. Compulsorily carry out turbine over speeding test as per OEM recommendations.
- 16. Regularly perform checks for functionality of all the Protection & Interlocks (P&I) for various equipment and system.

(C) Balance of Plant (BoP) Safety

- 1. Chlorine leak sensor probes must be provided for all chlorine cylinder bays at proper locations. Water sprinkler system need to be installed in chlorination plant to neutralize chlorine leak in addition to the extant system.
- 2. Dust suppression system must be in operating condition to prevent coal/ lignite dust accumulation in areas such as coal/ lignite yard, Crusher house, transfer junctions/ points, coal/ lignite conveyor, coal/ lignite Bunker etc.
- 3. Battery Room is to be properly lined with 'Acid resistance tiles' up to the height of 'Battery Bank'. It is suggested to provide Flame-proof lighting in the Battery

- room. It is also to be ensured that the Eye-wash system is located at a place nearby to the Battery Room.
- 4. Cable gallery/ racks must be maintained in healthy conditions with proper illumination levels, exhaust system and the cable dressing in the racks should be done properly. All entry & exit of cables must be sealed properly for preventing progression of fire and toxic gases to adjacent rooms.
- 5. Insulating floor or mat conforming to IS:15652 of appropriate voltage level shall be provided in front of the panels for the safety of operating personnel.
- 6. Regularly measure and maintain proper records of Resistance value of Earth pits and monitor Tan-Delta value of current transformers (CT) and all other oil-filled electrical equipment.
- 7. Oil soak pits of transformers should be kept free of waste material.
- 8. Manuals and Standard Operating Procedures (SOPs) for Ash Bund/ Dyke Maintenance should be prepared by Power Plant. Emergency Plan should be prepared to deal situations of Ash Dyke breach and should be made available to the Site engineers.

ANNEXURE-R15



दूरभाष Tel.- 26967840 / 42 / 45, 26967990, 26868681 ई-मेल e-mail: nrpcconiml@yahoo.com वैबसाइट Website: www.nrpc.gov.in

फैक्स Fax : 26865206

भारत सरकार

उत्तरी क्षेत्रीय विद्युत समिति

18-ए, शहीद जीत सिंह मार्ग, कटवारिया सराय, नई दिल्ली-110016.

Government of India

NORTHERN REGIONAL POWER COMMITTEE

18-A, Shaheed Jeet Singh Marg, Katwaria Sarai, New Delhi-110016.

पत्रांक : उक्षेविस/अधी.अभि.(वाणि)/12-क्षे.वि.स/09/**/27**2-/35/ दिनाँक :**06** -05-2009 No. NRPC / SE(C) /12-RPC / 09 / Dated : -05-2009

सेवा में,

To,

उत्तरी क्षेत्रीय विद्युत समिति तथा तकनीकी समन्वय उप-समिति के सदस्य (संलग्न सूची के अनुसार)

Members of Northern Regional Power Committee and TCC (As per list attached)

विषय : तकनीकी समन्वय उप-समिति की 11वीं बैठक तथा उत्तरी क्षेत्रीय विद्युत समिति की 12 वीं बैठक का कार्यवृत्त।

<u>Subject</u>: 11th meeting of TCC and 12th meeting of Northern Regional Power Committee - Minutes.

महोदय,

Sir.

तकनीकी समन्वय उप-समिति की 11वीं बैठक तथा उत्तरी क्षेत्रीय विद्युत समिति की 12वीं बैठक क्रमशः 21 अप्रैल , 2009 व 22 अप्रैल , 2009 को चंडीगढ में आयोजित की गयी थीं। इन बैठकों के कार्यवृत्त की एक प्रति आपकी सूचना व आवश्यक कार्यवाही हेतु इस पत्र के साथ संलग्न है।

The 11th meeting of TCC and 12th meeting of Northern Regional Power Committee were held on 21st April, 2009 and 22nd April, 2009 respectively at Chandigarh. A copy of the summary record of discussions of the meetings is enclosed herewith for favour of information and necessary action.

संलग्नक : यथोपरि ।

Encl.: As above.

भवदीय, Yours faithfully,

अशोक कुमार अग्रवाल)

(A. K. Aggarwal) सदस्य सचिव

Member Secretary

NORTHERN REGIONAL POWER COMMITTEE

SUMMARY RECORD OF DISCUSSIONS

OF

11th MEETING OF TECHNICAL COORDINATION SUB-COMMITTEE &

12th MEETING OF NORTHERN REGIONAL POWER COMMITTEE

The 11th meeting of Technical Coordination Sub-committee (TCC) and 12th meeting of Northern Regional Power Committee (NRPC) were held on 21st & 22nd April, 2009 respectively at Chandigarh. The lists of participants at the TCC and NRPC meetings are enclosed at Annexure-I & II respectively.

PROCEEDINGS OF 11th MEETING OF TCC

Shri Sanjay Kumar, Secretary (Power), UT of Chandigarh welcomed all the members of Technical Co-ordination Committee and other delegates. He congratulated NRPC in establishing such platform where the regional level technical problems relating to power are being discussed and resolved. He stated that a healthy power sector is a prime mover of development of economy of any country. Many countries in the past had been able to restructure their economies through reforming their power sector. He gave example of China in this regard. Unfortunately the power sector in India had been still beset with the problems like poor quality, high T&D losses. However, Chandigarh had been fulfilling the vision of Ministry of Power to provide reliable, affordable and quality power for all by 2012. By taking various measures, Chandigarh Administration had been able to reduce T&D losses to around 16.5%.

He further mentioned that Chandigarh had no source of own power generation and totally dependent on allocation from Central generating stations. Chandigarh had peaking shortages of 50 MW and being the Capital of two States they could not afford to impose power cuts. He stated that this small gap could be easily bridged with increase in allocation out of unallocated quota from Central generating stations.

He thanked Member Secretary, NRPC for giving them the opportunity to host the meeting.

Shri A.K. Aggarwal, Member Secretary, NRPC, welcomed TCC Members & other participants. He also welcomed Shri R.K.Seli, Development Commissioner, PDD, J&K on taking over the charge of Chairman, TCC w.e.f.1st April, 2009. He expressed hope that his presence would help TCC resolve the issues amicably. He

thanked Shri Sanjay Kumar, Secretary (Power), UT of Chandigarh, Sh. Surinder Pal, Chief Engineer, and their team of officers for hosting the meeting and making an excellent arrangements for the same as well as for comfortable stay of the participants at Chandigarh. He briefly mentioned the issues to be deliberated in the TCC meeting. Thereafter, he requested Shri R.K.Seli, Chairman, TCC to address the Sub-Committee.

Shri R.K.Seli, Chairman, TCC welcomed the TCC Members & other delegates. In the opening remarks, he appreciated the efforts by the POWERGRID and State TRANSCOs which had carried out insulator cleaning before/during the winter season due to which there were not much tripping of lines due to fog unlike last winter season. He requested all the constituents to take suitable measures to meet the demand in this summer months. He briefly mentioned about the CERC's new regulations on Unscheduled Interchange charges and also the amendments to Indian Electricity Grid Code (IEGC) applicable w.e.f. 1.4.2009 and requested all the members to follow the regulations of CERC strictly. He stressed the need for installation of shunt capacitors by the State utilities, which had been resulting into low voltage problems at certain locations in all the States. Regarding the generation planned during the year 2009-10, he requested generating companies to take all necessary steps to see that there is no slippage in meeting the target.

He thanked Shri Sanjay Kumar, Secretary (Power), UT of Chandigarh, Sh. Surinder Pal, Chief Engineer, and their team of officers for hosting the meeting at Chandigarh and making excellent arrangements for comfortable stay of the participants.

He then requested Member Secretary, NRPC to take up the agenda for discussions.

A. CONFIRMATION OF MINUTES (TCC)

A.1 MINUTES OF 10th MEETING OF TCC OF NRPC

Member Secretary, NRPC stated that as no request for amendment to the minutes had been received, the minutes of 10th TCC could be confirmed.

The members confirmed the minutes of 10th meeting of TCC.

PROCEEDINGS OF 12th MEETING OF NRPC

Shri Sanjay Kumar, Secretary (Power), UT of Chandigarh welcomed Chairman, NRPC, Shri R.K.Seli, Chairman, TCC, Member (GO&D), CEA, Member

Secretary, NRPC, and distinguished members of NRPC and other delegates in the meeting. He expressed that as discussed during the TCC meeting, we should continue the discussion to achieve outcome in the NRPC meeting. He stated that we all should endeavor to achieve what had been mandated not only in this meeting but otherwise also.

Shri A.K. Aggarwal, Member Secretary, NRPC welcomed members of Northern Regional Power Committee and other delegates to the meeting. He especially welcomed Shri Sundeep K Nayak, Commissioner and Secretary, PDD, J&K who took over charge of Chairman, Northern Regional Power Committee on 1.4.2009 on relinquishment of charge by Shri R.K.Jain , Chairman, HPSEB as Chairman, NRPC. He further stated during his tenure as Chairman, NRPC, Shri Jain had played an important role in resolving a number of operational, commercial & administrative issues. He had been a source of inspiration and provided continuous guidance. On behalf of NRPC, Member Secretary, NRPC thanked Shri Jain for his valuable contribution during his tenure.

The Committee passed the following resolution in appreciation of the services rendered by Shri R.K.Jain, Chairman, HPSEB during his tenure as Chairman, NRPC:

"Northern Regional Power Committee places on record its deep appreciation of the outstanding service rendered by Shri R.K.Jain , Chairman, HPSEB during his tenure as Chairman, NRPC. Shri Jain provided able guidance in various technical, commercial & administrative matters and made valuable contribution as Chairman of the Committee."

Member Secretary, NRPC also welcomed Shri Sudhansh Pant, CMD, RVPNL, Shri T.Panda, MD, PTCUL and Shri J.M.Lal, MD, UPCL who were attending the meeting for the first time. On behalf of NRPC, he also congratulated Shri H.S. Brar, who had taken over as Chairman, PSEB.

He thanked Shri Sanjay Kumar, Secretary (Power), UT of Chandigarh, Sh. Surinder Pal, Chief Engineer, and their team of officers for hosting the meeting and making an excellent arrangements for the same as well as for comfortable stay of the participants at Chandigarh. He requested Shri Sundeep K Nayak, Chairman, NRPC to address the Committee.

Shri Sundeep K Nayak, Chairman, NRPC welcomed the Members of the Northern Regional Power Committee and other delegates to the meeting.

He stated that during this winter season there had not been much line tripping due to foggy weather as a result of timely action taken by POWERGRID and State TRANSCOs in cleaning of insulators. POWERGRID had particularly done this with the help of Helicopter successfully for the first time in the country. On Behalf of NRPC, he appreciated the efforts by the POWERGRID and State TRANSCOs in minimizing the instances of line tripping due to fog and saving the grid. He also

requested all concerned to continue the work on replacement of porcelain insulators of line with polymers/Anti-fog as per the plan.

Referring to the anticipated power shortages in the coming summer, he requested all the constituents to manage the shortages by arranging bi-lateral assistance from outside region and maximization of generation as well as suitable demand management measures and statutory / notified load restrictions.

He also informed to the Committee about the new regulations on Unscheduled Interchange charges for electricity grid operations and also the amendments to Indian Electricity Grid Code (IEGC) notified by CERC and applicable w.e.f. 1.4.2009. He stated that CERC had narrowed down the operating frequency band from 49.0 -50.5 Hz to 49.2 to 50.3 Hz. In addition to UI Rate corresponding to frequency of 49.2 Hz, an Additional Unscheduled Interchange Charge at the rate of 40% of the UI Rate corresponding to frequency of 49.2 Hz had been introduced for over-drawal or under-injection of electricity below this frequency. He requested all the members to follow the regulations of CERC other wise CERC could consider penal action under sections 142 and 149 of the Electricity Act, 2003 for contravention of the overdrawl and under generation limit specified in the regulations.

He mentioned that certain locations of almost every States had been experiencing low voltage problems due to inadequate shunt compensation provided by the states. He expressed deep concern about poor progress in installation of shunt capacitors by the State utilities. He requested all the State to expedite the installation of capacitors in the State system to control the low voltage problems.

With regard to generation addition programme during this financial year, he requested the generating companies to take all necessary steps to see that there is no slippage in meeting the generation targets planned during the year 2009-10.

Finally, he thanked Shri Sanjay Kumar, Secretary (Power), UT of Chandigarh, and his team of officers for hosting and making an excellent arrangement for the meeting as well as for stay of the participants at this beautiful city of Chandigarh. Thereafter, he requested Member Secretary, NRPC to take up the agenda for discussions.

A. CONFIRMATION OF MINUTES(NRPC)

A.2 MINUTES OF 11th MEETING OF NRPC

Member Secretary, NRPC stated that as no request for amendment to the minutes had been received, the minutes of 11th NRPC meeting could be confirmed.

The members confirmed the minutes of 11th meeting of NRPC.

B. ITEMS FOR TCC ONLY

FOLLOW-UP ACTION

B.1 STATUS OF SPECIAL PROTECTION SCHEME (SPS) TO TAKE CARE OF TRIPPING OF RIHAND-DADRI HVDC BIPOLE

TCC Deliberation

M.S, NRPC, while briefing the progress made in implementing the SPS scheme on Rihand-Dadri HVDC Bipole line stated that the Special Protection Scheme (SPS) had been declared on commercial operation w.e.f. 1st August, 2008.

NTPC/POWERGRID informed that circuit modifications as well as testing works had been completed at Rihand and Singrauli STPS. Mock testing of complete scheme would be undertaken in next 15 days.

POWERGRID intimated that after January, 2009 there had been no report of any 'Mal Operation' in the SPS.

B.2 REPLACEMENT OF OBSOLETE ELECTRO MAGNETIC TYPE PROTECTION RELAYS IN NORTHERN REGION WITH STATE-OF-ART NUMERICAL RELAYS.

TCC Deliberation

MS, NRPC briefed the members about the decision of Protection sub committee meeting held on 24/03/09 on the issue and requested all the constituents to replace obsolete electro magnetic type protection relays with numerical relays in the region. He stated that the BBMB, POWERGRID and DTL had already taken action in this regard. Some constituents like UPPCL and PSEB were lagging behind, so they were requested to take immediate action to replace the obsolete relays on critical lines in their systems and replacement of remaining relays by March 2010.

PTCUL stated that they had already replaced the obsolete relays with numerical relays in their system.

HPSEB stated that studies were being conducted by them on the functionality of existing relays. They assured that top priority would be given for replacing the relays in their 220 kV system in the first instance. However, all the relays in their system would be of numerical type by March, 2010.

RRVPNL stated that they had undertaken Renovation, Modernization and Upgradation (RMU) programme on this issue.

HVPNL stated that they had received 49 numbers of numerical relays from M/s ABB Limited and additional 64 numbers such relays from M/s Areva Limited, which would be replaced soon.

MS, NRPC emphasized that due to limited shut down of lines and more time needed for procurement action, the programme of replacement of relays by constituents need to be coordinated by various constituents. The month wise targets for replacement of obsolete electro magnetic type protection relays in northern region should be fixed in coordination with NRLDC/SLDCs.

TCC decided that all the constituents would complete the process of installation of numerical relays by March, 2010.

NRPC Deliberation

NRPC accepted the recommendations of TCC and decided that all the constituents would complete the process of installation of numerical relays in their systems by March, 2010.

B.3 COORDINATION OF RELAY SETTINGS FOR PROTECTION OF TRANSMISSION LINE IN NORTHERN REGION.

TCC Deliberation

MS, NRPC informed the TCC that the Uniform philosophy for protection of lines to avoid indiscriminate tripping under fault conditions as agreed to in various Protection Sub-Committee Meetings had been widely circulated and it needs to be implemented by all the constituents.

NRPC Deliberation

NRPC noted the information.

B.4 BUS-BAR PROTECTION AT 400 kV AND 220 kV SUB STATIONS

TCC Deliberation

MS, NRPC, requested all the constituents to brief the current status of the bus bar protection on their 400 kV and 220 kV sub stations.

PTCUL stated that they had bus bar protection at all their sub stations.

UPPTCL stated that they had 14 numbers 400 kV sub stations and busbar protection had been provided in these substations. However, at six substations, the bus bar protection was out of order and action was being taken to rectify the same.

ANNEXURE-R16

दूरभाष Tel.- 26967842, 26868681

फैक्सFax : 26865206

वैबसाइट Website : www.nrpc.gov.in

भारत सरकार उत्तर क्षेत्रीय विद्युत समिति

18-ए, शहीद जीत सिंह मार्ग, कटवारिया सराय, नई दिल्ली - 110016

Government of India

Northern Regional Power Committee

18-A, Shaheed Jeet Singh Marg, Katwaria Sarai, New Delhi-110016

पत्रांक: उक्षेविस/अधी. अभि.(वा.)/22-क्षे.वि.स./11/ /685-1757 No. NRPC / SE(C)/22-RPC /11/

दिनांक: 05 अगस्त, 2011

Dated: 05th August, 2011

सेवा में, To.

> उत्तरी क्षेत्रीय विद्युत समिति तथा तकनीकी समंवय उप-समिति के सदस्य (संलग्न सूची के अनुसार)

Members of Northern Regional Power Committee and TCC (As per list attached)

विषय: तकनीकी समंवय उप - समिति की 20 वीं बैठक तथा उत्तरी क्षेत्रीय विद्युत समिति की 22 वीं बैठक काकार्यवृत।

Subject: 20th meeting of TCC and 22nd meeting of Northern Regional Power Committee – Minutes.

महोदय, Sir.

तकनीकी समंवय उप-समिति की 20 वीं बैठक तथा उत्तरी क्षेत्रीय विद्युत समिति की 22 वीं बैठक क्रमश: 28 व 29 जुलाई, 2011 को होटल होलीडे इनन, जेम पार्क, ऊटी (तमिलनाडु) में आयोजित की गयी थी। इन बैठकों के कार्यवृत की एक प्रति आपकी सूचना व आवश्यक कार्यवाही हेतु इस पत्र के साथ संलग्न है।

The 20^{th} meeting of TCC and 22^{nd} meeting of Northern Regional Power Committee were held on 28^{th} & 29^{th} July, 2011 respectively at Hotel Holiday Inn, Gem Park, Ooty (Tamilnadu). A copy of the summary record of discussions of the meetings is enclosed herewith for favour of information and necessary action.

संलग्नक: यथोपरि । Encl: As above

भवदीय, Yours faithfully,

31211m 3-1020101

(अशोक कुमार अग्रवाल) (A. K. Aggarwal) सदस्य सचिव Member Secretary

5.14 CONTROL, METERING AND PROTECTION

Following shall be included in the scope of the bidder:

- i) Complete control, operation and metering requirements for the following:
 - Generator, generator transformer, unit auxiliary transformers and associated circuit breakers
 - 11kV incomers, tie feeders and outgoing transformer, supply feeders of unit and station switchgears
 - 3.3kV incomers, bus-coupler feeders and outgoing transformer, supply feeders of unit switchgears and incomers of station switchgears
 - 415V incomers and bus-coupler feeders of unit and station switchgears
 - Diesel Generator sets
- ii) Protection and relay panels for generator, generator transformer and UATs including relay test kit

5.14.1 Codes and Standards

IEEE: Std.	Standard common format for transient data exchange (COMTRADE)
C37.111	for power systems
IEEE Std.	Standard for withstanding capability of relay systems to radiated
C37.90.2	electromagnetic interference from transceivers
ANSI/ IEEE	Relays and relay systems standard associated withelectric power
C37.90	apparatus
ANSI/ IEEE	Power system protective relay applications of audio tones over
C37.93	telephone channels
IS: 3231	Electrical relays for power system protection
IS: 8686	Specification for static protective relays

5.14.2 Control Requirements

- i) Operators work station (OWS) along with thin film transistor (TFT) and keyboard etc. shall be located in unit control room and shall be provided for operation, control and interlocking of the following:
 - Generator, generator transformer, unit auxiliary transformers and associated circuit breakers
 - 11kV incomers, tie feeders and outgoing transformer, supply feeders of unit and station switchgears
 - 3.3kV incomers, bus-coupler feeders and outgoing transformer, supply feeders of unit switchgears and incomers of station switchgears
 - 415V incomers and bus-coupler feeders of unit and station switchgears
 - Diesel Generator sets

ii) General Technical Description

a) Generator

The generator and auxiliary systems shall be controlled from OWS located in unit control room through DDCMIS. All necessary control, interlock, indication, metering and annunciation shall be provided. These controls shall be in addition to local control panels for generator auxiliary systems.

The synchronization of the 400kV Generator transformer circuit breaker shall be performed through auto-synchronizer in DDCMIS. The manual synchronizing shall also be provided in the generator metering panel.

b) Auxiliary power distribution system

The control, monitoring, metering as required for the electrical auxiliary power distribution system comprising of 11kV, 3.3kV, 415V circuit breakers and unit auxiliary transformers, 11kV/3.3kV, 3.3kV/415V auxiliary service transformers within the power block including ESP switchgear shall be performed.

c) Diesel Generator set

The remote control of DG set shall be provided in addition to those provided in associated automatic mains failure (AMF) panels.

5.14.3 Metering

i) Generator

The ammeters, voltmeters, MW meter, MVAR meter, frequency meter, power-factor meter, energy meter (MWH) meter, MVARH meter, exciter field voltage and exciter field current meters including necessary transducers shall be provided in the generator metering panel located in unit control room.

The energy meters mentioned above shall be used for energy accounting and audit purposes and shall be located at a point after the generator stator terminals and before the tap-off to UATs and shall comply with the requirements of CEA regulations on Metering.

The digital indication for the above meters shall also be provided.

ii) 11kV, 3.3kV incomers, tie feeders and outgoing transformer, outgoing supply feeders.

The digital indication of Ammeter, kW meter and kWH meter located on the respective switchgears and bus voltages shall be provided.

iii) 415V Incomer and bus-coupler feeders and Diesel Generator sets

The digital indication of Ammeter, kW meter and kWH meter located on the respective switchgears and bus voltages shall be provided.

5.14.4 Protection and Relay Panels

5.14.4.1 General requirements

i) Panels

- a) The panels shall be free standing, floor mounting type and completely metal enclosed. Cable entries shall be from bottom.
- b) The panels shall have removable gland plates with glands made of brass and suitable for armoured cables
- c) All equipment mounted on front and rear side of the panels shall have individual name plates with equipment designation engraved. Each panel shall also have circuit/ feeder designation name plate.
- d) Each panel shall be provided with a 240V AC fluorescent lighting fixture controlled by door switch as well as a 5A, 240V AC switch-socket unit.
- e) Voltage circuits for protection and metering shall be protected by fuses. Suitable fuse failure relays shall be provided to give an alarm for voltage circuits of protection/metering. Voltage selection scheme based on relays shall be provided for meters wherever possible.
- f) The DC supplies at the individual relay and protection panels shall be monitored by suitable relays and failure of DC supplies shall be annunciated.

ii) Relays

- a) The protective relays shall be numerical type. All relays, auxiliary relays and devices shall be of reputed make and types proven for the application and shall be subject to purchaser approval. The relays and timers shall have appropriate setting ranges, accuracy, resetting ratio, transient overreach and other characteristics to provide required sensitivity to the satisfaction of the owner.
- b) Relays shall be suitable for efficient and reliable operation of the protection scheme. Necessary auxiliary relays, timers, trip relays, etc. required for complete scheme, interlocking, alarm, logging, etc. shall be provided. No control relay, which shall trip the circuit breaker when relay is de-energized, shall be employed in the circuits.



- c) Relays shall be flush mounted on the front with connections at the rear shall be draw-out or plug-in type/ modular case with proper testing facilities. Provision shall be made for easy isolation of trip circuits for testing and maintenance.
- d) Relays shall be provided with self reset contacts except the trip, lockout relays and interlocking (contact multiplication) relays which shall be manual reset type
- e) Auxiliary relays shall be provided in the trip circuits of protections located outside the board, such as buchholz relay, temperature indicators, fire protection, etc.
- f) Suitable measures shall be provided to ensure that transients present in CT and VT connections due to extraneous sources in 400kV system do not cause damage to static circuit.
- g) Only DC/ DC converters shall be provided in the relays, wherever necessary to provide a stable auxiliary supply for relay operation
- h) All relays shall have hand-reset flags or other means for ready visual indication of their operation and also of the faulty phase.
- i) The numerical relays shall have continuous self-monitoring and cyclical test facilities. The internal clock of the system shall be synchronized through the GPS Time Synchronizing System.
- j) Each numerical relay shall have a serial interface on the front for local communication to a PC and Printer. Facilities shall be provided to access each discrete protection function including modification in relay settings and monitoring of the relay from a HMI or a separate protection. The printout of all settings, scheme logic, event records etc. shall be accessible through the HMI. The display of various measured parameters during normal as well as fault conditions on a segregated phase basis shall be provided. LEDs and a backlit LCD screen shall be provided for visual indication and display of messages related to major trips/ alarms. Necessary multilevel password protection shall be provided.
- k) The sampling rate of analog inputs, the processing speed and processing cycle of digital values shall be selected to achieve the operating times of various protection functions specified. In case all protection functions specified do not have as a part of the standard numerical relay, separate discrete numerical relays can be provided.
- 1) The numerical relays shall be provided with built-in disturbance recording facility. The output shall be available in IEEE/ COMTRADE format and shall be compatible with the dynamic relay test kit.



- m) The manufacturer of the numerical protection system shall carry out the complete engineering, testing and commissioning on site of the protection equipment including the associated relays and protection panels. The testing and commissioning protocols for the numerical protection systems offered shall be approved by the purchaser before commissioning on site.
- n) The numerical relays offered shall have self-diagnostic features to reduce the down time of the relay and to provide useful diagnostic information upon detection of an internal fault so as to speed up the maintenance. The necessary support documentation explaining in detail the self-diagnostic features of the numerical relays shall be furnished for the purchaser's use.

5.14.4.2 Protection

- 1) Protection Philosophy
- The protection and control equipment and circuitry, shall be provided with two independent channels with reliable protection systems with separate DC supplies, separate CT/ VT cores and separate cables and hand-reset trip relays to obtain 100% reliability. The DC supplies to these protections shall be monitored.
- Associated trip relays of the two systems shall be separate having sufficient number of contacts for all the functions.
- Each protection system shall energize both trip coils of the circuit breaker.
- The total critical fault clearance time from fault initiation in any part of the system shall be 80ms for phase to phase fault in the generator-transformer unit and for phase to phase and phase to earth faults in the 400kV system inter-connection.
- Protective relay system shall be provided to protect the Electrical equipments from faults, overloading and abnormal operating conditions.
- 2) Each generator, generator transformer and unit auxiliary transformer etc. shall be provided with microprocessor based protection system comprising of the following protections:
- i) Generator
 - a) Differential current protection (87)
 - b) Inter-turn fault protection (where split winding in stator is provided) if six neutral terminals are available (87TG)

ANNEXURE-R17



Standard Technical Specification for Sub- critical Thermal Power Project - 2x(500MW or above)

Main Plant Package

Section-5 (Electrical Works)

- c) 100% stator earth fault protection (64G)
- d) Loss of field protection (40) (to be duplicated)
- e) Back-up impedance protection (21)
- f) Negative sequence current protection (46)
- g) Reverse power protection (32) (preferably of 3-phase power relay)
- h) Low forward power interlock (37) (preferably of 3-ph. power relay)
- i) Rotor earth fault Protection:
 - First stage (alarm) (64F1)
 - Second stage (trip) (64F2)
- j) Over voltage protection (59)
- k) Generator pole slipping protection (98)
- 1) Synchro-check relay (25)
- m) Under-frequency protection (based on manufacturer's recommendations, under-frequency relays with timers set at prescribed values connected to alarm and trip (81).
- n) Stand by stator earth protection (64G2)
- o) Overload (51)
- p) Overheating (windings and/ or bearings) (49)(annunciation only)
- q) Over fluxing protection in addition to all aforecited protections (99) (to be duplicated)
- r) Accidental back energisation protection
- s) Voltage balance scheme for blocking voltage dependent protection, in case of VT-fuse failure (60)

In case digital multifunctional generator protection system (MGPS) is provided, the protections shall be duplicated. Each MGPS shall be preferably provided with individual inputs from CTs and VTs and connected to the independent set of hand-reset trip relays, such that one set is always available in case of testing and mal-operation of other set. Any protection, which is not a part of MGPS, separate discrete protection shall be provided as per the above table. The MGPS shall preferably have continuous self-monitoring and testing facilities.

ii) Generator Transformer

- a) Overall differential current protection covering the Generator zone also (87OA)
- b) Time graded IDMT type back up non-directional over current protection in all phases on HV side (51)
- c) Restricted earth fault protection (87NT)
- d) Over- fluxing protection (99) (to be duplicated)
- e) Neutral over-current protection against sustained external system earth faults (51 NT)
- f) Buchholz protection (annunciation and trip) (63)
- g) Winding temperature high for annunciation and trip (49T)
- h) Oil temperature high (annunciation and trip) (49Q)
- i) Pressure relief valve trip (PRV)
- j) Generator Transformer differential protection for single phase bank (87T)
- k) Overhead line connection differential protection(87L) (For 3 single phase banks, if 87L includes HV winding, separate 87NT is not mandatory)
- l) Pole discrepancy protection of the breaker if single pole breakers are used (162)
- m) Breaker (HV) back-up protection (protection against breaker failure) (50Z)

iii) Unit Auxiliary Transformer

- a) Differential current protection (87)
- b) Restricted earth fault protection for LV winding in case of low resistance grounding (87N)
- c) Back-up over- current protection on primary side (51)
- d) Back-up earth fault protection for low/ high resistance grounding (LV side)



- e) Winding temperature high (annunciation and trip LV side breaker) (49T)
- f) Oil temperature high (annunciation and trip the LV side breaker) (49Q)
- g) Buchholz protection (annunciation and trip) (63)
- h) Pressure relief valve trip (PRV)

5.14.5 Generator Disturbance Recorder (DR)

- a. One no. microprocessor based Disturbance Recorder (DR) shall be provided for each generator to record graphic form of instantaneous values of voltage and current in all three phases and neutral, open and closed positions of relay contacts and breaker during disturbances.
- b. It shall have the facility for slow and fast scan to record transient and dynamic performance of the system.
- c. Both slow and fast scan facility shall have atleast 8 analog and 16 digital inputs.
- d. The slow scan facility shall be provide with the following minimum features
 - The input shall be MW, MVAR, field voltage, frequency and generator terminal voltage etc. Any transducers, if required for interfacing, shall be provided.
 - It shall be suitable to record the frequency excursions and response of generator field and governor control on system fluctuations.
 - It shall have options to select the scan rate in the range having a min. of 10Hz suitable to facilitate capture of low frequency waveforms in the range of 0.5 3Hz.
 - The non-volatile memory shall be suitable for recording for a minimum of 15 minute at scan rate corresponding to selected pre-fault zone of recording.
- e. The fast scan facility shall be provide with the following minimum features
 - The input shall be voltages and current etc. Any transducers, if required for interfacing, shall be provided.
 - It shall have scan rate of 1000Hz or better for sampling each of the analog channel having fundamental frequency of 50Hz. The frequency response for these channels shall be DC on the lower side to 500Hz or better on the upper side. Any interposing devices provided shall be suitable for this frequency response.



- The pre and post fault recording time shall be atleast 200 ms and 5s respectively.
- f. All external and internal faults in the DR equipment such as power supply fail, printer faults, paper exhausting, processor failure, memory failure etc. are to be indicated by means of light emitting diodes on the front of the panel of restitution unit. The DR shall be provided with a MMI (man machine interface) through a PC with VDU, keyboard and printer.
- g. The internal clock of the system shall be synchronized through the GPS. The output shall be in IEEE/ COMTRADE format. The format shall be compatible for dynamic protection Relay Test Kit Necessary interfacing and software for analysis shall also be provided.
- h. The amplitude resolution of the analog channels shall not be less than 16 bit and event resolution for digital channels shall be 1ms or better.

5.14.6 Electrical Control Board:

- a. One no. 'Electrical Control Board' (ECB) shall also be provided in the Central Control Room with minimum control and indication facilities for various equipments described below, as a back-up to Operator Work Station/ CRT keyboard (OWS) for both units and station supply. ECB shall be Simplex panel in mosaic grid configuration.
- b. Semaphore indicators shall be provided for isolators, earth-switches of 400kV system associated with generators. Further, control and indication of the important but not limited to the followings breakers shall also be provided:
 - i. Generator Transformer breaker (at 400kV), field breaker for both units including manual synchronizing facilities, governor and excitation control.
 - ii. Incoming and Tie breakers of 11kV, 3.3kV and 415V Unit Switchgears including Unit Emergency Switchgears of both units.
 - iii. Incoming and Tie breakers of 11kV, 3.3kV and 415V Station Switchgears.
 - iv. Emergency Diesel Generator sets
- c. Relevant Mimic shall be provided to cover the above 400kV, 11kV, 3.3kV and 415V system. Mimic shall be atleast 3 mm thick and 10 mm width and colour coded.
- d. The analogue meters for the following shall also be provided on ECB:
 - i. Generator current, voltage, MW, MVAR, power-factor, frequency, field current, field voltage, etc.
 - ii. Bus voltages for 400kV, 11kV, 3.3kV and 415V system

NORTHERN REGIONAL POWER COMMITTEE

SUMMARY RECORD OF DISCUSSIONS OF 20th MEETING OF TECHNICAL COORDINATION SUB-COMMITTEE & 22nd MEETING OF NORTHERN REGIONAL POWER COMMITTEE

The 20th meeting of Technical Coordination Sub-committee (TCC) and 22nd meeting of Northern Regional Power Committee (NRPC) were held on 28th and 29th June, 2011 respectively at Ooty (Tamilnadu). The list of participants at the TCC and NRPC meetings is enclosed at Annexure- I & II respectively.

PROCEEDINGS OF 20th MEETING OF TCC

AGM, Commercial, NTPC Shri C.K.Mondal welcomed the TCC Members & other participants to the 20th TCC meeting. He gave brief background of NTPC Ltd. and its future plans.

Shri A.K. Aggarwal, Member Secretary, NRPC, welcomed TCC Members & other participants. He informed that as per decision taken in last NRPC meeting, an interactive workshop was organised successfully to clarify the issues related to implementation of POC transmission charges. He also stated that CERC regulation on PoC charges & losses has come into force from 01/07/2011. The Commission vide its order dated 29.06.2011 have approved three slab rates for POC transmission charges. The Commission has also approved POC losses in percentage and its applicable slab.

He emphasized the need for adequate protection Systems its upkeep by carrying out regular protection audit to avoid multiple tripping of transmission lines and other system elements. He also stressed the need to expedite System Protection Scheme as recommended by inquiry committee to minimise the impact of incidents in the grid.

MS, NRPC mentioned that the NR met highest demand of 38000 MW. Peak power shortage was around 6% and average energy shortage was about 4% in July. The average grid frequency was also around 49.9 HZ during this period. He touched upon the instances of heavy overdrawal by some States, huge reactive power drawal causing low voltages and TTC violations.

He expressed concern on extremely slow progress of installation of requisite quantum of shunt capacitors and associated low voltage problem. He requested States utilities, particularly those having paddy crops, to take up revival of defective capacitors and installation of new capacitors on war footing apart from maintaining their distribution system. He requested for cooperation of all concerned in resolving long pending issues such as Installation of adequate Capacitors & revival of defective Capacitors, AMRs for Interface

meters, Pollution Mapping, Third party Protection Audit, Replacement of obsolete protection relays with Numerical Relays.

With regard to capacity building he informed that 9 training programmes are being organised on reactive power management during the FY 2011-12 to enhance the capacity building of system operators and field staff.

He thanked Shri I.J.Kapoor, Director(commercial), NTPC, Shri Naresh Anand, AGM, NTPC and their team of officers for hosting and making excellent arrangements for the meeting as well as for stay of the participants at Ooty.

Shri Y.Raizada, Director (Tech.), RVPNL and Chairman, TCC welcomed the TCC Members & other delegates. Referring to the grid operation he expressed that the Power Supply Position during the period from April 2011- June 2011 was quite comfortable. The shortages were manageable. The grid frequency was for most of the time within the frequency band as stipulated in IEGC. In addition to the need for installation of Capacitors he emphasized the need for installation of reactors in view of the high voltages being faced in certain pockets.

Finally, he thanked Shri I.J.Kapoor, Director (commercial), NTPC and their team of officers for hosting and making excellent arrangements for the meeting as well as for stay of the participants at Ooty.

He then requested Member Secretary, NRPC to take up the agenda for discussions.

CONFIRMATION OF MINUTES (TCC)

A.1 Minutes of 19th Meeting of TCC of NRPC

MS, NRPC stated that the minutes of 19th meeting of TCC held at Parwanoo, on 1st June, 2011, were circulated vide letter No. NRPC / SE(C) / 21-RPC / 11/1038-1108 dated 27th June, 2011. As no comments had been received on TCC minutes, he proposed for confirmation of minutes.

TCC confirmed the minutes of meeting.

PROCEEDINGS OF 22nd MEETING OF NRPC

Shri I.J.Kapoor, Director(commercial), NTPC welcomed the NRPC Members & other participants to the 22nd NRPC meeting. He briefly explained the future plans of NTPC Ltd. As Shri A.K.Aggarwal, Member Secretary, NRPC is superannuating in August 2011, he appreciated the services rendered and hard work in resolving the important technical & commercial issues by Shri A.K.Aggarwal, Member Secretary, NRPC during his tenure as Member Secretary NRPC.

Shri A.K. Aggarwal, Member Secretary, NRPC welcomed members of Northern Regional Power Committee and other delegates to the meeting. He especially welcomed Shri Anurag Agarwal Ex-Chairman NRPC and CMD, Punjab State Transmission Corporation Ltd. During his tenure many visionary decisions taken with consensus in NRPC. He also welcomed Sh I.J.Kapoor, Director (Commercial) NTPC, Shri K. D. Chaudhary CMD, Punjab State Power Corporation Ltd, Sh A.K.Jain MD, Uttrakhand Power Trans. Co Ltd who are attending the meeting for the first time.

He informed that during the TCC meeting 30 agenda items covering technical, commercial and operational issues were discussed. He briefly explained the important issues such as Installation of adequate Capacitors & Revival of defective Capacitors, AMRs for Interface meters, Pollution Mapping, Third Party Protection Audit, Bus Bar Protection and implementation of System Protection Scheme as recommended by inquiry committee.

He further stated that as suggested by Chairman NRPC in last meeting, the matter had been taken up with CEA to establish a forum of all RPCs. This will bring uniformity on various common issues like certifying of additional generation due to re-scheduling of the planned maintenance programme, Non-ISTS lines, protection Co-ordination and Audit apart from sharing of best practices of each RPC.

He thanked Shri I.J.Kapoor, Director(commercial), NTPC, Shri Naresh Anand, AGM, NTPC and their team of officers for hosting and making excellent arrangements for the meeting as well as for stay of the participants at Ooty.

Shri Shailendra Agarwal, Chairman, NRPC welcomed members of Northern Regional Power Committee and other delegates to the meeting. He informed that the power supply during the April to June 2011 quarter was quite comfortable. He expressed concern over heavy overdrawal of power from the grid by many States. Some of the constituents sell power through power exchange and at the same time overdraw power from the grid endangering the grid security. He also stated that the overdrawal of power is not in the interest of safe and secure operation of grid. He expressed that only policy frame work would take care of such issues. He proposed that Heads of the power utilities needs to be informed in this regard.

He further stated that same agenda items had been repeating from last many of the meetings. He stressed the need for action from the utilities so that these issues get resolved.

He expressed happiness that the issue of formation of RPC forum at national level as decided in the last NRPC meeting was being examined in CEA.

Finally, he thanked Shri I.J.Kapoor, Director (commercial), NTPC and their dedicated team of officers for hosting and making excellent arrangements for the meeting.

He then requested Member Secretary, NRPC to take up the agenda for discussions.

CONFIRMATION OF MINUTES (NRPC)

A.2 Minutes of 20th Meeting of NRPC

MS, NRPC stated that the minutes of 20th meeting of NRPC held at Dehradun, on 1st March. , 2011, were circulated vide letter No. NRPC / SE(C) / 21-RPC / 11/1038-1108 dated 27th June, 2011. BBMB had requested for amendment in the minutes as given below:

"BBMB stated that the Board may recommend adoption of average YTC for BBMB to which no Constituent objected. Chairman, TCC also stated that there was no objection to the proposal of BBMB. The proposal of BBMB and its acceptance by the TCC may be intimated to concerned agencies for adoption."

The members confirmed the minutes of 20th meeting of NRPC with the above amendments.

ITEMS FOR TCC AND NRPC

OPERATIONAL ISSUES

B.1 Status of Major Decisions of NRPC.

The deliberations in the TCC and NRPC meeting are given at **Annexure-III**.

B.2 Status of Implementation of action plan for partial Grid Disturbance on 2nd January, 2010.

TCC Deliberations.

MS,NRPC stated that Northern Region had experienced a partial gird disturbance on 2nd January 2010 in which power supply in Punjab, North Haryana, Himachal Pradesh, J&K and UT Chandigarh sub system was affected. Central Electricity Authority had constituted a Committee under the Chairmanship of Member (GO&D), CEA, to inquire into the grid incident and ascertain the cause of grid disturbance and suggest remedial measures to avoid recurrence of such incident. The committee had submitted its Report along with recommendations to the Authority in May 2010. He added that the recommendations along with progress of implementation is being regularly monitored in OCC meetings. Further, he mentioned that presently the focus is on implementation of three major recommendations.

Annex-III

Major Decisions in earlier NRPC Meetings

Sr.	Issues	Decisions Taken/discussions in	20 th TCC	22 nd NRPC
No	Discussed	the subsequent meetings.	Deliberations	Deliberations
1.	12th NRPC r	neeting held on 22nd April, 2009 in	Chandigarh	
1.1	Replacement of obsolete protection relays with State of numerical relays	All the constituents agreed to complete the process of installation of numerical relays in their system by	To size the problem, NRPC Secretariat would prepare a format for capturing the information. Constituents would submit the information before next Protection Sub-Committee meeting.	
2	13th NRPC me	eting held on 24th June, 2009 at Lu	ucknow	
2.1	Automatic Meter Reading(AMR) for SEMs	The proposal for implementation of AMR through POWERGRID was approved by NRPC. In 21st NRPC meeting, POWERGRID had informed that the investment has been approved on 30.05.2011 and the work would be awarded in 3 months and would be implemented in 1 year thereafter. While implementing, priority shall be accorded to locations from where data		Members noted the deliberation of TCC.
		is getting delayed at present POWERGRID was requested to take timely actions to meet the time line.		
3	In 14th meetin	•	uraikund	
3.1		<u> </u>		Members noted
3 3.1	In 14th meetin	timely actions to meet the time line. g held on 9th September 2009 at September 200		Members noted